The Java EE 6 Tutorial

Part No: 821–1841–12
March 2011

ORACLE

110225@25097

Contents

Preface

This tutorial is a guide to developing enterprise applications for the Java Platform, Enterprise Edition 6 (Java EE 6) using GlassFish Server Open Source Edition.

Oracle GlassFish Server, a Java EE compatible application server, is based on GlassFish Server Open Source Edition, the leading open-source and open-community platform for building and deploying next-generation applications and services. GlassFish Server Open Source Edition, developed by the GlassFish project open-source community at `http://glassfish.java.net/`, is the first compatible implementation of the Java EE 6 platform specification. This lightweight, flexible, and open-source application server enables organizations not only to leverage the new capabilities introduced within the Java EE 6 specification, but also to add to their existing capabilities through a faster and more streamlined development and deployment cycle. Oracle GlassFish Server, the product version, and GlassFish Server Open Source Edition, the open-source version, are hereafter referred to as GlassFish Server.

The following topics are addressed here:

Before You Read This Book

Before proceeding with this tutorial, you should have a good knowledge of the Java programming language. A good way to get to that point is to work through *The Java Tutorial, Fourth Edition*, Sharon Zakhour et al. (Addison-Wesley, 2006).

Related Documentation

The GlassFish Server documentation set describes deployment planning and system installation. To obtain documentation for GlassFish Server Open Source Edition, you can download a ZIP file containing PDFs from `http://download.java.net/glassfish/3.1/release/glassfish-ose-3.1-docs-pdf.zip`. The Uniform Resource Locator (URL) for the Oracle GlassFish Server product documentation is `http://download.oracle.com/docs/cd/E18930_01/index.htm`.

Javadoc tool reference documentation for packages that are provided with GlassFish Server is available as follows.

- The API specification for version 6 of Java EE is located at `http://download.oracle.com/javaee/6/api/`.
- The API specification for GlassFish Server, including Java EE 6 platform packages and nonplatform packages that are specific to the GlassFish Server product, is located at `http://glassfish.java.net/nonav/docs/v3/api/`.

Additionally, the Java EE Specifications at `http://www.oracle.com/technetwork/java/javaee/tech/index.html` might be useful.

For information about creating enterprise applications in the NetBeans Integrated Development Environment (IDE), see `http://www.netbeans.org/kb/`.

For information about the Java DB database for use with the GlassFish Server, see `http://www.oracle.com/technetwork/java/javadb/overview/index.html`.

The GlassFish Samples project is a collection of sample applications that demonstrate a broad range of Java EE technologies. The GlassFish Samples are bundled with the Java EE Software Development Kit (SDK) and are also available from the GlassFish Samples project page at `http://glassfish-samples.java.net/`.

Symbol Conventions

The following table explains symbols that might be used in this book.

TABLE P–1 Symbol Conventions

Symbol	Description	Example	Meaning
`[ ]`	Contains optional arguments and command options.	`ls [-l]`	The `-l` option is not required.
`{ | }`	Contains a set of choices for a required command option.	`-d {y|n}`	The `-d` option requires that you use either the `y` argument or the `n` argument.

TABLE P–1 Symbol Conventions *(Continued)*

Symbol	Description	Example	Meaning
`${ }`	Indicates a variable reference.	`${com.sun.javaRoot}`	References the value of the `com.sun.javaRoot` variable.
-	Joins simultaneous multiple keystrokes.	Control-A	Press the Control key while you press the A key.
+	Joins consecutive multiple keystrokes.	Ctrl+A+N	Press the Control key, release it, and then press the subsequent keys.
→	Indicates menu item selection in a graphical user interface.	File → New → Templates	From the File menu, choose New. From the New submenu, choose Templates.

Typographic Conventions

The following table describes the typographic changes that are used in this book.

TABLE P–2 Typographic Conventions

Typeface	Meaning	Example
`AaBbCc123`	The names of commands, files, and directories, and onscreen computer output	Edit your `.login` file. Use `ls -a` to list all files. `machine_name% you have mail.`
`AaBbCc123`	What you type, contrasted with onscreen computer output	`machine_name%` **`su`** `Password:`
AaBbCc123	A placeholder to be replaced with a real name or value	The command to remove a file is `rm` *filename*.
AaBbCc123	Book titles, new terms, and terms to be emphasized (note that some emphasized items appear bold online)	Read Chapter 6 in the *User's Guide*. A *cache* is a copy that is stored locally. Do *not* save the file.

Default Paths and File Names

The following table describes the default paths and file names that are used in this book.

TABLE P–3 Default Paths and File Names

Placeholder	Description	Default Value
as-install	Represents the base installation directory for the GlassFish Server or the SDK of which the GlassFish Server is a part.	Installations on the Solaris operating system, Linux operating system, and Mac operating system: *user's-home-directory*`/glassfish3/glassfish` Windows, all installations: *SystemDrive*`:\glassfish3\glassfish`
as-install-parent	Represents the parent of the base installation directory for GlassFish Server.	Installations on the Solaris operating system, Linux operating system, and Mac operating system: *user's-home-directory*`/glassfish3` Windows, all installations: *SystemDrive*`:\glassfish3`
tut-install	Represents the base installation directory for the *Java EE Tutorial* after you install the GlassFish Server or the SDK and run the Update Tool.	*as-install*`/docs/javaee-tutorial`
domain-root-dir	Represents the directory in which a domain is created by default.	*as-install*`/domains/`
domain-dir	Represents the directory in which a domain's configuration is stored. In configuration files, *domain-dir* is represented as follows: `${com.sun.aas.instanceRoot}`	*domain-root-dir*`/`*domain-name*

Third-Party Web Site References

Third-party URLs are referenced in this document and provide additional, related information.

Note – Oracle is not responsible for the availability of third-party web sites mentioned in this document. Oracle does not endorse and is not responsible or liable for any content, advertising, products, or other materials that are available on or through such sites or resources. Oracle will not be responsible or liable for any actual or alleged damage or loss caused or alleged to be caused by or in connection with use of or reliance on any such content, goods, or services that are available on or through such sites or resources.

PART I

Introduction

Part I introduces the platform, the tutorial, and the examples. This part contains the following chapters:

- Chapter 1, "Overview"
- Chapter 2, "Using the Tutorial Examples"

◆ ◆ ◆ CHAPTER 1

Overview

Developers today increasingly recognize the need for distributed, transactional, and portable applications that leverage the speed, security, and reliability of server-side technology. *Enterprise applications* provide the business logic for an enterprise. They are centrally managed and often interact with other enterprise software. In the world of information technology, enterprise applications must be designed, built, and produced for less money, with greater speed, and with fewer resources.

With the Java Platform, Enterprise Edition (Java EE), development of Java enterprise applications has never been easier or faster. The aim of the Java EE platform is to provide developers with a powerful set of APIs while shortening development time, reducing application complexity, and improving application performance.

The Java EE platform is developed through the Java Community Process (the JCP), which is responsible for all Java technologies. Expert groups, composed of interested parties, have created Java Specification Requests (JSRs) to define the various Java EE technologies. The work of the Java Community under the JCP program helps to ensure Java technology's standard of stability and cross-platform compatibility.

The Java EE platform uses a simplified programming model. XML deployment descriptors are optional. Instead, a developer can simply enter the information as an *annotation* directly into a Java source file, and the Java EE server will configure the component at deployment and runtime. These annotations are generally used to embed in a program data that would otherwise be furnished in a deployment descriptor. With annotations, you put the specification information in your code next to the program element affected.

In the Java EE platform, dependency injection can be applied to all resources that a component needs, effectively hiding the creation and lookup of resources from application code. Dependency injection can be used in EJB containers, web containers, and application clients. Dependency injection allows the Java EE container to automatically insert references to other required components or resources, using annotations.

This tutorial uses examples to describe the features available in the Java EE platform for developing enterprise applications. Whether you are a new or experienced Enterprise developer, you should find the examples and accompanying text a valuable and accessible knowledge base for creating your own solutions.

If you are new to Java EE enterprise application development, this chapter is a good place to start. Here you will review development basics, learn about the Java EE architecture and APIs, become acquainted with important terms and concepts, and find out how to approach Java EE application programming, assembly, and deployment.

The following topics are addressed here:

Java EE 6 Platform Highlights

The most important goal of the Java EE 6 platform is to simplify development by providing a common foundation for the various kinds of components in the Java EE platform. Developers benefit from productivity improvements with more annotations and less XML configuration, more Plain Old Java Objects (POJOs), and simplified packaging. The Java EE 6 platform includes the following new features:

- Profiles: configurations of the Java EE platform targeted at specific classes of applications. Specifically, the Java EE 6 platform introduces a lightweight Web Profile targeted at next-generation web applications, as well as a Full Profile that contains all Java EE technologies and provides the full power of the Java EE 6 platform for enterprise applications.
- New technologies, including the following:
  - Java API for RESTful Web Services (JAX-RS)
  - Managed Beans
  - Contexts and Dependency Injection for the Java EE Platform (JSR 299), informally known as CDI
  - Dependency Injection for Java (JSR 330)

- Bean Validation (JSR 303)
- Java Authentication Service Provider Interface for Containers (JASPIC)

- New features for Enterprise JavaBeans (EJB) components (see "Enterprise JavaBeans Technology" on page 56 for details)
- New features for servlets (see "Java Servlet Technology" on page 57 for details)
- New features for JavaServer Faces components (see "JavaServer Faces Technology" on page 57 for details)

Java EE Application Model

The Java EE application model begins with the Java programming language and the Java virtual machine. The proven portability, security, and developer productivity they provide forms the basis of the application model. Java EE is designed to support applications that implement enterprise services for customers, employees, suppliers, partners, and others who make demands on or contributions to the enterprise. Such applications are inherently complex, potentially accessing data from a variety of sources and distributing applications to a variety of clients.

To better control and manage these applications, the business functions to support these various users are conducted in the middle tier. The middle tier represents an environment that is closely controlled by an enterprise's information technology department. The middle tier is typically run on dedicated server hardware and has access to the full services of the enterprise.

The Java EE application model defines an architecture for implementing services as multitier applications that deliver the scalability, accessibility, and manageability needed by enterprise-level applications. This model partitions the work needed to implement a multitier service into the following parts:

- The business and presentation logic to be implemented by the developer
- The standard system services provided by the Java EE platform

The developer can rely on the platform to provide solutions for the hard systems-level problems of developing a multitier service.

Distributed Multitiered Applications

The Java EE platform uses a distributed multitiered application model for enterprise applications. Application logic is divided into components according to function, and the application components that make up a Java EE application are installed on various machines, depending on the tier in the multitiered Java EE environment to which the application component belongs.

Figure 1–1 shows two multitiered Java EE applications divided into the tiers described in the following list. The Java EE application parts shown in Figure 1–1 are presented in "Java EE Components" on page 40.

- Client-tier components run on the client machine.
- Web-tier components run on the Java EE server.
- Business-tier components run on the Java EE server.
- Enterprise information system (EIS)-tier software runs on the EIS server.

Although a Java EE application can consist of the three or four tiers shown in Figure 1–1, Java EE multitiered applications are generally considered to be three-tiered applications because they are distributed over three locations: client machines, the Java EE server machine, and the database or legacy machines at the back end. Three-tiered applications that run in this way extend the standard two-tiered client-and-server model by placing a multithreaded application server between the client application and back-end storage.

FIGURE 1–1 Multitiered Applications



Security

Although other enterprise application models require platform-specific security measures in each application, the Java EE security environment enables security constraints to be defined at deployment time. The Java EE platform makes applications portable to a wide variety of security implementations by shielding application developers from the complexity of implementing security features.

The Java EE platform provides standard declarative access control rules that are defined by the developer and interpreted when the application is deployed on the server. Java EE also provides standard login mechanisms so application developers do not have to implement these mechanisms in their applications. The same application works in a variety of security environments without changing the source code.

Java EE Components

Java EE applications are made up of components. A *Java EE component* is a self-contained functional software unit that is assembled into a Java EE application with its related classes and files and that communicates with other components.

The Java EE specification defines the following Java EE components.

- Application clients and applets are components that run on the client.
- Java Servlet, JavaServer Faces, and JavaServer Pages (JSP) technology components are web components that run on the server.
- Enterprise JavaBeans (EJB) components (enterprise beans) are business components that run on the server.

Java EE components are written in the Java programming language and are compiled in the same way as any program in the language. The difference between Java EE components and "standard" Java classes is that Java EE components are assembled into a Java EE application, are verified to be well formed and in compliance with the Java EE specification, and are deployed to production, where they are run and managed by the Java EE server.

Java EE Clients

A Java EE client is usually either a web client or an application client.

Web Clients

A *web client* consists of two parts:

- Dynamic web pages containing various types of markup language (HTML, XML, and so on), which are generated by web components running in the web tier
- A web browser, which renders the pages received from the server

A web client is sometimes called a *thin client*. Thin clients usually do not query databases, execute complex business rules, or connect to legacy applications. When you use a thin client, such heavyweight operations are off-loaded to enterprise beans executing on the Java EE server, where they can leverage the security, speed, services, and reliability of Java EE server-side technologies.

Application Clients

An *application client* runs on a client machine and provides a way for users to handle tasks that require a richer user interface than can be provided by a markup language. An application client typically has a graphical user interface (GUI) created from the Swing or the Abstract Window Toolkit (AWT) API, but a command-line interface is certainly possible.

Application clients directly access enterprise beans running in the business tier. However, if application requirements warrant it, an application client can open an HTTP connection to establish communication with a servlet running in the web tier. Application clients written in languages other than Java can interact with Java EE servers, enabling the Java EE platform to interoperate with legacy systems, clients, and non-Java languages.

Applets

A web page received from the web tier can include an embedded applet. Written in the Java programming language, an *applet* is a small client application that executes in the Java virtual machine installed in the web browser. However, client systems will likely need the Java Plug-in and possibly a security policy file for the applet to successfully execute in the web browser.

Web components are the preferred API for creating a web client program, because no plug-ins or security policy files are needed on the client systems. Also, web components enable cleaner and more modular application design because they provide a way to separate applications programming from web page design. Personnel involved in web page design thus do not need to understand Java programming language syntax to do their jobs.

The JavaBeans Component Architecture

The server and client tiers might also include components based on the JavaBeans component architecture (JavaBeans components) to manage the data flow between the following:

- An application client or applet and components running on the Java EE server
- Server components and a database

JavaBeans components are not considered Java EE components by the Java EE specification.

JavaBeans components have properties and have `get` and `set` methods for accessing the properties. JavaBeans components used in this way are typically simple in design and implementation but should conform to the naming and design conventions outlined in the JavaBeans component architecture.

Java EE Server Communications

Figure 1–2 shows the various elements that can make up the client tier. The client communicates with the business tier running on the Java EE server either directly or, as in the case of a client running in a browser, by going through web pages or servlets running in the web tier.

FIGURE 1–2 Server Communication



Web Components

Java EE web components are either servlets or web pages created using JavaServer Faces technology and/or JSP technology (JSP pages). *Servlets* are Java programming language classes that dynamically process requests and construct responses. *JSP pages* are text-based documents that execute as servlets but allow a more natural approach to creating static content. *JavaServer Faces technology* builds on servlets and JSP technology and provides a user interface component framework for web applications.

Static HTML pages and applets are bundled with web components during application assembly but are not considered web components by the Java EE specification. Server-side utility classes can also be bundled with web components and, like HTML pages, are not considered web components.

As shown in Figure 1–3, the web tier, like the client tier, might include a JavaBeans component to manage the user input and send that input to enterprise beans running in the business tier for processing.

FIGURE 1–3 Web Tier and Java EE Applications



Business Components

Business code, which is logic that solves or meets the needs of a particular business domain, such as banking, retail, or finance, is handled by enterprise beans running in either the business tier or the web tier. Figure 1–4 shows how an enterprise bean receives data from client programs, processes it (if necessary), and sends it to the enterprise information system tier for storage. An enterprise bean also retrieves data from storage, processes it (if necessary), and sends it back to the client program.

FIGURE 1–4 Business and EIS Tiers



Enterprise Information System Tier

The enterprise information system tier handles EIS software and includes enterprise infrastructure systems, such as enterprise resource planning (ERP), mainframe transaction processing, database systems, and other legacy information systems. For example, Java EE application components might need access to enterprise information systems for database connectivity.

Java EE Containers

Normally, thin-client multitiered applications are hard to write because they involve many lines of intricate code to handle transaction and state management, multithreading, resource pooling, and other complex low-level details. The component-based and platform-independent Java EE architecture makes Java EE applications easy to write because business logic is organized into reusable components. In addition, the Java EE server provides underlying services in the form of a container for every component type. Because you do not have to develop these services yourself, you are free to concentrate on solving the business problem at hand.

Container Services

Containers are the interface between a component and the low-level platform-specific functionality that supports the component. Before it can be executed, a web, enterprise bean, or application client component must be assembled into a Java EE module and deployed into its container.

The assembly process involves specifying container settings for each component in the Java EE application and for the Java EE application itself. Container settings customize the underlying support provided by the Java EE server, including such services as security, transaction management, Java Naming and Directory Interface (JNDI) API lookups, and remote connectivity. Here are some of the highlights.

- The Java EE security model lets you configure a web component or enterprise bean so that system resources are accessed only by authorized users.
- The Java EE transaction model lets you specify relationships among methods that make up a single transaction so that all methods in one transaction are treated as a single unit.
- JNDI lookup services provide a unified interface to multiple naming and directory services in the enterprise so that application components can access these services.
- The Java EE remote connectivity model manages low-level communications between clients and enterprise beans. After an enterprise bean is created, a client invokes methods on it as if it were in the same virtual machine.

Because the Java EE architecture provides configurable services, application components within the same Java EE application can behave differently based on where they are deployed. For example, an enterprise bean can have security settings that allow it a certain level of access to database data in one production environment and another level of database access in another production environment.

The container also manages nonconfigurable services, such as enterprise bean and servlet lifecycles, database connection resource pooling, data persistence, and access to the Java EE platform APIs (see "Java EE 6 APIs" on page 53).

Container Types

The deployment process installs Java EE application components in the Java EE containers as illustrated in Figure 1–5.

FIGURE 1–5 Java EE Server and Containers



- **Java EE server**: The runtime portion of a Java EE product. A Java EE server provides EJB and web containers.
- **Enterprise JavaBeans (EJB) container**: Manages the execution of enterprise beans for Java EE applications. Enterprise beans and their container run on the Java EE server.
- **Web container**: Manages the execution of web pages, servlets, and some EJB components for Java EE applications. Web components and their container run on the Java EE server.

- **Application client container**: Manages the execution of application client components. Application clients and their container run on the client.
- **Applet container**: Manages the execution of applets. Consists of a web browser and Java Plug-in running on the client together.

Web Services Support

Web services are web-based enterprise applications that use open, XML-based standards and transport protocols to exchange data with calling clients. The Java EE platform provides the XML APIs and tools you need to quickly design, develop, test, and deploy web services and clients that fully interoperate with other web services and clients running on Java-based or non-Java-based platforms.

To write web services and clients with the Java EE XML APIs, all you do is pass parameter data to the method calls and process the data returned; for document-oriented web services, you send documents containing the service data back and forth. No low-level programming is needed, because the XML API implementations do the work of translating the application data to and from an XML-based data stream that is sent over the standardized XML-based transport protocols. These XML-based standards and protocols are introduced in the following sections.

The translation of data to a standardized XML-based data stream is what makes web services and clients written with the Java EE XML APIs fully interoperable. This does not necessarily mean that the data being transported includes XML tags, because the transported data can itself be plain text, XML data, or any kind of binary data, such as audio, video, maps, program files, computer-aided design (CAD) documents, and the like. The next section introduces XML and explains how parties doing business can use XML tags and schemas to exchange data in a meaningful way.

XML

Extensible Markup Language (XML) is a cross-platform, extensible, text-based standard for representing data. Parties that exchange XML data can create their own tags to describe the data, set up schemas to specify which tags can be used in a particular kind of XML document, and use XML style sheets to manage the display and handling of the data.

For example, a web service can use XML and a schema to produce price lists, and companies that receive the price lists and schema can have their own style sheets to handle the data in a way that best suits their needs. Here are examples.

- One company might put XML pricing information through a program to translate the XML to HTML so that it can post the price lists to its intranet.
- A partner company might put the XML pricing information through a tool to create a marketing presentation.

- Another company might read the XML pricing information into an application for processing.

SOAP Transport Protocol

Client requests and web service responses are transmitted as Simple Object Access Protocol (SOAP) messages over HTTP to enable a completely interoperable exchange between clients and web services, all running on different platforms and at various locations on the Internet. HTTP is a familiar request-and-response standard for sending messages over the Internet, and SOAP is an XML-based protocol that follows the HTTP request-and-response model.

The SOAP portion of a transported message does the following:

- Defines an XML-based envelope to describe what is in the message and explain how to process the message
- Includes XML-based encoding rules to express instances of application-defined data types within the message
- Defines an XML-based convention for representing the request to the remote service and the resulting response

WSDL Standard Format

The Web Services Description Language (WSDL) is a standardized XML format for describing network services. The description includes the name of the service, the location of the service, and ways to communicate with the service. WSDL service descriptions can be published on the Web. GlassFish Server provides a tool for generating the WSDL specification of a web service that uses remote procedure calls to communicate with clients.

Java EE Application Assembly and Deployment

A Java EE application is packaged into one or more standard units for deployment to any Java EE platform-compliant system. Each unit contains

- A functional component or components, such as an enterprise bean, web page, servlet, or applet
- An optional deployment descriptor that describes its content

Once a Java EE unit has been produced, it is ready to be deployed. Deployment typically involves using a platform's deployment tool to specify location-specific information, such as a list of local users who can access it and the name of the local database. Once deployed on a local platform, the application is ready to run.

Packaging Applications

A Java EE application is delivered in a Java Archive (JAR) file, a Web Archive (WAR) file, or an Enterprise Archive (EAR) file. A WAR or EAR file is a standard JAR (`.jar`) file with a `.war` or `.ear` extension. Using JAR, WAR, and EAR files and modules makes it possible to assemble a number of different Java EE applications using some of the same components. No extra coding is needed; it is only a matter of assembling (or packaging) various Java EE modules into Java EE JAR, WAR, or EAR files.

An EAR file (see Figure 1–6) contains Java EE modules and, optionally, deployment descriptors. A *deployment descriptor*, an XML document with an `.xml` extension, describes the deployment settings of an application, a module, or a component. Because deployment descriptor information is declarative, it can be changed without the need to modify the source code. At runtime, the Java EE server reads the deployment descriptor and acts upon the application, module, or component accordingly.

FIGURE 1–6 EAR File Structure



The two types of deployment descriptors are Java EE and runtime. A *Java EE deployment descriptor* is defined by a Java EE specification and can be used to configure deployment settings on any Java EE-compliant implementation. A *runtime deployment descriptor* is used to configure Java EE implementation-specific parameters. For example, the GlassFish Server runtime deployment descriptor contains such information as the context root of a web application, as well as GlassFish Server implementation-specific parameters, such as caching

directives. The GlassFish Server runtime deployment descriptors are named `sun-`*moduleType*`.xml` and are located in the same `META-INF` directory as the Java EE deployment descriptor.

A *Java EE module* consists of one or more Java EE components for the same container type and, optionally, one component deployment descriptor of that type. An enterprise bean module deployment descriptor, for example, declares transaction attributes and security authorizations for an enterprise bean. A Java EE module can be deployed as a *stand-alone* module.

Java EE modules are of the following types:

- EJB modules, which contain class files for enterprise beans and an EJB deployment descriptor. EJB modules are packaged as JAR files with a `.jar` extension.
- Web modules, which contain servlet class files, web files, supporting class files, GIF and HTML files, and a web application deployment descriptor. Web modules are packaged as JAR files with a `.war` (web archive) extension.
- Application client modules, which contain class files and an application client deployment descriptor. Application client modules are packaged as JAR files with a `.jar` extension.
- Resource adapter modules, which contain all Java interfaces, classes, native libraries, and other documentation, along with the resource adapter deployment descriptor. Together, these implement the Connector architecture (see "Java EE Connector Architecture" on page 60) for a particular EIS. Resource adapter modules are packaged as JAR files with an `.rar` (resource adapter archive) extension.

Development Roles

Reusable modules make it possible to divide the application development and deployment process into distinct roles so that different people or companies can perform different parts of the process.

The first two roles, Java EE product provider and tool provider, involve purchasing and installing the Java EE product and tools. After software is purchased and installed, Java EE components can be developed by application component providers, assembled by application assemblers, and deployed by application deployers. In a large organization, each of these roles might be executed by different individuals or teams. This division of labor works because each of the earlier roles outputs a portable file that is the input for a subsequent role. For example, in the application component development phase, an enterprise bean software developer delivers EJB JAR files. In the application assembly role, another developer may combine these EJB JAR files into a Java EE application and save it in an EAR file. In the application deployment role, a system administrator at the customer site uses the EAR file to install the Java EE application into a Java EE server.

The different roles are not always executed by different people. If you work for a small company, for example, or if you are prototyping a sample application, you might perform the tasks in every phase.

Java EE Product Provider

The Java EE product provider is the company that designs and makes available for purchase the Java EE platform APIs and other features defined in the Java EE specification. Product providers are typically application server vendors that implement the Java EE platform according to the Java EE 6 Platform specification.

Tool Provider

The tool provider is the company or person who creates development, assembly, and packaging tools used by component providers, assemblers, and deployers.

Application Component Provider

The application component provider is the company or person who creates web components, enterprise beans, applets, or application clients for use in Java EE applications.

Enterprise Bean Developer

An enterprise bean developer performs the following tasks to deliver an EJB JAR file that contains one or more enterprise beans:

- Writes and compiles the source code
- Specifies the deployment descriptor (optional)
- Packages the `.class` files and deployment descriptor into the EJB JAR file

Web Component Developer

A web component developer performs the following tasks to deliver a WAR file containing one or more web components:

- Writes and compiles servlet source code
- Writes JavaServer Faces, JSP, and HTML files
- Specifies the deployment descriptor (optional)
- Packages the `.class`, `.jsp`, and `.html` files and deployment descriptor into the WAR file

Application Client Developer

An application client developer performs the following tasks to deliver a JAR file containing the application client:

- Writes and compiles the source code
- Specifies the deployment descriptor for the client (optional)

- Packages the `.class` files and deployment descriptor into the JAR file

Application Assembler

The application assembler is the company or person who receives application modules from component providers and may assemble them into a Java EE application EAR file. The assembler or deployer can edit the deployment descriptor directly or can use tools that correctly add XML tags according to interactive selections.

A software developer performs the following tasks to deliver an EAR file containing the Java EE application:

- Assembles EJB JAR and WAR files created in the previous phases into a Java EE application (EAR) file
- Specifies the deployment descriptor for the Java EE application (optional)
- Verifies that the contents of the EAR file are well formed and comply with the Java EE specification

Application Deployer and Administrator

The application deployer and administrator is the company or person who configures and deploys the Java EE application, administers the computing and networking infrastructure where Java EE applications run, and oversees the runtime environment. Duties include setting transaction controls and security attributes and specifying connections to databases.

During configuration, the deployer follows instructions supplied by the application component provider to resolve external dependencies, specify security settings, and assign transaction attributes. During installation, the deployer moves the application components to the server and generates the container-specific classes and interfaces.

A deployer or system administrator performs the following tasks to install and configure a Java EE application:

- Configures the Java EE application for the operational environment
- Verifies that the contents of the EAR file are well formed and comply with the Java EE specification
- Deploys (installs) the Java EE application EAR file into the Java EE server

Java EE 6 APIs

Figure 1–7 shows the relationships among the Java EE containers.

FIGURE 1–7 Java EE Containers



Figure 1–8 shows the availability of the Java EE 6 APIs in the web container.

FIGURE 1–8 Java EE APIs in the Web Container



Figure 1–9 shows the availability of the Java EE 6 APIs in the EJB container.

FIGURE 1–9 Java EE APIs in the EJB Container



Figure 1–10 shows the availability of the Java EE 6 APIs in the application client container.

FIGURE 1–10 Java EE APIs in the Application Client Container



The following sections give a brief summary of the technologies required by the Java EE platform and the APIs used in Java EE applications.

Enterprise JavaBeans Technology

An Enterprise JavaBeans (EJB) component, or *enterprise bean*, is a body of code having fields and methods to implement modules of business logic. You can think of an enterprise bean as a building block that can be used alone or with other enterprise beans to execute business logic on the Java EE server.

Enterprise beans are either session beans or message-driven beans.

- A *session bean* represents a transient conversation with a client. When the client finishes executing, the session bean and its data are gone.
- A *message-driven bean* combines features of a session bean and a message listener, allowing a business component to receive messages asynchronously. Commonly, these are Java Message Service (JMS) messages.

In the Java EE 6 platform, new enterprise bean features include the following:

- The ability to package local enterprise beans in a WAR file
- Singleton session beans, which provide easy access to shared state
- A lightweight subset of Enterprise JavaBeans functionality (EJB Lite) that can be provided within Java EE Profiles, such as the Java EE Web Profile.

The Interceptors specification, which is part of the EJB 3.1 specification, makes more generally available the interceptor facility originally defined as part of the EJB 3.0 specification.

Java Servlet Technology

Java Servlet technology lets you define HTTP-specific servlet classes. A servlet class extends the capabilities of servers that host applications accessed by way of a request-response programming model. Although servlets can respond to any type of request, they are commonly used to extend the applications hosted by web servers.

In the Java EE 6 platform, new Java Servlet technology features include the following:

- Annotation support
- Asynchronous support
- Ease of configuration
- Enhancements to existing APIs
- Pluggability

JavaServer Faces Technology

JavaServer Faces technology is a user interface framework for building web applications. The main components of JavaServer Faces technology are as follows:

- A GUI component framework.
- A flexible model for rendering components in different kinds of HTML or different markup languages and technologies. A `Renderer` object generates the markup to render the component and converts the data stored in a model object to types that can be represented in a view.
- A standard `RenderKit` for generating HTML/4.01 markup.

The following features support the GUI components:

- Input validation
- Event handling
- Data conversion between model objects and components
- Managed model object creation
- Page navigation configuration

- Expression Language (EL)

All this functionality is available using standard Java APIs and XML-based configuration files.

In the Java EE 6 platform, new features of JavaServer Faces include the following:

- The ability to use annotations instead of a configuration file to specify managed beans
- Facelets, a display technology that replaces JavaServer Pages (JSP) technology using XHTML files
- Ajax support
- Composite components
- Implicit navigation

JavaServer Pages Technology

JavaServer Pages (JSP) technology lets you put snippets of servlet code directly into a text-based document. A JSP page is a text-based document that contains two types of text:

- Static data, which can be expressed in any text-based format such as HTML or XML
- JSP elements, which determine how the page constructs dynamic content

JavaServer Pages Standard Tag Library

The JavaServer Pages Standard Tag Library (JSTL) encapsulates core functionality common to many JSP applications. Instead of mixing tags from numerous vendors in your JSP applications, you use a single, standard set of tags. This standardization allows you to deploy your applications on any JSP container that supports JSTL and makes it more likely that the implementation of the tags is optimized.

JSTL has iterator and conditional tags for handling flow control, tags for manipulating XML documents, internationalization tags, tags for accessing databases using SQL, and commonly used functions.

Java Persistence API

The Java Persistence API is a Java standards-based solution for persistence. Persistence uses an object/relational mapping approach to bridge the gap between an object-oriented model and a relational database. The Java Persistence API can also be used in Java SE applications, outside of the Java EE environment. Java Persistence consists of the following areas:

- The Java Persistence API
- The query language

- Object/relational mapping metadata

Java Transaction API

The Java Transaction API (JTA) provides a standard interface for demarcating transactions. The Java EE architecture provides a default auto commit to handle transaction commits and rollbacks. An *auto commit* means that any other applications that are viewing data will see the updated data after each database read or write operation. However, if your application performs two separate database access operations that depend on each other, you will want to use the JTA API to demarcate where the entire transaction, including both operations, begins, rolls back, and commits.

Java API for RESTful Web Services

The Java API for RESTful Web Services (JAX-RS) defines APIs for the development of web services built according to the Representational State Transfer (REST) architectural style. A JAX-RS application is a web application that consists of classes that are packaged as a servlet in a WAR file along with required libraries.

The JAX-RS API is new to the Java EE 6 platform.

Managed Beans

Managed Beans, lightweight container-managed objects (POJOs) with minimal requirements, support a small set of basic services, such as resource injection, lifecycle callbacks, and interceptors. Managed Beans represent a generalization of the managed beans specified by JavaServer Faces technology and can be used anywhere in a Java EE application, not just in web modules.

The Managed Beans specification is part of the Java EE 6 platform specification (JSR 316).

Managed Beans are new to the Java EE 6 platform.

Contexts and Dependency Injection for the Java EE Platform (JSR 299)

Contexts and Dependency Injection (CDI) for the Java EE platform defines a set of contextual services, provided by Java EE containers, that make it easy for developers to use enterprise beans along with JavaServer Faces technology in web applications. Designed for use with stateful objects, CDI also has many broader uses, allowing developers a great deal of flexibility to integrate different kinds of components in a loosely coupled but type-safe way.

CDI is new to the Java EE 6 platform.

Dependency Injection for Java (JSR 330)

Dependency Injection for Java defines a standard set of annotations (and one interface) for use on injectable classes.

In the Java EE platform, CDI provides support for Dependency Injection. Specifically, you can use DI injection points only in a CDI-enabled application.

Dependency Injection for Java is new to the Java EE 6 platform.

Bean Validation

The Bean Validation specification defines a metadata model and API for validating data in JavaBeans components. Instead of distributing validation of data over several layers, such as the browser and the server side, you can define the validation constraints in one place and share them across the different layers.

Bean Validation is new to the Java EE 6 platform.

Java Message Service API

The Java Message Service (JMS) API is a messaging standard that allows Java EE application components to create, send, receive, and read messages. It enables distributed communication that is loosely coupled, reliable, and asynchronous.

Java EE Connector Architecture

The Java EE Connector architecture is used by tools vendors and system integrators to create resource adapters that support access to enterprise information systems that can be plugged in to any Java EE product. A *resource adapter* is a software component that allows Java EE application components to access and interact with the underlying resource manager of the EIS. Because a resource adapter is specific to its resource manager, a different resource adapter typically exists for each type of database or enterprise information system.

The Java EE Connector architecture also provides a performance-oriented, secure, scalable, and message-based transactional integration of Java EE based web services with existing EISs that can be either synchronous or asynchronous. Existing applications and EISs integrated through the Java EE Connector architecture into the Java EE platform can be exposed as XML-based web services by using JAX-WS and Java EE component models. Thus JAX-WS and the Java EE Connector architecture are complementary technologies for enterprise application integration (EAI) and end-to-end business integration.

JavaMail API

Java EE applications use the JavaMail API to send email notifications. The JavaMail API has two parts:

- An application-level interface used by the application components to send mail
- A service provider interface

The Java EE platform includes the JavaMail API with a service provider that allows application components to send Internet mail.

Java Authorization Contract for Containers

The Java Authorization Contract for Containers (JACC) specification defines a contract between a Java EE application server and an authorization policy provider. All Java EE containers support this contract.

The JACC specification defines `java.security.Permission` classes that satisfy the Java EE authorization model. The specification defines the binding of container access decisions to operations on instances of these permission classes. It defines the semantics of policy providers that use the new permission classes to address the authorization requirements of the Java EE platform, including the definition and use of roles.

Java Authentication Service Provider Interface for Containers

The Java Authentication Service Provider Interface for Containers (JASPIC) specification defines a service provider interface (SPI) by which authentication providers that implement message authentication mechanisms may be integrated in client or server message-processing containers or runtimes. Authentication providers integrated through this interface operate on network messages provided to them by their calling container. The authentication providers transform outgoing messages so that the source of the message can be authenticated by the receiving container, and the recipient of the message can be authenticated by the message sender. Authentication providers authenticate incoming messages and return to their calling container the identity established as a result of the message authentication.

JASPIC is new to the Java EE 6 platform.

Java EE 6 APIs in the Java Platform, Standard Edition 6.0

Several APIs that are required by the Java EE 6 platform are included in the Java Platform, Standard Edition 6.0 (Java SE 6) platform and are thus available to Java EE applications.

Java Database Connectivity API

The Java Database Connectivity (JDBC) API lets you invoke SQL commands from Java programming language methods. You use the JDBC API in an enterprise bean when you have a session bean access the database. You can also use the JDBC API from a servlet or a JSP page to access the database directly without going through an enterprise bean.

The JDBC API has two parts:

- An application-level interface used by the application components to access a database
- A service provider interface to attach a JDBC driver to the Java EE platform

Java Naming and Directory Interface API

The Java Naming and Directory Interface (JNDI) API provides naming and directory functionality, enabling applications to access multiple naming and directory services, including existing naming and directory services, such as LDAP, NDS, DNS, and NIS. The JNDI API provides applications with methods for performing standard directory operations, such as associating attributes with objects and searching for objects using their attributes. Using JNDI, a Java EE application can store and retrieve any type of named Java object, allowing Java EE applications to coexist with many legacy applications and systems.

Java EE naming services provide application clients, enterprise beans, and web components with access to a JNDI naming environment. A *naming environment* allows a component to be customized without the need to access or change the component's source code. A container implements the component's environment and provides it to the component as a JNDI *naming context*.

A Java EE component can locate its environment naming context by using JNDI interfaces. A component can create a `javax.naming.InitialContext` object and look up the environment naming context in `InitialContext` under the name `java:comp/env`. A component's naming environment is stored directly in the environment naming context or in any of its direct or indirect subcontexts.

A Java EE component can access named system-provided and user-defined objects. The names of system-provided objects, such as JTA `UserTransaction` objects, are stored in the environment naming context `java:comp/env`. The Java EE platform allows a component to name user-defined objects, such as enterprise beans, environment entries, JDBC `DataSource`

objects, and message connections. An object should be named within a subcontext of the naming environment according to the type of the object. For example, enterprise beans are named within the subcontext `java:comp/env/ejb`, and JDBC `DataSource` references are named within the subcontext `java:comp/env/jdbc`.

JavaBeans Activation Framework

The JavaBeans Activation Framework (JAF) is used by the JavaMail API. JAF provides standard services to determine the type of an arbitrary piece of data, encapsulate access to it, discover the operations available on it, and create the appropriate JavaBeans component to perform those operations.

Java API for XML Processing

The Java API for XML Processing (JAXP), part of the Java SE platform, supports the processing of XML documents using Document Object Model (DOM), Simple API for XML (SAX), and Extensible Stylesheet Language Transformations (XSLT). JAXP enables applications to parse and transform XML documents independently of a particular XML processing implementation.

JAXP also provides namespace support, which lets you work with schemas that might otherwise have naming conflicts. Designed to be flexible, JAXP lets you use any XML-compliant parser or XSL processor from within your application and supports the Worldwide Web Consortium (W3C) schema. You can find information on the W3C schema at this URL: `http://www.w3.org/XML/Schema`.

Java Architecture for XML Binding

The Java Architecture for XML Binding (JAXB) provides a convenient way to bind an XML schema to a representation in Java language programs. JAXB can be used independently or in combination with JAX-WS, where it provides a standard data binding for web service messages. All Java EE application client containers, web containers, and EJB containers support the JAXB API.

SOAP with Attachments API for Java

The SOAP with Attachments API for Java (SAAJ) is a low-level API on which JAX-WS depends. SAAJ enables the production and consumption of messages that conform to the SOAP 1.1 and 1.2 specifications and SOAP with Attachments note. Most developers do not use the SAAJ API, instead using the higher-level JAX-WS API.

Java API for XML Web Services

The Java API for XML Web Services (JAX-WS) specification provides support for web services that use the JAXB API for binding XML data to Java objects. The JAX-WS specification defines client APIs for accessing web services as well as techniques for implementing web service endpoints. The Implementing Enterprise Web Services specification describes the deployment of JAX-WS-based services and clients. The EJB and Java Servlet specifications also describe aspects of such deployment. It must be possible to deploy JAX-WS-based applications using any of these deployment models.

The JAX-WS specification describes the support for message handlers that can process message requests and responses. In general, these message handlers execute in the same container and with the same privileges and execution context as the JAX-WS client or endpoint component with which they are associated. These message handlers have access to the same JNDI `java:comp/env` namespace as their associated component. Custom serializers and deserializers, if supported, are treated in the same way as message handlers.

Java Authentication and Authorization Service

The Java Authentication and Authorization Service (JAAS) provides a way for a Java EE application to authenticate and authorize a specific user or group of users to run it.

JAAS is a Java programming language version of the standard Pluggable Authentication Module (PAM) framework, which extends the Java Platform security architecture to support user-based authorization.

GlassFish Server Tools

The GlassFish Server is a compliant implementation of the Java EE 6 platform. In addition to supporting all the APIs described in the previous sections, the GlassFish Server includes a number of Java EE tools that are not part of the Java EE 6 platform but are provided as a convenience to the developer.

This section briefly summarizes the tools that make up the GlassFish Server. Instructions for starting and stopping the GlassFish Server, starting the Administration Console, and starting and stopping the Java DB server are in Chapter 2, “Using the Tutorial Examples.”

The GlassFish Server contains the tools listed in Table 1–1. Basic usage information for many of the tools appears throughout the tutorial. For detailed information, see the online help in the GUI tools.

TABLE 1–1 GlassFish Server Tools

Tool	Description
Administration Console	A web-based GUI GlassFish Server administration utility. Used to stop the GlassFish Server and manage users, resources, and applications.
`asadmin`	A command-line GlassFish Server administration utility. Used to start and stop the GlassFish Server and manage users, resources, and applications.
`appclient`	A command-line tool that launches the application client container and invokes the client application packaged in the application client JAR file.
`capture-schema`	A command-line tool to extract schema information from a database, producing a schema file that the GlassFish Server can use for container-managed persistence.
`package-appclient`	A command-line tool to package the application client container libraries and JAR files.
Java DB database	A copy of the Java DB server.
`xjc`	A command-line tool to transform, or bind, a source XML schema to a set of JAXB content classes in the Java programming language.
`schemagen`	A command-line tool to create a schema file for each namespace referenced in your Java classes.
`wsimport`	A command-line tool to generate JAX-WS portable artifacts for a given WSDL file. After generation, these artifacts can be packaged in a WAR file with the WSDL and schema documents, along with the endpoint implementation, and then deployed.
`wsgen`	A command-line tool to read a web service endpoint class and generate all the required JAX-WS portable artifacts for web service deployment and invocation.

◆ ◆ ◆ CHAPTER 2

Using the Tutorial Examples

This chapter tells you everything you need to know to install, build, and run the examples. The following topics are addressed here:

Required Software

The following software is required to run the examples:

Java Platform, Standard Edition

To build, deploy, and run the examples, you need a copy of the Java Platform, Standard Edition 6.0 Development Kit (JDK 6). You can download the JDK 6 software from `http://www.oracle.com/technetwork/java/javase/downloads/index.html`.

Download the current JDK update that does not include any other software, such as NetBeans IDE or the Java EE SDK.

Java EE 6 Software Development Kit

GlassFish Server Open Source Edition 3.1 is targeted as the build and runtime environment for the tutorial examples. To build, deploy, and run the examples, you need a copy of the GlassFish Server and, optionally, NetBeans IDE. To obtain the GlassFish Server, you must install the Java EE 6 Software Development Kit (SDK), which you can download from `http://www.oracle.com/technetwork/java/javaee/downloads/index.html`. Make sure you download the Java EE 6 SDK, not the Java EE 6 Web Profile SDK.

SDK Installation Tips

During the installation of the SDK, do the following.

- Configure the GlassFish Server administration user name as `admin`, and specify no password. This is the default setting.
- Accept the default port values for the Admin Port (4848) and the HTTP Port (8080).
- Allow the installer to download and configure the Update Tool. If you access the Internet through a firewall, provide the proxy host and port.

This tutorial refers to *as-install-parent*, the directory where you install the GlassFish Server. For example, the default installation directory on Microsoft Windows is `C:\glassfishv3`, so *as-install-parent* is `C:\glassfishv3`. The GlassFish Server itself is installed in *as-install*, the `glassfish` directory under *as-install-parent*. So on Microsoft Windows, *as-install* is `C:\glassfishv3\glassfish`.

After you install the GlassFish Server, add the following directories to your `PATH` to avoid having to specify the full path when you use commands:

as-install-parent`/bin`

as-install`/bin`

Java EE 6 Tutorial Component

The tutorial example source is contained in the tutorial component. To obtain the tutorial component, use the Update Tool.

▼ To Obtain the Tutorial Component Using the Update Tool

1 Start the Update Tool.

- **From the command line, type the command `updatetool`.**
- **On a Windows system, from the Start menu, choose All Programs, then chooseJava EE 6 SDK, then choose Start Update Tool.**

2. **Expand the GlassFish Server Open Source Edition node.**
3. **Select the Available Add-ons node.**
4. **From the list, select the Java EE 6 Tutorial check box.**
5. **Click Install.**
6. **Accept the license agreement.**

   After installation, the Java EE 6 Tutorial appears in the list of installed components. The tool is installed in the *as-install*`/docs/javaee-tutorial` directory. This directory contains two subdirectories: `docs` and `examples`. The `examples` directory contains subdirectories for each of the technologies discussed in the tutorial.

Next Steps Updates to the Java EE 6 Tutorial are published periodically. For details on obtaining these updates, see "Getting the Latest Updates to the Tutorial" on page 74.

NetBeans IDE

The NetBeans integrated development environment (IDE) is a free, open-source IDE for developing Java applications, including enterprise applications. NetBeans IDE supports the Java EE platform. You can build, package, deploy, and run the tutorial examples from within NetBeans IDE.

To run the tutorial examples, you need the latest version of NetBeans IDE. You can download NetBeans IDE from `http://www.netbeans.org/downloads/index.html`.

▼ To Install NetBeans IDE without GlassFish Server

When you install NetBeans IDE, do not install the version of GlassFish Server that comes with NetBeans IDE. To skip the installation of GlassFish Server, follow these steps.

1. **Click Customize on the first page of the NetBeans IDE Installer wizard.**
2. **In the Customize Installation dialog, deselect the check box for GlassFish Server and click OK.**
3. **Continue with the installation of NetBeans IDE.**

Next Steps The first time you start NetBeans IDE, a dialog box asks you if you want to download and install the JUnit testing library. A few of the tutorial examples use this library, so you should install it.

▼ To Add GlassFish Server as a Server in NetBeans IDE

To run the tutorial examples in NetBeans IDE, you must add your GlassFish Server as a server in NetBeans IDE. Follow these instructions to add the GlassFish Server to NetBeans IDE.

1. **From the Tools menu, choose Servers.**
   The Servers wizard opens.
2. **Click Add Server.**
3. **Under Choose Server, select GlassFish Server 3 and click Next.**
4. **Under Server Location, browse the location of your GlassFish Server installation and click Next.**
5. **Under Domain Location, select Register Local Domain.**
6. **Click Finish.**

Apache Ant

Ant is a Java technology-based build tool developed by the Apache Software Foundation (`http://ant.apache.org/`) and is used to build, package, and deploy the tutorial examples. To run the tutorial examples, you need Ant 1.7.1 or higher. If you do not already have Ant, you can install it from the Update Tool that is part of the GlassFish Server.

▼ To Obtain Apache Ant

1. **Start the Update Tool.**
   - **From the command line, type the command `updatetool`.**
   - **On a Windows system, from the Start menu, choose All Programs, then choose Java EE 6 SDK, then choose Start Update Tool.**
2. **Expand the GlassFish Server Open Source Edition node.**
3. **Select the Available Add-ons node.**
4. **From the list, select the Apache Ant Build Tool check box.**
5. **Click Install.**

6. **Accept the license agreement.**

   After installation, Apache Ant appears in the list of installed components. The tool is installed in the *as-install-parent*`/ant` directory.

Next Steps To use the `ant` command, add *as-install-parent*`/ant/bin` to your `PATH` environment variable.

Starting and Stopping the GlassFish Server

To start the GlassFish Server, open a terminal window or command prompt and execute the following:

```
asadmin start-domain --verbose
```

A *domain* is a set of one or more GlassFish Server instances managed by one administration server. Associated with a domain are the following:

- The GlassFish Server's port number. The default is 8080.
- The administration server's port number. The default is 4848.
- An administration user name and password.

You specify these values when you install the GlassFish Server. The examples in this tutorial assume that you chose the default ports.

With no arguments, the `start-domain` command initiates the default domain, which is `domain1`. The `--verbose` flag causes all logging and debugging output to appear on the terminal window or command prompt. The output also goes into the server log, which is located in *domain-dir*`/logs/server.log`.

Or, on Windows, from the Start menu, choose All Programs, then choose Java EE 6 SDK, then choose Start Application Server.

After the server has completed its startup sequence, you will see the following output:

```
Domain domain1 started.
```

To stop the GlassFish Server, open a terminal window or command prompt and execute:

```
asadmin stop-domain domain1
```

Or, on Windows, from the Start menu, choose All Programs, then choose Java EE 6 SDK, then choose Stop Application Server.

When the server has stopped, you will see the following output:

```
Domain domain1 stopped.
```

Starting the Administration Console

To administer the GlassFish Server and manage users, resources, and Java EE applications, use the Administration Console tool. The GlassFish Server must be running before you invoke the Administration Console. To start the Administration Console, open a browser at `http://localhost:4848/`.

Or, on Windows, from the Start menu, choose All Programs, then choose Java EE 6 SDK, then choose Administration Console.

▼ To Start the Administration Console in NetBeans IDE

1. **Click the Services tab.**
2. **Expand the Servers node.**
3. **Right-click the GlassFish Server instance and select View Admin Console.**

Note – NetBeans IDE uses your default web browser to open the Administration Console.

Starting and Stopping the Java DB Server

The GlassFish Server includes the Java DB database server.

To start the Java DB server, open a terminal window or command prompt and execute:

```
asadmin start-database
```

To stop the Java DB server, open a terminal window or command prompt and execute:

```
asadmin stop-database
```

For information about the Java DB included with the GlassFish Server, see `http://www.oracle.com/technetwork/java/javadb/overview/index.html`.

▼ To Start the Database Server Using NetBeans IDE

1. **Click the Services tab.**
2. **Expand the Databases node.**
3. **Right-click Java DB and choose Start Server.**

Next Steps To stop the database using NetBeans IDE, right-click Java DB and choose Stop Server.

Building the Examples

The tutorial examples are distributed with a configuration file for either NetBeans IDE or Ant. Directions for building the examples are provided in each chapter. Either NetBeans IDE or Ant may be used to build, package, deploy, and run the examples.

Tutorial Example Directory Structure

To facilitate iterative development and keep application source separate from compiled files, the tutorial examples use the Java BluePrints application directory structure.

Each application module has the following structure:

- `build.xml`: Ant build file
- `src/java`: Java source files for the module
- `src/conf`: configuration files for the module, with the exception of web applications
- `web`: web pages, style sheets, tag files, and images (web applications only)
- `web/WEB-INF`: configuration files for web applications (web applications only)
- `nbproject`: NetBeans project files

Examples that have multiple application modules packaged into an EAR file have submodule directories that use the following naming conventions:

- *example-name*`-app-client`: application clients
- *example-name*`-ejb`: enterprise bean JAR files
- *example-name*`-war`: web applications

The Ant build files (`build.xml`) distributed with the examples contain targets to create a `build` subdirectory and to copy and compile files into that directory; a `dist` subdirectory, which holds the packaged module file; and a `client-jar` directory, which holds the retrieved application client JAR.

The directory *tut-install*`/examples/bp-project` contains additional Ant targets called by the `build.xml` file targets.

Some Ant targets for web examples will open the example URL in a browser if one is available. This happens automatically on Windows systems. If you are running on a UNIX system, you may want to modify a line in the *tut-install*`/examples/bp-project/build.properties` file. Remove the comment character from the line specifying the `default.browser` property and specify the path to the command that invokes a browser. If you do not make the change, you can open the URL in the browser yourself.

Getting the Latest Updates to the Tutorial

Check for any updates to the tutorial by using the Update Center included with the Java EE 6 SDK.

▼ To Update the Tutorial Through the Update Center

1. **Open the Services tab in NetBeans IDE and expand Servers.**
2. **Right-click the GlassFish Server 3 instance and select View Update Center to display the Update Tool.**
3. **Select Available Updates in the tree to display a list of updated packages.**
4. **Look for updates to the Java EE 6 Tutorial (javaee-tutorial) package.**
5. **If there is an updated version of the Tutorial, select Java EE 6 Tutorial (javaee-tutorial) and click Install.**

Debugging Java EE Applications

This section explains how to determine what is causing an error in your application deployment or execution.

Using the Server Log

One way to debug applications is to look at the server log in *domain-dir*`/logs/server.log`. The log contains output from the GlassFish Server and your applications. You can log messages from any Java class in your application with `System.out.println` and the Java Logging APIs (documented at `http://download.oracle.com/javase/6/docs/technotes/guides/logging/index.html`) and from web components with the `ServletContext.log` method.

If you start the GlassFish Server with the `--verbose` flag, all logging and debugging output will appear on the terminal window or command prompt and the server log. If you start the GlassFish Server in the background, debugging information is available only in the log. You can view the server log with a text editor or with the Administration Console log viewer.

▼ To Use the Log Viewer

1. **Select the GlassFish Server node.**
2. **Click the View Log Files button.**
   The log viewer opens and displays the last 40 entries.
3. **To display other entries, follow these steps.**
   a. **Click the Modify Search button.**
   b. **Specify any constraints on the entries you want to see.**
   c. **Click the Search button at the top of the log viewer.**

Using a Debugger

The GlassFish Server supports the Java Platform Debugger Architecture (JPDA). With JPDA, you can configure the GlassFish Server to communicate debugging information using a socket.

▼ To Debug an Application Using a Debugger

1. **Enable debugging in the GlassFish Server using the Administration Console:**
   a. **Expand the Configurations node, then expand the server-config node.**
   b. **Select the JVM Settings node. The default debug options are set to:**
      ```
      -Xdebug -Xrunjdwp:transport=dt_socket,server=y,suspend=n,address=9009
      ```
      As you can see, the default debugger socket port is 9009. You can change it to a port not in use by the GlassFish Server or another service.
   c. **Select the Debug Enabled check box.**
   d. **Click the Save button.**
2. **Stop the GlassFish Server and then restart it.**

PART II

The Web Tier

Part II explores the technologies in the web tier. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 3

Getting Started with Web Applications

A *web application* is a dynamic extension of a web or application server. Web applications are of the following types:

- **Presentation-oriented**: A presentation-oriented web application generates interactive web pages containing various types of markup language (HTML, XHTML, XML, and so on) and dynamic content in response to requests. Development of presentation-oriented web applications is covered in Chapter 4, "JavaServer Faces Technology," through Chapter 9, "Developing with JavaServer Faces Technology."
- **Service-oriented**: A service-oriented web application implements the endpoint of a web service. Presentation-oriented applications are often clients of service-oriented web applications. Development of service-oriented web applications is covered in Chapter 18, "Building Web Services with JAX-WS," and Chapter 19, "Building RESTful Web Services with JAX-RS," in Part III, "Web Services."

The following topics are addressed here:

Web Applications

In the Java EE platform, *web components* provide the dynamic extension capabilities for a web server. Web components can be Java servlets, web pages implemented with JavaServer Faces technology, web service endpoints, or JSP pages. Figure 3–1 illustrates the interaction between a web client and a web application that uses a servlet. The client sends an HTTP request to the web server. A web server that implements Java Servlet and JavaServer Pages technology converts the request into an `HTTPServletRequest` object. This object is delivered to a web component, which can interact with JavaBeans components or a database to generate dynamic

content. The web component can then generate an `HTTPServletResponse` or can pass the request to another web component. A web component eventually generates a `HTTPServletResponse` object. The web server converts this object to an HTTP response and returns it to the client.

FIGURE 3–1 Java Web Application Request Handling



Servlets are Java programming language classes that dynamically process requests and construct responses. Java technologies, such as JavaServer Faces and Facelets, are used for building interactive web applications. (Frameworks can also be used for this purpose.) Although servlets and Java Server Faces and Facelets pages can be used to accomplish similar things, each has its own strengths. Servlets are best suited for service-oriented applications (web service endpoints can be implemented as servlets) and the control functions of a presentation-oriented application, such as dispatching requests and handling nontextual data. Java Server Faces and Facelets pages are more appropriate for generating text-based markup, such as XHTML, and are generally used for presentation–oriented applications.

Web components are supported by the services of a runtime platform called a *web container*. A web container provides such services as request dispatching, security, concurrency, and lifecycle management. A web container also gives web components access to such APIs as naming, transactions, and email.

Certain aspects of web application behavior can be configured when the application is installed, or *deployed*, to the web container. The configuration information can be specified using Java EE annotations or can be maintained in a text file in XML format called a *web application deployment descriptor* (DD). A web application DD must conform to the schema described in the Java Servlet specification.

This chapter gives a brief overview of the activities involved in developing web applications. First, it summarizes the web application lifecycle and explains how to package and deploy very simple web applications on the GlassFish Server. The chapter moves on to configuring web applications and discusses how to specify the most commonly used configuration parameters.

Web Application Lifecycle

A web application consists of web components; static resource files, such as images; and helper classes and libraries. The web container provides many supporting services that enhance the capabilities of web components and make them easier to develop. However, because a web application must take these services into account, the process for creating and running a web application is different from that of traditional stand-alone Java classes.

The process for creating, deploying, and executing a web application can be summarized as follows:

1. Develop the web component code.
2. Develop the web application deployment descriptor, if necessary.
3. Compile the web application components and helper classes referenced by the components.
4. Optionally, package the application into a deployable unit.
5. Deploy the application into a web container.
6. Access a URL that references the web application.

Developing web component code is covered in the later chapters. Steps 2 through 4 are expanded on in the following sections and illustrated with a Hello, World-style presentation-oriented application. This application allows a user to enter a name into an HTML form (Figure 3–2) and then displays a greeting after the name is submitted (Figure 3–3).

FIGURE 3–2 Greeting Form for `hello1` Web Application



FIGURE 3–3 Response Page for `hello1` Web Application



The Hello application contains two web components that generate the greeting and the response. This chapter discusses the following simple applications:

- `hello1`, a JavaServer Faces technology-based application that uses two XHTML pages and a backing bean
- `hello2`, a servlet-based web application in which the components are implemented by two servlet classes

The applications are used to illustrate tasks involved in packaging, deploying, configuring, and running an application that contains web components. The source code for the examples is in the *tut-install*/examples/web/hello1/ and *tut-install*/examples/web/hello2/ directories.

Web Modules: The hello1 Example

In the Java EE architecture, web components and static web content files, such as images, are called *web resources*. A *web module* is the smallest deployable and usable unit of web resources. A Java EE web module corresponds to a web application as defined in the Java Servlet specification.

In addition to web components and web resources, a web module can contain other files:

- Server-side utility classes, such as shopping carts
- Client-side classes, such as applets and utility classes

A web module has a specific structure. The top-level directory of a web module is the *document root* of the application. The document root is where XHTML pages, client-side classes and archives, and static web resources, such as images, are stored.

The document root contains a subdirectory named WEB-INF, which can contain the following files and directories:

- classes: A directory that contains server-side classes: servlets, enterprise bean class files, utility classes, and JavaBeans components
- tags: A directory that contains tag files, which are implementations of tag libraries
- lib: A directory that contains JAR files that contain enterprise beans, and JAR archives of libraries called by server-side classes
- Deployment descriptors, such as web.xml (the web application deployment descriptor) and ejb-jar.xml (an EJB deployment descriptor)

A web module needs a web.xml file if it uses JavaServer Faces technology, if it must specify certain kinds of security information, or if you want to override information specified by web component annotations.

You can also create application-specific subdirectories (that is, package directories) in either the document root or the WEB-INF/classes/ directory.

A web module can be deployed as an unpacked file structure or can be packaged in a JAR file known as a Web Archive (WAR) file. Because the contents and use of WAR files differ from those of JAR files, WAR file names use a .war extension. The web module just described is portable; you can deploy it into any web container that conforms to the Java Servlet specification.

To deploy a WAR on the GlassFish Server, the file must contain a runtime deployment descriptor. The runtime DD is an XML file that contains such information as the context root of

the web application and the mapping of the portable names of an application's resources to the GlassFish Server's resources. The GlassFish Server web application runtime DD is named `glassfish-web.xml` and is located in the `WEB-INF` directory. The structure of a web module that can be deployed on the GlassFish Server is shown in Figure 3–4.

For example, the `glassfish-web.xml` file for the `hello1` application specifies the following context root:

```
<context-root>/hello1</context-root>
```

FIGURE 3–4 Web Module Structure



Examining the `hello1` Web Module

The `hello1` application is a web module that uses JavaServer Faces technology to display a greeting and response. You can use a text editor to view the application files, or you can use NetBeans IDE.

▼ To View the `hello1` Web Module Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/web/`

3 Select the `hello1` folder.

4 Select the Open as Main Project check box.

5 Expand the Web Pages node and double-click the `index.xhtml` file to view it in the right-hand pane.

The `index.html` file is the default landing page for a Facelets application. For this application, the page uses simple tag markup to display a form with a graphic image, a header, a text field, and two command buttons:

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head>
        <title>Facelets Hello Greeting</title>
    </h:head>
    <h:body>
        <h:form>
            <h:graphicImage url="duke.waving.gif"/>
            <h2>Hello, my name is Duke. What's yours?</h2>
            <h:inputText id="username"
                         value="#{hello.name}"
                         required="true"
                         requiredMessage="A name is required."
                         maxlength="25">
            </h:inputText>
            <p></p>
            <h:commandButton id="submit" value="Submit" action="response">
            </h:commandButton>
            <h:commandButton id="reset" value="Reset" type="reset">
            </h:commandButton>
        </h:form>
    </h:body>
</html>
```

The most complex element on the page is the `inputText` text field. The `maxlength` attribute specifies the maximum length of the field. The `required` attribute specifies that the field must be filled out; the `requiredMessage` attribute provides the error message to be displayed if the field is left empty. Finally, the `value` attribute contains an expression that will be provided by the `Hello` backing bean.

The Submit `commandButton` element specifies the action as `response`, meaning that when the button is clicked, the `response.xhtml` page is displayed.

6 Double-click the `response.xhtml` file to view it.

The response page appears. Even simpler than the greeting page, the response page contains a graphic image, a header that displays the expression provided by the backing bean, and a single button whose `action` element transfers you back to the `index.xhtml` page:

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
```

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head>
        <title>Facelets Hello Response</title>
    </h:head>
    <h:body>
        <h:form>
            <h:graphicImage url="duke.waving.gif"/>
            <h2>Hello, #{hello.name}!</h2>
            <p></p>
            <h:commandButton id="back" value="Back" action="index" />
        </h:form>
    </h:body>
</html>
```

7 Expand the Source Packages node, then the `hello1` node.

8 Double-click the `Hello.java` file to view it.

The `Hello` class, called a backing bean class, provides getter and setter methods for the `name` property used in the Facelets page expressions. By default, the expression language refers to the class name, with the first letter in lowercase (`hello.name`).

```
package hello1;

import javax.faces.bean.ManagedBean;
import javax.faces.bean.RequestScoped;

@ManagedBean
@RequestScoped
public class Hello {

    private String name;

    public Hello() {
    }

    public String getName() {
        return name;
    }

    public void setName(String user_name) {
        this.name = user_name;
    }
}
```

9 Under the Web Pages node, expand the `WEB-INF` node and double-click the `web.xml` file to view it.

The `web.xml` file contains several elements that are required for a Facelets application. All these are created automatically when you use NetBeans IDE to create an application:

- A context parameter specifying the project stage:

```
<context-param>
    <param-name>javax.faces.PROJECT_STAGE</param-name>
    <param-value>Development</param-value>
</context-param>
```

A context parameter provides configuration information needed by a web application. An application can define its own context parameters. In addition, JavaServer Faces technology and Java Servlet technology define context parameters that an application can use.

- A `servlet` element and its `servlet-mapping` element specifying the `FacesServlet`:

```
<servlet>
    <servlet-name>Faces Servlet</servlet-name>
    <servlet-class>javax.faces.webapp.FacesServlet</servlet-class>
    <load-on-startup>1</load-on-startup>
</servlet>
<servlet-mapping>
    <servlet-name>Faces Servlet</servlet-name>
    <url-pattern>/faces/*</url-pattern>
</servlet-mapping>
```

- A `welcome-file-list` element specifying the location of the landing page; note that the location is `faces/index.xhtml`, not just `index.xhtml`:

```
<welcome-file-list>
    <welcome-file>faces/index.xhtml</welcome-file>
</welcome-file-list>
```

Packaging a Web Module

A web module must be packaged into a WAR in certain deployment scenarios and whenever you want to distribute the web module. You package a web module into a WAR by executing the `jar` command in a directory laid out in the format of a web module, by using the Ant utility, or by using the IDE tool of your choice. This tutorial shows you how to use NetBeans IDE or Ant to build, package, and deploy the `hello1` sample application.

▼ To Set the Context Root

A *context root* identifies a web application in a Java EE server. A context root must start with a forward slash (`/`) and end with a string.

In a packaged web module for deployment on the GlassFish Server, the context root is stored in `glassfish-web.xml`.

To view or edit the context root, follow these steps.

1. **Expand the Web Pages and WEB-INF nodes of the `hello1` project.**
2. **Double-click `glassfish-web.xml`.**
3. **In the General tab, observe that the Context Root field is set to `/hello1`.**

   If you needed to edit this value, you could do so here. When you create a new application, you type the context root here.

4. **(Optional) Click the XML tab.**

   Observe that the context root value `/hello1` is enclosed by the `context-root` element. You could also edit the value here.

▼ To Build and Package the `hello1` Web Module Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/web/`
3. **Select the `hello1` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `hello1` project and select Build.**

▼ To Build and Package the `hello1` Web Module Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/web/hello1/`
2. **Type the following command:**

   `ant`

   This command spawns any necessary compilations, copies files to the directory *tut-install*`/examples/web/hello1/build/`, creates the WAR file, and copies it to the directory *tut-install*`/examples/web/hello1/dist/`.

Deploying a Web Module

You can deploy a WAR file to the GlassFish Server by

- Using NetBeans IDE
- Using the Ant utility
- Using the `asadmin` command
- Using the Administration Console
- Copying the WAR file into the *domain-dir*`/autodeploy/` directory

Throughout the tutorial, you will use NetBeans IDE or Ant for packaging and deploying.

▼ To Deploy the hello1 Web Module Using NetBeans IDE

- **Right-click the hello1 project and select Deploy.**

▼ To Deploy the hello1 Web Module Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/web/hello1/
2. **Type the following command:**
   ```
   ant deploy
   ```

Running a Deployed Web Module

Now that the web module is deployed, you can view it by opening the application in a web browser. By default, the application is deployed to host localhost on port 8080. The context root of the web application is hello1.

▼ To Run a Deployed Web Module

1. **Open a web browser.**
2. **Type the following URL:**
   ```
   http://localhost:8080/hello1/
   ```
3. **Type your name and click Submit.**
   The response page displays the name you submitted. Click the Back button to try again.

Listing Deployed Web Modules

The GlassFish Server provides two ways to view the deployed web modules: the Administration Console and the asadmin command.

▼ To List Deployed Web Modules Using the Administration Console

1. **Open the URL http://localhost:4848/ in a browser.**
2. **Select the Applications node.**
   The deployed web modules appear in the Deployed Applications table.

▼ To List Deployed Web Modules Using the asadmin Command

- **Type the following command:**

```
asadmin list-applications
```

Updating a Web Module

A typical iterative development cycle involves deploying a web module and then making changes to the application components. To update a deployed web module, follow these steps.

▼ To Update a Deployed Web Module

1. **Recompile any modified classes.**
2. **Redeploy the module.**
3. **Reload the URL in the client.**

Dynamic Reloading

If dynamic reloading is enabled, you do not have to redeploy an application or module when you change its code or deployment descriptors. All you have to do is copy the changed pages or class files into the deployment directory for the application or module. The deployment directory for a web module named *context-root* is *domain-dir*/applications/*context-root*. The server checks for changes periodically and redeploys the application, automatically and dynamically, with the changes.

This capability is useful in a development environment because it allows code changes to be tested quickly. Dynamic reloading is not recommended for a production environment, however, because it may degrade performance. In addition, whenever a reload is done, the sessions at that time become invalid, and the client must restart the session.

In the GlassFish Server, dynamic reloading is enabled by default.

▼ To Disable or Modify Dynamic Reloading

If for some reason you do not want the default dynamic reloading behavior, follow these steps in the Administration Console.

1. **Open the URL http://localhost:4848/ in a browser.**
2. **Select the GlassFish Server node.**

3. **Select the Advanced tab.**
4. **To disable dynamic reloading, deselect the Reload Enabled check box.**
5. **To change the interval at which applications and modules are checked for code changes and dynamically reloaded, type a number of seconds in the Reload Poll Interval field.**
   The default value is 2 seconds.
6. **Click the Save button.**

Undeploying Web Modules

You can undeploy web modules and other types of enterprise applications by using either NetBeans IDE or the Ant tool.

▼ To Undeploy the hello1 Web Module Using NetBeans IDE

1. **Ensure that the GlassFish Server is running.**
2. **In the Services window, expand the Servers node, GlassFish Server instance, and the Applications node.**
3. **Right-click the hello1 module and choose Undeploy.**
4. **To delete the class files and other build artifacts, right-click the project and choose Clean.**

▼ To Undeploy the hello1 Web Module Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/web/hello1/
2. **Type the following command:**
   ```
   ant undeploy
   ```
3. **To delete the class files and other build artifacts, type the following command:**
   ```
   ant clean
   ```

Configuring Web Applications: The hello2 Example

Web applications are configured by means of annotations or by elements contained in the web application deployment descriptor.

The following sections give a brief introduction to the web application features you will usually want to configure. Examples demonstrate procedures for configuring the Hello, World application.

Mapping URLs to Web Components

When it receives a request, the web container must determine which web component should handle the request. The web container does so by mapping the URL path contained in the request to a web application and a web component. A URL path contains the context root and, optionally, a URL pattern:

`http://`*host*`:`*port*`/`*context-root*`[/`*url-pattern*`]`

You set the URL pattern for a servlet by using the `@WebServlet` annotation in the servlet source file. For example, the `GreetingServlet.java` file in the `hello2` application contains the following annotation, specifying the URL pattern as `/greeting`:

```
@WebServlet("/greeting")
public class GreetingServlet extends HttpServlet {
    ...
```

This annotation indicates that the URL pattern `/greeting` follows the context root. Therefore, when the servlet is deployed locally, it is accessed with the following URL:

```
http://localhost:8080/hello2/greeting
```

To access the servlet by using only the context root, specify `"/"` as the URL pattern.

Examining the hello2 Web Module

The `hello2` application behaves almost identically to the `hello1` application, but it is implemented using Java Servlet technology instead of JavaServer Faces technology. You can use a text editor to view the application files, or you can use NetBeans IDE.

▼ To View the hello2 Web Module Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/web/`

3. **Select the `hello2` folder.**

4. **Select the Open as Main Project check box.**

5. **Expand the Source Packages node, then the `servlets` node.**

6. **Double-click the `GreetingServlet.java` file to view it.**

   This servlet overrides the `doGet` method, implementing the `GET` method of HTTP. The servlet displays a simple HTML greeting form whose Submit button, like that of `hello1`, specifies a response page for its action. The following excerpt begins with the `@WebServlet` annotation that specifies the URL pattern, relative to the context root:

```
@WebServlet("/greeting")
public class GreetingServlet extends HttpServlet {

    @Override
    public void doGet(HttpServletRequest request,
            HttpServletResponse response)
            throws ServletException, IOException {

        response.setContentType("text/html");
        response.setBufferSize(8192);
        PrintWriter out = response.getWriter();

        // then write the data of the response
        out.println("<html>"
                + "<head><title>Servlet Hello</title></head>");

        // then write the data of the response
        out.println("<body  bgcolor=\"#ffffff\">"
                + "<img src=\"duke.waving.gif\" alt=\"Duke waving\">"
                + "<h2>Hello, my name is Duke. What's yours?</h2>"
                + "<form method=\"get\">"
                + "<input type=\"text\" name=\"username\" size=\"25\">"
                + "<p></p>"
                + "<input type=\"submit\" value=\"Submit\">"
                + "<input type=\"reset\" value=\"Reset\">"
                + "</form>");

        String username = request.getParameter("username");
        if (username != null && username.length() > 0) {
            RequestDispatcher dispatcher =
                    getServletContext().getRequestDispatcher("/response");

            if (dispatcher != null) {
                dispatcher.include(request, response);
            }
        }
        out.println("</body></html>");
        out.close();
    }
    ...
```

7. **Double-click the `ResponseServlet.java` file to view it.**

   This servlet also overrides the `doGet` method, displaying only the response. The following excerpt begins with the `@WebServlet` annotation, which specifies the URL pattern, relative to the context root:

```
@WebServlet("/response")
public class ResponseServlet extends HttpServlet {

    @Override
    public void doGet(HttpServletRequest request,
            HttpServletResponse response)
            throws ServletException, IOException {
        PrintWriter out = response.getWriter();

        // then write the data of the response
        String username = request.getParameter("username");
        if (username != null && username.length() > 0) {
            out.println("<h2>Hello, " + username + "!</h2>");
        }
    }
    ...
```

8. **Under the Web Pages node, expand the `WEB-INF` node and double-click the `glassfish-web.xml` file to view it.**

   In the General tab, observe that the Context Root field is set to `/hello2`.

   For this simple servlet application, a `web.xml` file is not required.

Building, Packaging, Deploying, and Running the `hello2` Example

You can use either NetBeans IDE or Ant to build, package, deploy, and run the `hello2` example.

▼ To Build, Package, Deploy, and Run the `hello2` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/web/`
3. **Select the `hello2` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**

6. **In the Projects tab, right-click the `hello2` project and select Build.**

7. **Right-click the project and select Deploy.**

8. **In a web browser, open the URL `http://localhost:8080/hello2/greeting`.**

   The URL specifies the context root, followed by the URL pattern.

   The application looks much like the `hello1` application shown in Figure 3–2. The major difference is that after you click the Submit button, the response appears below the greeting, not on a separate page.

▼ To Build, Package, Deploy, and Run the `hello2` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/web/hello2/`

2. **Type the following command:**

   ```
   ant
   ```

   This target builds the WAR file and copies it to the *tut-install*`/examples/web/hello2/dist/` directory.

3. **Type `ant deploy`.**

   Ignore the URL shown in the deploy target output.

4. **In a web browser, open the URL `http://localhost:8080/hello2/greeting`.**

   The URL specifies the context root, followed by the URL pattern.

   The application looks much like the `hello1` application shown in Figure 3–2. The major difference is that after you click the Submit button, the response appears below the greeting, not on a separate page.

Declaring Welcome Files

The *welcome files* mechanism allows you to specify a list of files that the web container will use for appending to a request for a URL (called a valid partial request) that is not mapped to a web component. For example, suppose that you define a welcome file `welcome.html`. When a client requests a URL such as *host*`:`*port*`/`*webapp*`/`*directory*, where *directory* is not mapped to a servlet or XHTML page, the file *host*`:`*port*`/`*webapp*`/`*directory*`/welcome.html` is returned to the client.

If a web container receives a valid partial request, the web container examines the welcome file list and appends to the partial request each welcome file in the order specified and checks whether a static resource or servlet in the WAR is mapped to that request URL. The web container then sends the request to the first resource that matches in the WAR.

If no welcome file is specified, the GlassFish Server will use a file named `index.html` as the default welcome file. If there is no welcome file and no file named `index.html`, the GlassFish Server returns a directory listing.

By convention, you specify the welcome file for a JavaServer Faces application as `faces/`*file-name*`.xhtml`.

Setting Context and Initialization Parameters

The web components in a web module share an object that represents their application context. You can pass initialization parameters to the context or to a web component.

▼ To Add a Context Parameter Using NetBeans IDE

These steps apply generally to web applications, but do not apply specifically to the examples in this chapter.

1. **Open the project.**
2. **Expand the project's node in the Projects pane.**
3. **Expand the Web Pages node and then the WEB-INF node.**
4. **Double-click `web.xml`.**

   If the project does not have a `web.xml` file, follow the steps in "To Create a `web.xml` File Using NetBeans IDE" on page 96.
5. **Click General at the top of the editor pane.**
6. **Expand the Context Parameters node.**
7. **Click Add.**

   An Add Context Parameter dialog opens.
8. **In the Parameter Name field, type the name that specifies the context object.**
9. **In the Parameter Value field, type the parameter to pass to the context object.**
10. **Click OK.**

▼ To Create a `web.xml` File Using NetBeans IDE

1. **From the File menu, choose New File.**

2. **In the New File wizard, select the Web category, then select Standard Deployment Descriptor under File Types.**
3. **Click Next.**
4. **Click Finish.**

   An empty `web.xml` file appears in `web/WEB-INF/`.

To Add an Initialization Parameter Using NetBeans IDE

You can use the `@WebServlet` annotation to specify web component initialization parameters by using the `initParams` attribute and the `@WebInitParam` annotation. For example:

```
@WebServlet(urlPatterns="/MyPattern", initParams=
  {@WebInitParam(name="ccc", value="333")})
```

Alternatively, you can add an initialization parameter to the `web.xml` file. To do this using NetBeans IDE, follow these steps.

These steps apply generally to web applications, but do not apply specifically to the examples in this chapter.

1. **Open the project.**
2. **Expand the project's node in the Projects pane.**
3. **Expand the Web Pages node and then the WEB-INF node.**
4. **Double-click `web.xml`.**

   If the project does not have a `web.xml` file, follow the steps in "To Create a `web.xml` File Using NetBeans IDE" on page 96.
5. **Click Servlets at the top of the editor pane.**
6. **Click the Add button under the Initialization Parameters table.**

   An Add Initialization Parameter dialog opens.
7. **In the Parameter Name field, type the name of the parameter.**
8. **In the Parameter Value Field, type the parameter's value.**
9. **Click OK.**

Mapping Errors to Error Screens

When an error occurs during execution of a web application, you can have the application display a specific error screen according to the type of error. In particular, you can specify a mapping between the status code returned in an HTTP response or a Java programming language exception returned by any web component and any type of error screen.

You can have multiple `error-page` elements in your deployment descriptor. Each element identifies a different error that causes an error page to open. This error page can be the same for any number of `error-page` elements.

▼ To Set Up Error Mapping Using NetBeans IDE

These steps apply generally to web applications, but do not apply specifically to the examples in this chapter.

1. **Open the project.**
2. **Expand the project's node in the Projects pane.**
3. **Expand the Web Pages node and then the WEB-INF node.**
4. **Double-click `web.xml`.**

   If the project does not have a `web.xml` file, follow the steps in "To Create a `web.xml` File Using NetBeans IDE" on page 96.
5. **Click Pages at the top of the editor pane.**
6. **Expand the Error Pages node.**
7. **Click Add.**

   The Add Error Page dialog opens.
8. **Click Browse to locate the page that you want to act as the error page.**
9. **In the Error Code field, type the HTTP status code that will cause the error page to be opened, or leave the field blank to include all error codes.**
10. **In the Exception Type field, type the exception that will cause the error page to load.**

    To specify all exceptions, type `java.lang.Throwable`.
11. **Click OK.**

Declaring Resource References

If your web component uses such objects as enterprise beans, data sources, or web services, you use Java EE annotations to inject these resources into your application. Annotations eliminate a lot of the boilerplate lookup code and configuration elements that previous versions of Java EE required.

Although resource injection using annotations can be more convenient for the developer, there are some restrictions on using it in web applications. First, you can inject resources only into container-managed objects, since a container must have control over the creation of a component so that it can perform the injection into a component. As a result, you cannot inject resources into such objects as simple JavaBeans components. However, JavaServer Faces managed beans are managed by the container; therefore, they can accept resource injections.

Components that can accept resource injections are listed in Table 3–1.

This section explains how to use a couple of the annotations supported by a servlet container to inject resources. Chapter 33, "Running the Persistence Examples," explains how web applications use annotations supported by the Java Persistence API. Chapter 40, "Getting Started Securing Web Applications," explains how to use annotations to specify information about securing web applications.

TABLE 3–1 Web Components That Accept Resource Injections

Component	Interface/Class
Servlets	`javax.servlet.Servlet`
Servlet filters	`javax.servlet.ServletFilter`
Event listeners	`javax.servlet.ServletContextListener`
	`javax.servlet.ServletContextAttributeListener`
	`javax.servlet.ServletRequestListener`
	`javax.servlet.ServletRequestAttributeListener`
	`javax.servlet.http.HttpSessionListener`
	`javax.servlet.http.HttpSessionAttributeListener`
	`javax.servlet.http.HttpSessionBindingListener`
Taglib listeners	Same as above
Taglib tag handlers	`javax.servlet.jsp.tagext.JspTag`
Managed beans	Plain Old Java Objects

Declaring a Reference to a Resource

The @Resource annotation is used to declare a reference to a resource, such as a data source, an enterprise bean, or an environment entry.

The @Resource annotation is specified on a class, a method, or a field. The container is responsible for injecting references to resources declared by the @Resource annotation and mapping it to the proper JNDI resources.

In the following example, the @Resource annotation is used to inject a data source into a component that needs to make a connection to the data source, as is done when using JDBC technology to access a relational database:

```
@Resource javax.sql.DataSource catalogDS;
public getProductsByCategory() {
    // get a connection and execute the query
    Connection conn = catalogDS.getConnection();
    ..
}
```

The container injects this data source prior to the component's being made available to the application. The data source JNDI mapping is inferred from the field name catalogDS and the type, javax.sql.DataSource.

If you have multiple resources that you need to inject into one component, you need to use the @Resources annotation to contain them, as shown by the following example:

```
@Resources ({
    @Resource (name="myDB" type=java.sql.DataSource),
    @Resource(name="myMQ" type=javax.jms.ConnectionFactory)
})
```

The web application examples in this tutorial use the Java Persistence API to access relational databases. This API does not require you to explicitly create a connection to a data source. Therefore, the examples do not use the @Resource annotation to inject a data source. However, this API supports the @PersistenceUnit and @PersistenceContext annotations for injecting EntityManagerFactory and EntityManager instances, respectively. Chapter 33, "Running the Persistence Examples," describes these annotations and the use of the Java Persistence API in web applications.

Declaring a Reference to a Web Service

The @WebServiceRef annotation provides a reference to a web service. The following example shows uses the @WebServiceRef annotation to declare a reference to a web service. WebServiceRef uses the wsdlLocation element to specify the URI of the deployed service's WSDL file:

```
...
import javax.xml.ws.WebServiceRef;
...
```

```
public class ResponseServlet extends HTTPServlet {
@WebServiceRef(wsdlLocation=
    "http://localhost:8080/helloservice/hello?wsdl")
static HelloService service;
```

Further Information about Web Applications

For more information on web applications, see

- JavaServer Faces 2.0 specification:

  `http://jcp.org/en/jsr/detail?id=314`
- JavaServer Faces technology web site:

  `http://www.oracle.com/technetwork/java/javaee/javaserverfaces-139869.html`
- Java Servlet 3.0 specification:

  `http://jcp.org/en/jsr/detail?id=315`
- Java Servlet web site:

  `http://www.oracle.com/technetwork/java/index-jsp-135475.html`

◆ ◆ ◆ CHAPTER 4

JavaServer Faces Technology

JavaServer Faces technology is a server-side component framework for building Java technology-based web applications.

JavaServer Faces technology consists of the following:

- An API for representing components and managing their state; handling events, server-side validation, and data conversion; defining page navigation; supporting internationalization and accessibility; and providing extensibility for all these features
- Tag libraries for adding components to web pages and for connecting components to server-side objects

JavaServer Faces technology provides a well-defined programming model and various tag libraries. These features significantly ease the burden of building and maintaining web applications with server-side user interfaces (UIs). With minimal effort, you can complete the following tasks.

- Create a web page.
- Drop components onto a web page by adding component tags.
- Bind components on a page to server-side data.
- Wire component-generated events to server-side application code.
- Save and restore application state beyond the life of server requests.
- Reuse and extend components through customization.

This chapter provides an overview of JavaServer Faces technology. After explaining what a JavaServer Faces application is and reviewing some of the primary benefits of using JavaServer Faces technology, this chapter describes the process of creating a simple JavaServer Faces application. This chapter also introduces the JavaServer Faces lifecycle by describing the example JavaServer Faces application progressing through the lifecycle stages.

The following topics are addressed here:

- "Creating a Simple JavaServer Faces Application" on page 106
- "Further Information about JavaServer Faces Technology" on page 110

What Is a JavaServer Faces Application?

The functionality provided by a JavaServer Faces application is similar to that of any other Java web application. A typical JavaServer Faces application includes the following parts:

- A set of web pages in which components are laid out
- A set of tags to add components to the web page
- A set of *backing beans*, which are JavaBeans components that define properties and functions for components on a page
- A web deployment descriptor (`web.xml` file)
- Optionally, one or more application configuration resource files, such as a `faces-config.xml` file, which can be used to define page navigation rules and configure beans and other custom objects, such as custom components
- Optionally, a set of custom objects, which can include custom components, validators, converters, or listeners, created by the application developer
- A set of custom tags for representing custom objects on the page

Figure 4–1 shows the interaction between client and server in a typical JavaServer Faces application. In response to a client request, a web page is rendered by the web container that implements JavaServer Faces technology.

FIGURE 4–1 Responding to a Client Request for a JavaServer Faces Page



The web page, `myfacelet.xhtml`, is built using JavaServer Faces component tags. Component tags are used to add components to the `view` (represented by `myUI` in the diagram), which is the server-side representation of the page. In addition to components, the web page can also reference objects, such as the following:

- Any event listeners, validators, and converters that are registered on the components
- The JavaBeans components that capture the data and process the application-specific functionality of the components

On request from the client, the view is rendered as a response. Rendering is the process whereby, based on the server-side view, the web container generates output, such as HTML or XHTML, that can be read by the client, such as a browser.

JavaServer Faces Technology Benefits

One of the greatest advantages of JavaServer Faces technology is that it offers a clean separation between behavior and presentation for web applications. A JavaServer Faces application can map HTTP requests to component-specific event handling and manage components as stateful objects on the server. JavaServer Faces technology allows you to build web applications that implement the finer-grained separation of behavior and presentation that is traditionally offered by client-side UI architectures.

The separation of logic from presentation also allows each member of a web application development team to focus on a single piece of the development process and provides a simple programming model to link the pieces. For example, page authors with no programming expertise can use JavaServer Faces technology tags in a web page to link to server-side objects without writing any scripts.

Another important goal of JavaServer Faces technology is to leverage familiar component and web-tier concepts without limiting you to a particular scripting technology or markup language. JavaServer Faces technology APIs are layered directly on top of the Servlet API, as shown in Figure 4–2.

FIGURE 4–2 Java Web Application Technologies



This layering of APIs enables several important application use cases, such as using different presentation technologies, creating your own custom components directly from the component classes, and generating output for various client devices.

Facelets technology, available as part of JavaServer Faces 2.0, is now the preferred presentation technology for building JavaServer Faces technology-based web applications. For more information on Facelets technology features, see Chapter 5, "Introduction to Facelets."

Facelets technology offers several advantages.

- Code can be reused and extended for components through the templating and composite component features.
- When you use the JavaServer Faces Annotations feature, you can automatically register the backing bean as a resource available for JavaServer Faces applications. In addition, *implicit navigation* rules allow developers to quickly configure page navigation. These features reduce the manual configuration process for applications.
- Most important, JavaServer Faces technology provides a rich architecture for managing component state, processing component data, validating user input, and handling events.

Creating a Simple JavaServer Faces Application

JavaServer Faces technology provides an easy and user-friendly process for creating web applications. Developing a simple JavaServer Faces application typically requires the following tasks:

- Developing backing beans
- Adding managed bean declarations
- Creating web pages using component tags
- Mapping the `FacesServlet` instance

This section describes those tasks through the process of creating a simple JavaServer Faces Facelets application.

The example is a Hello application that includes a backing bean and a web page. When accessed by a client, the web page prints out a `Hello World` message. The example application is located in the directory *tut-install*`/examples/web/hello`. The tasks involved in developing this application can be examined by looking at the application components in detail.

Developing the Backing Bean

As mentioned earlier in this chapter, a backing bean, a type of managed bean, is a JavaBeans component that is managed by JavaServer Faces technology. Components in a page are associated with backing beans that provide application logic. The example backing bean, `Hello.java`, contains the following code:

```
package hello;

import javax.faces.bean.ManagedBean;

@ManagedBean
public class Hello {

    final String world = "Hello World!";

    public String getworld() {
        return world;
    }
}
```

The example backing bean sets the value of the variable `world` with the string "`Hello World!`". The `@ManagedBean` annotation registers the backing bean as a resource with the JavaServer Faces implementation. For more information on managed beans and annotations, see Chapter 9, "Developing with JavaServer Faces Technology."

Creating the Web Page

In a typical Facelets application, web pages are created in XHTML. The example web page, `beanhello.xhtml`, is a simple XHTML page. It has the following content:

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head>
        <title>Facelets Hello World</title>
    </h:head>
    <h:body>
        #{hello.world}
    </h:body>
</html>
```

A Facelets XHTML web page can also contain several other elements, which are covered later in this tutorial.

The web page connects to the backing bean through the Expression Language (EL) value expression `#{hello.world}`, which retrieves the value of the `world` property from the backing bean `Hello`. Note the use of `hello` to reference the backing bean `Hello`. If no name is specified in the `@ManagedBean` annotation, the backing bean is always accessed with the first letter of the class name in lowercase.

For more information on using EL expressions, see Chapter 6, "Expression Language." For more information about Facelets technology, see Chapter 5, "Introduction to Facelets." For more information about the JavaServer Faces programming model and building web pages using JavaServer Faces technology, see Chapter 7, "Using JavaServer Faces Technology in Web Pages."

Mapping the `FacesServlet` Instance

The final task requires mapping the `FacesServlet`, which is done through the web deployment descriptor (`web.xml`). A typical mapping of `FacesServlet` is as follows:

```
<servlet>
    <servlet-name>Faces Servlet</servlet-name>
    <servlet-class>javax.faces.webapp.FacesServlet</servlet-class>
    <load-on-startup>1</load-on-startup>
</servlet>
<servlet-mapping>
    <servlet-name>Faces Servlet</servlet-name>
    <url-pattern>/faces/*</url-pattern>
</servlet-mapping>
```

The preceding file segment represents part of a typical JavaServer Faces web deployment descriptor. The web deployment descriptor can also contain other content relevant to a JavaServer Faces application configuration, but that information is not covered here.

Mapping the `FacesServlet` is automatically done for you if you are using an IDE such as NetBeans IDE.

The Lifecycle of the `hello` Application

Every web application has a lifecycle. Common tasks, such as handling incoming requests, decoding parameters, modifying and saving state, and rendering web pages to the browser, are all performed during a web application lifecycle. Some web application frameworks hide the details of the lifecycle from you, whereas others require you to manage them manually.

By default, JavaServer Faces automatically handles most of the lifecycle actions for you. However, it also exposes the various stages of the request lifecycle, so that you can modify or perform different actions if your application requirements warrant it.

It is not necessary for the beginning user to understand the lifecycle of a JavaServer Faces application, but the information can be useful for creating more complex applications.

The lifecycle of a JavaServer Faces application starts and ends with the following activity: The client makes a request for the web page, and the server responds with the page. The lifecycle consists of two main phases: *execute* and *render*.

During the execute phase, several actions can take place:

- The application view is built or restored.
- The request parameter values are applied.
- Conversions and validations are performed for component values.
- Backing beans are updated with component values.
- Application logic is invoked.

For a first (initial) request, only the view is built. For subsequent (postback) requests, some or all of the other actions can take place.

In the render phase, the requested view is rendered as a response to the client. Rendering is typically the process of generating output, such as HTML or XHTML, that can be read by the client, usually a browser.

The following short description of the example JavaServer Faces application passing through its lifecycle summarizes the activity that takes place behind the scenes.

The `hello` example application goes through the following stages when it is deployed on the GlassFish Server.

1. When the `hello` application is built and deployed on the GlassFish Server, the application is in an uninitiated state.
2. When a client makes an initial request for the `beanhello.xhtml` web page, the `hello` Facelets application is compiled.
3. The compiled Facelets application is executed, and a new component tree is constructed for the `hello` application and is placed in a `FacesContext`.
4. The component tree is populated with the component and the backing bean property associated with it, represented by the EL expression `hello.world`.
5. A new view is built, based on the component tree.
6. The view is rendered to the requesting client as a response.
7. The component tree is destroyed automatically.
8. On subsequent (postback) requests, the component tree is rebuilt, and the saved state is applied.

For more detailed information on the JavaServer Faces lifecycle, see the JavaServer Faces Specification, Version 2.0.

▼ To Build, Package, Deploy, and Run the Application in NetBeans IDE

1 From the File menu, choose Open Project.

2 In the Open Project dialog box, navigate to:

tut-install`/examples/web`

3 Select the `hello` folder.

4 Select the Open as Main Project check box.

5 **Click Open Project.**

6 **In the Projects tab, right-click the `hello` project and select Run.**

This step compiles, assembles, and deploys the application and then brings up a web browser window displaying the following URL:

```
http://localhost:8080/hello
```

The output looks like this:

```
Hello World!
```

Further Information about JavaServer Faces Technology

For more information on JavaServer Faces technology, see

- JavaServer Faces 2.0 specification:

  `http://jcp.org/en/jsr/detail?id=314`
- JavaServer Faces technology web site:

  `http://www.oracle.com/technetwork/java/javaee/javaserverfaces-139869.html`
- JavaServer Faces 2.0 technology download web site:

  `http://www.oracle.com/technetwork/java/javaee/download-139288.html`
- Mojarra (JavaServer Faces 2.0) Release Notes:

  `http://javaserverfaces.java.net/nonav/rlnotes/2.0.0/index.html`

◆ ◆ ◆ CHAPTER 5

Introduction to Facelets

The term *Facelets* refers to the view declaration language for JavaServer Faces technology. JavaServer Pages (JSP) technology, previously used as the presentation technology for JavaServer Faces, does not support all the new features available in JavaServer Faces 2.0. JSP technology is considered to be a deprecated presentation technology for JavaServer Faces 2.0. Facelets is a part of the JavaServer Faces specification and also the preferred presentation technology for building JavaServer Faces technology-based applications.

The following topics are addressed here:

What Is Facelets?

Facelets is a powerful but lightweight page declaration language that is used to build JavaServer Faces views using HTML style templates and to build component trees. Facelets features include the following:

- Use of XHTML for creating web pages
- Support for Facelets tag libraries in addition to JavaServer Faces and JSTL tag libraries
- Support for the Expression Language (EL)
- Templating for components and pages

Advantages of Facelets for large-scale development projects include the following:

- Support for code reuse through templating and composite components
- Functional extensibility of components and other server-side objects through customization

- Faster compilation time
- Compile-time EL validation
- High-performance rendering

In short, the use of Facelets reduces the time and effort that needs to be spent on development and deployment.

Facelets views are usually created as XHTML pages. JavaServer Faces implementations support XHTML pages created in conformance with the XHTML Transitional Document Type Definition (DTD), as listed at `http://www.w3.org/TR/xhtml1/#a_dtd_XHTML-1.0-Transitional`. By convention, web pages built with XHTML have an `.xhtml` extension.

JavaServer Faces technology supports various tag libraries to add components to a web page. To support the JavaServer Faces tag library mechanism, Facelets uses XML namespace declarations. Table 5–1 lists the tag libraries supported by Facelets.

TABLE 5–1 Tag Libraries Supported by Facelets

Tag Library	URI	Prefix	Example	Contents
JavaServer Faces Facelets Tag Library	`http://java.sun.com/jsf/facelets`	`ui:`	`ui:component` `ui:insert`	Tags for templating

JavaServer Faces HTML Tag Library	`http://java.sun.com/jsf/html`	`h:`	`h:head`
			`h:body`
			`h:outputText`
			`h:inputText`
				JavaServer Faces component tags for all `UIComponents`

JavaServer Faces Core Tag Library	`http://java.sun.com/jsf/core`	`f:`	`f:actionListener` `f:attribute`	Tags for JavaServer Faces custom actions that are independent of any particular `RenderKit`
JSTL Core Tag Library	`http://java.sun.com/jsp/jstl/core`	`c:`	`c:forEach` `c:catch`	JSTL 1.1 Core Tags
JSTL Functions Tag Library	`http://java.sun.com/jsp/jstl/functions`	`fn:`	`fn:toUpperCase` `fn:toLowerCase`	JSTL 1.1 Functions Tags

In addition, Facelets supports tags for composite components for which you can declare custom prefixes. For more information on composite components, see "Composite Components" on page 121.

Based on the JavaServer Faces support for Expression Language (EL) syntax defined by JSP 2.1, Facelets uses EL expressions to reference properties and methods of backing beans. EL expressions can be used to bind component objects or values to methods or properties of managed beans. For more information on using EL expressions, see "Using the EL to Reference Backing Beans" on page 185.

Developing a Simple Facelets Application

This section describes the general steps involved in developing a JavaServer Faces application. The following tasks are usually required:

- Developing the backing beans
- Creating the pages using the component tags
- Defining page navigation
- Mapping the `FacesServlet` instance
- Adding managed bean declarations

Creating a Facelets Application

The example used in this tutorial is the `guessnumber` application. The application presents you with a page that asks you to guess a number between 0 and 10, validates your input against a random number, and responds with another page that informs you whether you guessed the number correctly or incorrectly.

Developing a Backing Bean

In a typical JavaServer Faces application, each page of the application connects to a backing bean, a type of managed bean. The backing bean defines the methods and properties that are associated with the components.

The following managed bean class, `UserNumberBean.java`, generates a random number from 0 to 10:

```
package guessNumber;

import java.util.Random;
import javax.faces.bean.ManagedBean;
import javax.faces.bean.SessionScoped;

@ManagedBean
@SessionScoped
```

```
public class UserNumberBean {

    Integer randomInt = null;
    Integer userNumber = null;
    String response = null;
    private long maximum=10;
    private long minimum=0;

    public UserNumberBean() {
        Random randomGR = new Random();
        randomInt = new Integer(randomGR.nextInt(10));
        System.out.println("Duke's number: " + randomInt);
    }
    public void setUserNumber(Integer user_number) {
        userNumber = user_number;
    }

    public Integer getUserNumber() {
        return userNumber;
    }

    public String getResponse() {
        if ((userNumber != null) && (userNumber.compareTo(randomInt) == 0)) {
            return "Yay! You got it!";
        } else {
            return "Sorry, " + userNumber + " is incorrect.";
        }
    }

    public long getMaximum() {
        return (this.maximum);
    }

    public void setMaximum(long maximum) {
        this.maximum = maximum;
    }

    public long getMinimum() {
        return (this.minimum);
    }

    public void setMinimum(long minimum) {
        this.minimum = minimum;
    }
}
```

Note the use of the `@ManagedBean` annotation, which registers the backing bean as a resource with JavaServer Faces implementation. The `@SessionScoped` annotation registers the bean scope as `session`.

Creating Facelets Views

Creating a page or view is the responsibility of a page author. This task involves adding components on the pages, wiring the components to backing bean values and properties, and registering converters, validators, or listeners onto the components.

For the example application, XHTML web pages serve as the front end. The first page of the example application is a page called `greeting.xhtml`. A closer look at various sections of this web page provides more information.

The first section of the web page declares the content type for the page, which is XHTML:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
```

The next section declares the XML namespace for the tag libraries that are used in the web page:

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html"
      xmlns:f="http://java.sun.com/jsf/core">
```

The next section uses various tags to insert components into the web page:

```
<h:head>
        <title>Guess Number Facelets Application</title>
    </h:head>
    <h:body>
        <h:form>
            <h:graphicImage value="#{resource['images:wave.med.gif']}"/>
            <h2>
                Hi, my name is Duke. I am thinking of a number from
                #{userNumberBean.minimum} to #{userNumberBean.maximum}.
                Can you guess it?
                <p></p>
                <h:inputText
                    id="userNo"
                    value="#{userNumberBean.userNumber}">
                    <f:validateLongRange
                        minimum="#{userNumberBean.minimum}"
                        maximum="#{userNumberBean.maximum}"/>
                </h:inputText>

                <h:commandButton id="submit" value="Submit"
                                 action="response.xhtml"/>
                <h:message showSummary="true" showDetail="false"
                           style="color: red;
                           font-family: 'New Century Schoolbook', serif;
                           font-style: oblique;
                           text-decoration: overline"
                           id="errors1"
                           for="userNo"/>
            </h2>
        </h:form>
    </h:body>
```

Note the use of the following tags:

- Facelets HTML tags (those beginning with `h:`) to add components
- The Facelets core tag `f:validateLongRange` to validate the user input

An `inputText` component accepts user input and sets the value of the backing bean property `userNumber` through the EL expression `#{userNumberBean.userNumber}`. The input value is validated for value range by the JavaServer Faces standard validator `f:validateLongRange`.

The image file, `wave.med.gif`, is added to the page as a resource. For more details about the resources facility, see "Resources" on page 124.

A `commandButton` component with the ID `submit` starts validation of the input data when a user clicks the button. Using implicit navigation, the component redirects the client to another page, `response.xhtml`, which shows the response to your input.

You can now create the second page, `response.xhtml`, with the following content:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">

<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">

    <h:head>
        <title>Guess Number Facelets Application</title>
    </h:head>
    <h:body>
        <h:form>
            <h:graphicImage value="#{resource['images:wave.med.gif']}"/>
            <h2>
                <h:outputText id="result" value="#{userNumberBean.response}"/>
            </h2>
            <h:commandButton id="back" value="Back" action="greeting.xhtml"/>
        </h:form>
    </h:body>
</html>
```

Configuring the Application

Configuring a JavaServer Faces application involves mapping the Faces Servlet in the web deployment descriptor file, such as a `web.xml` file, and possibly adding managed bean declarations, navigation rules, and resource bundle declarations to the application configuration resource file, `faces-config.xml`.

If you are using NetBeans IDE, a web deployment descriptor file is automatically created for you. In such an IDE-created `web.xml` file, change the default greeting page, which is `index.xhtml`, to `greeting.xhtml`. Here is an example `web.xml` file, showing this change in bold.

```
<?xml version="1.0" encoding="UTF-8"?>
<web-app version="3.0" xmlns="http://java.sun.com/xml/ns/javaee"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://java.sun.com/xml/ns/javaee
  http://java.sun.com/xml/ns/javaee/web-app_3_0.xsd">
```

```
    <context-param>
        <param-name>javax.faces.PROJECT_STAGE</param-name>
        <param-value>Development</param-value>
    </context-param>
    <servlet>
        <servlet-name>Faces Servlet</servlet-name>
        <servlet-class>javax.faces.webapp.FacesServlet</servlet-class>
        <load-on-startup>1</load-on-startup>
    </servlet>
    <servlet-mapping>
        <servlet-name>Faces Servlet</servlet-name>
        <url-pattern>/faces/*</url-pattern>
    </servlet-mapping>
    <session-config>
        <session-timeout>
            30
        </session-timeout>
    </session-config>
    <welcome-file-list>
        <welcome-file>faces/greeting.xhtml</welcome-file>
    </welcome-file-list>
</web-app>
```

Note the use of the context parameter `PROJECT_STAGE`. This parameter identifies the status of a JavaServer Faces application in the software lifecycle.

The stage of an application can affect the behavior of the application. For example, if the project stage is defined as `Development`, debugging information is automatically generated for the user. If not defined by the user, the default project stage is `Production`.

Building, Packaging, Deploying, and Running the `guessnumber` Facelets Example

You can use either NetBeans IDE or Ant to build, package, deploy, and run the `guessnumber` example. The source code for this example is available in the *tut-install*`/examples/web/guessnumber` directory.

▼ To Build, Package, and Deploy the `guessnumber` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/web/`
3. **Select the `guessnumber` folder.**
4. **Select the Open as Main Project check box.**

5. **Click Open Project.**

6. **In the Projects tab, right-click the `guessnumber` project and select Deploy.**

   This option builds and deploys the example application to your GlassFish Server instance.

▼ To Build, Package, and Deploy the `guessnumber` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/web/guessnumber/`

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `guessnumber.war`, that is located in the `dist` directory.

3. **Make sure that the GlassFish Server is started.**

4. **To deploy the application, type the following command:**

   ```
   ant deploy
   ```

▼ To Run the `guessnumber` Example

1. **Open a web browser.**

2. **Type the following URL in your web browser:**

   ```
   http://localhost:8080/guessnumber
   ```

   The web page shown in Figure 5–1 appears.

FIGURE 5–1 Running the `guessnumber` Application



3 **In the text field, type a number from 0 to 10 and click Submit.**

Another page appears, reporting whether your guess is correct or incorrect.

4 **If you guessed incorrectly, click the Back button to return to the main page.**

You can continue to guess until you get the correct answer.

Templating

JavaServer Faces technology provides the tools to implement user interfaces that are easy to extend and reuse. Templating is a useful Facelets feature that allows you to create a page that will act as the base, or *template*, for the other pages in an application. By using templates, you can reuse code and avoid recreating similarly constructed pages. Templating also helps in maintaining a standard look and feel in an application with a large number of pages.

Table 5–2 lists Facelets tags that are used for templating and their respective functionality.

TABLE 5–2 Facelets Templating Tags

Tag	Function
`ui:component`	Defines a component that is created and added to the component tree.
`ui:composition`	Defines a page composition that optionally uses a template. Content outside of this tag is ignored.
`ui:debug`	Defines a debug component that is created and added to the component tree.

TABLE 5–2 Facelets Templating Tags *(Continued)*

Tag	Function
`ui:decorate`	Similar to the composition tag but does not disregard content outside this tag.
`ui:define`	Defines content that is inserted into a page by a template.
`ui:fragment`	Similar to the component tag but does not disregard content outside this tag.
`ui:include`	Encapsulate and reuse content for multiple pages.
`ui:insert`	Inserts content into a template.
`ui:param`	Used to pass parameters to an included file.
`ui:repeat`	Used as an alternative for loop tags, such as `c:forEach` or `h:dataTable`.
`ui:remove`	Removes content from a page.

For more information on Facelets templating tags, see the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

The Facelets tag library includes the main templating tag `ui:insert`. A template page that is created with this tag allows you to define a default structure for a page. A template page is used as a template for other pages, usually referred to as client pages.

Here is an example of a template saved as `template.xhtml`:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
      "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:ui="http://java.sun.com/jsf/facelets"
      xmlns:h="http://java.sun.com/jsf/html">

    <h:head>
        <meta http-equiv="Content-Type"
              content="text/html; charset=UTF-8" />
        <link href="./resources/css/default.css"
              rel="stylesheet" type="text/css" />
        <link href="./resources/css/cssLayout.css"
              rel="stylesheet" type="text/css" />
        <title>Facelets Template</title>
    </h:head>

    <h:body>
        <div id="top" class="top">
            <ui:insert name="top">Top Section</ui:insert>
        </div>
        <div>
        <div id="left">
             <ui:insert name="left">Left Section</ui:insert>
        </div>
        <div id="content" class="left_content">
             <ui:insert name="content">Main Content</ui:insert>
        </div>
```

```
        </div>
    </h:body>
</html>
```

The example page defines an XHTML page that is divided into three sections: a top section, a left section, and a main section. The sections have style sheets associated with them. The same structure can be reused for the other pages of the application.

The client page invokes the template by using the `ui:composition` tag. In the following example, a client page named `templateclient.xhtml` invokes the template page named `template.xhtml` from the preceding example. A client page allows content to be inserted with the help of the `ui:define` tag.

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:ui="http://java.sun.com/jsf/facelets"
      xmlns:h="http://java.sun.com/jsf/html">

    <h:body>
        <ui:composition template="./template.xhtml">
            <ui:define name="top">
                Welcome to Template Client Page
            </ui:define>

            <ui:define name="left">
                <h:outputLabel value="You are in the Left Section"/>
            </ui:define>

            <ui:define name="content">
                <h:graphicImage value="#{resource['images:wave.med.gif']}"/>
                <h:outputText value="You are in the Main Content Section"/>
            </ui:define>
        </ui:composition>
    </h:body>
</html>
```

You can use NetBeans IDE to create Facelets template and client pages. For more information on creating these pages, see `http://netbeans.org/kb/docs/web/jsf20-intro.html`.

Composite Components

JavaServer Faces technology offers the concept of composite components with Facelets. A composite component is a special type of template that acts as a component.

Any component is essentially a piece of reusable code that behaves in a particular way. For example, an `inputText` component accepts user input. A component can also have validators, converters, and listeners attached to it to perform certain defined actions.

A composite component consists of a collection of markup tags and other existing components. This reusable, user-created component has a customized, defined functionality and can have validators, converters, and listeners attached to it like any other component.

With Facelets, any XHTML page that contains markup tags and other components can be converted into a composite component. Using the resources facility, the composite component can be stored in a library that is available to the application from the defined resources location.

Table 5–3 lists the most commonly used composite tags and their functions.

TABLE 5–3 Composite Component Tags

Tag	Function
`composite:interface`	Declares the usage contract for a composite component. The composite component can be used as a single component whose feature set is the union of the features declared in the usage contract.
`composite:implementation`	Defines the implementation of the composite component. If a `composite:interface` element appears, there must be a corresponding `composite:implementation`.
`composite:attribute`	Declares an attribute that may be given to an instance of the composite component in which this tag is declared.
`composite:insertChildren`	Any child components or template text within the composite component tag in the using page will be reparented into the composite component at the point indicated by this tag's placement within the `composite:implementation` section.
`composite:valueHolder`	Declares that the composite component whose contract is declared by the `composite:interface` in which this element is nested exposes an implementation of `ValueHolder` suitable for use as the target of attached objects in the using page.
`composite:editableValueHolder`	Declares that the composite component whose contract is declared by the `composite:interface` in which this element is nested exposes an implementation of `EditableValueHolder` suitable for use as the target of attached objects in the using page.
`composite:actionSource`	Declares that the composite component whose contract is declared by the `composite:interface` in which this element is nested exposes an implementation of `ActionSource2` suitable for use as the target of attached objects in the using page.

For more information and a complete list of Facelets composite tags, see the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

The following example shows a composite component that accepts an email address as input:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
  xmlns:composite="http://java.sun.com/jsf/composite"
  xmlns:h="http://java.sun.com/jsf/html">
```

```
    <h:head>
        <title>This content will not be displayed</title>
    </h:head>
    <h:body>
        <composite:interface>
            <composite:attribute name="value" required="false"/>
        </composite:interface>

        <composite:implementation>
            <h:outputLabel value="Email id: "></h:outputLabel>
            <h:inputText value="#{cc.attrs.value}"></h:inputText>
        </composite:implementation>
    </h:body>
</html>
```

Note the use of `cc.attrs.value` when defining the value of the `inputText` component. The word `cc` in JavaServer Faces is a reserved word for composite components. The `#{cc.attrs.`*attribute-name*`}` expression is used to access the attributes defined for the composite component's interface, which in this case happens to be `value`.

The preceding example content is stored as a file named `email.xhtml` in a folder named `resources/emcomp`, under the application web root directory. This directory is considered a library by JavaServer Faces, and a component can be accessed from such a library. For more information on resources, see "Resources" on page 124.

The web page that uses this composite component is generally called a *using page*. The using page includes a reference to the composite component, in the `xml` namespace declarations:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
  xmlns:h="http://java.sun.com/jsf/html"
  xmlns:em="http://java.sun.com/jsf/composite/emcomp/">

    <h:head>
        <title>Using a sample composite component</title>
    </h:head>

    <body>
        <h:form>
            <em:email value="Enter your email id" />
        </h:form>
    </body>
</html>
```

The local composite component library is defined in the `xml` namespace with the declaration `xmlns:em="http://java.sun.com/jsf/composite/emcomp/"`. The component itself is accessed through the use of `em:email` tag. The preceding example content can be stored as a web page named `emuserpage.xhtml` under the web root directory. When compiled and deployed on a server, it can be accessed with the following URL:

```
http://localhost:8080/application-name/faces/emuserpage.xhtml
```

Resources

Web resources are any software artifacts that the web application requires for proper rendering, including images, script files, and any user-created component libraries. Resources must be collected in a standard location, which can be one of the following.

- A resource packaged in the web application root must be in a subdirectory of a `resources` directory at the web application root: `resources/`*resource-identifier*.
- A resource packaged in the web application's classpath must be in a subdirectory of the `META-INF/resources` directory within a web application: `META-INF/resources/`*resource-identifier*.

The JavaServer Faces runtime will look for the resources in the preceding listed locations, in that order.

Resource identifiers are unique strings that conform to the following format:

[*locale-prefix*/][*library-name*/][*library-version*/]*resource-name*[/*resource-version*]

Elements of the resource identifier in brackets ([]) are optional, indicating that only a *resource-name*, which is usually a file name, is a required element.

Resources can be considered as a library location. Any artifact, such as a composite component or a template that is stored in the `resources` directory, becomes accessible to the other application components, which can use it to create a resource instance.

◆ ◆ ◆ CHAPTER 6

Expression Language

This chapter introduces the Expression Language (also referred to as the EL), which provides an important mechanism for enabling the presentation layer (web pages) to communicate with the application logic (backing beans). The EL is used by both JavaServer Faces technology and JavaServer Pages (JSP) technology. The EL represents a union of the expression languages offered by JavaServer Faces technology and JSP technology.

The following topics are addressed here:

Overview of the EL

The EL allows page authors to use simple expressions to dynamically access data from JavaBeans components. For example, the `test` attribute of the following conditional tag is supplied with an EL expression that compares 0 with the number of items in the session-scoped bean named `cart`.

```
<c:if test="${sessionScope.cart.numberOfItems > 0}">
  ...
</c:if>
```

JavaServer Faces technology uses the EL for the following functions:

- Deferred and immediate evaluation of expressions
- The ability to set as well as get data

- The ability to invoke methods

See "Using the EL to Reference Backing Beans" on page 185 for more information on how to use the EL in JavaServer Faces applications.

To summarize, the EL provides a way to use simple expressions to perform the following tasks:

- Dynamically read application data stored in JavaBeans components, various data structures, and implicit objects
- Dynamically write data, such as user input into forms, to JavaBeans components
- Invoke arbitrary static and public methods
- Dynamically perform arithmetic operations

The EL is also used to specify the following kinds of expressions that a custom tag attribute will accept:

- **Immediate evaluation expressions** or **deferred evaluation expressions**. An immediate evaluation expression is evaluated at once by the underlying technology, such as JavaServer Faces. A deferred evaluation expression can be evaluated later by the underlying technology using the EL.
- **Value expression** or **method expression**. A value expression references data, whereas a method expression invokes a method.
- **Rvalue expression** or **lvalue expression**. An rvalue expression can only read a value, whereas an lvalue expression can both read and write that value to an external object.

Finally, the EL provides a pluggable API for resolving expressions so custom resolvers that can handle expressions not already supported by the EL can be implemented.

Immediate and Deferred Evaluation Syntax

The EL supports both immediate and deferred evaluation of expressions. Immediate evaluation means that the expression is evaluated and the result returned as soon as the page is first rendered. Deferred evaluation means that the technology using the expression language can use its own machinery to evaluate the expression sometime later during the page's lifecycle, whenever it is appropriate to do so.

Those expressions that are evaluated immediately use the `${}` syntax. Expressions whose evaluation is deferred use the `#{}` syntax.

Because of its multiphase lifecycle, JavaServer Faces technology uses mostly deferred evaluation expressions. During the lifecycle, component events are handled, data is validated, and other tasks are performed in a particular order. Therefore, a JavaServer Faces implementation must defer evaluation of expressions until the appropriate point in the lifecycle.

Other technologies using the EL might have different reasons for using deferred expressions.

Immediate Evaluation

All expressions using the `${}` syntax are evaluated immediately. These expressions can be used only within template text or as the value of a tag attribute that can accept runtime expressions.

The following example shows a tag whose `value` attribute references an immediate evaluation expression that gets the total price from the session-scoped bean named `cart`:

```
<fmt:formatNumber value="${sessionScope.cart.total}"/>
```

The JavaServer Faces implementation evaluates the expression `${sessionScope.cart.total}`, converts it, and passes the returned value to the tag handler.

Immediate evaluation expressions are always read-only value expressions. The preceding example expression cannot set the total price, but instead can only get the total price from the cart bean.

Deferred Evaluation

Deferred evaluation expressions take the form `#{expr}` and can be evaluated at other phases of a page lifecycle as defined by whatever technology is using the expression. In the case of JavaServer Faces technology, its controller can evaluate the expression at different phases of the lifecycle, depending on how the expression is being used in the page.

The following example shows a JavaServer Faces `inputText` tag, which represents a text field component into which a user enters a value. The `inputText` tag's `value` attribute references a deferred evaluation expression that points to the `name` property of the `customer` bean:

```
<h:inputText id="name" value="#{customer.name}" />
```

For an initial request of the page containing this tag, the JavaServer Faces implementation evaluates the `#{customer.name}` expression during the render-response phase of the lifecycle. During this phase, the expression merely accesses the value of `name` from the `customer` bean, as is done in immediate evaluation.

For a postback request, the JavaServer Faces implementation evaluates the expression at different phases of the lifecycle, during which the value is retrieved from the request, validated, and propagated to the `customer` bean.

As shown in this example, deferred evaluation expressions can be

- Value expressions that can be used to both read and write data
- Method expressions

Value expressions (both immediate and deferred) and method expressions are explained in the next section.

Value and Method Expressions

The EL defines two kinds of expressions: value expressions and method expressions. Value expressions can either yield a value or set a value. Method expressions reference methods that can be invoked and can return a value.

Value Expressions

Value expressions can be further categorized into rvalue and lvalue expressions. Rvalue expressions can read data but cannot write it. Lvalue expressions can both read and write data.

All expressions that are evaluated immediately use the `${}` delimiters and are always rvalue expressions. Expressions whose evaluation can be deferred use the `#{}` delimiters and can act as both rvalue and lvalue expressions. Consider the following two value expressions:

```
${customer.name}

#{customer.name}
```

The former uses immediate evaluation syntax, whereas the latter uses deferred evaluation syntax. The first expression accesses the `name` property, gets its value, adds the value to the response, and gets rendered on the page. The same can happen with the second expression. However, the tag handler can defer the evaluation of this expression to a later time in the page lifecycle, if the technology using this tag allows.

In the case of JavaServer Faces technology, the latter tag's expression is evaluated immediately during an initial request for the page. In this case, this expression acts as an rvalue expression. During a postback request, this expression can be used to set the value of the `name` property with user input. In this case, the expression acts as an lvalue expression.

Referencing Objects Using Value Expressions

Both rvalue and lvalue expressions can refer to the following objects and their properties or attributes:

- JavaBeans components
- Collections
- Java SE enumerated types
- Implicit objects

To refer to these objects, you write an expression using a variable that is the name of the object. The following expression references a backing bean (a JavaBeans component) called `customer`:

```
${customer}
```

The web container evaluates the variable that appears in an expression by looking up its value according to the behavior of `PageContext.findAttribute(String)`, where the `String` argument is the name of the variable. For example, when evaluating the expression `${customer}`, the container will look for `customer` in the page, request, session, and application scopes and will return its value. If `customer` is not found, a null value is returned.

You can use a custom EL resolver to alter the way variables are resolved. For instance, you can provide an EL resolver that intercepts objects with the name `customer`, so that `${customer}` returns a value in the EL resolver instead.

To reference an `enum` constant with an expression, use a `String` literal. For example, consider this `Enum` class:

```
public enum Suit {hearts, spades, diamonds, clubs}
```

To refer to the `Suit` constant `Suit.hearts` with an expression, use the `String` literal `"hearts"`. Depending on the context, the `String` literal is converted to the `enum` constant automatically. For example, in the following expression in which `mySuit` is an instance of `Suit`, `"hearts"` is first converted to `Suit.hearts` before it is compared to the instance:

```
${mySuit == "hearts"}
```

Referring to Object Properties Using Value Expressions

To refer to properties of a bean or an `enum` instance, items of a collection, or attributes of an implicit object, you use the `.` or `[]` notation.

To reference the `name` property of the `customer` bean, use either the expression `${customer.name}` or the expression `${customer["name"]}`. The part inside the brackets is a `String` literal that is the name of the property to reference.

You can use double or single quotes for the `String` literal. You can also combine the `[]` and `.` notations, as shown here:

```
${customer.address["street"]}
```

Properties of an `enum` constant can also be referenced in this way. However, as with JavaBeans component properties, the properties of an `Enum` class must follow JavaBeans component conventions. This means that a property must at least have an accessor method called `get`*Property*, where *Property* is the name of the property that can be referenced by an expression.

For example, consider an `Enum` class that encapsulates the names of the planets of our galaxy and includes a method to get the mass of a planet. You can use the following expression to reference the method `getMass` of the `Enum` class `Planet`:

```
${myPlanet.mass}
```

If you are accessing an item in an array or list, you must use either a literal value that can be converted to `int` or the `[]` notation with an `int` and without quotes. The following examples could resolve to the same item in a list or array, assuming that `socks` can be converted to `int`:

- `${customer.orders[1]}`
- `${customer.orders.socks}`

In contrast, an item in a `Map` can be accessed using a string literal key; no coercion is required:

```
${customer.orders["socks"]}
```

An rvalue expression also refers directly to values that are not objects, such as the result of arithmetic operations and literal values, as shown by these examples:

- `${"literal"}`
- `${customer.age + 20}`
- `${true}`
- `${57}`

The EL defines the following literals:

- Boolean: `true` and `false`
- Integer: as in Java
- Floating-point: as in Java
- String: with single and double quotes; " is escaped as `\"`, ' is escaped as `\'`, and \ is escaped as `\\`
- Null: `null`

You can also write expressions that perform operations on an `enum` constant. For example, consider the following `Enum` class:

```
public enum Suit {club, diamond, heart, spade}
```

After declaring an `enum` constant called `mySuit`, you can write the following expression to test whether `mySuit` is `spade`:

```
${mySuit == "spade"}
```

When it resolves this expression, the EL resolving mechanism will invoke the `valueOf` method of the `Enum` class with the `Suit` class and the `spade` type, as shown here:

```
mySuit.valueOf(Suit.class, "spade"}
```

Where Value Expressions Can Be Used

Value expressions using the `${}` delimiters can be used in

- Static text
- Any standard or custom tag attribute that can accept an expression

The value of an expression in static text is computed and inserted into the current output. Here is an example of an expression embedded in static text:

```
<some:tag>
    some text ${expr} some text
</some:tag>
```

If the static text appears in a tag body, note that an expression *will not* be evaluated if the body is declared to be `tagdependent`.

Lvalue expressions can be used only in tag attributes that can accept lvalue expressions.

A tag attribute value using either an rvalue or lvalue expression can be set in the following ways:

- With a single expression construct:

  ```
  <some:tag value="${expr}"/>
  ```

  ```
  <another:tag value="#{expr}"/>
  ```

  These expressions are evaluated, and the result is converted to the attribute's expected type.

- With one or more expressions separated or surrounded by text:

  ```
  <some:tag value="some${expr}${expr}text${expr}"/>
  ```

  ```
  <another:tag value="some#{expr}#{expr}text#{expr}"/>
  ```

  These kinds of expression, called *composite expressions*, are evaluated from left to right. Each expression embedded in the composite expression is converted to a `String` and then concatenated with any intervening text. The resulting `String` is then converted to the attribute's expected type.

- With text only:

  ```
  <some:tag value="sometext"/>
  ```

  This expression is called a *literal expression*. In this case, the attribute's `String` value is converted to the attribute's expected type. Literal value expressions have special syntax rules. See "Literal Expressions" on page 135 for more information. When a tag attribute has an `enum` type, the expression that the attribute uses must be a literal expression. For example, the tag attribute can use the expression `"hearts"` to mean `Suit.hearts`. The literal is converted to `Suit`, and the attribute gets the value `Suit.hearts`.

All expressions used to set attribute values are evaluated in the context of an expected type. If the result of the expression evaluation does not match the expected type exactly, a type conversion will be performed. For example, the expression `${1.2E4}` provided as the value of an attribute of type `float` will result in the following conversion:

```
Float.valueOf("1.2E4").floatValue()
```

See Section 1.18 of the JavaServer Pages 2.2 Expression Language specification (available from http://jcp.org/aboutJava/communityprocess/final/jsr245/) for the complete type conversion rules.

Method Expressions

Another feature of the EL is its support of deferred method expressions. A method expression is used to invoke an arbitrary public method of a bean, which can return a result.

In JavaServer Faces technology, a component tag represents a component on a page. The component tag uses method expressions to invoke methods that perform some processing for the component. These methods are necessary for handling events that the components generate and for validating component data, as shown in this example:

```
<h:form>
    <h:inputText
        id="name"
        value="#{customer.name}"
        validator="#{customer.validateName}"/>
    <h:commandButton
        id="submit"
        action="#{customer.submit}" />
</h:form>
```

The `inputText` tag displays as a text field. The `validator` attribute of this `inputText` tag references a method, called `validateName`, in the bean, called `customer`.

Because a method can be invoked during different phases of the lifecycle, method expressions must always use the deferred evaluation syntax.

Like lvalue expressions, method expressions can use the `.` and the `[]` operators. For example, `#{object.method}` is equivalent to `#{object["method"]}`. The literal inside the `[]` is converted to `String` and is used to find the name of the method that matches it. Once the method is found, it is invoked, or information about the method is returned.

Method expressions can be used only in tag attributes and only in the following ways:

- With a single expression construct, where *bean* refers to a JavaBeans component and *method* refers to a method of the JavaBeans component:

  ```
  <some:tag value="#{bean.method}"/>
  ```

  The expression is evaluated to a method expression, which is passed to the tag handler. The method represented by the method expression can then be invoked later.
- With text only:

  ```
  <some:tag value="sometext"/>
  ```

Method expressions support literals primarily to support `action` attributes in JavaServer Faces technology. When the method referenced by this method expression is invoked, the method returns the `String` literal, which is then converted to the expected return type, as defined in the tag's tag library descriptor.

Parameterized Method Calls

The EL offers support for parameterized method calls. Method calls can use parameters without having to use static EL functions.

Both the `.` and `[]` operators can be used for invoking method calls with parameters, as shown in the following expression syntax:

- *expr-a*`[`*expr-b*`]`(*parameters*)
- *expr-a*`.`*identifier-b*(*parameters*)

In the first expression syntax, *expr-a* is evaluated to represent a bean object. The expression *expr-b* is evaluated and cast to a string that represents a method in the bean represented by *expr-a*. In the second expression syntax, *expr-a* is evaluated to represent a bean object, and *identifier-b* is a string that represents a method in the bean object. The *parameters* in parentheses are the arguments for the method invocation. Parameters can be zero or more values or expressions, separated by commas.

Parameters are supported for both value expressions and method expressions. In the following example, which is a modified tag from the `guessnumber` application, a random number is provided as an argument rather than from user input to the method call:

```
<h:inputText value="#{userNumberBean.userNumber('5')}">
```

The preceding example uses a value expression.

Consider the following example of a JavaServer Faces component tag that uses a method expression:

```
<h:commandButton action="#{trader.buy}" value="buy"/>
```

The EL expression `trader.buy` calls the `trader` bean's `buy` method. You can modify the tag to pass on a parameter. Here is the revised tag where a parameter is passed:

```
<h:commandButton action="#{trader.buy('SOMESTOCK')}" value="buy"/>
```

In the preceding example, you are passing the string `'SOMESTOCK'` (a stock symbol) as a parameter to the `buy` method.

For more information on the updated EL, see `http://uel.java.net/`.

Defining a Tag Attribute Type

As explained in the previous section, all kinds of expressions can be used in tag attributes. Which kind of expression and how it is evaluated, whether immediately or deferred, are determined by the `type` attribute of the tag's definition in the Page Description Language (PDL) that defines the tag.

If you plan to create custom tags, for each tag in the PDL, you need to specify what kind of expression to accept. Table 6–1 shows the kinds of tag attributes that accept EL expressions, gives examples of expressions they accept, and provides the type definitions of the attributes that must be added to the PDL. You cannot use `#{}` syntax for a dynamic attribute, meaning an attribute that accepts dynamically calculated values at runtime. Similarly, you also cannot use the `${}` syntax for a deferred attribute.

TABLE 6–1 Definitions of Tag Attributes That Accept EL Expressions

Attribute Type	Example Expression	Type Attribute Definition
Dynamic	`"literal"`	`<rtexprvalue>true</rtexprvalue>`
	`${literal}`	`<rtexprvalue>true</rtexprvalue>`

Deferred value	`"literal"`	`<deferred-value>`
		`  <type>java.lang.String</type>`
		`</deferred-value>`

	`#{customer.age}`	`<deferred-value>`
		`  <type>int</type>`
		`</deferred-value>`

Deferred method	`"literal"`	`<deferred-method>`
		`  <method-signature>`
		`  java.lang.String submit()`
		`  </method-signature>`
		`<deferred-method>`

	`#{customer.calcTotal}`	`<deferred-method>`
		`  <method-signature>`
		`  double calcTotal(int, double)`
		`  </method-signature>`
		`</deferred-method>`

In addition to the tag attribute types shown in Table 6–1, you can define an attribute to accept both dynamic and deferred expressions. In this case, the tag attribute definition contains both an `rtexprvalue` definition set to `true` and either a `deferred-value` or `deferred-method` definition.

Literal Expressions

A literal expression is evaluated to the text of the expression, which is of type `String`. A literal expression does not use the `${}` or `#{}` delimiters.

If you have a literal expression that includes the reserved `${}` or `#{}` syntax, you need to escape these characters as follows:

- By creating a composite expression as shown here:

  ```
  ${'${'}exprA}
  #{'#{'}exprB}
  ```

  The resulting values would then be the strings `${exprA}` and `#{exprB}`.
- By using the escape characters `\$` and `\#` to escape what would otherwise be treated as an eval-expression:

  ```
  \${exprA}
  \#{exprB}
  ```

  The resulting values would again be the strings `${exprA}` and `#{exprB}`.

When a literal expression is evaluated, it can be converted to another type. Table 6–2 shows examples of various literal expressions and their expected types and resulting values.

TABLE 6–2 Literal Expressions

Expression	Expected Type	Result
`Hi`	`String`	`Hi`
`true`	`Boolean`	`Boolean.TRUE`
`42`	`int`	`42`

Literal expressions can be evaluated immediately or deferred and can be either value or method expressions. At what point a literal expression is evaluated depends on where it is being used. If the tag attribute that uses the literal expression is defined to accept a deferred value expression, when referencing a value, the literal expression is evaluated at a point in the lifecycle that is determined by other factors, such as where the expression is being used and to what it is referring.

In the case of a method expression, the method that is referenced is invoked and returns the specified `String` literal. For example, the `commandButton` tag of the `guessnumber` application uses a literal method expression as a logical outcome to tell the JavaServer Faces navigation system which page to display next.

Operators

In addition to the `.` and `[]` operators discussed in "Value and Method Expressions" on page 128, the EL provides the following operators, which can be used in rvalue expressions only:

- **Arithmetic**: `+`, `-` (binary), `*`, `/` and `div`, `%` and `mod`, `-` (unary)
- **Logical**: `and`, `&&`, `or`, `||`, `not`, `!`
- **Relational**: `==`, `eq`, `!=`, `ne`, `<`, `lt`, `>`, `gt`, `<=`, `ge`, `>=`, `le`. Comparisons can be made against other values or against Boolean, string, integer, or floating-point literals.
- **Empty**: The `empty` operator is a prefix operation that can be used to determine whether a value is `null` or empty.
- **Conditional**: `A ? B : C`. Evaluate `B` or `C`, depending on the result of the evaluation of `A`.

The precedence of operators highest to lowest, left to right is as follows:

- `[] .`
- `()` (used to change the precedence of operators)
- `-` (unary) `not ! empty`
- `* / div % mod`
- `+ -` (binary)
- `< > <= >= lt gt le ge`
- `== != eq ne`
- `&& and`
- `|| or`
- `? :`

Reserved Words

The following words are reserved for the EL and should not be used as identifiers:

`and`	`or`	`not`	`eq`
`ne`	`lt`	`gt`	`le`
`ge`	`true`	`false`	`null`
`instanceof`	`empty`	`div`	`mod`

Examples of EL Expressions

Table 6–3 contains example EL expressions and the result of evaluating them.

TABLE 6–3 Example Expressions

EL Expression	Result
`${1 > (4/2)}`	`false`
`${4.0 >= 3}`	`true`
`${100.0 == 100}`	`true`
`${(10*10) ne 100}`	`false`
`${'a' < 'b'}`	`true`
`${'hip' gt 'hit'}`	`false`
`${4 > 3}`	`true`
`${1.2E4 + 1.4}`	`12001.4`
`${3 div 4}`	`0.75`
`${10 mod 4}`	`2`
`${!empty param.Add}`	`False` if the request parameter named `Add` is `null` or an empty string.
`${pageContext.request.contextPath}`	The context path.
`${sessionScope.cart.numberOfItems}`	The value of the `numberOfItems` property of the session-scoped attribute named `cart`.
`${param['mycom.productId']}`	The value of the request parameter named `mycom.productId`.
`${header["host"]}`	The host.
`${departments[deptName]}`	The value of the entry named `deptName` in the `departments` map.
`${requestScope['javax.servlet.forward.servlet_path']}`	The value of the request-scoped attribute named `javax.servlet.forward.servlet_path`.
`#{customer.lName}`	Gets the value of the property `lName` from the `customer` bean during an initial request. Sets the value of `lName` during a postback.
`#{customer.calcTotal}`	The return value of the method `calcTotal` of the `customer` bean.

◆ ◆ ◆ CHAPTER 7

Using JavaServer Faces Technology in Web Pages

Web pages represent the presentation layer for web applications. The process of creating web pages of a JavaServer Faces application includes adding components to the page and wiring them to backing beans, validators, converters, and other server-side objects that are associated with the page.

This chapter explains how to create web pages using various types of component and core tags. In the next chapter, you will learn about adding converters, validators, and listeners to component tags to provide additional functionality to components.

The following topics are addressed here:

Setting Up a Page

A typical JavaServer Faces web page includes the following elements:

- A set of namespace declarations that declare the JavaServer Faces tag libraries
- Optionally, the new HTML head (`h:head`) and body (`h:body`) tags
- A form tag (`h:form`) that represents the user input components

To add the JavaServer Faces components to your web page, you need to provide the page access to the two standard tag libraries: the JavaServer Faces HTML tag library and the JavaServer Faces core tag library. The JavaServer Faces standard HTML tag library defines tags that represent common HTML user interface components. This library is linked to the HTML render kit at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/renderkitdocs/`. The JavaServer Faces core tag library defines tags that perform core actions.

For a complete list of JavaServer Faces Facelets tags and their attributes, refer to the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

To use any of the JavaServer Faces tags, you need to include appropriate directives at the top of each page specifying the tag libraries.

For Facelets applications, the XML namespace directives uniquely identify the tag library URI and the tag prefix.

For example, when creating a Facelets XHTML page, include namespace directives as follows:

```
<html xmlns="http://www.w3.org/1999/xhtml"
  xmlns:h="http://java.sun.com/jsf/html"
  xmlns:f="http://java.sun.com/jsf/core">
```

The XML namespace URI identifies the tag library location, and the prefix value is used to distinguish the tags belonging to that specific tag library. You can also use other prefixes instead of the standard `h` or `f`. However, when including the tag in the page, you must use the prefix that you have chosen for the tag library. For example, in the following web page, the `form` tag must be referenced using the `h` prefix because the preceding tag library directive uses the `h` prefix to distinguish the tags defined in HTML tag library:

```
<h:form ...>
```

The sections "Adding Components to a Page Using HTML Tags" on page 140 and "Using Core Tags" on page 168 describe how to use the component tags from the JavaServer Faces standard HTML tag library and the core tags from the JavaServer Faces core tag library.

Adding Components to a Page Using HTML Tags

The tags defined by the JavaServer Faces standard HTML tag library represent HTML form components and other basic HTML elements. These components display data or accept data from the user. This data is collected as part of a form and is submitted to the server, usually when the user clicks a button. This section explains how to use each of the component tags shown in Table 7–1.

TABLE 7–1 The Component Tags

Tag	Functions	Rendered as	Appearance
`column`	Represents a column of data in a data component	A column of data in an HTML table	A column in a table
`commandButton`	Submits a form to the application	An HTML `<input type=type>` element, where the `type` value can be `submit`, `reset`, or `image`	A button
`commandLink`	Links to another page or location on a page	An HTML `<a href>` element	A hyperlink
`dataTable`	Represents a data wrapper	An HTML `<table>` element	A table that can be updated dynamically
`form`	Represents an input form (inner tags of the form receive the data that will be submitted with the form)	An HTML `<form>` element	No appearance
`graphicImage`	Displays an image	An HTML `<img>` element	An image
`inputHidden`	Allows a page author to include a hidden variable in a page	An HTML `<input type=hidden>` element	No appearance
`inputSecret`	Allows a user to input a string without the actual string appearing in the field	An HTML `<input type=password>` element	A text field, which displays a row of characters instead of the actual string entered
`inputText`	Allows a user to input a string	An HTML `<input type=text>` element	A text field
`inputTextarea`	Allows a user to enter a multiline string	An HTML `<textarea>` element	A multi-row text field
`message`	Displays a localized message	An HTML `<span>` tag if styles are used	A text string
`messages`	Displays localized messages	A set of HTML `<span>` tags if styles are used	A text string
`outputFormat`	Displays a localized message	Plain text	Plain text
`outputLabel`	Displays a nested component as a label for a specified input field	An HTML `<label>` element	Plain text

TABLE 7–1 The Component Tags *(Continued)*

Tag	Functions	Rendered as	Appearance
`outputLink`	Links to another page or location on a page without generating an action event	An HTML `<a>` element	A hyperlink
`outputText`	Displays a line of text	Plain text	Plain text
`panelGrid`	Displays a table	An HTML `<table>` element with `<tr>` and `<td>` elements	A table
`panelGroup`	Groups a set of components under one parent	A HTML `<div>` or `<span>` element	A row in a table
`selectBooleanCheckbox`	Allows a user to change the value of a Boolean choice	An HTML `<input type=checkbox>` element.	A check box
`selectItem`	Represents one item in a list of items from which the user must select one	An HTML `<option>` element	No appearance
`selectItems`	Represents a list of items from which the user must select one	A list of HTML `<option>` elements	No appearance
`selectManyCheckbox`	Displays a set of check boxes from which the user can select multiple values	A set of HTML `<input>` elements of type `checkbox`	A set of check boxes
`selectManyListbox`	Allows a user to select multiple items from a set of items, all displayed at once	An HTML `<select>` element	A list box
`selectManyMenu`	Allows a user to select multiple items from a set of items	An HTML `<select>` element	A scrollable combo box
`selectOneListbox`	Allows a user to select one item from a set of items, all displayed at once	An HTML `<select>` element	A list box
`selectOneMenu`	Allows a user to select one item from a set of items	An HTML `<select>` element	A scrollable combo box
`selectOneRadio`	Allows a user to select one item from a set of items	An HTML `<input type=radio>` element	A set of radio buttons

The next section explains the important tag attributes that are common to most component tags. For each of the components discussed in the following sections, "Writing Bean Properties" on page 186 explains how to write a bean property bound to a particular component or its value.

Common Component Tag Attributes

Most of the component tags support the attributes shown in Table 7–2.

TABLE 7–2 Common Component Tag Attributes

Attribute	Description
`binding`	Identifies a bean property and binds the component instance to it.
`id`	Uniquely identifies the component.
`immediate`	If set to `true`, indicates that any events, validation, and conversion associated with the component should happen when request parameter values are applied,
`rendered`	Specifies a condition under which the component should be rendered. If the condition is not satisfied, the component is not rendered.
`style`	Specifies a Cascading Style Sheet (CSS) style for the tag.
`styleClass`	Specifies a CSS class that contains definitions of the styles.
`value`	Identifies an external data source and binds the component's value to it.

All the tag attributes (except `id`) can accept expressions, as defined by the EL, described in Chapter 6, "Expression Language."

The `id` Attribute

The `id` attribute is not usually required for a component tag but is used when another component or a server-side class must refer to the component. If you don't include an `id` attribute, the JavaServer Faces implementation automatically generates a component ID. Unlike most other JavaServer Faces tag attributes, the `id` attribute takes expressions using only the evaluation syntax described in "The `immediate` Attribute" on page 143, which uses the `${}` delimiters. For more information on expression syntax, see "Value Expressions" on page 128.

The `immediate` Attribute

Input components and command components (those that implement the `ActionSource` interface, such as buttons and hyperlinks) can set the `immediate` attribute to `true` to force events, validations, and conversions to be processed when request parameter values are applied.

You need to carefully consider how the combination of an input component's `immediate` value and a command component's `immediate` value determines what happens when the command component is activated.

Assume that you have a page with a button and a field for entering the quantity of a book in a shopping cart. If the `immediate` attributes of both the button and the field are set to `true`, the

new value entered in the field will be available for any processing associated with the event that is generated when the button is clicked. The event associated with the button as well as the event validation and conversion associated with the field are all handled when request parameter values are applied.

If the button's `immediate` attribute is set to `true` but the field's `immediate` attribute is set to `false`, the event associated with the button is processed without updating the field's local value to the model layer. The reason is that any events, conversion, or validation associated with the field occurs *after* request parameter values are applied.

The `rendered` Attribute

A component tag uses a Boolean EL expression along with the `rendered` attribute to determine whether the component will be rendered. For example, the `commandLink` component in the following section of a page is not rendered if the cart contains no items:

```
<h:commandLink id="check"
    ...
    rendered="#{cart.numberOfItems > 0}">
    <h:outputText
        value="#{bundle.CartCheck}"/>
</h:commandLink>
```

Unlike nearly every other JavaServer Faces tag attribute, the `rendered` attribute is restricted to using rvalue expressions. As explained in "Value and Method Expressions" on page 128, these rvalue expressions can only read data; they cannot write the data back to the data source. Therefore, expressions used with `rendered` attributes can use the arithmetic operators and literals that rvalue expressions can use but lvalue expressions cannot use. For example, the expression in the preceding example uses the > operator.

The `style` and `styleClass` Attributes

The `style` and `styleClass` attributes allow you to specify CSS styles for the rendered output of your tags. "Displaying Error Messages with the `h:message` and `h:messages` Tags" on page 163 describes an example of using the `style` attribute to specify styles directly in the attribute. A component tag can instead refer to a CSS class.

The following example shows the use of a `dataTable` tag that references the style class `list-background`:

```
<h:dataTable id="books"
    ...
    styleClass="list-background"
    value="#{bookDBAO.books}"
    var="book">
```

The style sheet that defines this class is `stylesheet.css`, which will be included in the application. For more information on defining styles, see *Cascading Style Sheets Specification* at `http://www.w3.org/Style/CSS/`.

The `value` and `binding` Attributes

A tag representing an output component uses the `value` and `binding` attributes to bind its component's value or instance, respectively, to an external data source.

Adding HTML Head and Body Tags

The HTML head (`h:head`) and body (`h:body`) tags add HTML page structure to JavaServer Faces web pages.

- The `h:head` tag represents the head element of an HTML page
- The `h:body` tag represents the body element of an HTML page

The following is an example of an XHTML page using the usual head and body markup tags:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
  <html xmlns="http://www.w3.org/1999/xhtml">
  <head>
    <title>Add a title</title>
  </head>
  <body>
    Add Content
  </body>
```

The following is an example of an XHTML page using `h:head` and `h:body` tags:

```
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
  "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
  <html xmlns="http://www.w3.org/1999/xhtml"
        xmlns:h="http://java.sun.com/jsf/html">
  <h:head>
    Add a title
  </h:head>
  <h:body>
    Add Content
  </h:body>
```

Both of the preceding example code segments render the same HTML elements. The head and body tags are useful mainly for resource relocation. For more information on resource relocation, see "Resource Relocation Using `h:output` Tags" on page 166.

Adding a Form Component

An `h:form` tag represents an input form, which includes child components that can contain data that is either presented to the user or submitted with the form.

Figure 7–1 shows a typical login form in which a user enters a user name and password, then submits the form by clicking the Login button.

FIGURE 7–1 A Typical Form

The `h:form` tag represents the form on the page and encloses all the components that display or collect data from the user, as shown here:

```
<h:form>
... other JavaServer Faces tags and other content...
</h:form>
```

The `h:form` tag can also include HTML markup to lay out the components on the page. Note that the `h:form` tag itself does not perform any layout; its purpose is to collect data and to declare attributes that can be used by other components in the form.

A page can include multiple `h:form` tags, but only the values from the form submitted by the user will be included in the postback request.

Using Text Components

Text components allow users to view and edit text in web applications. The basic types of text components are as follows:

- Label, which displays read-only text
- Text field, which allows users to enter text, often to be submitted as part of a form
- Text area, which is a type of text field that allows users to enter multiple lines of text
- Password field, which is a type of text field that displays a set of characters, such as asterisks, instead of the password text that the user enters

Figure 7–2 shows examples of these text components.

FIGURE 7–2 Example Text Components



Text components can be categorized as either input or output. A JavaServer Faces output component is rendered as read-only text. An example is a label. A JavaServer Faces input component is rendered as editable text. An example is a text field.

The input and output components can each be rendered in various ways to display more specialized text.

Table 7–3 lists the tags that represent the input components.

TABLE 7–3 Input Tags

Tag	Function
`h:inputHidden`	Allows a page author to include a hidden variable in a page
`h:inputSecret`	The standard password field: accepts one line of text with no spaces and displays it as a set of asterisks as it is typed
`h:inputText`	The standard text field: accepts a one-line text string
`h:inputTextarea`	The standard text area: accepts multiple lines of text

The input tags support the tag attributes shown in Table 7–4 in addition to those described in "Common Component Tag Attributes" on page 143. Note that this table does not include all the attributes supported by the input tags but just those that are used most often. For the complete list of attributes, refer to the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

TABLE 7–4 Input Tag Attributes

Attribute	Description
`converter`	Identifies a converter that will be used to convert the component's local data. See "Using the Standard Converters" on page 171 for more information on how to use this attribute.
`converterMessage`	Specifies an error message to display when the converter registered on the component fails.

TABLE 7–4 Input Tag Attributes *(Continued)*

Attribute	Description
`dir`	Specifies the direction of the text displayed by this component. Acceptable values are `LTR`, meaning left-to-right, and `RTL`, meaning right-to-left.
`label`	Specifies a name that can be used to identify this component in error messages.
`lang`	Specifies the code for the language used in the rendered markup, such as `en_US`.
`required`	Takes a `boolean` value that indicates whether the user must enter a value in this component.
`requiredMessage`	Specifies an error message to display when the user does not enter a value into the component.
`validator`	Identifies a method expression pointing to a backing bean method that performs validation on the component's data. See "Referencing a Method That Performs Validation" on page 181 for an example of using the `f:validator` tag.
`f:validatorMessage`	Specifies an error message to display when the validator registered on the component fails to validate the component's local value.
`valueChangeListener`	Identifies a method expression that points to a backing bean method that handles the event of entering a value in this component. See "Referencing a Method That Handles a Value-Change Event" on page 182 for an example of using `valueChangeListener`.

Table 7–5 lists the tags that represent the output components.

TABLE 7–5 Output Tags

Tag	Function
`h:outputFormat`	Displays a localized message
`h:outputLabel`	The standard read-only label: displays a component as a label for a specified input field
`h:outputLink`	Displays an `<a href>` tag that links to another page without generating an action event
`h:outputText`	Displays a one-line text string

The output tags support the `converter` tag attribute in addition to those listed in "Common Component Tag Attributes" on page 143.

The rest of this section explains how to use some of the tags listed in Table 7–3 and Table 7–5. The other tags are written in a similar way.

Rendering a Text Field with the `h:inputText` Tag

The `h:inputText` tag is used to display a text field. A similar tag, the `h:outputText` tag, displays a read-only, single-line string. This section shows you how to use the `h:inputText` tag. The `h:outputText` tag is written in a similar way.

Here is an example of an `h:inputText` tag:

```
<h:inputText id="name" label="Customer Name" size="50"
    value="#{cashier.name}"
    required="true"
    requiredMessage="#{customMessages.CustomerName}">
    <f:valueChangeListener
        type="com.sun.bookstore6.listeners.NameChanged" />
 </h:inputText>
```

The `label` attribute specifies a user-friendly name that will be used in the substitution parameters of error messages displayed for this component.

The `value` attribute refers to the `name` property of a backing bean named `CashierBean`. This property holds the data for the `name` component. After the user submits the form, the value of the `name` property in `CashierBean` will be set to the text entered in the field corresponding to this tag.

The `required` attribute causes the page to reload, displaying errors, if the user does not enter a value in the `name` text field. The JavaServer Faces implementation checks whether the value of the component is null or is an empty string.

If your component must have a non-null value or a `String` value at least one character in length, you should add a `required` attribute to your tag and set its value to `true`. If your tag has a `required` attribute that is set to `true` and the value is null or a zero-length string, no other validators that are registered on the tag are called. If your tag does not have a `required` attribute set to `true`, other validators that are registered on the tag are called, but those validators must handle the possibility of a null or zero-length string. See "Validating Null and Empty Strings" on page 201 for more information.

Rendering a Password Field with the `h:inputSecret` Tag

The `h:inputSecret` tag renders an `<input type="password">` HTML tag. When the user types a string into this field, a row of asterisks is displayed instead of the text typed by the user. Here is an example:

```
<h:inputSecret redisplay="false"
    value="#{LoginBean.password}" />
```

In this example, the `redisplay` attribute is set to `false`. This will prevent the password from being displayed in a query string or in the source file of the resulting HTML page.

Rendering a Label with the `h:outputLabel` Tag

The `h:outputLabel` tag is used to attach a label to a specified input field for the purpose of making it accessible. The following page uses an `h:outputLabel` tag to render the label of a check box:

```
<h:selectBooleanCheckbox
     id="fanClub"
     binding="#{cashier.specialOffer}" />
<h:outputLabel for="fanClub"
     binding="#{cashier.specialOfferText}" >
   <h:outputText id="fanClubLabel"
        value="#{bundle.DukeFanClub}" />
</h:outputLabel>
...
```

The `for` attribute of the `h:outputLabel` tag maps to the `id` of the input field to which the label is attached. The `h:outputText` tag nested inside the `h:outputLabel` tag represents the label component. The `value` attribute on the `h:outputText` tag indicates the text that is displayed next to the input field.

Instead of using an `h:outputText` tag for the text displayed as a label, you can simply use the `h:outputLabel` tag's `value` attribute. The following code snippet shows what the previous code snippet would look like if it used the `value` attribute of the `h:outputLabel` tag to specify the text of the label:

```
<h:selectBooleanCheckbox
     id="fanClub"
     binding="#{cashier.specialOffer}" />
<h:outputLabel for="fanClub"
     binding="#{cashier.specialOfferText}"
     value="#{bundle.DukeFanClub}" />
</h:outputLabel>
...
```

Rendering a Hyperlink with the `h:outputLink` Tag

The `h:outputLink` tag is used to render a hyperlink that, when clicked, loads another page but does not generate an action event. You should use this tag instead of the `h:commandLink` tag if you always want the URL specified by the `h:outputLink` tag's `value` attribute to open and do not want any processing to be performed when the user clicks the link. Here is an example:

```
<h:outputLink value="javadocs">
    Documentation for this demo
</h:outputLink>
```

The text in the body of the `outputLink` tag identifies the text that the user clicks to get to the next page.

Displaying a Formatted Message with the `h:outputFormat` Tag

The `h:outputFormat` tag allows display of concatenated messages as a `MessageFormat` pattern, as described in the API documentation for `java.text.MessageFormat`. Here is an example of an `outputFormat` tag:

```
<h:outputFormat value="Hello, {0}!">
    <f:param value="#{hello.name}"/>
</h:outputFormat>
```

The `value` attribute specifies the `MessageFormat` pattern. The `param` tag specifies the substitution parameters for the message. The value of the parameter replaces the `{0}` in the sentence. If the value of `"#{hello.name}"` is "Bill", the message displayed in the page is as follows:

```
Hello, Bill!
```

An `h:outputFormat` tag can include more than one `param` tag for those messages that have more than one parameter that must be concatenated into the message. If you have more than one parameter for one message, make sure that you put the `param` tags in the proper order so that the data is inserted in the correct place in the message. Here is the preceding example modified with an additional parameter:

```
<h:outputFormat value="Hello, {0}! You are visitor number {1} to the page.">
<f:param value="#{hello.name}" />
<f:param value="#{bean.numVisitor}"/>
</h:outputFormat>
```

The value of `{1}` is replaced by the second parameter. The parameter is an EL expression, `bean.numVisitor`, where the property `numVisitor` of the backing bean `bean` keeps track of visitors to the page. This is an example of a value-expression-enabled tag attribute accepting an EL expression. The message displayed in the page is now as follows:

```
Hello, Bill! You are visitor number 10 to the page.
```

Using Command Component Tags for Performing Actions and Navigation

In JavaServer Faces applications, the button and hyperlink component tags are used to perform actions, such as submitting a form, and for navigating to another page. These tags are called command component tags because they perform an action when activated.

The `h:commandButton` tag is rendered as a button. The `h:commandLink` tag is rendered as a hyperlink.

In addition to the tag attributes listed in "Common Component Tag Attributes" on page 143, the `h:commandButton` and `h:commandLink` tags can use the following attributes:

- `action`, which is either a logical outcome `String` or a method expression pointing to a bean method that returns a logical outcome `String`. In either case, the logical outcome `String` is used to determine what page to access when the command component tag is activated.
- `actionListener`, which is a method expression pointing to a bean method that processes an action event fired by the command component tag.

See "Referencing a Method That Performs Navigation" on page 181 for more information on using the `action` attribute. See "Referencing a Method That Handles an Action Event" on page 181 for details on using the `actionListener` attribute.

Rendering a Button with the `h:commandButton` Tag

If you are using a `commandButton` component tag, the data from the current page is processed when a user clicks the button, and the next page is opened. Here is an example of the `h:commandButton` tag:

```
<h:commandButton value="Submit"
     action="#{cashier.submit}"/>
```

Clicking the button will cause the `submit` method of `CashierBean` to be invoked because the `action` attribute references this method. The `submit` method performs some processing and returns a logical outcome.

The `value` attribute of the example `commandButton` tag references the button's label. For information on how to use the `action` attribute, see "Referencing a Method That Performs Navigation" on page 181.

Rendering a Hyperlink with the `h:commandLink` Tag

The `h:commandLink` tag represents an HTML hyperlink and is rendered as an HTML `<a>` element. This tag acts like a form's Submit button and is used to submit an action event to the application.

A `h:commandLink` tag must include a nested `h:outputText` tag, which represents the text that the user clicks to generate the event. Here is an example:

```
<h:commandLink id="NAmerica" action="bookstore"
     actionListener="#{localeBean.chooseLocaleFromLink}">
     <h:outputText value="#{bundle.English}" />
</h:commandLink>
```

This tag will render the following HTML:

```
<a id="_id3:NAmerica" href="#"
     onclick="document.forms['_id3']['_id3:NAmerica'].
```

```
value='_id3:NAmerica';
document.forms['_id3'].submit();
return false;">English</a>
```

Note – The `h:commandLink` tag will render JavaScript programming language. If you use this tag, make sure that your browser is enabled for JavaScript technology.

Adding Graphics and Images with the `h:graphicImage` Tag

In a JavaServer Faces application, use the `h:graphicImage` tag to render an image on a page:

```
<h:graphicImage id="mapImage" url="/template/world.jpg"/>
```

The `url` attribute specifies the path to the image. The URL of the example tag begins with a `/`, which adds the relative context path of the web application to the beginning of the path to the image.

Alternatively, you can use the facility described in "Resources" on page 124 to point to the image location. Here is an example:

```
<h:graphicImage value="#{resource['images:wave.med.gif']}"/>
```

Laying Out Components with the `h:panelGrid` and `h:panelGroup` Tags

In a JavaServer Faces application, you use a panel as a layout container for a set of other components. A panel is rendered as an HTML table. Table 7–6 lists the tags used to create panels.

TABLE 7–6 Panel Component Tags

Tag	Attributes	Function
`h:panelGrid`	`columns`, `columnClasses`, `footerClass`, `headerClass`, `panelClass`, `rowClasses`	Displays a table
`h:panelGroup`	`layout`	Groups a set of components under one parent

The `h:panelGrid` tag is used to represent an entire table. The `h:panelGroup` tag is used to represent rows in a table. Other tags are used to represent individual cells in the rows.

The `columns` attribute defines how to group the data in the table and therefore is required if you want your table to have more than one column. The `h:panelGrid` tag also has a set of optional attributes that specify CSS classes: `columnClasses`, `footerClass`, `headerClass`, `panelClass`, and `rowClasses`.

If the `headerClass` attribute value is specified, the `panelGrid` must have a header as its first child. Similarly, if a `footerClass` attribute value is specified, the `panelGrid` must have a footer as its last child.

Here is an example:

```
<h:panelGrid columns="3" headerClass="list-header"
    rowClasses="list-row-even, list-row-odd"
    styleClass="list-background"
    title="#{bundle.Checkout}">
    <f:facet name="header">
        <h:outputText value="#{bundle.Checkout}"/>
    </f:facet>
    <h:outputText value="#{bundle.Name}" />
    <h:inputText id="name" size="50"
         value="#{cashier.name}"
        required="true">
         <f:valueChangeListener
             type="listeners.NameChanged" />
    </h:inputText>
    <h:message styleClass="validationMessage" for="name"/>
    <h:outputText value="#{bundle.CCNumber}"/>
    <h:inputText id="ccno" size="19"
        converter="CreditCardConverter" required="true">
         <bookstore:formatValidator
             formatPatterns="9999999999999999|
                9999 9999 9999 9999|9999-9999-9999-9999"/>
    </h:inputText>
    <h:message styleClass="validationMessage"  for="ccno"/>
    ...
</h:panelGrid>
```

The preceding `h:panelGrid` tag is rendered as a table that contains components in which a customer inputs personal information. This `h:panelGrid` tag uses style sheet classes to format the table. The following code shows the `list-header` definition:

```
.list-header {
    background-color: #ffffff;
    color: #000000;
    text-align: center;
}
```

Because the `h:panelGrid` tag specifies a `headerClass`, the `panelGrid` must contain a header. The example `panelGrid` tag uses a `facet` tag for the header. Facets can have only one child, so an `h:panelGroup` tag is needed if you want to group more than one component within a `facet`. The example `h:panelGrid` tag has only one cell of data, so an `h:panelGroup` tag is not needed.

The `h:panelGroup` tag has an attribute, `layout`, in addition to those listed in "Common Component Tag Attributes" on page 143. If the `layout` attribute has the value `block`, an HTML

`div` element is rendered to enclose the row; otherwise, an HTML `span` element is rendered to enclose the row. If you are specifying styles for the `h:panelGroup` tag, you should set the `layout` attribute to `block` in order for the styles to be applied to the components within the `h:panelGroup` tag. You should do this because styles, such as those that set width and height, are not applied to inline elements, which is how content enclosed by the `span` element is defined.

An `h:panelGroup` tag can also be used to encapsulate a nested tree of components so that the tree of components appears as a single component to the parent component.

Data, represented by the nested tags, is grouped into rows according to the value of the `columns` attribute of the `h:panelGrid` tag. The `columns` attribute in the example is set to `3`, and therefore the table will have three columns. The column in which each component is displayed is determined by the order in which the component is listed on the page modulo 3. So, if a component is the fifth one in the list of components, that component will be in the 5 modulo 3 column, or column 2.

Displaying Components for Selecting One Value

Another commonly used component is one that allows a user to select one value, whether it is the only value available or one of a set of choices. The most common tags for this kind of component are as follows:

- An `h:selectBooleanCheckbox` tag, displayed as a check box, which represents a Boolean state
- An `h:selectOneRadio` tag, displayed as a set of radio buttons
- An `h:selectOneMenu` tag, displayed as a drop-down menu, with a scrollable list
- An `h:selectOneListbox` tag, displayed as a list box, with an unscrollable list

Figure 7–3 shows examples of these components.

FIGURE 7–3 Example Components for Selecting One Item



Displaying a Check Box Using the `h:selectBooleanCheckbox` Tag

The `h:selectBooleanCheckbox` tag is the only tag that JavaServer Faces technology provides for representing a Boolean state.

Here is an example that shows how to use the `h:selectBooleanCheckbox` tag:

```
<h:selectBooleanCheckbox
    id="fanClub"
    rendered="false"
    binding="#{cashier.specialOffer}" />
<h:outputLabel
    for="fanClub"
    rendered="false"
    binding="#{cashier.specialOfferText}">
     <h:outputText
        id="fanClubLabel"
        value="#{bundle.DukeFanClub}" />
</h:outputLabel>
```

This example tag displays a check box to allow users to indicate whether they want to join the Duke Fan Club. The label for the check box is rendered by the `outputLabel` tag. The text is represented by the nested `outputText` tag.

Displaying a Menu Using the `h:selectOneMenu` Tag

A component that allows the user to select one value from a set of values can be rendered as a list box, a set of radio buttons, or a menu. This section describes the `h:selectOneMenu` tag. The `h:selectOneRadio` and `h:selectOneListbox` tags are used in a similar way. The `h:selectOneListbox` tag is similar to the `h:selectOneMenu` tag except that `h:selectOneListbox` defines a `size` attribute that determines how many of the items are displayed at once.

The `h:selectOneMenu` tag represents a component that contains a list of items from which a user can choose one item. This menu component is also commonly known as a drop-down list or a combo box. The following code snippet shows how the `h:selectOneMenu` tag is used to allow the user to select a shipping method:

```
<h:selectOneMenu id="shippingOption"
    required="true"
    value="#{cashier.shippingOption}">
    <f:selectItem
        itemValue="2"
        itemLabel="#{bundle.QuickShip}"/>
    <f:selectItem
        itemValue="5"
        itemLabel="#{bundle.NormalShip}"/>
    <f:selectItem
        itemValue="7"
        itemLabel="#{bundle.SaverShip}"/>
 </h:selectOneMenu>
```

The `value` attribute of the `h:selectOneMenu` tag maps to the property that holds the currently selected item's value. You are not required to provide a value for the currently selected item. If you don't provide a value, the first item in the list is selected by default.

Like the `h:selectOneRadio` tag, the `selectOneMenu` tag must contain either an `f:selectItems` tag or a set of `f:selectItem` tags for representing the items in the list. "Using the `f:selectItem` and `f:selectItems` Tags" on page 159 describes these tags.

Displaying Components for Selecting Multiple Values

In some cases, you need to allow your users to select multiple values rather than just one value from a list of choices. You can do this using one of the following component tags:

- An `h:selectManyCheckbox` tag, displayed as a set of check boxes
- An `h:selectManyMenu` tag, displayed as a drop-down menu
- An `h:selectManyListbox` tag, displayed as a list box

Figure 7–4 shows examples of these components.

FIGURE 7–4 Example Components for Selecting Multiple Values



These tags allow the user to select zero or more values from a set of values. This section explains the `h:selectManyCheckbox` tag. The `h:selectManyListbox` and `h:selectManyMenu` tags are used in a similar way.

Unlike a menu, a list box displays a subset of items in a box; a menu displays only one item at a time when the user is not selecting the menu. The `size` attribute of the `h:selectManyListbox` tag determines the number of items displayed at one time. The list box includes a scroll bar for scrolling through any remaining items in the list.

The `h:selectManyCheckbox` tag renders a set of check boxes, with each check box representing one value that can be selected:

```
<h:selectManyCheckbox
    id="newsletters"
    layout="pageDirection"
    value="#{cashier.newsletters}">
    <f:selectItems
        value="#{newsletters}"/>
</h:selectManyCheckbox>
```

The `value` attribute of the `h:selectManyCheckbox` tag identifies the `newsletters` property of the `Cashier` backing bean. This property holds the values of the currently selected items from the set of check boxes. You are not required to provide a value for the currently selected items. If you don't provide a value, the first item in the list is selected by default.

The `layout` attribute indicates how the set of check boxes is arranged on the page. Because layout is set to `pageDirection`, the check boxes are arranged vertically. The default is `lineDirection`, which aligns the check boxes horizontally.

The `h:selectManyCheckbox` tag must also contain a tag or set of tags representing the set of check boxes. To represent a set of items, you use the `f:selectItems` tag. To represent each item individually, you use a `f:selectItem` tag. The following subsection explains these tags in more detail.

Using the `f:selectItem` and `f:selectItems` Tags

The `f:selectItem` and `f:selectItems` tags represent components that can be nested inside a component that allows you to select one or multiple items. An `f:selectItem` tag contains the value, label, and description of a single item. An `f:selectItems` tag contains the values, labels, and descriptions of the entire list of items.

You can use either a set of `f:selectItem` tags or a single `f:selectItems` tag within your component tag.

The advantages of using the `f:selectItems` tag are as follows.

- Items can be represented by using different data structures, including `Array`, `Map`, and `Collection`. The value of the `f:selectItems` tag can represent even a generic collection of POJOs.
- Different lists can be concatenated into a single component, and the lists can be grouped within the component.
- Values can be generated dynamically at runtime.

The advantages of using `f:selectItem` are as follows:

- Items in the list can be defined from the page.
- Less code is needed in the bean for the `selectItem` properties.

The rest of this section shows you how to use the `f:selectItems` and `f:selectItem` tags.

Using the `f:selectItems` Tag

The following example from "Displaying Components for Selecting Multiple Values" on page 157 shows how to use the `h:selectManyCheckbox` tag:

```
<h:selectManyCheckbox
    id="newsletters"
    layout="pageDirection"
    value="#{cashier.newsletters}">
    <f:selectItems
        value="#{newsletters}"/>
</h:selectManyCheckbox>
```

The `value` attribute of the `f:selectItems` tag is bound to the backing bean `newsletters`.

You can also create the list of items programmatically in the backing bean. See "Writing Bean Properties" on page 186 for information on how to write a backing bean property for one of these tags.

Using the `f:selectItem` Tag

The `f:selectItem` tag represents a single item in a list of items. Here is the example from "Displaying a Menu Using the `h:selectOneMenu` Tag" on page 156 once again:

```
<h:selectOneMenu
      id="shippingOption" required="true"
      value="#{cashier.shippingOption}">
    <f:selectItem
        itemValue="2"
        itemLabel="#{bundle.QuickShip}"/>
    <f:selectItem
        itemValue="5"
        itemLabel="#{bundle.NormalShip}"/>
    <f:selectItem
        itemValue="7"
        itemLabel="#{bundle.SaverShip}"/>
 </h:selectOneMenu>
```

The `itemValue` attribute represents the default value for the `selectItem` tag. The `itemLabel` attribute represents the `String` that appears in the drop-down menu component on the page.

The `itemValue` and `itemLabel` attributes are value-binding-enabled, meaning that they can use value-binding expressions to refer to values in external objects. These attributes can also define literal values, as shown in the example `h:selectOneMenu` tag.

Using Data-Bound Table Components

Data-bound table components display relational data in a tabular format. In a JavaServer Faces application, the `h:dataTable` component tag supports binding to a collection of data objects and displays the data as an HTML table. The `h:column` tag represents a column of data within the table, iterating over each record in the data source, which is displayed as a row. Here is an example:

```
<h:dataTable id="items"
    captionClass="list-caption"
    columnClasses="list-column-center, list-column-left,
         list-column-right, list-column-center"
    footerClass="list-footer"
    headerClass="list-header"
    rowClasses="list-row-even, list-row-odd"
    styleClass="list-background">
    <h:column headerClass="list-header-left">
        <f:facet name="header">
            <h:outputText value=Quantity"" />
        </f:facet>
        <h:inputText id="quantity" size="4"
            value="#{item.quantity}" >
            ...
        </h:inputText>
        ...
    </h:column>
    <h:column>
        <f:facet name="header">
            <h:outputText value="Title"/>
        </f:facet>
        <h:commandLink>
            <h:outputText value="#{item.title}"/>
```

```
        </h:commandLink>
    </h:column>
    ...
    <f:facet name="footer"
        <h:panelGroup>
            <h:outputText value="Total}"/>
            <h:outputText value="#{cart.total}" />
                <f:convertNumber type="currency" />
            </h:outputText>
        </h:panelGroup>
    </f:facet>
</h:dataTable>
```

Figure 7–5 shows a data grid that this `h:dataTable` tag can display.

FIGURE 7–5 Table on a Web Page

Quantity	Title	Price	
1	Web Servers for Fun and Profit	$40.75	Remove Item
3	Web Components for Web Developers	$27.75	Remove Item
1	From Oak to Java: The Revolution of a Language	$10.75	Remove Item
2	My Early Years: Growing up on *7	$30.75	Remove Item
1	Java Intermediate Bytecodes	$30.95	Remove Item
3	Duke: A Biography of the Java Evangelist	$45.00	Remove Item
	Subtotal:$362.20		

Update Quantities

The example `h:dataTable` tag displays the books in the shopping cart, as well as the quantity of each book in the shopping cart, the prices, and a set of buttons the user can click to remove books from the shopping cart.

The `h:column` tags represent columns of data in a data component. While the data component is iterating over the rows of data, it processes the column component associated with each `h:column` tag for each row in the table.

The `h:dataTable` tag shown in the preceding code example iterates through the list of books (`cart.items`) in the shopping cart and displays their titles, authors, and prices. Each time the `h:dataTable` tag iterates through the list of books, it renders one cell in each column.

The `h:dataTable` and `h:column` tags use facets to represent parts of the table that are not repeated or updated. These parts include headers, footers, and captions.

In the preceding example, `h:column` tags include `f:facet` tags for representing column headers or footers. The `h:column` tag allows you to control the styles of these headers and footers by supporting the `headerClass` and `footerClass` attributes. These attributes accept space-separated lists of CSS classes, which will be applied to the header and footer cells of the corresponding column in the rendered table.

Facets can have only one child, so an `h:panelGroup` tag is needed if you want to group more than one component within an `f:facet`. Because the facet tag representing the footer includes more than one tag, the `panelGroup` is needed to group those tags. Finally, this `h:dataTable` tag includes an `f:facet` tag with its `name` attribute set to `caption`, causing a table caption to be rendered below the table.

This table is a classic use case for a data component because the number of books might not be known to the application developer or the page author when that application is developed. The data component can dynamically adjust the number of rows of the table to accommodate the underlying data.

The `value` attribute of an `h:dataTable` tag references the data to be included in the table. This data can take the form of any of the following:

- A list of beans
- An array of beans
- A single bean
- A `javax.faces.model.DataModel` object
- A `java.sql.ResultSet` object
- A `javax.servlet.jsp.jstl.sql.Result` object
- A `javax.sql.RowSet` object

All data sources for data components have a `DataModel` wrapper. Unless you explicitly construct a `DataModel` wrapper, the JavaServer Faces implementation will create one around data of any of the other acceptable types. See "Writing Bean Properties" on page 186 for more information on how to write properties for use with a data component.

The `var` attribute specifies a name that is used by the components within the `h:dataTable` tag as an alias to the data referenced in the `value` attribute of `dataTable`.

In the example `h:dataTable` tag, the `value` attribute points to a list of books. The `var` attribute points to a single book in that list. As the `h:dataTable` tag iterates through the list, each reference to `item` points to the current book in the list.

The `h:dataTable` tag also has the ability to display only a subset of the underlying data. This feature is not shown in the preceding example. To display a subset of the data, you use the optional `first` and `rows` attributes.

The `first` attribute specifies the first row to be displayed. The `rows` attribute specifies the number of rows, starting with the first row, to be displayed. For example, if you wanted to display records 2 through 10 of the underlying data, you would set `first` to 2 and `rows` to 9. When you display a subset of the data in your pages, you might want to consider including a link or button that causes subsequent rows to display when clicked. By default, both `first` and `rows` are set to zero, and this causes all the rows of the underlying data to display.

Table 7–7 shows the optional attributes for the `h:dataTable` tag.

TABLE 7–7 Optional Attributes for the `h:dataTable` Tag

Attribute	Defines Styles for
`captionClass`	Table caption
`columnClasses`	All the columns
`footerClass`	Footer
`headerClass`	Header
`rowClasses`	Rows
`styleClass`	The entire table

Each of the attributes in Table 7–7 can specify more than one style. If `columnClasses` or `rowClasses` specifies more than one style, the styles are applied to the columns or rows in the order that the styles are listed in the attribute. For example, if `columnClasses` specifies styles `list-column-center` and `list-column-right` and if the table has two columns, the first column will have style `list-column-center`, and the second column will have style `list-column-right`.

If the style attribute specifies more styles than there are columns or rows, the remaining styles will be assigned to columns or rows starting from the first column or row. Similarly, if the style attribute specifies fewer styles than there are columns or rows, the remaining columns or rows will be assigned styles starting from the first style.

Displaying Error Messages with the `h:message` and `h:messages` Tags

The `h:message` and `h:messages` tags are used to display error messages when conversion or validation fails. The `h:message` tag displays error messages related to a specific input component, whereas the `h:messages` tag displays the error messages for the entire page.

Here is an example `h:message` tag from the `guessnumber` application:

```
<h:inputText id="userNo" value="#{UserNumberBean.userNumber}">
    <f:validateLongRange minimum="0" maximum="10" />
 <h:commandButton id="submit"
         action="success" value="Submit" /><p>
<h:message
     style="color: red;
     font-family: 'New Century Schoolbook', serif;
     font-style: oblique;
     text-decoration: overline" id="errors1" for="userNo"/>
```

The `for` attribute refers to the ID of the component that generated the error message. The error message is displayed at the same location that the `h:message` tag appears in the page. In this case, the error message will appear after the Submit button.

The `style` attribute allows you to specify the style of the text of the message. In the example in this section, the text will be red, New Century Schoolbook, serif font family, and oblique style, and a line will appear over the text. The message and messages tags support many other attributes for defining styles. For more information on these attributes, refer to the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

Another attribute supported by the `h:messages` tag is the `layout` attribute. Its default value is `list`, which indicates that the messages are displayed in a bullet list using the HTML `ul` and `li` elements. If you set the attribute value to `table`, the messages will be rendered in a table using the HTML `table` element.

The preceding example shows a standard validator that is registered on the input component. The message tag displays the error message that is associated with this validator when the validator cannot validate the input component's value. In general, when you register a converter or validator on a component, you are queueing the error messages associated with the converter or validator on the component. The `h:message` and `h:messages` tags display the appropriate error messages that are queued on the component when the validators or converters registered on that component fail to convert or validate the component's value.

Standard error messages are provided with standard converters and standard validators. An application architect can override these standard messages and supply error messages for custom converters and validators by registering custom error messages with the application.

Creating Bookmarkable URLs with the `h:button` and `h:link` Tags

The ability to create bookmarkable URLs refers to the ability to generate hyperlinks based on a specified navigation outcome and on component parameters.

In HTTP, most browsers by default send GET requests for URL retrieval and POST requests for data processing. The GET requests can have query parameters and can be cached, which is not advised for POST requests, which send data to the external servers. The other JavaServer Faces tags capable of generating hyperlinks use either simple GET requests, as in the case of `h:outputlink`, or POST requests, as in the case of `h:commandLink` or `h:commandButton` tags. GET requests with query parameters provide finer granularity to URL strings. These URLs are created with one or more `name=value` parameters appended to the simple URL after a `?` character and separated by either `&;` or `&` strings.

To create a bookmarkable URL, use an `h:link` or `h:button` tag. Both of these tags can generate a hyperlink based on the `outcome` attribute of the component. For example:

```
<h:link outcome="response" value="Message">
  <f:param name="Result" value="#{sampleBean.result}"/>
</h:link>
```

The `h:link` tag will generate a URL link that points to the `response.xhtml` file on the same server, appended with the single query parameter created by the `f:param` tag. When processed, the parameter `Result` is assigned the value of backing bean's result method `#{sampleBean.result}`. The following sample HTML is generated from the preceding set of tags, assuming that the value of the parameter is `success`:

```
<a href="http://localhost:8080/guessnumber/response.xhtml?Result=success">Response</a>
```

This is a simple GET request. To create more complex GET requests and utilize the complete functionality of the `h:link` tag, you can use view parameters.

Using View Parameters to Configure Bookmarkable URLs

The core tags `f:metadata` and `f:viewparam` are used as a source of parameters for configuring the URLs. View parameters are declared as part of `f:metadata` for a page, as shown in the following example:

```
<h:body>
<f:metadata>
  <f:viewParam id="name" name="Name" value="#{sampleBean.username}"/>
  <f:viewParam id="ID" name="uid" value="#{sampleBean.useridentity}"/>
</f:metadata>
<h:link outcome="response" value="Message" includeViewParams="true">
</h:link>
</h:body>
```

View parameters are declared with the `f:viewparam` tag and are placed inside the `f:metadata` tag. If the `includeViewParams` attribute is set on the component, the view parameters are added to the hyperlink.

The resulting URL will look like this:

```
http://localhost:8080/guessnumber/response.xhtml?Name=Duke&;uid=2001
```

Because the URL can be the result of various parameter values, the order of the URL creation has been predefined. The order in which the various parameter values are read is as follows:

1. Component
2. Navigation-case parameters
3. View parameters

Resource Relocation Using `h:output` Tags

Resource relocation refers to the ability of a JavaServer Faces application to specify the location where a resource can be rendered. Resource relocation can be defined with the following HTML tags:

- `h:outputScript`
- `h:outputStylesheet`

These tags have `name` and `target` attributes, which can be used to define the render location. For a complete list of attributes for these tags, see the documentation at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/facelets/`.

For the `h:outputScript` tag, the name and target attributes define where the output of a resource may appear. Here is an example:

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head id="head">
        <title>Resource Relocation</title>
    </h:head>
    <h:body id="body">
        <h:form id="form">
            <h:outputScript name="hello.js"/>
            <h:outputStylesheet name="hello.css"/>
        </h:form>
    </h:body>
</html>
```

Since the `target` attribute is not defined in the tag, the style sheet `hello.css` is rendered in the head, and the `hello.js` script is rendered in the body of the page as defined by the `h:head` tag.

Here is the HTML generated by the preceding code:

```
<html xmlns="http://www.w3.org/1999/xhtml">
    <head>
        <title>Resource Relocation</title>
        <link type="text/css" rel="stylesheet"
              href="/ctx/faces/javax.faces.resource/hello.css"/>
    </head>
    <body>
        <form id="form" name="form" method="post" action="..." enctype="...">
            <script type="text/javascript"
             src="/ctx/faces/javax.faces.resource/hello.js">
            </script>
        </form>
    </body>
</html>
```

The original page can be recreated by setting the `target` attribute for the `h:outputScript` tag, which allows the incoming GET request to provide the location parameter. Here is an example:

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head id="head">
        <title>Resource Relocation</title>
    </h:head>
    <h:body id="body">
        <h:form id="form">
            <h:outputScript name="hello.js" target="#{param.location}"/>
            <h:outputStylesheet name="hello.css"/>
        </h:form>
    </h:body>
</html>
```

In this case, if the incoming request does not provide a location parameter, the default locations will still apply: The style sheet is rendered in the head, and the script is rendered inline. However, if the incoming request provides the location parameter as the head, both the style sheet and the script will be rendered in the head element.

The HTML generated by the preceding code is as follows:

```
<html xmlns="http://www.w3.org/1999/xhtml">
    <head>
        <title>Resource Relocation</title>
        <link type="text/css" rel="stylesheet"
              href="/ctx/faces/javax.faces.resource/hello.css"/>
          <script type="text/javascript"
           src="/ctx/faces/javax.faces.resource/hello.js">
          </script>
    </head>
    <body>
        <form id="form" name="form" method="post" action="..." enctype="...">
        </form>
    </body>
</html>
```

Similarly, if the incoming request provides the location parameter as the body, the script will be rendered in the body element.

The preceding section describes simple uses for resource relocation. That feature can add even more functionality for the components and pages. A page author does not have to know the location of a resource or its placement.

By using a `@ResourceDependency` annotation for the components, component authors can define the resources for the component, such as a style sheet and script. This allows the page authors freedom from defining resource locations.

Using Core Tags

The tags included in the JavaServer Faces core tag library are used to perform core actions that are not performed by HTML tags. Commonly used core tags, along with the functions they perform, are listed in Table 7–8.

TABLE 7–8 The Core Tags

Tag Categories	Tags	Functions
Event handling	`f:actionListener`	Adds an action listener to a parent component
	`f:phaseListener`	Adds a `PhaseListener` to a page
	`f:setPropertyActionListener`	Registers a special action listener whose sole purpose is to push a value into a backing bean when a form is submitted
	`f:valueChangeListener`	Adds a value-change listener to a parent component
Attribute configuration	`f:attribute`	Adds configurable attributes to a parent component
Data conversion	`f:converter`	Adds an arbitrary converter to the parent component
	`f:convertDateTime`	Adds a `DateTimeConverter` instance to the parent component
	`f:convertNumber`	Adds a `NumberConverter` instance to the parent component
Facet	`f:facet`	Adds a nested component that has a special relationship to its enclosing tag
	`f:metadata`	Registers a `facet` on a parent component
Localization	`f:loadBundle`	Specifies a `ResourceBundle` that is exposed as a `Map`
Parameter substitution	`f:param`	Substitutes parameters into a `MessageFormat` instance and adds query string name-value pairs to a URL
Representing items in a list	`f:selectItem`	Represents one item in a list of items
	`f:selectItems`	Represents a set of items

TABLE 7–8 The Core Tags *(Continued)*

Tag Categories	Tags	Functions
Validator	`f:validateDoubleRange`	Adds a `DoubleRangeValidator` to a component
	`f:validateLength`	Adds a `LengthValidator` to a component
	`f:validateLongRange`	Adds a `LongRangeValidator` to a component
	`f:validator`	Adds a custom validator to a component
	`f:validateRegEx`	Adds a `RegExValidator` to a component
	`f:validateBean`	Delegates the validation of a local value to a `BeanValidator`
	`f:validateRequired`	Enforces the presence of a value in a component
Ajax	`f:ajax`	Associates an Ajax action with a single component or a group of components based on placement
Event	`f:event`	Allows installing a `ComponentSystemEventListener` on a component

These tags, which are used in conjunction with component tags, are explained in other sections of this tutorial. Table 7–9 lists the sections that explain how to use specific core tags.

TABLE 7–9 Where the Core Tags Are Explained

Tags	Where Explained
Event handling tags	"Registering Listeners on Components" on page 176
Data conversion tags	"Using the Standard Converters" on page 171
`facet`	"Using Data-Bound Table Components" on page 160 and "Laying Out Components with the `h:panelGrid` and `h:panelGroup` Tags" on page 153
`loadBundle`	"Displaying Components for Selecting Multiple Values" on page 157
`param`	"Displaying a Formatted Message with the `h:outputFormat` Tag" on page 151
`selectItem` and `selectItems`	"Using the `f:selectItem` and `f:selectItems` Tags" on page 159
Validator tags	"Using the Standard Validators" on page 178

◆ ◆ ◆ CHAPTER 8

Using Converters, Listeners, and Validators

The previous chapter described components and explained how to add them to a web page. This chapter provides information on adding more functionality to the components through converters, listeners, and validators.

- Converters are used to convert data that is received from the input components.
- Listeners are used to listen to the events happening in the page and perform actions as defined.
- Validators are used to validate the data that is received from the input components.

The following topics are addressed here:

Using the Standard Converters

The JavaServer Faces implementation provides a set of `Converter` implementations that you can use to convert component data. The standard `Converter` implementations, located in the `javax.faces.convert` package, are as follows:

- `BigDecimalConverter`
- `BigIntegerConverter`
- `BooleanConverter`
- `ByteConverter`
- `CharacterConverter`
- `DateTimeConverter`
- `DoubleConverter`
- `EnumConverter`
- `FloatConverter`

- `IntegerConverter`
- `LongConverter`
- `NumberConverter`
- `ShortConverter`

A standard error message is associated with each of these converters. If you have registered one of these converters onto a component on your page, and the converter is not able to convert the component's value, the converter's error message will display on the page. For example, the following error message appears if `BigIntegerConverter` fails to convert a value:

```
{0} must be a number consisting of one or more digits
```

In this case, the `{0}` substitution parameter will be replaced with the name of the input component on which the converter is registered.

Two of the standard converters (`DateTimeConverter` and `NumberConverter`) have their own tags, which allow you to configure the format of the component data using the tag attributes. For more information about using `DateTimeConverter`, see "Using `DateTimeConverter`" on page 173. For more information about using `NumberConverter`, see "Using `NumberConverter`" on page 175. The following section explains how to convert a component's value, including how to register other standard converters with a component.

Converting a Component's Value

To use a particular converter to convert a component's value, you need to register the converter onto the component. You can register any of the standard converters in one of the following ways:

- Nest one of the standard converter tags inside the component's tag. These tags are `convertDateTime` and `convertNumber`, which are described in "Using `DateTimeConverter`" on page 173 and "Using `NumberConverter`" on page 175, respectively.
- Bind the value of the component to a backing bean property of the same type as the converter.
- Refer to the converter from the component tag's `converter` attribute.
- Nest a `converter` tag inside of the component tag, and use either the `converter` tag's `converterId` attribute or its `binding` attribute to refer to the converter.

As an example of the second method, if you want a component's data to be converted to an `Integer`, you can simply bind the component's value to a backing bean property. Here is an example:

```
Integer age = 0;
public Integer getAge(){ return age;}
public void setAge(Integer age) {this.age = age;}
```

If the component is not bound to a bean property, you can use the third method by using the `converter` attribute directly on the component tag:

```
<h:inputText
    converter="javax.faces.convert.IntegerConverter" />
```

This example shows the `converter` attribute referring to the fully qualified class name of the converter. The `converter` attribute can also take the ID of the component.

The data from the `inputText` tag in the this example will be converted to a `java.lang.Integer` value. The `Integer` type is a supported type of `NumberConverter`. If you don't need to specify any formatting instructions using the `convertNumber` tag attributes, and if one of the standard converters will suffice, you can simply reference that converter by using the component tag's `converter` attribute.

Finally, you can nest a `converter` tag within the component tag and use either the converter tag's `converterId` attribute or its `binding` attribute to reference the converter.

The `converterId` attribute must reference the converter's ID. Here is an example:

```
<h:inputText value="#{LoginBean.Age}" />
    <f:converter converterId="Integer" />
</h:inputText>
```

Instead of using the `converterId` attribute, the `converter` tag can use the `binding` attribute. The `binding` attribute must resolve to a bean property that accepts and returns an appropriate `Converter` instance.

Using `DateTimeConverter`

You can convert a component's data to a `java.util.Date` by nesting the `convertDateTime` tag inside the component tag. The `convertDateTime` tag has several attributes that allow you to specify the format and type of the data. Table 8–1 lists the attributes.

Here is a simple example of a `convertDateTime` tag:

```
<h:outputText id= "shipDate" value="#{cashier.shipDate}">
    <f:convertDateTime dateStyle="full" />
</h:outputText>
```

When binding the `DateTimeConverter` to a component, ensure that the backing bean property to which the component is bound is of type `java.util.Date`. In the preceding example, `cashier.shipDate` must be of type `java.util.Date`.

The example tag can display the following output:

```
Saturday, September 25, 2010
```

You can also display the same date and time by using the following tag where the date format is specified:

```
<h:outputText value="#{cashier.shipDate}">
    <f:convertDateTime
         pattern="EEEEEEEE, MMM dd, yyyy" />
</h:outputText>
```

If you want to display the example date in Spanish, you can use the `locale` attribute:

```
<h:inputText value="#{cashier.shipDate}">
    <f:convertDateTime dateStyle="full"
        locale="Locale.SPAIN"
        timeStyle="long" type="both" />
</h:inputText>
```

This tag would display the following output:

```
sabado 25 de septiembre de 2010
```

Refer to the "Customizing Formats" lesson of the *Java Tutorial* at `http://download.oracle.com/javase/tutorial/i18n/format/simpleDateFormat.html` for more information on how to format the output using the `pattern` attribute of the `convertDateTime` tag.

TABLE 8–1 Attributes for the `convertDateTime` Tag

Attribute	Type	Description
`binding`	`DateTimeConverter`	Used to bind a converter to a backing bean property.
`dateStyle`	`String`	Defines the format, as specified by `java.text.DateFormat`, of a date or the date part of a `date` string. Applied only if `type` is `date` or `both` and if `pattern` is not defined. Valid values: `default`, `short`, `medium`, `long`, and `full`. If no value is specified, `default` is used.
`for`	`String`	Used with composite components. Refers to one of the objects within the composite component inside which this tag is nested.
`locale`	`String` or `Locale`	`Locale` whose predefined styles for dates and times are used during formatting or parsing. If not specified, the `Locale` returned by `FacesContext.getLocale` will be used.
`pattern`	`String`	Custom formatting pattern that determines how the date/time string should be formatted and parsed. If this attribute is specified, `dateStyle`, `timeStyle`, and `type` attributes are ignored.
`timeStyle`	`String`	Defines the format, as specified by `java.text.DateFormat`, of a `time` or the time part of a `date` string. Applied only if `type` is time and `pattern` is not defined. Valid values: `default`, `short`, `medium`, `long`, and `full`. If no value is specified, `default` is used.

TABLE 8–1 Attributes for the `convertDateTime` Tag *(Continued)*

Attribute	Type	Description
`timeZone`	`String` or `TimeZone`	Time zone in which to interpret any time information in the `date` string.
`type`	`String`	Specifies whether the string value will contain a date, a time, or both. Valid values are `date`, `time`, or `both`. If no value is specified, `date` is used.

Using `NumberConverter`

You can convert a component's data to a `java.lang.Number` by nesting the `convertNumber` tag inside the component tag. The `convertNumber` tag has several attributes that allow you to specify the format and type of the data. Table 8–2 lists the attributes.

The following example uses a `convertNumber` tag to display the total prices of the contents of a shopping cart:

```
<h:outputText value="#{cart.total}" >
    <f:convertNumber type="currency"/>
</h:outputText>
```

When binding the `NumberConverter` to a component, ensure that the backing bean property to which the component is bound is of a primitive type or has a type of `java.lang.Number`. In the preceding example, `cart.total` is of type `java.lang.Number`.

Here is an example of a number that this tag can display:

```
$934
```

This result can also be displayed by using the following tag, where the currency pattern is specified:

```
<h:outputText id="cartTotal"
     value="#{cart.Total}" >
    <f:convertNumber pattern="$####" />
</h:outputText>
```

See the "Customizing Formats" lesson of the *Java Tutorial* at `http://download.oracle.com/javase/tutorial/i18n/format/decimalFormat.html` for more information on how to format the output by using the `pattern` attribute of the `convertNumber` tag.

TABLE 8–2 Attributes for the `convertNumber` Tag

Attribute	Type	Description
`binding`	`NumberConverter`	Used to bind a converter to a backing bean property.

TABLE 8–2 Attributes for the `convertNumber` Tag *(Continued)*

Attribute	Type	Description
`currencyCode`	`String`	ISO 4217 currency code, used only when formatting currencies.
`currencySymbol`	`String`	Currency symbol, applied only when formatting currencies.
`for`	`String`	Used with composite components. Refers to one of the objects within the composite component inside which this tag is nested.
`groupingUsed`	`Boolean`	Specifies whether formatted output contains grouping separators.
`integerOnly`	`Boolean`	Specifies whether only the integer part of the value will be parsed.
`locale`	`String` or `Locale`	`Locale` whose number styles are used to format or parse data.
`maxFractionDigits`	`int`	Maximum number of digits formatted in the fractional part of the output.
`maxIntegerDigits`	`int`	Maximum number of digits formatted in the integer part of the output.
`minFractionDigits`	`int`	Minimum number of digits formatted in the fractional part of the output.
`minIntegerDigits`	`int`	Minimum number of digits formatted in the integer part of the output.
`pattern`	`String`	Custom formatting pattern that determines how the number string is formatted and parsed.
`type`	`String`	Specifies whether the string value is parsed and formatted as a `number`, `currency`, or `percentage`. If not specified, `number` is used.

Registering Listeners on Components

An application developer can implement listeners as classes or as backing bean methods. If a listener is a backing bean method, the page author references the method from either the component's `valueChangeListener` attribute or its `actionListener` attribute. If the listener is a class, the page author can reference the listener from either a `valueChangeListener` tag or an `actionListener` tag and nest the tag inside the component tag to register the listener on the component.

"Referencing a Method That Handles an Action Event" on page 181 and "Referencing a Method That Handles a Value-Change Event" on page 182 explain how a page author uses the `valueChangeListener` and `actionListener` attributes to reference backing bean methods that handle events.

This section explains how to register the `NameChanged` value-change listener and a hypothetical `LocaleChange` action listener implementation on components.

Registering a Value-Change Listener on a Component

A `ValueChangeListener` implementation can be registered on a component that implements `EditableValueHolder` by nesting a `valueChangeListener` tag within the component's tag on the page. The `valueChangeListener` tag supports the attributes shown in Table 8–3, one of which must be used.

TABLE 8–3 Attributes for the `valueChangeListener` Tag

Attribute	Description
`type`	References the fully qualified class name of a `ValueChangeListener` implementation. Can accept a literal or a value expression.
`binding`	References an object that implements `ValueChangeListener`. Can accept only a value expression, which must point to a backing bean property that accepts and returns a `ValueChangeListener` implementation.

The following example shows a value-change listener registered on a component:

```
<h:inputText id="name" size="50" value="#{cashier.name}"
     required="true">
     <f:valueChangeListener type="listeners.NameChanged" />
</h:inputText>
```

In the example, the core tag `type` attribute specifies the custom `NameChanged` listener as the `ValueChangeListener` implementation registered on the `name` component.

After this component tag is processed and local values have been validated, its corresponding component instance will queue the `ValueChangeEvent` associated with the specified `ValueChangeListener` to the component.

The `binding` attribute is used to bind a `ValueChangeListener` implementation to a backing bean property. This attribute works in a similar way to the `binding` attribute supported by the standard converter tags.

Registering an Action Listener on a Component

A page author can register an `ActionListener` implementation on a command component by nesting an `actionListener` tag within the component's tag on the page. Similarly to the `valueChangeListener` tag, the `actionListener` tag supports both the `type` and `binding` attributes. One of these attributes must be used to reference the action listener.

Here is an example of a `commandLink` tag that references an `ActionListener` implementation rather than a backing bean method:

```
<h:commandLink id="NAmerica" action="bookstore">
     <f:actionListener type="listeners.LocaleChange" />
</h:commandLink>
```

The `type` attribute of the `actionListener` tag specifies the fully qualified class name of the `ActionListener` implementation. Similarly to the `valueChangeListener` tag, the `actionListener` tag also supports the `binding` attribute.

Using the Standard Validators

JavaServer Faces technology provides a set of standard classes and associated tags that page authors and application developers can use to validate a component's data. Table 8–4 lists all the standard validator classes and the tags that allow you to use the validators from the page.

TABLE 8–4 The Validator Classes

Validator Class	Tag	Function
`BeanValidator`	`validateBean`	Registers a bean validator for the component.
`DoubleRangeValidator`	`validateDoubleRange`	Checks whether the local value of a component is within a certain range. The value must be floating-point or convertible to floating-point.
`LengthValidator`	`validateLength`	Checks whether the length of a component's local value is within a certain range. The value must be a `java.lang.String`.
`LongRangeValidator`	`validateLongRange`	Checks whether the local value of a component is within a certain range. The value must be any numeric type or `String` that can be converted to a `long`.
`RegexValidator`	`validateRegEx`	Checks whether the local value of a component is a match against a regular expression from the `java.util.regex` package.

TABLE 8–4 The Validator Classes *(Continued)*

Validator Class	Tag	Function
`RequiredValidator`	`validateRequired`	Ensures that the local value is not empty on an `EditableValueHolder` component.

Similar to the standard converters, each of these validators has one or more standard error messages associated with it. If you have registered one of these validators onto a component on your page, and the validator is unable to validate the component's value, the validator's error message will display on the page. For example, the error message that displays when the component's value exceeds the maximum value allowed by `LongRangeValidator` is as follows:

```
{1}: Validation Error: Value is greater than allowable maximum of "{0}"
```

In this case, the `{1}` substitution parameter is replaced by the component's label or `id`, and the `{0}` substitution parameter is replaced with the maximum value allowed by the validator.

Instead of using the standard validators, you can use Bean Validation to validate data. See "Using Bean Validation" on page 198 for more information.

Validating a Component's Value

To validate a component's value using a particular validator, you need to register that validator on the component. You can do this in one of the following ways:

- Nest the validator's corresponding tag (shown in Table 8–4) inside the component's tag. "Using `LongRangeValidator`" on page 180 explains how to use the `validateLongRange` tag. You can use the other standard tags in the same way.
- Refer to a method that performs the validation from the component tag's `validator` attribute.
- Nest a `validator` tag inside the component tag, and use either the validator tag's `validatorId` attribute or its `binding` attribute to refer to the validator.

See "Referencing a Method That Performs Validation" on page 181 for more information on using the `validator` attribute.

The `validatorId` attribute works similarly to the `converterId` attribute of the `converter` tag, as described in "Converting a Component's Value" on page 172.

Keep in mind that validation can be performed only on components that implement `EditableValueHolder`, because these components accept values that can be validated.

Using `LongRangeValidator`

The following example shows how to use the `validateLongRange` validator on an input component named `quantity`:

```
<h:inputText id="quantity" size="4"
      value="#{item.quantity}" >
    <f:validateLongRange minimum="1"/>
</h:inputText>
<h:message for="quantity"/>
```

This tag requires the user to enter a number that is at least 1. The `size` attribute specifies that the number can have no more than four digits. The `validateLongRange` tag also has a `maximum` attribute, which sets a maximum value for the input.

The attributes of all the standard validator tags accept EL value expressions. This means that the attributes can reference backing bean properties rather than specify literal values. For example, the `validateLongRange` tag in the preceding example can reference a backing bean property called `minimum` to get the minimum value acceptable to the validator implementation, as shown here:

```
<f:validateLongRange minimum="#{ShowCartBean.minimum}" />
```

Referencing a Backing Bean Method

A component tag has a set of attributes for referencing backing bean methods that can perform certain functions for the component associated with the tag. These attributes are summarized in Table 8–5.

TABLE 8–5 Component Tag Attributes That Reference Backing Bean Methods

Attribute	Function
`action`	Refers to a backing bean method that performs navigation processing for the component and returns a logical outcome `String`
`actionListener`	Refers to a backing bean method that handles action events
`validator`	Refers to a backing bean method that performs validation on the component's value
`valueChangeListener`	Refers to a backing bean method that handles value-change events

Only components that implement `ActionSource` can use the `action` and `actionListener` attributes. Only components that implement `EditableValueHolder` can use the `validator` or `valueChangeListener` attributes.

The component tag refers to a backing bean method using a method expression as a value of one of the attributes. The method referenced by an attribute must follow a particular signature,

which is defined by the tag attribute's definition in the documentation at http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/vdldocs/jsp/. For example, the definition of the `validator` attribute of the `inputText` tag is the following:

```
void validate(javax.faces.context.FacesContext,
     javax.faces.component.UIComponent, java.lang.Object)
```

The following sections give examples of how to use the attributes.

Referencing a Method That Performs Navigation

If your page includes a component, such as a button or a hyperlink, that causes the application to navigate to another page when the component is activated, the tag corresponding to this component must include an `action` attribute. This attribute does one of the following:

- Specifies a logical outcome `String` that tells the application which page to access next
- References a backing bean method that performs some processing and returns a logical outcome `String`

The following example shows how to reference a navigation method:

```
<h:commandButton
    value="#{bundle.Submit}"
    action="#{cashier.submit}" />
```

Referencing a Method That Handles an Action Event

If a component on your page generates an action event, and if that event is handled by a backing bean method, you refer to the method by using the component's `actionListener` attribute.

The following example shows how the method is referenced:

```
<h:commandLink id="NAmerica" action="bookstore"
     actionListener="#{localeBean.chooseLocaleFromLink}">
```

The `actionListener` attribute of this component tag references the `chooseLocaleFromLink` method using a method expression. The `chooseLocaleFromLink` method handles the event when the user clicks the hyperlink rendered by this component.

Referencing a Method That Performs Validation

If the input of one of the components on your page is validated by a backing bean method, refer to the method from the component's tag by using the `validator` attribute.

The following example shows how to reference a method that performs validation on `email`, an input component:

```
<h:inputText id="email" value="#{checkoutFormBean.email}"
    size="25" maxlength="125"
    validator="#{checkoutFormBean.validateEmail}"/>
```

Referencing a Method That Handles a Value-Change Event

If you want a component on your page to generate a value-change event and you want that event to be handled by a backing bean method, you refer to the method by using the component's `valueChangeListener` attribute.

The following example shows how a component references a `ValueChangeListener` implementation that handles the event when a user enters a name in the `name` input field:

```
<h:inputText
     id="name"
     size="50"
     value="#{cashier.name}"
     required="true">
    <f:valueChangeListener type="listeners.NameChanged" />
</h:inputText>
```

To refer to this backing bean method, the tag uses the `valueChangeListener` attribute:

```
<h:inputText
     id="name"
     size="50"
     value="#{cashier.name}"
     required="true"
     valueChangeListener="#{cashier.processValueChange}" />
</h:inputText>
```

The `valueChangeListener` attribute of this component tag references the `processValueChange` method of `CashierBean` by using a method expression. The `processValueChange` method handles the event of a user entering a name in the input field rendered by this component.

◆ ◆ ◆ CHAPTER 9

Developing with JavaServer Faces Technology

Chapter 7, "Using JavaServer Faces Technology in Web Pages," and Chapter 8, "Using Converters, Listeners, and Validators," show how to add components to a page and connect them to server-side objects by using component tags and core tags, as well as how to provide additional functionality to the components through converters, listeners, and validators. Developing a JavaServer Faces application also involves the task of programming the server-side objects: backing beans, converters, event handlers, and validators.

This chapter provides an overview of backing beans and explains how to write methods and properties of backing beans that are used by a JavaServer Faces application. This chapter also introduces the Bean Validation feature.

The following topics are addressed here:

Backing Beans

A typical JavaServer Faces application includes one or more backing beans, each of which is a type of JavaServer Faces managed bean that can be associated with the components used in a particular page. This section introduces the basic concepts of creating, configuring, and using backing beans in an application.

Creating a Backing Bean

A backing bean is created with a constructor with no arguments (like all JavaBeans components) and a set of properties and a set of methods that perform functions for a component. Each of the backing bean properties can be bound to one of the following:

- A component value
- A component instance
- A converter instance
- A listener instance
- A validator instance

The most common functions that backing bean methods perform include the following:

- Validating a component's data
- Handling an event fired by a component
- Performing processing to determine the next page to which the application must navigate

As with all JavaBeans components, a property consists of a private data field and a set of accessor methods, as shown by this code:

```
Integer userNumber = null;
...
public void setUserNumber(Integer user_number) {
    userNumber = user_number;
}
public Integer getUserNumber() {
    return userNumber;
}
public String getResponse() {
    ...
}
```

When bound to a component's value, a bean property can be any of the basic primitive and numeric types or any Java object type for which the application has access to an appropriate converter. For example, a property can be of type `Date` if the application has access to a converter that can convert the `Date` type to a `String` and back again. See "Writing Bean Properties" on page 186 for information on which types are accepted by which component tags.

When a bean property is bound to a component instance, the property's type must be the same as the component object. For example, if a `javax.faces.component.UISelectBoolean` component is bound to the property, the property must accept and return a `UISelectBoolean` object. Likewise, if the property is bound to a converter, validator, or listener instance, the property must be of the appropriate converter, validator, or listener type.

For more information on writing beans and their properties, see "Writing Bean Properties" on page 186.

Using the EL to Reference Backing Beans

To bind component values and objects to backing bean properties or to reference backing bean methods from component tags, page authors use the Expression Language syntax. As explained in "Overview of the EL" on page 125, the following are some of the features that EL offers:

- Deferred evaluation of expressions
- The ability to use a value expression to both read and write data
- Method expressions

Deferred evaluation of expressions is important because the JavaServer Faces lifecycle is split into several phases in which component event handling, data conversion and validation, and data propagation to external objects are all performed in an orderly fashion. The implementation must be able to delay the evaluation of expressions until the proper phase of the lifecycle has been reached. Therefore, the implementation's tag attributes always use deferred-evaluation syntax, which is distinguished by the `#{}` delimiter.

To store data in external objects, almost all JavaServer Faces tag attributes use lvalue expressions, which are expressions that allow both getting and setting data on external objects.

Finally, some component tag attributes accept method expressions that reference methods that handle component events or validate or convert component data.

To illustrate a JavaServer Faces tag using the EL, suppose that a tag of an application referenced a method to perform the validation of user input:

```
<h:inputText id="userNo"
     value="#{UserNumberBean.userNumber}"
     validator="#{UserNumberBean.validate}" />
```

This tag binds the `userNo` component's value to the `UserNumberBean.userNumber` backing bean property by using an lvalue expression. The tag uses a method expression to refer to the `UserNumberBean.validate` method, which performs validation of the component's local value. The local value is whatever the user enters into the field corresponding to this tag. This method is invoked when the expression is evaluated.

Nearly all JavaServer Faces tag attributes accept value expressions. In addition to referencing bean properties, value expressions can reference lists, maps, arrays, implicit objects, and resource bundles.

Another use of value expressions is binding a component instance to a backing bean property. A page author does this by referencing the property from the `binding` attribute:

```
<inputText binding="#{UserNumberBean.userNoComponent}" />
```

In addition to using expressions with the standard component tags, you can configure your custom component properties to accept expressions by creating `javax.el.ValueExpression` or `javax.el.MethodExpression` instances for them.

For information on the EL, see Chapter 6, "Expression Language."

For information on referencing backing bean methods from component tags, see "Referencing a Backing Bean Method" on page 180.

Writing Bean Properties

As explained in "Backing Beans" on page 183, a backing bean property can be bound to one of the following items:

- A component value
- A component instance
- A converter implementation
- A listener implementation
- A validator implementation

These properties follow the conventions of JavaBeans components (also called beans). For more information on JavaBeans components, see the *JavaBeans Tutorial* at `http://download.oracle.com/javase/tutorial/javabeans/index.html`.

The component's tag binds the component's value to a backing bean property by using its `value` attribute and binds the component's instance to a backing bean property by using its `binding` attribute. Likewise, all the converter, listener, and validator tags use their `binding` attributes to bind their associated implementations to backing bean properties.

To bind a component's value to a backing bean property, the type of the property must match the type of the component's value to which it is bound. For example, if a backing bean property is bound to a `UISelectBoolean` component's value, the property should accept and return a `boolean` value or a `Boolean` wrapper `Object` instance.

To bind a component instance to a backing bean property, the property must match the type of component. For example, if a backing bean property is bound to a `UISelectBoolean` instance, the property should accept and return a `UISelectBoolean` value.

Similarly, to bind a converter, listener, or validator implementation to a backing bean property, the property must accept and return the same type of converter, listener, or validator object. For example, if you are using the `convertDateTime` tag to bind a `DateTimeConverter` to a property, that property must accept and return a `DateTimeConverter` instance.

The rest of this section explains how to write properties that can be bound to component values, to component instances for the component objects described in "Adding Components to a Page Using HTML Tags" on page 140, and to converter, listener, and validator implementations.

Writing Properties Bound to Component Values

To write a backing bean property that is bound to a component's value, you must match the property type to the component's value.

Table 9–1 lists the `javax.faces.component` classes and the acceptable types of their values.

TABLE 9–1 Acceptable Types of Component Values

Component Class	Acceptable Types of Component Values
`UIInput`, `UIOutput`, `UISelectItem`, `UISelectOne`	Any of the basic primitive and numeric types or any Java programming language object type for which an appropriate `Converter` implementation is available
`UIData`	`array` of beans, `List` of beans, single bean, `java.sql.ResultSet`, `javax.servlet.jsp.jstl.sql.Result`, `javax.sql.RowSet`
`UISelectBoolean`	`boolean` or `Boolean`
`UISelectItems`	`java.lang.String`, `Collection`, `Array`, `Map`
`UISelectMany`	`array` or `List`, though elements of the `array` or `List` can be any of the standard types

When they bind components to properties by using the `value` attributes of the component tags, page authors need to ensure that the corresponding properties match the types of the components' values.

`UIInput` and `UIOutput` Properties

In the following example, an `h:inputText` tag binds the `name` component to the `name` property of a backing bean called `CashierBean`.

```
<h:inputText id="name" size="50"
    value="#{cashier.name}">
</h:inputText>
```

The following code snippet from the backing bean `CashierBean` shows the bean property type bound by the preceding component tag:

```
protected String name = null;

public void setName(String name) {
    this.name = name;
}
public String getName() {
    return this.name;
}
```

As described in "Using the Standard Converters" on page 171, to convert the value of an input or output component, you can either apply a converter or create the bean property bound to the component with the matching type. Here is the example tag, from "Using DateTimeConverter" on page 173, that displays the date when items will be shipped.

```
<h:outputText value="#{cashier.shipDate}">
    <f:convertDateTime dateStyle="full" />
</h:outputText>
```

The bean property represented by this tag must have a type of `java.util.Date`. The following code snippet shows the `shipDate` property, from the backing bean `CashierBean`, that is bound by the tag's value in the preceding example:

```
protected Date shipDate;

public Date getShipDate() {
    return this.shipDate;
}
public void setShipDate(Date shipDate) {
    this.shipDate = shipDate;
}
```

`UIData` Properties

Data components must be bound to one of the backing bean property types listed in Table 9–1. Data components are discussed in "Using Data-Bound Table Components" on page 160. Here is part of the start tag of `dataTable` from that section:

```
<h:dataTable id="items"
    ...
    value="#{cart.items}"
    var="item" >
```

The value expression points to the `items` property of a shopping cart bean named `cart`. The `cart` bean maintains a map of `ShoppingCartItem` beans.

The `getItems` method from the `cart` bean populates a `List` with `ShoppingCartItem` instances that are saved in the items map when the customer adds items to the cart, as shown in the following code segment:

```
public synchronized List getItems() {
    List results = new ArrayList();
    results.addAll(this.items.values());
    return results;
}
```

All the components contained in the data component are bound to the properties of the `cart` bean that is bound to the entire data component. For example, here is the `h:outputText` tag that displays the item name in the table:

```
<h:commandLink action="#{showcart.details}">
    <h:outputText value="#{item.item.name}"/>
</h:commandLink>
```

`UISelectBoolean` Properties

Backing bean properties that hold a `UISelectBoolean` component's data must be of `boolean` or `Boolean` type. The example `selectBooleanCheckbox` tag from the section "Displaying Components for Selecting One Value" on page 155 binds a component to a property. The following example shows a tag that binds a component value to a `boolean` property:

```
<h:selectBooleanCheckbox title="#{bundle.receiveEmails}"
     value="#{custFormBean.receiveEmails}" >
</h:selectBooleanCheckbox>
<h:outputText value="#{bundle.receiveEmails}">
```

Here is an example property that can be bound to the component represented by the example tag:

```
protected boolean receiveEmails = false;
        ...
    public void setReceiveEmails(boolean receiveEmails) {
        this.receiveEmails = receiveEmails;
    }
    public boolean getReceiveEmails() {
        return receiveEmails;
    }
```

`UISelectMany` Properties

Because a `UISelectMany` component allows a user to select one or more items from a list of items, this component must map to a bean property of type `List` or `array`. This bean property represents the set of currently selected items from the list of available items.

The following example of the `selectManyCheckbox` tag comes from "Displaying Components for Selecting Multiple Values" on page 157:

```
<h:selectManyCheckbox
    id="newsletters"
    layout="pageDirection"
    value="#{cashier.newsletters}">
    <f:selectItems value="#{newsletters}"/>
</h:selectManyCheckbox>
```

Here is the bean property that maps to the `value` of the `selectManyCheckbox` tag from the preceding example:

```
protected String newsletters[] = new String[0];

public void setNewsletters(String newsletters[]) {
    this.newsletters = newsletters;
}
```

```
public String[] getNewsletters() {
    return this.newsletters;
}
```

The `UISelectItem` and `UISelectItems` components are used to represent all the values in a `UISelectMany` component. See "`UISelectItem` Properties" on page 191 and "`UISelectItems` Properties" on page 191 for information on writing the bean properties for the `UISelectItem` and `UISelectItems` components.

`UISelectOne` Properties

`UISelectOne` properties accept the same types as `UIInput` and `UIOutput` properties, because a `UISelectOne` component represents the single selected item from a set of items. This item can be any of the primitive types and anything else for which you can apply a converter.

Here is an example of the `selectOneMenu` tag from "Displaying a Menu Using the `h:selectOneMenu` Tag" on page 156:

```
<h:selectOneMenu   id="shippingOption"
    required="true"
    value="#{cashier.shippingOption}">
    <f:selectItem
        itemValue="2"
        itemLabel="#{bundle.QuickShip}"/>
    <f:selectItem
        itemValue="5"
        itemLabel="#{bundle.NormalShip}"/>
    <f:selectItem
        itemValue="7"
        itemLabel="#{bundle.SaverShip}"/>
 </h:selectOneMenu>
```

Here is the bean property corresponding to this tag:

```
protected String shippingOption = "2";

public void setShippingOption(String shippingOption) {
    this.shippingOption = shippingOption;
}
public String getShippingOption() {
    return this.shippingOption;
}
```

Note that `shippingOption` represents the currently selected item from the list of items in the `UISelectOne` component.

The `UISelectItem` and `UISelectItems` components are used to represent all the values in a `UISelectOne` component. This is explained in the section "Displaying a Menu Using the `h:selectOneMenu` Tag" on page 156.

For information on how to write the backing bean properties for the `UISelectItem` and `UISelectItems` components, see "`UISelectItem` Properties" on page 191 and "`UISelectItems` Properties" on page 191.

`UISelectItem` Properties

A `UISelectItem` component represents a single value in a set of values in a `UISelectMany` or a `UISelectOne` component. A `UISelectItem` component must be bound to a backing bean property of type `javax.faces.model.SelectItem`. A `SelectItem` object is composed of an `Object` representing the value, along with two `Strings` representing the label and description of the `UISelectItem` object.

The example `selectOneMenu` tag from "Displaying a Menu Using the `h:selectOneMenu` Tag" on page 156 contains `selectItem` tags that set the values of the list of items in the page. Here is an example of a bean property that can set the values for this list in the bean:

```
SelectItem itemOne = null;

SelectItem getItemOne(){
    return itemOne;
}
void setItemOne(SelectItem item) {
    itemOne = item;
}
```

`UISelectItems` Properties

`UISelectItems` components are children of `UISelectMany` and `UISelectOne` components. Each `UISelectItems` component is composed of a set of either `javax.faces.model.SelectItem` instances or any collection of objects, such as an array, a list, or even POJOs.

This section explains how to write the properties for `selectItems` tags containing `SelectItem` instances.

You can populate the `UISelectItems` with `SelectItem` instances programmatically in the backing bean.

1. In your backing bean, create a list that is bound to the `SelectItem` component.
2. Define a set of `SelectItem` objects, set their values, and populate the list with the `SelectItem` objects.

The following example code snippet from a backing bean shows how to create a `SelectItems` property:

```
import javax.faces.model.SelectItem;
...
protected ArrayList options = null;
protected SelectItem newsletter0 =
     new SelectItem("200", "Duke's Quarterly", "");
...
//in constructor, populate the list
    options.add(newsletter0);
    options.add(newsletter1);
```

```
    options.add(newsletter2);
...
public SelectItem getNewsletter0(){
    return newsletter0;
}

void setNewsletter0(SelectItem firstNL) {
    newsletter0 = firstNL;
}
// Other SelectItem properties

public Collection[] getOptions(){
    return options;
}
public void setOptions(Collection[] options){
    this.options = new ArrayList(options);
}
```

The code first initializes `options` as a list. Each newsletter property is defined with values. Then each newsletter `SelectItem` is added to the list. Finally, the code includes the obligatory `setOptions` and `getOptions` accessor methods.

Writing Properties Bound to Component Instances

A property bound to a component instance returns and accepts a component instance rather than a component value. The following components bind a component instance to a backing bean property:

```
<h:selectBooleanCheckbox
    id="fanClub"
    rendered="false"
    binding="#{cashier.specialOffer}" />
<h:outputLabel for="fanClub"
    rendered="false"
    binding="#{cashier.specialOfferText}"  >
    <h:outputText id="fanClubLabel"
        value="#{bundle.DukeFanClub}" />
</h:outputLabel>
```

The `selectBooleanCheckbox` tag renders a check box and binds the `fanClub` `UISelectBoolean` component to the `specialOffer` property of `CashierBean`. The `outputLabel` tag binds the `fanClubLabel` component, which represents the check box's label, to the `specialOfferText` property of `CashierBean`. If the user orders more than $100 worth of items and clicks the Submit button, the `submit` method of `CashierBean` sets both components' `rendered` properties to `true`, causing the check box and label to display when the page is rerendered.

Because the components corresponding to the example tags are bound to the backing bean properties, these properties must match the components' types. This means that the `specialOfferText` property must be of type `UIOutput`, and the `specialOffer` property must be of type `UISelectBoolean`:

```
UIOutput specialOfferText = null;

public UIOutput getSpecialOfferText() {
    return this.specialOfferText;
}
public void setSpecialOfferText(UIOutput specialOfferText) {
    this.specialOfferText = specialOfferText;
}

UISelectBoolean specialOffer = null;

public UISelectBoolean getSpecialOffer() {
    return this.specialOffer;
}
public void setSpecialOffer(UISelectBoolean specialOffer) {
    this.specialOffer = specialOffer;
}
```

For more general information on component binding, see "Backing Beans" on page 183.

For information on how to reference a backing bean method that performs navigation when a button is clicked, see "Referencing a Method That Performs Navigation" on page 181.

For more information on writing backing bean methods that handle navigation, see "Writing a Method to Handle Navigation" on page 194.

Writing Properties Bound to Converters, Listeners, or Validators

All the standard converter, listener, and validator tags included with JavaServer Faces technology support binding attributes that allow you to bind converter, listener, or validator implementations to backing bean properties.

The following example shows a standard `convertDateTime` tag using a value expression with its `binding` attribute to bind the `DateTimeConverter` instance to the `convertDate` property of `LoginBean`:

```
<h:inputText value="#{LoginBean.birthDate}">
    <f:convertDateTime binding="#{LoginBean.convertDate}" />
</h:inputText>
```

The `convertDate` property must therefore accept and return a `DateTimeConverter` object, as shown here:

```
private DateTimeConverter convertDate;
public DateTimeConverter getConvertDate() {
       ...
    return convertDate;
{
public void setConvertDate(DateTimeConverter convertDate) {
```

```
    convertDate.setPattern("EEEEEEEE, MMM dd, yyyy");
    this.convertDate = convertDate;
}
```

Because the converter is bound to a backing bean property, the backing bean property can modify the attributes of the converter or add new functionality to it. In the case of the preceding example, the property sets the date pattern that the converter uses to parse the user's input into a `Date` object.

The backing bean properties that are bound to validator or listener implementations are written in the same way and have the same general purpose.

Writing Backing Bean Methods

Methods of a backing bean can perform several application-specific functions for components on the page. These functions include

- Performing processing associated with navigation
- Handling action events
- Performing validation on the component's value
- Handling value-change events

By using a backing bean to perform these functions, you eliminate the need to implement the `Validator` interface to handle the validation or one of the listener interfaces to handle events. Also, by using a backing bean instead of a `Validator` implementation to perform validation, you eliminate the need to create a custom tag for the `Validator` implementation.

In general, it's good practice to include these methods in the same backing bean that defines the properties for the components referencing these methods. The reason for doing so is that the methods might need to access the component's data to determine how to handle the event or to perform the validation associated with the component.

The following sections explain how to write various types of backing bean methods.

Writing a Method to Handle Navigation

An action method, a backing bean method that handles navigation processing, must be a public method that takes no parameters and returns an `Object`, which is the logical outcome that the navigation system uses to determine the page to display next. This method is referenced using the component tag's `action` attribute.

The following action method is from a backing bean named `CashierBean`, which is invoked when a user clicks the Submit button on the page. If the user has ordered more than $100 worth of items, this method sets the `rendered` properties of the `fanClub` and `specialOffer` components to `true`, causing them to be displayed on the page the next time that page is rendered.

After setting the components' `rendered` properties to `true`, this method returns the logical outcome `null`. This causes the JavaServer Faces implementation to rerender the page without creating a new view of the page, retaining the customer's input. If this method were to return `purchase`, which is the logical outcome to use to advance to a payment page, the page would rerender without retaining the customer's input.

If the user does not purchase more than $100 worth of items, or if the `thankYou` component has already been rendered, the method returns `receipt`. The JavaServer Faces implementation loads the page after this method returns:

```
public String submit() {
    ...
    if(cart().getTotal() > 100.00 &&
         !specialOffer.isRendered())
    {
        specialOfferText.setRendered(true);
        specialOffer.setRendered(true);
        return null;
    } else if (specialOffer.isRendered() &&
         !thankYou.isRendered()){
        thankYou.setRendered(true);
        return null;
    } else {
        clear();
        return ("receipt");
    }
}
```

Typically, an action method will return a `String` outcome, as shown in the previous example. Alternatively, you can define an `Enum` class that encapsulates all possible outcome strings and then make an action method return an `enum` constant, which represents a particular `String` outcome defined by the `Enum` class.

The following example uses an `Enum` class to encapsulate all logical outcomes:

```
public enum Navigation  {
    main, accountHist, accountList, atm, atmAck, transferFunds,
     transferAck, error
}
```

When it returns an outcome, an action method uses the dot notation to reference the outcome from the `Enum` class:

```
public Object submit(){
    ...
    return Navigation.accountHist;
}
```

The section "Referencing a Method That Performs Navigation" on page 181 explains how a component tag references this method. The section "Writing Properties Bound to Component Instances" on page 192 explains how to write the bean properties to which the components are bound.

Writing a Method to Handle an Action Event

A backing bean method that handles an action event must be a public method that accepts an action event and returns `void`. This method is referenced using the component tag's `actionListener` attribute. Only components that implement `javax.faces.component.ActionSource` can refer to this method.

In the following example, a method from a backing bean named `LocaleBean` processes the event of a user clicking one of the hyperlinks on the page:

```
public void chooseLocaleFromLink(ActionEvent event) {
    String current = event.getComponent().getId();
    FacesContext context = FacesContext.getCurrentInstance();
    context.getViewRoot().setLocale((Locale)
        locales.get(current));
}
```

This method gets the component that generated the event from the event object; then it gets the component's ID, which indicates a region of the world. The method matches the ID against a `HashMap` object that contains the locales available for the application. Finally, the method sets the locale by using the selected value from the `HashMap` object.

"Referencing a Method That Handles an Action Event" on page 181 explains how a component tag references this method.

Writing a Method to Perform Validation

Instead of implementing the `Validator` interface to perform validation for a component, you can include a method in a backing bean to take care of validating input for the component. A backing bean method that performs validation must accept a `FacesContext`, the component whose data must be validated, and the data to be validated, just as the `validate` method of the `Validator` interface does. A component refers to the backing bean method by using its `validator` attribute. Only values of `UIInput` components or values of components that extend `UIInput` can be validated.

Here is an example of a backing bean method that validates user input:

```
public void validateEmail(FacesContext context,
     UIComponent toValidate, Object value) {

    String message = "";
    String email = (String) value;
    if (!email.contains('@')) {
        ((UIInput)toValidate).setValid(false);
        message = CoffeeBreakBean.loadErrorMessage(context,
            CoffeeBreakBean.CB_RESOURCE_BUNDLE_NAME,
            "EMailError");
        context.addMessage(toValidate.getClientId(context),
```

```
            new FacesMessage(message));
    }
}
```

Take a closer look at the preceding code segment:

1. The `validateEmail` method first gets the local value of the component.
2. The method then checks whether the `@` character is contained in the value.
3. If not, the method sets the component's `valid` property to `false`.
4. The method then loads the error message and queues it onto the `FacesContext` instance, associating the message with the component ID.

See "Referencing a Method That Performs Validation" on page 181 for information on how a component tag references this method.

Writing a Method to Handle a Value-Change Event

A backing bean that handles a value-change event must use a public method that accepts a value-change event and returns `void`. This method is referenced using the component's `valueChangeListener` attribute. This section explains how to write a backing bean method to replace the `ValueChangeListener` implementation.

The following example tag comes from "Registering a Value-Change Listener on a Component" on page 177, where the `h:inputText` tag with the `id` of `name` has a `ValueChangeListener` instance registered on it. This `ValueChangeListener` instance handles the event of entering a value in the field corresponding to the component. When the user enters a value, a value-change event is generated, and the `processValueChange(ValueChangeEvent)` method of the `ValueChangeListener` class is invoked:

```
<h:inputText  id="name" size="50" value="#{cashier.name}"
     required="true">
     <f:valueChangeListener type="listeners.NameChanged" />
</h:inputText>
```

Instead of implementing `ValueChangeListener`, you can write a backing bean method to handle this event. To do this, you move the `processValueChange(ValueChangeEvent)` method from the `ValueChangeListener` class, called `NameChanged`, to your backing bean.

Here is the backing bean method that processes the event of entering a value in the `name` field on the page:

```
public void processValueChange(ValueChangeEvent event)
    throws AbortProcessingException {
    if (null != event.getNewValue()) {
        FacesContext.getCurrentInstance().
            getExternalContext().getSessionMap().
                put("name", event.getNewValue());
    }
}
```

To make this method handle the `ValueChangeEvent` generated by an input component, reference this method from the component tag's `valueChangeListener` attribute. See "Referencing a Method That Handles a Value-Change Event" on page 182 for more information.

Using Bean Validation

Validating input received from the user to maintain data integrity is an important part of application logic. Validation of data can take place at different layers in even the simplest of applications, as shown in the `guessnumber` example application from an earlier chapter. The `guessnumber` example application validates the user input (in the `h:inputText` tag) for numerical data at the presentation layer and for a valid range of numbers at the business layer.

JavaBeans Validation (Bean Validation) is a new validation model available as part of Java EE 6 platform. The Bean Validation model is supported by constraints in the form of annotations placed on a field, method, or class of a JavaBeans component, such as a backing bean.

Constraints can be built in or user defined. User-defined constraints are called custom constraints. Several built-in constraints are available in the `javax.validation.constraints` package. Table 9–2 lists all the built-in constraints.

TABLE 9–2 Built-In Bean Validation Constraints

Constraint	Description	Example
`@AssertFalse`	The value of the field or property must be false.	`@AssertFalse` `boolean isUnsupported;`
`@AssertTrue`	The value of the field or property must be true.	`@AssertTrue` `boolean isActive;`
`@DecimalMax`	The value of the field or property must be a decimal value lower than or equal to the number in the value element.	`@DecimalMax("30.00")` `BigDecimal discount;`
`@DecimalMin`	The value of the field or property must be a decimal value greater than or equal to the number in the value element.	`@DecimalMin("5.00")` `BigDecimal discount;`

TABLE 9–2 Built-In Bean Validation Constraints *(Continued)*

Constraint	Description	Example
`@Digits`	The value of the field or property must be a number within a specified range. The `integer` element specifies the maximum integral digits for the number, and the `fraction` element specifies the maximum fractional digits for the number.	`@Digits(integer=6, fraction=2)` `BigDecimal price;`
`@Future`	The value of the field or property must be a date in the future.	`@Future` `Date eventDate;`
`@Max`	The value of the field or property must be an integer value lower than or equal to the number in the value element.	`@Max(10)` `int quantity;`
`@Min`	The value of the field or property must be an integer value greater than or equal to the number in the value element.	`@Min(5)` `int quantity;`
`@NotNull`	The value of the field or property must not be null.	`@NotNull` `String username;`
`@Null`	The value of the field or property must be null.	`@Null` `String unusedString;`
`@Past`	The value of the field or property must be a date in the past.	`@Past` `Date birthday;`
`@Pattern`	The value of the field or property must match the regular expression defined in the `regexp` element.	`@Pattern(regexp="\\(\\d{3}\\)\\d{3}-\\d{4}")` `String phoneNumber;`

TABLE 9–2 Built-In Bean Validation Constraints *(Continued)*

Constraint	Description	Example
`@Size`	The size of the field or property is evaluated and must match the specified boundaries. If the field or property is a `String`, the size of the string is evaluated. If the field or property is a `Collection`, the size of the `Collection` is evaluated. If the field or property is a `Map`, the size of the `Map` is evaluated. If the field or property is an array, the size of the array is evaluated. Use one of the optional `max` or `min` elements to specify the boundaries.	`@Size(min=2, max=240)` `String briefMessage;`

In the following example, a constraint is placed on a field using the built-in `@NotNull` constraint:

```
public class Name {
    @NotNull
    private String firstname;

    @NotNull
    private String lastname;
}
```

You can also place more than one constraint on a single JavaBeans component object. For example, you can place an additional constraint for size of field on the `firstname` and the `lastname` fields:

```
public class Name {
    @NotNull
    @Size(min=1, max=16)
    private String firstname;

    @NotNull
    @Size(min=1, max=16)
    private String lastname;
}
```

The following example shows a method with a user-defined constraint that checks for a predefined email address pattern such as a corporate email account:

```
@ValidEmail
public String getEmailAddress() {
    return emailAddress;
}
```

For a built-in constraint, a default implementation is available. A user-defined or custom constraint needs a validation implementation. In the above example, the `@ValidEmail` custom constraint needs an implementation class.

Any validation failures are gracefully handled and can be displayed by the `h:messages` tag.

Any backing bean that contains Bean Validation annotations automatically gets validation constraints placed on the fields on a JavaServer Faces application's web pages.

See "Validating Persistent Fields and Properties" on page 541 for more information on using validation constraints.

Validating Null and Empty Strings

The Java programming language distinguishes between null and empty strings. An empty string is a string instance of zero length, whereas a null string has no value at all.

An empty string is represented as "". It is a character array of zero characters. A null string is represented by `null`. It can be described as the absence of a string instance.

Backing bean elements represented as a JavaServer Faces text component such as `inputText` are initialized with the value of the empty string by the JavaServer Faces implementation. Validating these strings can be an issue when user input for such fields is not required. Consider the following example, where the string `testString` is a bean variable that will be set using input typed by the user. In this case, the user input for the field is not required.

```
if (testString.equals(null)) {
  doSomething();
} else  {
  doAnotherThing();
}
```

By default, the `doAnotherThing` method is called even when the user enters no data, because the `testString` element has been initialized with the value of an empty string.

In order for the Bean Validation model to work as intended, you must set the context parameter `javax.faces.INTERPRET_EMPTY_STRING_SUBMITTED_VALUES_AS_NULL` to `true` in the web deployment descriptor file, `web.xml`:

```
<context-param>
    <param-name>
        javax.faces.INTERPRET_EMPTY_STRING_SUBMITTED_VALUES_AS_NULL
    </param-name>
    <param-value>true</param-value>
</context-param>
```

This parameter enables the JavaServer Faces implementation to treat empty strings as null.

Suppose, on the other hand, that you have a `@NotNull` constraint on an element, meaning that input is required. In this case, an empty string will pass this validation constraint. However, if you set the context parameter `javax.faces.INTERPRET_EMPTY_STRING_SUBMITTED_VALUES_AS_NULL` to true, the value of the backing bean attribute is passed to the Bean Validation runtime as a null value, causing the `@NotNull` constraint to fail.

◆ ◆ ◆ CHAPTER 10

JavaServer Faces Technology Advanced Concepts

Previous chapters have introduced JavaServer Faces technology and Facelets, the preferred presentation layer for the Java for the Java EE platform. This chapter and the following chapters introduce advanced concepts in this area.

- This chapter describes the JavaServer Faces lifecycle in detail. Some of the complex applications use the well-defined and identified lifecycle phases to customize application behavior.
- Chapter 11, "Configuring JavaServer Faces Applications," introduces the process of creating and deploying JavaServer Faces applications, the use of various configuration files, and the deployment structure.
- Chapter 12, "Using Ajax with JavaServer Faces Technology," introduces Ajax concepts and the use of Ajax in JavaServer Faces applications.
- Chapter 13, "Advanced Composite Components," introduces advanced features of composite components.
- Chapter 14, "Creating Custom UI Components," describes the process of creating new components, renderers, converters, listeners, and validators from scratch.

The following topics are addressed here:

Overview of the JavaServer Faces Lifecycle

The lifecycle of an application refers to the various stages of processing that application, from its initiation to its conclusion. All applications have lifecycles. During a web application lifecycle, common tasks such as the following are performed:

- Handling incoming requests
- Decoding parameters
- Modifying and saving state
- Rendering web pages to the browser

The JavaServer Faces web application framework manages its lifecycle phases automatically for simple applications or allows you to manage them manually for more complex applications as required.

JavaServer Faces applications that use advanced features may require interaction with the lifecycle at certain phases. For example, Ajax applications use partial processing features of the lifecycle. A clearer understanding of the lifecycle phases is key to creating well-designed components.

A simplified view of the JavaServer faces lifecycle, consisting of the two main phases of a JavaServer Faces web application, is introduced in "The Lifecycle of the `hello` Application" on page 108. This chapter examines the JavaServer Faces lifecycle in more detail.

The Lifecycle of a JavaServer Faces Application

The lifecycle of a JavaServer Faces application begins when the client makes an HTTP request for a page and ends when the server responds with the page, translated to HTML.

The lifecycle can be divided into two main phases, `execute` and `render`. The execute phase is further divided into sub-phases to support the sophisticated component tree. This structure requires that component data be converted and validated, component events be handled, and component data be propagated to beans in an orderly fashion.

A JavaServer Faces page is represented by a tree of components, called a *view*. During the lifecycle, the JavaServer Faces implementation must build the view while considering the state saved from a previous submission of the page. When the client submits a page, the JavaServer Faces implementation performs several tasks, such as validating the data input of components in the view and converting input data to types specified on the server side.

The JavaServer Faces implementation performs all these tasks as a series of steps in the JavaServer Faces request-response lifecycle. Figure 10–1 illustrates these steps.

FIGURE 10–1 JavaServer Faces Standard Request-Response Lifecycle



The lifecycle handles two kinds of requests: *initial requests* and *postbacks*. An initial request occurs when a user makes a request for a page for the first time. A postback request occurs when a user submits the form contained on a page that was previously loaded into the browser as a result of executing an initial request.

When the lifecycle handles an initial request, it executes only the Restore View and Render Response phases, because there is no user input or actions to process. Conversely, when the lifecycle handles a postback, it executes all of the phases.

Usually, the first request for a JavaServer Faces page comes in from a client, as a result of clicking a hyperlink on an HTML page that links to the JavaServer Faces page. To render a response that is another JavaServer Faces page, the application creates a new view and stores it in the `FacesContext` instance, which represents all of the information associated with processing an incoming request and creating a response. The application then acquires object references needed by the view and calls `FacesContext.renderResponse` method, which forces immediate rendering of the view by skipping to the "Render Response Phase" on page 209 of the lifecycle, as is shown by the arrows labelled Render Response in the diagram.

Sometimes, an application might need to redirect to a different web application resource, such as a web service, or generate a response that does not contain JavaServer Faces components. In these situations, the developer must skip the Render Response phase by calling the `FacesContext.responseComplete` method. This situation is also shown in the diagram, this time with the arrows labelled Response Complete.

The most common situation is that a JavaServer Faces component submits a request for another JavaServer Faces page. In this case, the JavaServer Faces implementation handles the request and automatically goes through the phases in the lifecycle to perform any necessary conversions, validations, and model updates, and to generate the response.

There is one exception to the lifecycle described in this section. When a component's `immediate` attribute is set to `true`, the validation, conversion, and events associated with these components are processed during the "Apply Request Values Phase" on page 207 rather than in a later phase.

The details of the lifecycle explained in the following sections are primarily intended for developers who need to know information such as when validations, conversions, and events are usually handled and what they can do to change how and when they are handled. For more information on each of the lifecycle phases, download the latest JavaServer Faces Specification documentation from `https://javaserverfaces.java.net/`.

The JavaServer Faces application lifecycle contains the following phases:

- "Render Response Phase" on page 209

Restore View Phase

When a request for a JavaServer Faces page is made, usually by an action on the page, such as when a link or a button is clicked, the JavaServer Faces implementation begins the Restore View phase.

During this phase, the JavaServer Faces implementation builds the view of the page, wires event handlers and validators to components in the view, and saves the view in the `FacesContext` instance, which contains all the information needed to process a single request. All the application's component tags, event handlers, converters, and validators have access to the `FacesContext` instance.

If the request for the page is an initial request, the JavaServer Faces implementation creates an empty view during this phase and the lifecycle advances to the Render Response phase, during which the empty view is populated with the components referenced by the tags in the page.

If the request for the page is a postback, a view corresponding to this page already exists. During this phase, the JavaServer Faces implementation restores the view by using the state information saved on the client or the server.

Apply Request Values Phase

After the component tree is restored during a postback request, each component in the tree extracts its new value from the request parameters by using its `decode` (`processDecodes()`) method. The value is then stored locally on the component. If the conversion of the value fails, an error message that is associated with the component is generated and queued on `FacesContext`. This message will be displayed during the Render Response phase, along with any validation errors resulting from the Process Validations phase.

If any `decode` methods or event listeners have called `renderResponse` on the current `FacesContext` instance, the JavaServer Faces implementation skips to the Render Response phase.

If events have been queued during this phase, the JavaServer Faces implementation broadcasts the events to interested listeners.

If some components on the page have their `immediate` attributes (see "The `immediate` Attribute" on page 143) set to `true`, then the validation, conversion, and events associated with these components will be processed during this phase.

At this point, if the application needs to redirect to a different web application resource or generate a response that does not contain any JavaServer Faces components, it can call `FacesContext.responseComplete`.

At the end of this phase, the components are set to their new values, and messages and events have been queued.

If the current request is identified as a partial request, the partial context is retrieved from the `FacesContext`, and the partial processing method is applied.

Process Validations Phase

During this phase, the JavaServer Faces implementation processes all validators registered on the components in the tree, by using its `validate` (`processValidators`) method. It examines the component attributes that specify the rules for the validation and compares these rules to the local value stored for the component.

If the local value is invalid, the JavaServer Faces implementation adds an error message to the `FacesContext` instance, and the lifecycle advances directly to the Render Response phase so that the page is rendered again with the error messages displayed. If there were conversion errors from the Apply Request Values phase, the messages for these errors are also displayed.

If any `validate` methods or event listeners have called the `renderResponse` method on the current `FacesContext`, the JavaServer Faces implementation skips to the Render Response phase.

At this point, if the application needs to redirect to a different web application resource or generate a response that does not contain any JavaServer Faces components, it can call the `FacesContext.responseComplete` method.

If events have been queued during this phase, the JavaServer Faces implementation broadcasts them to interested listeners.

If the current request is identified as a partial request, the partial context is retrieved from the `Faces Context`, and the partial processing method is applied.

Update Model Values Phase

After the JavaServer Faces implementation determines that the data is valid, it traverses the component tree and sets the corresponding server-side object properties to the components' local values. The JavaServer Faces implementation updates only the bean properties pointed at by an input component's value attribute. If the local data cannot be converted to the types specified by the bean properties, the lifecycle advances directly to the Render Response phase so that the page is re-rendered with errors displayed. This is similar to what happens with validation errors.

If any `updateModels` methods or any listeners have called the `renderResponse` method on the current `FacesContext` instance, the JavaServer Faces implementation skips to the Render Response phase.

At this point, if the application needs to redirect to a different web application resource or generate a response that does not contain any JavaServer Faces components, it can call `FacesContext.responseComplete` method.

If events have been queued during this phase, the JavaServer Faces implementation broadcasts them to interested listeners.

If the current request is identified as a partial request, the partial context is retrieved from the `FacesContext`, and the partial processing method is applied.

Invoke Application Phase

During this phase, the JavaServer Faces implementation handles any application-level events, such as submitting a form or linking to another page.

At this point, if the application needs to redirect to a different web application resource or generate a response that does not contain any JavaServer Faces components, it can call the `FacesContext.responseComplete` method.

If the view being processed was reconstructed from state information from a previous request and if a component has fired an event, these events are broadcast to interested listeners.

Finally, the JavaServer Faces implementation transfers control to the Render Response phase.

Render Response Phase

During this phase, JavaServer Faces builds the view and delegates authority to the appropriate resource for rendering the pages.

If this is an initial request, the components that are represented on the page will be added to the component tree. If this is not an initial request, the components are already added to the tree, so they need not be added again.

If the request is a postback and errors were encountered during the Apply Request Values phase, Process Validations phase, or Update Model Values phase, the original page is rendered during this phase. If the pages contain `message` or `messages` tags, any queued error messages are displayed on the page.

After the content of the view is rendered, the state of the response is saved so that subsequent requests can access it. The saved state is available to the Restore View phase.

Partial Processing and Partial Rendering

The JavaServer Faces lifecycle spans the entire execute and render processes of applications. It is also possible to process and render only parts of an application, such as a single component. For example, the JavaServer Faces Ajax framework can generate requests containing information on which particular component may be processed and which particular component may be rendered back to the client.

Once such a partial request enters the JavaServer Faces lifecycle, the information is identified and processed by a `javax.faces.context.PartialViewContext` object. The JavaServer Faces lifecycle is still aware of such Ajax requests and modifies the component tree accordingly.

The execute and render attributes of the `f:ajax` tag are used to identify which components may be executed and rendered. For more information on these attributes, see Chapter 12, "Using Ajax with JavaServer Faces Technology."

The Lifecycle of a Facelets Application

The JavaServer Faces specification defines the lifecycle of a JavaServer Faces application. For more information on this lifecycle, see "The Lifecycle of a JavaServer Faces Application" on page 204. The following steps describe that process as applied to a Facelets based application.

- When a client, such as a browser, makes a new request to a page that is created using Facelets, a new component tree or `UIViewRoot` is created and placed in the `FacesContext`.
- The `UIViewRoot` is applied to the Facelets, and the view is populated with components for rendering.
- The newly built view is rendered back as a response to the client.
- On rendering, the state of this view is stored for the next request. The state of input components and form data is stored.
- The client may interact with the view and request another view or change from the JavaServer Faces application. At this time the saved view is restored from the stored state.
- The restored view is once again passed through the JavaServer Faces lifecycle and eventually will either generate a new view or re-render the current view if there were no validation problems or no action was triggered.
- If the same view is requested, the stored view is rendered once again.
- If a new view is requested, then the process described in the second step is continued.
- The new view is then rendered back as a response to the client.

User Interface Component Model

In addition to the lifecycle description, an overview of JavaServer Faces architecture provides better understanding of the technology.

JavaServer Faces components are the building blocks of a JavaServer Faces view. A component can be a user interface (UI) component or a non-UI component.

JavaServer Faces UI components are configurable, reusable elements that compose the user interfaces of JavaServer Faces applications. A component can be simple, such as a button, or can be compound, such as a table, composed of multiple components.

JavaServer Faces technology provides a rich, flexible component architecture that includes the following:

- A set of `UIComponent` classes for specifying the state and behavior of UI components
- A rendering model that defines how to render the components in various ways
- An event and listener model that defines how to handle component events
- A conversion model that defines how to register data converters onto a component
- A validation model that defines how to register validators onto a component

This section briefly describes each of these pieces of the component architecture.

User Interface Component Classes

JavaServer Faces technology provides a set of UI component classes and associated behavioral interfaces that specify all the UI component functionality, such as holding component state, maintaining a reference to objects, and driving event handling and rendering for a set of standard components.

The component classes are completely extensible, allowing component writers to create their own custom components. See Chapter 14, "Creating Custom UI Components," for more information.

The abstract base class for all components is `javax.faces.component.UIComponent`. JavaServer Faces UI component classes extend `UIComponentBase` class, (a subclass of `UIComponent` class) which defines the default state and behavior of a component. The following set of component classes is included with JavaServer Faces technology:

- `UIColumn`: Represents a single column of data in a `UIData` component.
- `UICommand`: Represents a control that fires actions when activated.
- `UIData`: Represents a data binding to a collection of data represented by a `DataModel` instance.
- `UIForm`: Encapsulates a group of controls that submit data to the application. This component is analogous to the `form` tag in HTML.

- `UIGraphic`: Displays an image.
- `UIInput`: Takes data input from a user. This class is a subclass of `UIOutput`.
- `UIMessage`: Displays a localized error message.
- `UIMessages`: Displays a set of localized error messages.
- `UIOutcomeTarget`: Displays a hyperlink in the form of a link or a button.
- `UIOutput`: Displays data output on a page.
- `UIPanel`: Manages the layout of its child components.
- `UIParameter`: Represents substitution parameters.
- `UISelectBoolean`: Allows a user to set a `boolean` value on a control by selecting or deselecting it. This class is a subclass of `UIInput` class.
- `UISelectItem`: Represents a single item in a set of items.
- `UISelectItems`: Represents an entire set of items.
- `UISelectMany`: Allows a user to select multiple items from a group of items. This class is a subclass of `UIInput` class.
- `UISelectOne`: Allows a user to select one item from a group of items. This class is a subclass of `UIInput` class.
- `UIViewParameter`: Represents the query parameters in a request. This class is a subclass of `UIInput` class.
- `UIViewRoot`: Represents the root of the component tree.

In addition to extending `UIComponentBase`, the component classes also implement one or more *behavioral interfaces*, each of which defines certain behavior for a set of components whose classes implement the interface.

These behavioral interfaces are as follows:

- `ActionSource`: Indicates that the component can fire an action event. This interface is intended for use with components based on JavaServer Faces technology 1.1_01 and earlier versions. This interface is deprecated in JavaServer Faces 2.x.
- `ActionSource2`: Extends `ActionSource`, and therefore provides the same functionality. However, it allows components to use the unified EL when they are referencing methods that handle action events.
- `EditableValueHolder`: Extends `ValueHolder` and specifies additional features for editable components, such as validation and emitting value-change events.
- `NamingContainer`: Mandates that each component rooted at this component have a unique ID.
- `StateHolder`: Denotes that a component has state that must be saved between requests.
- `ValueHolder`: Indicates that the component maintains a local value as well as the option of accessing data in the model tier.

- `SystemEventListenerHolder`: Maintains a list of `SystemEventListener` instances for each type of `SystemEvent` defined by that class.
- `ClientBehaviorHolder`: Adds the ability to attach `ClientBehavior` instances such as a reusable script.

`UICommand` implements `ActionSource2` and `StateHolder`. `UIOutput` and component classes that extend `UIOutput` implement `StateHolder` and `ValueHolder`. `UIInput` and component classes that extend `UIInput` implement `EditableValueHolder`, `StateHolder`, and `ValueHolder`. `UIComponentBase` implements `StateHolder`.

Only component writers will need to use the component classes and behavioral interfaces directly. Page authors and application developers will use a standard component by including a tag that represents it on a page. Most of the components can be rendered in different ways on a page. For example, a `UICommand` component can be rendered as a button or a hyperlink.

The next section explains how the rendering model works and how page authors can choose to render the components by selecting the appropriate tags.

Component Rendering Model

The JavaServer Faces component architecture is designed such that the functionality of the components is defined by the component classes, whereas the component rendering can be defined by a separate renderer class. This design has several benefits, including:

- Component writers can define the behavior of a component once but create multiple renderers, each of which defines a different way to render the component to the same client or to different clients.
- Page authors and application developers can change the appearance of a component on the page by selecting the tag that represents the appropriate combination of component and renderer.

A *render kit* defines how component classes map to component tags that are appropriate for a particular client. The JavaServer Faces implementation includes a standard HTML render kit for rendering to an HTML client.

The render kit defines a set of `Renderer` classes for each component that it supports. Each `Renderer` class defines a different way to render the particular component to the output defined by the render kit. For example, a `UISelectOne` component has three different renderers. One of them renders the component as a set of radio buttons. Another renders the component as a combo box. The third one renders the component as a list box.

Each custom tag defined in the standard HTML render kit is composed of the component functionality (defined in the `UIComponent` class) and the rendering attributes (defined by the `Renderer` class). For example, the two tags in Table 10–1 represent a `UICommand` component rendered in two different ways.

TABLE 10–1 `UICommand` Tags

Tag	Rendered As
`commandButton`	
`commandLink`	

The command part of the tags shown in Table 10–1 corresponds to the `UICommand` class, specifying the functionality, which is to fire an action. The button and hyperlink parts of the tags each correspond to a separate `Renderer` class, which defines how the component appears on the page.

The JavaServer Faces implementation provides a custom tag library for rendering components in HTML. The section "Adding Components to a Page Using HTML Tags" on page 140 lists all supported component tags and describes how to use the tags in an example.

Conversion Model

A JavaServer Faces application can optionally associate a component with server-side object data. This object is a JavaBeans component, such as a backing bean. An application gets and sets the object data for a component by calling the appropriate object properties for that component.

When a component is bound to an object, the application has two views of the component's data:

- The model view, in which data is represented as data types, such as `int` or `long`.
- The presentation view, in which data is represented in a manner that can be read or modified by the user. For example, a `java.util.Date` might be represented as a text string in the format *mm/dd/yy* or as a set of three text strings.

The JavaServer Faces implementation automatically converts component data between these two views when the bean property associated with the component is of one of the types supported by the component's data. For example, if a `UISelectBoolean` component is associated with a bean property of type `java.lang.Boolean`, the JavaServer Faces implementation will automatically convert the component's data from `String` to `Boolean`. In addition, some component data must be bound to properties of a particular type. For example, a `UISelectBoolean` component must be bound to a property of type `boolean` or `java.lang.Boolean`.

Sometimes you might want to convert a component's data to a type other than a standard type, or you might want to convert the format of the data. To facilitate this, JavaServer Faces technology allows you to register a `Converter` implementation on `UIOutput` components and components whose classes subclass `UIOutput`. If you register the `Converter` implementation on a component, the `Converter` implementation converts the component's data between the two views.

You can either use the standard converters supplied with the JavaServer Faces implementation or create your own custom converter. Custom converter creation is covered in Chapter 14, "Creating Custom UI Components."

Event and Listener Model

The JavaServer Faces event and listener model is similar to the JavaBeans event model in that it has strongly typed event classes and listener interfaces that an application can use to handle events generated by components.

The JavaServer Faces specification defines three types of events: application events, system events and data-model events.

Application events are tied to a particular application and are generated by a `UIComponent`. They represent the standard events available in previous versions of JavaServer Faces technology.

An `Event` object identifies the component that generated the event and stores information about the event. To be notified of an event, an application must provide an implementation of the `Listener` class and must register it on the component that generates the event. When the user activates a component, such as by clicking a button, an event is fired. This causes the JavaServer Faces implementation to invoke the listener method that processes the event.

JavaServer Faces supports two kinds of application events: action events and value-change events.

An *action event* (class `ActionEvent`) occurs when the user activates a component that implements `ActionSource`. These components include buttons and hyperlinks.

A *value-change event* (class `ValueChangeEvent`) occurs when the user changes the value of a component represented by `UIInput` or one of its subclasses. An example is selecting a check box, an action that results in the component's value changing to `true`. The component types that can generate these types of events are the `UIInput`, `UISelectOne`, `UISelectMany`, and `UISelectBoolean` components. Value-change events are fired only if no validation errors were detected.

Depending on the value of the `immediate` property (see "The `immediate` Attribute" on page 143) of the component emitting the event, action events can be processed during the invoke application phase or the apply request values phase, and value-change events can be processed during the process validations phase or the apply request values phase.

System events are generated by an `Object` rather than a `UIComponent`. They are generated during the execution of an application at predefined times. They are applicable to the entire application rather than to a specific component.

A *data-model event* occurs when a new row of a `UIData` component is selected.

There are two ways to cause your application to react to action events or value-change events that are emitted by a standard component:

- Implement an event listener class to handle the event and register the listener on the component by nesting either a `valueChangeListener` tag or an `actionListener` tag inside the component tag.
- Implement a method of a backing bean to handle the event and refer to the method with a method expression from the appropriate attribute of the component's tag.

See "Implementing an Event Listener" on page 286 for information on how to implement an event listener. See "Registering Listeners on Components" on page 176 for information on how to register the listener on a component.

See "Writing a Method to Handle an Action Event" on page 196 and "Writing a Method to Handle a Value-Change Event" on page 197 for information on how to implement backing bean methods that handle these events.

See "Referencing a Backing Bean Method" on page 180 for information on how to refer to the backing bean method from the component tag.

When emitting events from custom components, you must implement the appropriate `Event` class and manually queue the event on the component in addition to implementing an event listener class or a backing bean method that handles the event. "Handling Events for Custom Components" on page 280 explains how to do this.

Validation Model

JavaServer Faces technology supports a mechanism for validating the local data of editable components (such as text fields). This validation occurs before the corresponding model data is updated to match the local value.

Like the conversion model, the validation model defines a set of standard classes for performing common data validation checks. The JavaServer Faces core tag library also defines a set of tags that correspond to the standard `Validator` implementations. See "Using the Standard Validators" on page 178 for a list of all the standard validation classes and corresponding tags.

Most of the tags have a set of attributes for configuring the validator's properties, such as the minimum and maximum allowable values for the component's data. The page author registers the validator on a component by nesting the validator's tag within the component's tag.

In addition to validators that are registered on the component, you can declare a default validator which is registered on all `UIInput` components in the application. For more information on default validators, see "Using Default Validators" on page 238.

The validation model also allows you to create your own custom validator and corresponding tag to perform custom validation. The validation model provides two ways to implement custom validation:

- Implement a `Validator` interface that performs the validation.
- Implement a backing bean method that performs the validation.

If you are implementing a `Validator` interface, you must also:

- Register the `Validator` implementation with the application.
- Create a custom tag or use a `validator` tag to register the validator on the component.

In the previously described standard validation model, the validator is defined for each input component on a page. The Bean Validation model allows the validator to be applied to all fields in a page. See "Using Bean Validation" on page 198 and Chapter 47, "Advanced Bean Validation Concepts and Examples," for more information on Bean Validation.

Navigation Model

The JavaServer Faces navigation model makes it easy to define page navigation and to handle any additional processing that is needed to choose the sequence in which pages are loaded.

In JavaServer Faces technology, *navigation* is a set of rules for choosing the next page or view to be displayed after an application action, such as when a button or hyperlink is clicked.

Navigation can be implicit or user-defined. Implicit navigation comes into play when user-defined navigation rules are not available. For more information on implicit navigation, see "Implicit Navigation Rules" on page 241.

User-defined navigation rules are declared in zero or more application configuration resource files such as `faces-config.xml`, by using a set of XML elements. The default structure of a navigation rule is as follows:

```
<navigation-rule>
    <description></description
    <from-view-id></from-view-id>
    <navigation-case>
        <from-action></from-action>
        <from-outcome></from-outcome>
        <if></if>
        <to-view-id></to-view-id>
    </navigation-case>
</navigation-rule>
```

User-defined navigation is handled as follows::

- Define the rules in the application configuration resource file.
- Refer to an outcome `String` from the button or hyperlink component's `action` attribute. This outcome `String` is used by the JavaServer Faces implementation to select the navigation rule.

Here is an example navigation rule:

```
<navigation-rule>
    <from-view-id>/greeting.xhtml</from-view-id>
    <navigation-case>
        <from-outcome>success</from-outcome>
        <to-view-id>/response.xhtml</to-view-id>
    </navigation-case>
</navigation-rule>
```

This rule states that when a command component (such as a `commandButton` or a `commandLink`) on `greeting.xhtml` is activated, the application will navigate from the `greeting.xhtml` page to the `response.xhtml` page if the outcome referenced by the button component's tag is `success`. Here is the `commandButton` tag from `greeting.xhtml` that specifies a logical outcome of success:

```
<h:commandButton id="submit" action="success"
         value="Submit" />
```

As the example demonstrates, each `navigation-rule` element defines how to get from one page (specified in the `from-view-id` element) to the other pages of the application. The `navigation-rule` elements can contain any number of `navigation-case` elements, each of which defines the page to open next (defined by `to-view-id`) based on a logical outcome (defined by `from-outcome`) .

In more complicated applications, the logical outcome can also come from the return value of an *action method* in a backing bean. This method performs some processing to determine the outcome. For example, the method can check whether the password the user entered on the page matches the one on file. If it does, the method might return `success`; otherwise, it might return `failure`. An outcome of `failure` might result in the logon page being reloaded. An outcome of `success` might cause the page displaying the user's credit card activity to open. If you want the outcome to be returned by a method on a bean, you must refer to the method using a method expression, with the `action` attribute, as shown by this example:

```
<h:commandButton id="submit"
     action="#{userNumberBean.getOrderStatus}" value="Submit" />
```

When the user clicks the button represented by this tag, the corresponding component generates an action event. This event is handled by the default `ActionListener` instance, which calls the action method referenced by the component that triggered the event. The action method returns a logical outcome to the action listener.

The listener passes the logical outcome and a reference to the action method that produced the outcome to the default `NavigationHandler`. The `NavigationHandler` selects the page to display next by matching the outcome or the action method reference against the navigation rules in the application configuration resource file by the following process:

1. The `NavigationHandler` selects the navigation rule that matches the page currently displayed.
2. It matches the outcome or the action method reference that it received from the default `ActionListener` with those defined by the navigation cases.
3. It tries to match both the method reference and the outcome against the same navigation case.
4. If the previous step fails, the navigation handler attempts to match the outcome.
5. Finally, the navigation handler attempts to match the action method reference if the previous two attempts failed.
6. If no navigation case is matched, it displays the same view again.

When the `NavigationHandler` achieves a match, the render response phase begins. During this phase, the page selected by the `NavigationHandler` will be rendered.

For more information on how to define navigation rules, see "Configuring Navigation Rules" on page 238.

For more information on how to implement action methods to handle navigation, see "Writing a Method to Handle an Action Event" on page 196.

For more information on how to reference outcomes or action methods from component tags, see "Referencing a Method That Performs Navigation" on page 181.

◆ ◆ ◆ CHAPTER 11

Configuring JavaServer Faces Applications

The process of building and deploying simple JavaServer Faces applications has been described in earlier chapters of this tutorial. When you create large and complex applications, however, various additional configuration tasks are required. These tasks include the following:

- Registering back-end objects with the application so that all parts of the application have access to them
- Configuring backing beans and model beans so that they are instantiated with the proper values when a page makes reference to them
- Defining navigation rules for each of the pages in the application so that the application has a smooth page flow, if non-default navigation is needed
- Packaging the application to include all the pages, resources, and other files so that the application can be deployed on any compliant container

The following topics are addressed here:

Using Annotations to Configure Managed Beans

JavaServer Faces support for bean annotations has been introduced in Chapter 4, "JavaServer Faces Technology." Bean annotations can be used for configuring JavaServer Faces applications.

The `@ManagedBean` (`javax.faces.bean.ManagedBean`) annotation in a class automatically registers that class as a managed bean class with the server runtime. Such a registered managed bean does not need `managed-bean` configuration entries in the application configuration resource file.

An example of using the `@ManagedBean` annotation on a class is as follows:

```
@ManagedBean
@SessionScoped
public class DukesBday{
...
}
```

The above code snippet shows a bean that is managed by the JavaServer Faces implementation and is available for the length of that session. You do not need to configure the managed bean instance in the `faces-config.xml` file. In effect, it is an alternative to the application configuration resource file approach and reduces the task of configuring managed beans.

You can also define the scope of the managed bean within the class file, as shown in the above example. You can annotate beans with request, session, or application scope, but not view scope.

All classes will be scanned for annotations at startup unless the `faces-config` element in the `faces-config.xml` file has the `metadata-complete` attribute set to `true`.

Annotations are also available for other artifacts such as components, converters, validators, and renderers to be used in place of application configuration resource file entries. They are discussed, along with registration of custom listeners, custom validators, and custom converters, in Chapter 14, "Creating Custom UI Components."

Using Managed Bean Scopes

You can use annotations to define the scope in which the bean will be stored. You can specify one of the following scopes for a bean class:

- Application (`@ApplicationScoped`): Application scope persists across all users' interactions with a web application.
- Session (`@SessionScoped`): Session scope persists across multiple HTTP requests in a web application
- View (`@ViewScoped`): View scope persists during a user's interaction with a single page (view) of a web application.

- Request (`@RequestScoped`): Request scope persists during a single HTTP request in a web application.
- None (`@NoneScoped`):

  Indicates a scope is not defined for the application.
- Custom (`@CustomScoped`): A user-defined, nonstandard scope. Its value must be configured as a map. Custom scopes are used infrequently.

You may want to use `@NoneScoped` when a managed bean references another managed bean. The second bean should not be in a scope (`@NoneScoped`) if it is supposed to be created only when it is referenced. If you define a bean as `@NoneScoped`, the bean is instantiated anew each time that it is referenced, and so it does not get saved in any scope.

If your managed bean takes part in a single HTTP request, you should define the bean with a request scope. If you placed the bean in session or application scope instead, the bean would need to take precautions to ensure thread safety because component instances depend on running inside of a single thread.

If you are configuring a bean that allows attributes to be associated with the view, you can use the view scope. The attributes persist until the user has navigated to the next view.

Eager Application—scoped Beans

Managed beans are lazily instantiated. That is, that they are instantiated when a request is made from the application.

To force an application-scoped bean to be instantiated and placed in the application scope as soon as the application is started and before any request is made, the `eager` attribute of the managed bean should be set to `true` as shown in the following example:

```
@ManagedBean(eager=true)
@ApplicationScoped
```

Application Configuration Resource File

JavaServer Faces technology provides a portable configuration format (as an XML document) for configuring application resources. One or more XML documents, called application configuration resource files, may use this format to register and configure objects and resources, and to define navigation rules for applications. An application configuration resource file is usually named `faces-config.xml`.

You need an application configuration resource file in the following cases:

- To specify configuration elements for your application that are not available through managed bean annotations, such as localized messages and navigation rules
- To override managed bean annotations when the application is deployed

The application configuration resource file must be valid against the XML schema located at `http://java.sun.com/xml/ns/javaee/web-facesconfig_2_0.xsd`.

In addition, each file must include the following information, in the following order:

- The XML version number, usually with an `encoding` attribute:

```
<?xml version="1.0" encoding='UTF-8'?>
```

- A `faces-config` tag enclosing all the other declarations:

```
<faces-config version="2.0" xmlns="http://java.sun.com/xml/ns/javaee"
   xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
   xsi:schemaLocation="http://java.sun.com/xml/ns/javaee
   http://java.sun.com/xml/ns/javaee/web-facesconfig_2_0.xsd">
   ...
</faces-config>
```

You can have more than one application configuration resource file for an application. The JavaServer Faces implementation finds the configuration file or files by looking for the following:

- A resource named `/META-INF/faces-config.xml` in any of the JAR files in the web application's `/WEB-INF/lib/` directory and in parent class loaders. If a resource with this name exists, it is loaded as a configuration resource. This method is practical for a packaged library containing some components and renderers. In addition, any file with a name that ends in `faces-config.xml` is also considered a configuration resource and is loaded as such.
- A context initialization parameter, `javax.faces.application.CONFIG_FILES`, in your web deployment descriptor file that specifies one or more (comma-delimited) paths to multiple configuration files for your web application. This method is most often used for enterprise-scale applications that delegate to separate groups the responsibility for maintaining the file for each portion of a big application.
- A resource named `faces-config.xml` in the `/WEB-INF/` directory of your application. Simple web applications make their configuration files available in this way.

To access the resources registered with the application, you can use an instance of the `Application` class, which is automatically created for each application. The `Application` instance acts as a centralized factory for resources that are defined in the XML file.

When an application starts up, the JavaServer Faces implementation creates a single instance of the `Application` class and configures it with the information that you provided in the application configuration resource file.

Ordering of Application Configuration Resource Files

Because JavaServer Faces technology allows the use of multiple application configuration resource files stored in different locations, the order in which they are loaded by the implementation becomes important in certain situations (for example, when using application

level objects). This order can be defined through an `ordering` element and its sub-elements in the application configuration resource file itself. The ordering of application configuration resource files can be absolute or relative.

Absolute ordering is defined by an `absolute-ordering` element in the file. With absolute ordering, the user specifies the order in which application configuration resource files will be loaded. The following example shows an entry for absolute ordering:

File `my-faces-config.xml`:

```
<faces-config>
    <name>myJSF</name>
    <absolute-ordering>
        <name>A</name>
        <name>B</name>
        <name>C</name>
    </absolute-ordering>
</faces-config>
```

In this example, A, B, and C are different application configuration resource files and are to be loaded in the listed order.

If there is an `absolute-ordering` element in the file, only the files listed by the sub-element `name` are processed. To process any other application configuration resource files, an `others` sub-element is required. In the absence of the `others` sub-element, all other unlisted files will be ignored at load time.

Relative ordering is defined by an `ordering` element and its sub-elements `before` and `after`. With relative ordering, the order in which application configuration resource files will be loaded is calculated by considering ordering entries from the different files. The following example shows some of these considerations. In the following example, `config-A`, `config-B`, and `config-C` are different application configuration resource files.

File `config-A` contains the following elements:

```
<faces-config>
    <name>config-A</name>
    <ordering>
        <before>
            <name>config-B</name>
        </before>
    </ordering>
</faces-config>
```

File `config-B` (not shown here) does not contain any `ordering` elements.

File `config-C` contains the following elements:

```
<faces-config>
    <name>config-C</name>
    <ordering>
```

```
        <after>
            <name>config-B</name>
        </after>
    </ordering>
</faces-config>
```

Based on the `before` sub-element entry, file `config-A` will be loaded before the `config-B` file. Based on the `after` sub-element entry, file `config-C` will be loaded after the `config-B` file.

In addition, a sub-element `others` can also be nested within the `before` and `after` sub-elements. If the `others` element is present, the file may receive highest or lowest preference among both listed and unlisted configuration files.

If an `ordering` element is not present in an application configuration file, then that file will receive the lowest order when being loaded, compared to the files that contain an `ordering` element.

Configuring Beans

When a page references a managed bean for the first time, the JavaServer Faces implementation initializes it based on either a `@ManagedBean` annotation in the bean class, or according to its configuration in the application configuration resource file. For information on using annotations to initialize beans, see "Using Annotations to Configure Managed Beans" on page 222.

You can use either annotations or the application configuration resource file to instantiate backing beans and other managed beans that are used in a JavaServer Faces application and to store them in scope. The managed bean creation facility is configured in the application configuration resource file using `managed-bean` XML elements to define each bean. This file is processed at application startup time. For information on using this facility, see "Using the `managed-bean` Element" on page 227.

With the managed bean creation facility, you can:

- Create beans in one centralized file that is available to the entire application, rather than conditionally instantiate beans throughout the application
- Customize the bean's properties without any additional code
- Customize the bean's property values directly from within the configuration file so that it is initialized with these values when it is created
- Using `value` elements, set the property of one managed bean to be the result of evaluating another value expression

This section shows you how to initialize beans using the managed bean creation facility. See "Writing Bean Properties" on page 186 and "Writing Backing Bean Methods" on page 194 for information on programming backing beans.

Using the `managed-bean` Element

A managed bean is initiated using a `managed-bean` element in the application configuration resource file, which represents an instance of a bean class that must exist in the application. At runtime, the JavaServer Faces implementation processes the `managed-bean` element. If a page references the bean, and if no bean instance exists, the JavaServer Faces implementation instantiates the bean as specified by the element configuration.

Here is an example managed bean configuration:

```
<managed-bean>
    <managed-bean-name> UserNumberBean </managed-bean-name>
    <managed-bean-class>
        guessNumber.UserNumberBean
    </managed-bean-class>
    <managed-bean-scope> session </managed-bean-scope>
    <managed-property>
        <property-name> maximum </property-name>
        <property-class> long </property-class>
        <value> 10 </value>
    </managed-property>
        ...
</managed-bean>
```

Using NetBeans IDE, you can add a managed bean declaration by doing the following:

1. After opening your project in NetBeans IDE, expand the project node in the Projects pane.
2. Expand the Web Pages and WEB-INF nodes of the project node.
3. If there is no `faces-config.xml` in the project, create one as follows:
    a. From the File menu, choose New File.
    b. Select File→New File.
    c. In the New File wizard, select the JavaServer Faces category, then select JSF Faces Configuration and click Next.
    d. On the Name and Location page, change the name and location of the file if necessary. The default file name is `faces-config.xml`.
    e. Click Finish.
4. Double-click `faces-config.xml` if the file is not already open.
5. After `faces-config.xml` opens in the editor pane, select XML from the sub tab panel options.
6. Right-click in the editor pane.
7. From the Insert menu, choose Managed Bean.
8. In the Add Managed Bean dialog box:
    a. Type the display name of the bean in the Bean Name field.
    b. Click Browse to locate the bean's class.

9. In the Browse Class dialog box:
    a. Start typing the name of the class that you are looking for in the Class Name field. While you are typing, the dialog will show the matching classes.
    b. Select the class from the Matching Classes box.
    c. Click OK.
10. In the Add Managed Bean dialog box:
    a. Select the bean's scope from the Scope menu.
    b. Click Add.

The preceding steps will add the `managed-bean` element and three elements inside of that element: a `managed-bean-name` element, a `managed-bean-class` element, and a `managed-bean-scope` element. You will need to edit the XML of the configuration file directly to further configure this managed bean.

The `managed-bean-name` element defines the key under which the bean will be stored in a scope. For a component's value to map to this bean, the component tag's `value` attribute must match the `managed-bean-name` up to the first period.

The `managed-bean-class` element defines the fully qualified name of the JavaBeans component class used to instantiate the bean.

The `managed-bean` element can contain zero or more `managed-property` elements, each corresponding to a property defined in the bean class. These elements are used to initialize the values of the bean properties. If you don't want a particular property initialized with a value when the bean is instantiated, do not include a `managed-property` definition for it in your application configuration resource file.

If a `managed-bean` element does not contain other `managed-bean` elements, it can contain one `map-entries` element or `list-entries` element. The `map-entries` element configures a set of beans that are instances of `Map`. The `list-entries` element configures a set of beans that are instances of `List`.

To map to a property defined by a `managed-property` element, you must ensure that the part of a component tag's `value` expression after the period matches the `managed-property` element's `property-name` element. In the earlier example, the `maximum` property is initialized with the value `10`. "Initializing Properties Using the `managed-property` Element" on page 229 explains in more detail how to use the `managed-property` element. See "Initializing Managed Bean Properties" on page 232 for an example of initializing a managed bean property.

Initializing Properties Using the `managed-property` Element

A `managed-property` element must contain a `property-name` element, which must match the name of the corresponding property in the bean. A `managed-property` element must also contain one of a set of elements (listed in Table 11–1) that defines the value of the property. This value must be of the same type as that defined for the property in the corresponding bean. Which element you use to define the value depends on the type of the property defined in the bean. Table 11–1 lists all the elements that are used to initialize a value.

TABLE 11–1 Sub-elements of `managed-property` Elements That Define Property Values

Element	Value That It Defines
`list-entries`	Defines the values in a list
`map-entries`	Defines the values of a map
`null-value`	Explicitly sets the property to `null`
`value`	Defines a single value, such as a `String`, `int`, or JavaServer Faces EL expression

"Using the `managed-bean` Element" on page 227 includes an example of initializing an `int` property (a primitive type) using the `value` sub-element. You also use the `value` sub-element to initialize `String` and other reference types. The rest of this section describes how to use the `value` sub-element and other sub-elements to initialize properties of Java `Enum` types, `java.util.Map`, `array`, and `java.util.Collection`, as well as initialization parameters.

Referencing a Java `Enum` Type

A managed bean property can also be a Java `Enum` type (see `http://download.oracle.com/javase/6/docs/api/java/lang/Enum.html`). In this case, the `value` element of the `managed-property` element must be a `String` that matches one of the `String` constants of the `Enum`. In other words, the `String` must be one of the valid values that can be returned if you were to call `valueOf(Class, String)` on `enum`, where `Class` is the `Enum` class and `String` is the contents of the `value` subelement. For example, suppose the managed bean property is the following:

```
public enum Suit { Hearts, Spades, Diamonds, Clubs}
 ...
public Suit getSuit() { ... return Suit.Hearts; }
```

Assuming that you want to configure this property in the application configuration resource file, the corresponding `managed-property` element would look like this:

```
<managed-property>
    <property-name>Suit</property-name>
```

```
    <value>Hearts</value>
</managed-property>
```

When the system encounters this property, it iterates over each of the members of the `enum` and calls `toString()` on each member until it finds one that is exactly equal to the value from the `value` element.

Referencing an Initialization Parameter

Another powerful feature of the managed bean creation facility is the ability to reference implicit objects from a managed bean property.

Suppose that you have a page that accepts data from a customer, including the customer's address. Suppose also that most of your customers live in a particular area code. You can make the area code component render this area code by saving it in an implicit object and referencing it when the page is rendered.

You can save the area code as an initial default value in the context `initParam` implicit object by adding a context parameter to your web application and setting its value in the deployment descriptor. For example, to set a context parameter called `defaultAreaCode` to `650`, add a `context-param` element to the deployment descriptor, and give the parameter the name `defaultAreaCode` and the value `650`.

Next, you write a `managed-bean` declaration that configures a property that references the parameter:

```
<managed-bean>
    <managed-bean-name>customer</managed-bean-name>
        <managed-bean-class>CustomerBean</managed-bean-class>
        <managed-bean-scope>request</managed-bean-scope>
        <managed-property>
            <property-name>areaCode</property-name>
                <value>#{initParam.defaultAreaCode}</value>
            </managed-property>
            ...
</managed-bean>
```

To access the area code at the time that the page is rendered, refer to the property from the `area` component tag's `value` attribute:

```
<h:inputText id=area value="#{customer.areaCode}"
```

Retrieving values from other implicit objects is done in a similar way.

Initializing Map Properties

The `map-entries` element is used to initialize the values of a bean property with a type of `java.util.Map` if the `map-entries` element is used within a `managed-property` element. A `map-entries` element contains an optional `key-class` element, an optional `value-class` element, and zero or more `map-entry` elements.

Each of the `map-entry` elements must contain a `key` element and either a `null-value` or `value` element. Here is an example that uses the `map-entries` element:

```
<managed-bean>
    ...
    <managed-property>
        <property-name>prices</property-name>
        <map-entries>
            <map-entry>
                <key>My Early Years: Growing Up on *7</key>
                <value>30.75</value>
            </map-entry>
            <map-entry>
                <key>Web Servers for Fun and Profit</key>
                <value>40.75</value>
            </map-entry>
        </map-entries>
    </managed-property>
</managed-bean>
```

The map that is created from this `map-entries` tag contains two entries. By default, all the keys and values are converted to `java.lang.String`. If you want to specify a different type for the keys in the map, embed the `key-class` element just inside the `map-entries` element:

```
<map-entries>
    <key-class>java.math.BigDecimal</key-class>
    ...
</map-entries>
```

This declaration will convert all the keys into `java.math.BigDecimal`. Of course, you must make sure that the keys can be converted to the type that you specify. The key from the example in this section cannot be converted to a `java.math.BigDecimal`, because it is a `String`.

If you also want to specify a different type for all the values in the map, include the `value-class` element after the `key-class` element:

```
<map-entries>
    <key-class>int</key-class>
    <value-class>java.math.BigDecimal</value-class>
    ...
</map-entries>
```

Note that this tag sets only the type of all the `value` subelements.

The first `map-entry` in the preceding example includes a `value` subelement. The `value` subelement defines a single value, which will be converted to the type specified in the bean.

The second `map-entry` defines a `value` element, which references a property on another bean. Referencing another bean from within a bean property is useful for building a system from fine-grained objects. For example, a request-scoped form-handling object might have a pointer to an application-scoped database mapping object. Together the two can perform a form-handling task. Note that including a reference to another bean will initialize the bean if it does not already exist.

Instead of using a `map-entries` element, it is also possible to assign the entire map using a `value` element that specifies a map-typed expression.

Initializing Array and List Properties

The `list-entries` element is used to initialize the values of an `array` or `java.util.List` property. Each individual value of the array or `List` is initialized using a `value` or `null-value` element. Here is an example:

```
<managed-bean>
    ...
    <managed-property>
        <property-name>books</property-name>
        <list-entries>
            <value-class>java.lang.String</value-class>
            <value>Web Servers for Fun and Profit</value>
            <value>#{myBooks.bookId[3]}</value>
            <null-value/>
        </list-entries>
    </managed-property>
</managed-bean>
```

This example initializes an `array` or a `List`. The type of the corresponding property in the bean determines which data structure is created. The `list-entries` element defines the list of values in the `array` or `List`. The `value` element specifies a single value in the `array` or `List` and can reference a property in another bean. The `null-value` element will cause the `setBooks` method to be called with an argument of `null`. A `null` property cannot be specified for a property whose data type is a Java primitive, such as `int` or `boolean`.

Initializing Managed Bean Properties

Sometimes you might want to create a bean that also references other managed beans so that you can construct a graph or a tree of beans. For example, suppose that you want to create a bean representing a customer's information, including the mailing address and street address, each of which is also a bean. The following `managed-bean` declarations create a `CustomerBean` instance that has two `AddressBean` properties: one representing the mailing address, and the other representing the street address. This declaration results in a tree of beans with `CustomerBean` as its root and the two `AddressBean` objects as children.

```
<managed-bean>
    <managed-bean-name>customer</managed-bean-name>
    <managed-bean-class>
        com.mycompany.mybeans.CustomerBean
    </managed-bean-class>
    <managed-bean-scope> request </managed-bean-scope>
    <managed-property>
        <property-name>mailingAddress</property-name>
        <value>#{addressBean}</value>
    </managed-property>
    <managed-property>
        <property-name>streetAddress</property-name>
```

```
        <value>#{addressBean}</value>
    </managed-property>
    <managed-property>
        <property-name>customerType</property-name>
        <value>New</value>
    </managed-property>
</managed-bean>
<managed-bean>
    <managed-bean-name>addressBean</managed-bean-name>
    <managed-bean-class>
        com.mycompany.mybeans.AddressBean
    </managed-bean-class>
    <managed-bean-scope> none </managed-bean-scope>
    <managed-property>
        <property-name>street</property-name>
        <null-value/>
    <managed-property>
    ...
</managed-bean>
```

The first `CustomerBean` declaration (with the `managed-bean-name` of `customer`) creates a `CustomerBean` in request scope. This bean has two properties, `mailingAddress` and `streetAddress`. These properties use the `value` element to reference a bean named `addressBean`.

The second managed bean declaration defines an `AddressBean`, but does not create it, because its `managed-bean-scope` element defines a scope of `none`. Recall that a scope of `none` means that the bean is created only when something else references it. Because both the `mailingAddress` and the `streetAddress` properties reference `addressBean` using the `value` element, two instances of `AddressBean` are created when `CustomerBean` is created.

When you create an object that points to other objects, do not try to point to an object with a shorter life span, because it might be impossible to recover that scope's resources when it goes away. A session-scoped object, for example, cannot point to a request-scoped object. And objects with `none` scope have no effective life span managed by the framework, so they can point only to other `none` scoped objects. Table 11–2 outlines all of the allowed connections.

TABLE 11–2 Allowable Connections Between Scoped Objects

An Object of This Scope	May Point to an Object of This Scope
`none`	`none`
`application`	`none`, `application`
`session`	`none`, `application`, `session`
`request`	`none`, `application`, `session`, `request`, `view`
`view`	`none`, `application`, `session`, `view`

Be sure not to allow cyclical references between objects. For example, neither of the `AddressBean` objects in the preceding example should point back to the `CustomerBean` object, because `CustomerBean` already points to the `AddressBean` objects.

Initializing Maps and Lists

In addition to configuring `Map` and `List` properties, you can also configure a `Map` and a `List` directly so that you can reference them from a tag rather than referencing a property that wraps a `Map` or a `List`.

Registering Custom Error Messages

If you create custom error messages (which are displayed by the `message` and `messages` tags) for your custom converters or validators, you must make them available at application startup time. You do this in one of two ways:

- By queuing the message onto the `FacesContext` instance programmatically, as described in "Using `FacesMessage` to Create a Message" on page 235
- By registering the messages with your application using the application configuration resource file

Here is an example of the section of the `faces-config.xml` file that registers the messages for an application:

```
<application>
    <resource-bundle>
        <base-name>dukestutoring.web.messages.Messages</base-name>
        <var>bundle</var>
    </resource-bundle>
    <locale-config>
        <default-locale>en</default-locale>
        <supported-locale>es</supported-locale>
        <supported-locale>de</supported-locale>
        <supported-locale>fr</supported-locale>
    </locale-config>
</application>
```

This set of elements will cause your `Application` instance to be populated with the messages that are contained in the specified resource bundle.

The `resource-bundle` element represents a set of localized messages. It must contain the fully qualified path to the resource bundle containing the localized messages (in this case, `dukestutoring.web.messages.Messages`).

The `locale-config` element lists the default locale and the other supported locales. The `locale-config` element enables the system to find the correct locale based on the browser's language settings.

The `supported-locale` and `default-locale` tags accept the lowercase, two-character codes as defined by ISO 639 (see `http://ftp.ics.uci.edu/pub/ietf/http/related/iso639.txt`). Make sure that your resource bundle actually contains the messages for the locales that you specify with these tags.

To access the localized message, the application developer merely references the key of the message from the resource bundle.

Using `FacesMessage` to Create a Message

Instead of registering messages in the application configuration resource file, you can access the `ResourceBundle` directly from backing bean code. The code snippet below locates an email error message:

```
String message = "";
...
message = ExampleBean.loadErrorMessage(context,
    ExampleBean.EX_RESOURCE_BUNDLE_NAME,
         "EMailError");
context.addMessage(toValidate.getClientId(context),
    new FacesMessage(message));
```

These lines call the bean's `loadErrorMessage` method to get the message from the `ResourceBundle`. Here is the `loadErrorMessage` method:

```
public static String loadErrorMessage(FacesContext context,
     String basename, String key) {
    if ( bundle == null ) {
         try {
            bundle = ResourceBundle.getBundle(basename,
                 context.getViewRoot().getLocale());
        } catch (Exception e) {
            return null;
        }
    }
    return bundle.getString(key);
}
```

Referencing Error Messages

A JavaServer Faces page uses the `message` or `messages` tags to access error messages, as explained in "Displaying Error Messages with the `h:message` and `h:messages` Tags" on page 163.

The error messages that these tags access include:

- The standard error messages that accompany the standard converters and validators that ship with the API. See Section 2.5.2.4 of the JavaServer Faces specification for a complete list of standard error messages.
- Custom error messages contained in resource bundles registered with the application by the application architect using the `resource-bundle` element in the configuration file.

When a converter or validator is registered on an input component, the appropriate error message is automatically queued on the component.

A page author can override the error messages queued on a component by using the following attributes of the component's tag:

- `converterMessage`: References the error message to display when the data on the enclosing component can not be converted by the converter registered on this component.
- `requiredMessage`: References the error message to display when no value has been entered into the enclosing component.
- `validatorMessage`: References the error message to display when the data on the enclosing component cannot be validated by the validator registered on this component.

All three attributes are enabled to take literal values and value expressions. If an attribute uses a value expression, this expression references the error message in a resource bundle. This resource bundle must be made available to the application in one of the following ways:

- By the application architect using the `resource-bundle` element in the configuration file
- By the page author using the `f:loadBundle` tag

Conversely, the `resource-bundle` element must be used to make available to the application those resource bundles containing custom error messages that are queued on the component as a result of a custom converter or validator being registered on the component.

The following tags show how to specify the `requiredMessage` attribute using a value expression to reference an error message:

```
<h:inputText id="ccno" size="19"
    required="true"
    requiredMessage="#{customMessages.ReqMessage}" >
    ...
</h:inputText>
<h:message styleClass="error-message" for="ccno"/>
```

The value expression that `requiredMessage` is using in this example references the error message with the `ReqMessage` key in the resource bundle, `customMessages`.

This message replaces the corresponding message queued on the component and will display wherever the `message` or `messages` tag is placed on the page.

Registering Custom Localized Static Text

You can register custom localized static text with the application by using the `resource-bundle` element in the application configuration resource file. Any custom error messages that are referenced by the `converterMessage`, `requiredMessage`, or `validatorMessage` attributes of an input component tag can be made available to the application by using the `resource-bundle` element of the application configuration file.

Here is the part of a file that registers some custom error messages:

```
<application>
    ...
    <resource-bundle>
        <base-name>
            guessNumber.ApplicationMessages
        </base-name>
        <var>customMessages</var>
    </resource-bundle>
    ...
</application>
```

The value of the `base-name` sub-element specifies the fully-qualified class name of the `ResourceBundle` class, which in this case is located in the `resources` package of the application.

The `var` sub-element of the `resource-bundle` element is an alias to the `ResourceBundle` class. This alias is used by tags in the page to identify the resource bundle.

The `locale-config` element shown in the previous section also applies to the messages and static text identified by the `resource-bundle` element. As with resource bundles identified by the `message-bundle` element, make sure that the resource bundle identified by the `resource-bundle` element actually contains the messages for the locales that you specify with these `locale-config` elements.

You can also pull localized text into an `alt` tag for a graphic image, as in the following example:

```
<h:graphicImage id="mapImage" url="/template/world.jpg"
    alt="#{bundle.ChooseLocale}"
    usemap="#worldMap" />
```

The `alt` attribute can accept value expressions. In this case, the `alt` attribute refers to localized text that will be included in the alternative text of the image rendered by this tag.

You can also use the `f:loadBundle` tag to load a resource bundle. This tag has attributes named `var` and `basename` that specify the same values as the `var` and `basename` sub-elements of the resource bundle specification in the configuration file.

Using Default Validators

In addition to the validators you declare on the components, you can also specify zero or more default validators in the application configuration resource file. The default validator applies to all `UIInput` instances in a view or component tree and is appended after the local defined validators. Here is an example of a default validator registered in the application configuration resource file:

```
<faces-config>
    <application>
        <default-validators>
            <validator-id>javax.faces.Bean</validator-id>
        </default-validators>
    <application/>
</faces-config>
```

Configuring Navigation Rules

Navigation between different pages of a JavaServer Faces application, such as choosing the next page to be displayed after a button or hyperlink component is clicked, is defined by a set of rules. Navigation rules can be implicit, or they can be explicitly defined in the application configuration resource file. For more information on implicit navigation rules, see "Implicit Navigation Rules" on page 241.

Each navigation rule specifies how to navigate from one page to another page or a set of other pages. The JavaServer Faces implementation chooses the proper navigation rule according to which page is currently displayed.

After the proper navigation rule is selected, the choice of which page to access next from the current page depends on two factors:

- The action method that was invoked when the component was clicked
- The logical outcome that is referenced by the component's tag or was returned from the action method

The outcome can be anything that the developer chooses, but Table 11–3 lists some outcomes commonly used in web applications.

TABLE 11–3 Common Outcome Strings

Outcome	What It Means
`success`	Everything worked. Go on to the next page.
`failure`	Something is wrong. Go on to an error page.
`login`	The user needs to log in first. Go on to the login page.

TABLE 11–3 Common Outcome Strings *(Continued)*

Outcome	What It Means
`no results`	The search did not find anything. Go to the search page again.

Usually, the action method performs some processing on the form data of the current page. For example, the method might check whether the user name and password entered in the form match the user name and password on file. If they match, the method returns the outcome `success`. Otherwise, it returns the outcome `failure`. As this example demonstrates, both the method used to process the action and the outcome returned are necessary to determine the proper page to access.

Here is a navigation rule that could be used with the example just described:

```
<navigation-rule>
    <from-view-id>/login.xhtml</from-view-id>
    <navigation-case>
        <from-action>#{LoginForm.login}</from-action>
        <from-outcome>success</from-outcome>
        <to-view-id>/storefront.xhtml</to-view-id>
    </navigation-case>
    <navigation-case>
        <from-action>#{LoginForm.logon}</from-action>
        <from-outcome>failure</from-outcome>
        <to-view-id>/logon.xhtml</to-view-id>
    </navigation-case>
</navigation-rule>
```

This navigation rule defines the possible ways to navigate from `login.xhtml`. Each `navigation-case` element defines one possible navigation path from `login.xhtml`. The first `navigation-case` says that if `LoginForm.login` returns an outcome of `success`, then `storefront.xhtml` will be accessed. The second `navigation-case` says that `login.xhtml` will be re-rendered if `LoginForm.login` returns `failure`.

The configuration of an application's page flow consists of a set of navigation rules. Each rule is defined by the `navigation-rule` element in the `faces-config.xml` file.

Each `navigation-rule` element corresponds to one component tree identifier defined by the optional `from-view-id` element. This means that each rule defines all the possible ways to navigate from one particular page in the application. If there is no `from-view-id` element, the navigation rules defined in the `navigation-rule` element apply to all the pages in the application. The `from-view-id` element also allows wildcard matching patterns. For example, this `from-view-id` element says that the navigation rule applies to all the pages in the `books` directory:

```
<from-view-id>/books/*</from-view-id>
```

A `navigation-rule` element can contain zero or more `navigation-case` elements. The `navigation-case` element defines a set of matching criteria. When these criteria are satisfied, the application will navigate to the page defined by the `to-view-id` element contained in the same `navigation-case` element.

The navigation criteria are defined by optional `from-outcome` and `from-action` elements. The `from-outcome` element defines a logical outcome, such as `success`. The `from-action` element uses a method expression to refer to an action method that returns a `String`, which is the logical outcome. The method performs some logic to determine the outcome and returns the outcome.

The `navigation-case` elements are checked against the outcome and the method expression in this order:

- Cases specifying both a `from-outcome` value and a `from-action` value. Both of these elements can be used if the action method returns different outcomes depending on the result of the processing it performs.
- Cases specifying only a `from-outcome` value. The `from-outcome` element must match either the outcome defined by the `action` attribute of the `UICommand` component or the outcome returned by the method referred to by the `UICommand` component.
- Cases specifying only a `from-action` value. This value must match the `action` expression specified by the component tag.

When any of these cases is matched, the component tree defined by the `to-view-id` element will be selected for rendering.

Using NetBeans IDE, you can configure a navigation rule by doing the following:

1. After opening your project in NetBeans IDE, expand the project node in the Projects pane.
2. Expand the Web Pages and WEB-INF nodes of the project node.
3. Double-click `faces-config.xml`.
4. After `faces-config.xml` opens in the editor pane, right-click in the editor pane.
5. From the Insert menu, choose Navigation Rule.
6. In the Add Navigation Rule dialog:
    a. Enter or browse for the page that represents the starting view for this navigation rule.
    b. Click Add.
7. Right-click again in the editor pane.
8. From the Insert menu, choose Navigation Case.
9. In the Add Navigation Case dialog box:
    a. From the From View menu, choose the page that represents the starting view for the navigation rule (from Step 6 a).
    b. (optional) In the From Action field, type the action method invoked when the component that triggered navigation is activated.

c. (optional) In the From Outcome field, enter the logical outcome string that the activated component references from its `action` attribute.

d. From the To View menu, choose or browse for the page that will be opened if this navigation case is selected by the navigation system.

e. Click Add.

"Referencing a Method That Performs Navigation" on page 181 explains how to use a component tag's `action` attribute to point to an action method. "Writing a Method to Handle Navigation" on page 194 explains how to write an action method.

Implicit Navigation Rules

JavaServer Faces technology supports implicit navigation rules for Facelets applications. Implicit navigation applies when `navigation-rules` are not configured in the application configuration resource files.

When you add a component such as a `commandButton` in a page, and assign another page as the value for its `action` property, the default navigation handler will try to match a suitable page within the application implicitly.

```
<h:commandButton value="submit" action="response">
```

In the above example, the default navigation handler will try to locate a page named `response.xhtml` within the application and navigate to it.

Basic Requirements of a JavaServer Faces Application

In addition to configuring your application, you must satisfy other requirements of JavaServer Faces applications, including properly packaging all the necessary files and providing a deployment descriptor. This section describes how to perform these administrative tasks.

JavaServer Faces 2.x applications must be compliant with at least version 2.5 of the Servlet specification, and at least version 2.1 of the JavaServer Pages specification. All applications compliant with these specifications can be packaged in a WAR file, which must conform to specific requirements to execute across different containers. At a minimum, a WAR file for a JavaServer Faces application must contain the following:

- A web application deployment descriptor, called `web.xml`, to configure resources required by a web application
- An application configuration resource file, which configures application resources
- A specific set of JAR files containing essential classes
- A set of application classes, JavaServer Faces pages, and other required resources, such as image files

For example, a Java Server Faces web application WAR file using Facelets typically has the following directory structure:

```
$PROJECT_DIR
[Web Pages]
+- /[xhtml documents]
+- /resources
+- /WEB-INF
   +- /classes
   +- /lib
   +- /web.xml
   +- /faces-config.xml
   +- /glassfish-web.xml
```

The `web.xml` file (or web deployment descriptor), the set of JAR files, and the set of application files must be contained in the `WEB-INF` directory of the WAR file.

Configuring an Application With a Web Deployment Descriptor

Web applications are commonly configured using elements that are contained in the web application deployment descriptor. The deployment descriptor for a JavaServer Faces application must specify certain configurations, which include the following:

- The servlet used to process JavaServer Faces requests
- The servlet mapping for the processing servlet
- The path to the configuration resource file, if it exists and is not located in a default location

The deployment descriptor can also specify other, optional configurations, including:

- Specifying where component state is saved
- Encrypting state saved on the client
- Compressing state saved on the client
- Restricting access to pages containing JavaServer Faces tags
- Turning on XML validation
- Information regarding Project Stage
- Verifying custom objects

This section gives more details on these configurations. Where appropriate, it also describes how you can make these configurations using NetBeans IDE.

Identifying the Servlet for Lifecycle Processing

A requirement of a JavaServer Faces application is that all requests to the application that reference previously saved JavaServer Faces components must go through `javax.faces.webapp.FacesServlet`. A `FacesServlet` instance manages the request processing lifecycle for web applications and initializes the resources required by JavaServer Faces technology.

Before a JavaServer Faces application can launch its first web page, the web container must invoke the `FacesServlet` instance in order for the application lifecycle process to start.

The following example shows the default configuration of the `FacesServlet`:

```
<servlet>
        <servlet-name>FacesServlet</servlet-name>
        <servlet-class>javax.faces.webapp.FacesServlet</servlet-class>
        </servlet>
```

To make sure that the `FacesServlet` instance is invoked, you must provide a mapping to it. The mapping to `FacesServlet` can be a prefix mapping, such as `/faces/*`, or an extension mapping, such as `*.faces`. The mapping is used to identify a page as having JavaServer Faces content. Because of this, the URL to the first page of the application must include the URL pattern mapping.

```
<servlet-mapping>
    <servlet-name>FacesServlet</servlet-name>
    <url-pattern>/faces/* </url-pattern>
</servlet-mapping>
```

In the case of prefix mapping, there are two ways to accomplish this:

- The page author can include a simple HTML page, such as an `index.xhtml` file in the application that provides the URL to the first page. This URL must include the path to `FacesServlet`, as shown by this tag, which uses the mapping defined in the `guessNumber` application:

  ```
  <a href="faces/greeting.xhtml">
  ```

- Users of the application can include the path to `FacesServlet` in the URL to the first page when they enter it in their browser, as shown in the example below:

  ```
  http://localhost:8080/guessNumber/faces/greeting.xhtml
  ```

The second method allows users to start the application from the first page of the application, rather than start it from another HTML page. However, the second method requires users to identify the first page of the application in the URL. When you use the first method, users need only enter the path to the application, as shown in the following example:

```
http://localhost:8080/guessNumber
```

In the case of extension mapping, if a request comes to the server for a page with a `.faces` extension, the container will send the request to the `FacesServlet` instance, which will expect a corresponding page of the same name to exist containing the content.

If you are using NetBeans IDE to create your application, a web deployment descriptor is automatically created for you with default configurations. If you created your application without an IDE, you can create a web deployment descriptor.

Specifying a Path to an Application Configuration Resource File

As explained in "Application Configuration Resource File" on page 223, an application can have multiple application configuration resource files. If these files are not located in the directories that the implementation searches by default or the files are not named `faces-config.xml`, you need to specify paths to these files.

To specify these paths using NetBeans IDE, do the following:

1. Expand the node of your project in the Projects pane.
2. Expand the Web Pages and WEB-INF nodes that are under the project node.
3. Double-click `web.xml`.
4. After the `web.xml` file appears in the editor pane, click General at the top of the editor pane.
5. Expand the Context Parameters node.
6. Click Add.
7. In the Add Context Parameter dialog:
   a. Enter `javax.faces.CONFIG_FILES` in the Param Name field.
   b. Enter the path to your configuration file in the Param Value field.
   c. Click OK.
8. Repeat steps 1 through 7 for each configuration file.

To specify paths to the files by editing the deployment descriptor directly, follow these steps:

1. Add a `context-param` element to the deployment descriptor.
2. Add a `param-value` element inside the `context-param` element and call it `javax.faces.CONFIG_FILES`.
3. Add a `param-value` element inside the `context-param` element and give it the path to your configuration file. For example, the path to the `guessNumber` application's application configuration resource file is `/WEB-INF/faces-config.xml`.
4. Repeat steps 2 and 3 for each application configuration resource file that your application contains.

Specifying Where State Is Saved

When implementing the state-holder methods, you specify in your deployment descriptor where you want the state to be saved, either client or server. You do this by setting a context parameter in your deployment descriptor.

To specify where state is saved using NetBeans IDE, do the following:

1. Expand the node of your project in the Projects pane.
2. Expand the Web Pages and WEB-INF nodes that are under the project node.
3. Double-click `web.xml`.

4. After the `web.xml` file appears in the editor pane, click General at the top of the editor pane.
5. Expand the Context Parameters node.
6. Click Add.
7. In the Add Context Parameter dialog:
   a. Enter `javax.faces.STATE_SAVING_METHOD` in the Param Name field.
   b. Enter `client` or `server` in the Param Value field.
   c. Click OK.

To specify where state is saved by editing the deployment descriptor directly, follow these steps:

1. Add a `context-param` element to the deployment descriptor.
2. Add a `param-name` element inside the `context-param` element and give it the name `javax.faces.STATE_SAVING_METHOD`.
3. Add a `param-value` element to the `context-param` element and give it the value `client` or `server`, depending on whether you want state saved in the client or the server.

If state is saved on the client, the state of the entire view is rendered to a hidden field on the page. The JavaServer Faces implementation saves the state on the client by default. Duke's Bookstore saves its state in the client.

Configuring Project Stage

Project Stage is a context parameter identifying the status of a JavaServer Faces application in the software lifecycle. The stage of an application can affect the behavior of the application. For example, error messages can be displayed during the Development stage but suppressed during the Production stage.

The possible Project Stage values are as follows:

- `Production`
- `Development`
- `UnitTest`
- `SystemTest`
- `Extension`

Project Stage is configured through a context parameter in the web deployment descriptor file. Here is an example:

```
<context-param>
    <param-name>javax.faces.PROJECT_STAGE </param-name>
    <param-value>Development </param-value>
</context-param>
```

If no Project Stage is defined, the default stage is considered as `Development`. You can also add custom stages according to your requirements.

The Project Stage value can also be configured through JNDI. When using JNDI based Project Stage, you need to configure the JNDI resource in the web deployment descriptor file.

```
<resource-ref>
<res-ref-name>jsf/ProjectStage</res-ref-name>
<res-type>java.lang.String</res-type>
</resource-ref>
```

Including the Classes, Pages, and Other Resources

When packaging web applications using the included build scripts, you'll notice that the scripts package resources in the following ways:

- All web pages are placed at the top level of the WAR file.
- The `faces-config.xml` file and the `web.xml` file are packaged in the `WEB-INF` directory.
- All packages are stored in the `WEB-INF/classes/` directory.
- All application JAR files are packaged in the `WEB-INF/lib/` directory.
- All resource files are either under the root of the web application `/resources` directory, or in the web application's classpath, `META-INF/resources/<resourceIdentifier>` directory. For more information on resources, see "Resources" on page 124.

When packaging your own applications, you can use NetBeans IDE or you can use the build scripts such as those built for Ant. You can modify the build scripts to fit your situation. However, you can continue to package your WAR files by using the directory structure described in this section, because this technique complies with the commonly accepted practice for packaging web applications.

◆ ◆ ◆ CHAPTER 12

Using Ajax with JavaServer Faces Technology

Early web applications were created mostly as static web pages. When a static web page is updated by a client, the entire page has to reload to reflect the update. In effect, every update needs a page reload to reflect the change. Repetitive reloads can result in excessive network access and can impact application performance. Technologies such as Ajax were created to overcome these deficiencies.

Ajax is an acronym for Asynchronous JavaScript and XML, a group of web technologies that enables creation of dynamic and highly responsive web applications. Using Ajax, web applications can retrieve content from the server without interfering with the display on the client.

JavaServer Faces 2.x provides built—in support for Ajax. This chapter describes using Ajax functionality in JavaServer Faces based web applications.

The following topics are addressed here:

Overview

Ajax refers to JavaScript and XML, technologies that are widely used for creating dynamic and asynchronous web content. While Ajax is not limited to JavaScript and XML technologies, more often than not they are used together by web applications. The focus of this tutorial is on JavaScript based Ajax functionality for JavaServer Faces web applications.

About Ajax

JavaScript is a dynamic scripting language for web applications. It is an object-oriented language that allows users to add enhanced functionality to user interfaces and allows web pages to interact with clients asynchronously. JavaScript mainly runs on the client side (such as a browser) and thereby reduces server access by clients.

When a JavaScript function sends an asynchronous request from the client to the server, the server sends back a response which is used to update the page's Document Object Model (DOM). This response is often in the format of a XML document. The term Ajax refers to this interaction between the client and server.

The server response need not be in XML only but can also be in other formats such as JSON. This tutorial does not focus on the response formats.

Ajax enables asynchronous and partial updating of web applications. Such functionality allows for highly responsive web pages that are rendered in near real time. Ajax based web applications can access server and process information as well as retrieve data without interfering with the display and rendering of the current web page on a client (such as a browser).

Some of the advantages of using Ajax are as follows:

- Form data validation in real time, eliminating the need to submit the form for verification
- Enhanced functionality for web pages, such as username and password prompts
- Partial update of the web content, avoiding complete page reloads

Using Ajax Functionality with JavaServer Faces Technology

Ajax functionality can be added to a JavaServer Faces application in one of the following ways:

- Adding the required JavaScript code to an application
- Using the built-in Ajax resource library in JavaServer Faces 2.x

Prior to JavaServer Faces 2.x, JavaServer Faces applications provided Ajax functionality by adding the necessary JavaScript to the web page. From JavaServer Faces 2.x, standard Ajax support is provided by a built-in JavaScript resource library.

With the support of this JavaScript resource library, JavaServer Faces standard UI components, such as buttons, labels, or text fields, can be enabled for Ajax functionality. You can also load this resource library and use its methods directly from within the backing bean code. The next sections of the tutorial describe the use of the built-in Ajax resource library in more detail.

In addition, because the JavaServer Faces technology component model can be extended, custom components can be created with Ajax functionality.

An Ajax version of the `guessnumber` application, `ajaxguessnumber`, is available in the example repository. See "The `ajaxguessnumber` Example Application" on page 258 for more information.

The Ajax specific `f:ajax` tag and its attributes are explained in the next sections.

Using Ajax with Facelets

As mentioned in the previous section, JavaServer Faces technology supports Ajax by using a built-in JavaScript resource library that is provided as part of the JavaServer Faces core libraries. This built-in Ajax resource can be used in JavaServer Faces web applications in one of the following ways:

- By using the `f:ajax` tag along with another standard component in a Facelets application. This method adds Ajax functionality to any UI component without additional coding and configuration.
- By using the JavaScript API method `jsf.ajax.request()`, directly within the Facelets application. This method provides direct access to Ajax methods, and allows customized control of component behavior.

Using the `f:ajax` Tag

The `f:ajax` tag is a JavaServer Faces core tag that provides Ajax functionality to any regular UI component when used in conjunction with that component. In the following example, Ajax behavior is added to an input component by including the `f:ajax` core tag:

```
<h:inputText value="#{bean.message}">
    <f:ajax event="click"/>
</h:inputText >
```

In this example, although Ajax is enabled, the other attributes of the `f:ajax` tag are not defined. Table 12–1 lists the attributes of the `f:ajax` tag.

TABLE 12–1 Attributes of the `f:ajax` Tag

Name	Type	Description
`disabled`	`javax.el.ValueExpression` that evaluates to a Boolean	A Boolean value that identifies the tag status. A value of `true` indicates that the Ajax behavior should not be rendered. A value of `false` indicates that the Ajax behavior should be rendered. The default value is `false`.
`event`	`javax.el.ValueExpression` that evaluates to a `String`	A `String` that identifies the type of event to which the Ajax action will apply. If specified, it must be one of the events supported by the component. If not specified, the default event (the event that triggers the Ajax request) is determined for the component. The default event is `action` for `ActionSource` components and `valueChange` for `EditableValueHolder` components.
`execute`	`javax.el.ValueExpression` that evaluates to an `Object`	A `Collection` that identifies a list of components to be executed on the server. If a literal is specified, it must be a space-delimited `String` of component identifiers and/or one of the keywords. If a `ValueExpression` is specified, it must refer to a property that returns a `Collection` of `String` objects. If not specified, the default value is `@this`.
`immediate`	`javax.el.ValueExpression` that evaluates to a Boolean	A Boolean value that indicates whether inputs are to be processed early in the lifecycle. If `true`, behavior events generated from this behavior are broadcast during the Apply Request Values phase. Otherwise, the events will be broadcast during the Invoke Applications phase.
`listener`	`javax.el.MethodExpression`	The name of the listener method that is called when an `AjaxBehaviorEvent` has been broadcast for the listener.
`onevent`	`javax.el.ValueExpression` that evaluates to a `String`	The name of the JavaScript function that handles UI events.
`onerror`	`javax.el.ValueExpression` that evaluates to a `String`	The name of the JavaScript function that handles errors.
`render`	`javax.el.ValueExpression` that evaluates to an `Object`	A `Collection` that identifies a list of components to be rendered on the client. If a literal is specified, it must be a space-delimited `String` of component identifiers and/or one of the keywords. If a `ValueExpression` is specified, it must refer to a property that returns a `Collection` of `String` objects. If not specified, the default value is `@none`.

The keywords listed in Table 12–2 can be used with the `execute` and `render` attributes of the `f:ajax` tag.

TABLE 12–2 Execute and Render Keywords

Keyword	Description
`@all`	All component identifiers
`@form`	The form that encloses the component
`@none`	No component identifiers
`@this`	The element that triggered the request

Note that when you use the `f:ajax` tag in a Facelets page, the JavaScript resource library is loaded implicitly. This resource library can also be loaded explicitly as described in "Loading JavaScript as a Resource" on page 256.

Sending an Ajax Request

To activate Ajax functionality, the web application must create an Ajax request and send it to the server. The server then processes the request.

The application uses the attributes of the `f:ajax` tag listed in Table 12–1 to create the Ajax request. The following sections explain the process of creating and sending an Ajax request using each of these attributes.

Note – Behind the scenes, the `jsf.ajax.request()` method of the JavaScript resource library collects the data provided by the Ajax tag and posts the request to the JavaServer Faces lifecycle.

Using the `event` Attribute

The `event` attribute defines the event that triggers the Ajax action. Some of the possible values for this attribute are `click`, `keyup`, `mouseover`, `focus`, and `blur`.

If not specified, a default event based on the parent component will be applied. The default event is `action` for `ActionSource` components such as a `commandButton`, and `valueChange` for `EditableValueHolder` components such as `inputText`. In the following example, an Ajax tag is associated with the button component, and the event that triggers the Ajax action is a mouse click:

```
<h:commandButton id="submit" value="Submit">
    <f:ajax event="click" />
</h:commandButton>
<h:outputText id="result" value="#{userNumberBean.response}" />
```

Note – You may have noticed that the listed events are very similar to JavaScript events. In fact, they are based on JavaScript events, but do not have the `on` prefix.

For a command button, the default event is `click`, so that you do not actually need to specify `event="click"` to obtain the desired behavior.

Using the `execute` Attribute

The `execute` attribute defines the component or components to be executed on the server. The component is identified by its `id` attribute. You can specify more than one executable component. If more than one component is to be executed, specify a space-delimited list of components.

The `execute` attribute can also be a keyword, such as `@all`, `@none`, `@this`, or `@form`. The default value is `@this`, which refers to the component within which the `f:ajax` tag is nested.

The following code specifies that the `h:inputText` component with the `id` value of `userNo` should be executed when the button is clicked:

```
<h:inputText id="userNo" value="#{userNumberBean.userNumber}">
    ...
</h:inputText>
<h:commandButton id="submit" value="Submit">
    <f:ajax event="click" execute="userNo" />
</h:commandButton>
```

Using the `immediate` Attribute

The `immediate` attribute indicates whether user inputs are to be processed early in the application lifecycle or later. If the attribute is set to `true`, events generated from this component are broadcast during the Apply Request Values phase. Otherwise, the events will be broadcast during the Invoke Applications phase.

If not defined, the default value of this attribute is `false`.

Using the `listener` Attribute

The `listener` attribute refers to a method expression that is executed on the server side in response to an Ajax action on the client. The listener's `processAjaxBehavior` method is called once during the Invoke Application phase of the lifecycle. In the following example, a `listener` attribute is defined by an `f:ajax` tag, which refers to a method from the bean.

```
<f:ajax listener="#{mybean.someaction}" render="somecomponent" />
```

The following code represents the `someaction` method in `mybean`.

```
public void someaction(AjaxBehaviorEvent event) {
    dosomething;
}
```

Monitoring Events on the Client

The ongoing Ajax requests can be monitored by using the `onevent` attribute of the `f:ajax` tag. The value of this attribute is the name of a JavaScript function. JavaServer Faces calls the `onevent` function at each stage of the processing of an Ajax request: begin, complete and success.

When calling the JavaScript function assigned to the `onevent` property, JavaServer Faces passes a data object to it. The data object contains the properties listed in Table 12–3.

TABLE 12–3 Properties of the `onEvent` Data Object

Property	Description
`responseXML`	The response to the Ajax call in XML format
`responseText`	The response to the Ajax call in text format
`responseCode`	The response to the Ajax call in numeric code
`source`	The source of the current Ajax event: the DOM element
`status`	The status of the current Ajax call: `begin`, `success`, or `complete`
`type`	The type of the Ajax call: `event`

By using the `status` property of the data object, you can identify the current status of the Ajax request and monitor its progress. In the following example, `monitormyajaxevent` is a JavaScript function that monitors the Ajax request sent by the event:

```
<f:ajax event="click" render="errormessage" onevent="monitormyajaxevent"/>
```

Handling Errors

JavaServer Faces handles Ajax errors through use of the `onerror` attribute of the `f:ajax` tag. The value of this attribute is the name of a JavaScript function.

When there is an error in processing a Ajax request, JavaServer Faces calls the defined `onerror` JavaScript function and passes a data object to it. The data object contains all the properties available for the `onevent` attribute, and in addition, the following properties:

- `description`
- `errorName`
- `errorMessage`

The `type` is `error`. The `status` property of the data object contains one of the valid error values listed in Table 12–4.

TABLE 12–4 Valid Error Values for the Data Object `status` Property

Values	Description
`emptyResponse`	No Ajax response from server.
`httpError`	One of the valid HTTP errors: `request.status==null` or `request.status==undefined` or `request.status < 200` or `request.status >= 300`
`malformedXML`	The Ajax response is not well formed.
`serverError`	The Ajax response contains an `error` element.

In the following example, any errors that occurred in processing the Ajax request are handled by the `handlemyajaxerror` JavaScript function:

```
<f:ajax event="click" render="test" onerror="handlemyajaxerror"/>
```

Receiving an Ajax Response

After the application sends an Ajax request, it is processed on the server side, and a response is sent back to the client. As described earlier, Ajax allows for partial updating of web pages. To enable such partial updating, JavaServer Faces technology allows for partial processing of the view. The handling of the response is defined by the `render` attribute of the `f:ajax` tag.

Similar to the `execute` attribute, the `render` attribute defines which sections of the page will be updated. The value of a `render` attribute can be one or more component `id` values, one of the keywords `@this`, `@all`, `@none`, and `@form`, or an EL expression. In the following example, the `render` attribute simply identifies an output component to be displayed when the Ajax action has successfully completed.

```
<h:commandButton id="submit" value="Submit">
    <f:ajax execute="userNo" render="result" />
</h:commandButton>
<h:outputText id="result" value="#{userNumberBean.response}" />
```

However, more often than not, the `render` attribute is likely to be associated with an `event` attribute. In the following example, an output component is displayed when the button component is clicked.

```
<h:commandButton id="submit" value="Submit">
    <f:ajax event="click" execute="userNo" render="result"/>
</h:commandButton>
<h:outputText id="result" value="#{userNumberBean.response}"/>
```

Note – Behind the scenes, once again the `jsf.ajax.request()` method handles the response. It registers a response handling callback when the original request is created. When the response is sent back to the client, the callback is invoked. This callback automatically updates the client-side DOM to reflect the rendered response.

Ajax Request Lifecycle

An Ajax request varies from other typical JavaServer Faces requests, and its processing is also handled differently by the JavaServer Faces lifecycle.

As described in "Partial Processing and Partial Rendering" on page 210, when an Ajax request is received, the state associated with that request is captured by the `PartialViewContext`. This object provides access to information such as which components are targeted for processing/rendering. The `processPartial` method of `PartialViewContext` uses this information to perform partial component tree processing/rendering.

The `execute` attribute of the `f:ajax` tag identifies which segments of the server side component tree should be processed. Because components can be uniquely identified in the JavaServer Faces component tree, it is easy to identify and process a single component, a few components or a whole tree. This is made possible by the `visitTree` method of the `UIComponent` class. The identified components then run through the JavaServer Faces request lifecycle phases.

Similar to the `execute` attribute, the `render` attribute identifies which segments of the JavaServer Faces component tree need to be rendered during the render response phase.

During the render response phase, the render attribute is examined. The identified components are found and asked to render themselves and their children. The components are then packaged up and sent back to the client as a response.

Grouping of Components

The previous sections describe how to associate a single UI component with Ajax functionality. You can also associate Ajax with more than one component at a time by grouping them together on a page. The following example shows how a number of components can be grouped by using the `f:ajax` tag.

```
<f:ajax>
    <h:form>
        <h:inputText id="input1"/>
        <h:commandButton id="Submit"/>
    </h:form>
</f:ajax>
```

In the example, neither component is associated with any Ajax `event` or `render` attributes yet. Therefore, no action will take place in case of user input. You can associate the above components with an `event` and a `render` attribute as follows:

```
<f:ajax event="click" render="@all">
    <h:form>
        <h:inputText id="input1" value="#{user.name}"/>
        <h:commandButton id="Submit"/>
    </h:form>
</f:ajax>
```

In the updated example, when the user clicks either component, the updated results will be displayed for all components. You can further fine tune the Ajax action by adding specific events to each of the components, in which case Ajax functionality becomes cumulative. Consider the following example:

```
<f:ajax event="click" render="@all">
    ...
    <h:commandButton id="Submit">
        <f:ajax event="mouseover"/>
    </h:commandButton>
    ...
</f:ajax>
```

Now the button component will fire an Ajax action in case of a `mouseover` event as well as a mouse click event.

Loading JavaScript as a Resource

The JavaScript resource file bundled with JavaServer Faces 2.x is named `jsf.js` and is available in the `javax.faces` library. This resource library supports Ajax functionality in JavaServer Faces applications.

In order to use this resource directly with a component or a bean class, you need to explicitly load the resource library. The resource can be loaded in one of the following ways:

- By using the resource API directly in a Facelets page
- By using the `javax.faces.application.ResourceDependency` annotation and the resource API in a bean class

Using JavaScript API in a Facelets Application

To use the bundled JavaScript resource API directly in a web application, such as a Facelets page, you need to first identify the default JavaScript resource for the page with the help of the `h:outputScript` tag. For example, consider the following section of a Facelets page:

```
<h:form>
    <h:outputScript name="jsf.js" library="javax.faces" target="head"/>
</h:form>
```

Specifying the target as `head` causes the script resource to be rendered within the `head` element on the HTML page.

In the next step, identify the component to which you would like to attach the Ajax functionality. Add the Ajax functionality to the component by using the JavaScript API. For example, consider the following:

```
<h:form>
    <h:outputScript name="jsf.js" library="javax.faces" target="head">
    <h:inputText id="inputname" value="#{userBean.name}"/>
    <h:outputText id="outputname" value="#{userBean.name}"/>
    <h:commandButton id="submit" value="Submit"
                        onclick="jsf.ajax.request(this, event,
                              {execute:'inputname',render:'outputname'});
                        return false;" />
</h:form>
```

The `jsf.ajax.request` method takes up to three parameters that specify source, event, and options. The source parameter identifies the DOM element that triggered the Ajax request, typically `this`. The optional event parameter identifies the DOM event that triggered this request. The optional options parameter contains a set of name/value pairs from Table 12–5.

TABLE 12–5 Possible Values for the Options Parameter

Name	Value
`execute`	A space-delimited list of client identifiers or one of the keywords listed in Table 12–2. The identifiers reference the components that will be processed during the execute phase of the lifecycle.

TABLE 12–5 Possible Values for the Options Parameter *(Continued)*

Name	Value
render	A space-delimited list of client identifiers or one of the keywords listed in Table 12–2. The identifiers reference the components that will be processed during the render phase of the lifecycle.
onevent	A String that is the name of the JavaScript function to call when an event occurs.
onerror	A String that is the name of the JavaScript function to call when an error occurs.
params	An object that may include additional parameters to include in the request.

If no identifier is specified, the default assumed keyword for the execute attribute is @this, and for the render attribute it is @none.

You can also place the JavaScript method in a file and include it as a resource.

Using the @ResourceDependency Annotation in a Bean Class

Use the javax.faces.application.ResourceDependency annotation to cause the bean class to load the default jsf.js library.

To load the Ajax resource from the server side, use the jsf.ajax.request method within the bean class. This method is usually used when creating a custom component or a custom renderer for a component.

The following example shows how the resource is loaded in a bean class:

```
@ResourceDependency(name="jsf.js" library="javax.faces" target="head")
```

The ajaxguessnumber Example Application

To demonstrate the advantages of using Ajax, revisit the guessnumber example from Chapter 5, "Introduction to Facelets." If you modify this example to use Ajax, the response need not be displayed in the response.xhtml page. Instead, an asynchronous call is made to the bean on the server side, and the response is displayed in the originating page by executing just the input component rather than by form submission.

The ajaxguessnumber Source Files

The changes to the guessnumber application occur in two source files, as well as the addition of a JavaScript file.

The ajaxgreeting.xhtml Facelets Page

The Facelets page for ajaxguessnumber, ajaxgreeting.xhtml, is almost the same as the greeting.xhtml page for the guessnumber application:

```
<h:head>
    <title>Ajax Guess Number Facelets Application</title>
</h:head>
<h:body>
    <h:form id="AjaxGuess">
        <h:outputScript name="ui.js" target="head"/>
        <h:graphicImage value="#{resource['images:wave.med.gif']}"/>
        <h2>
            Hi, my name is Duke. I am thinking of a number from
            #{userNumberBean.minimum} to #{userNumberBean.maximum}.
            Can you guess it?
            <p></p>
            <h:inputText id="userNo" value="#{userNumberBean.userNumber}">
                <f:validateLongRange
                    minimum="#{userNumberBean.minimum}"
                    maximum="#{userNumberBean.maximum}"/>
            </h:inputText>

            <h:commandButton id="submit" value="Submit" >
                <!--<f:ajax execute="userNo" render="result errors1" />-->
                <f:ajax execute="userNo" render="result errors1"
                        onevent="msg"/>
            </h:commandButton>
            <p></p>
            <h:outputText id="result" value="#{userNumberBean.response}"/>
            <p></p>

            <h:message id="errors1" showSummary="true" showDetail="false"
                       style="color: red;
                       font-family: 'New Century Schoolbook', serif;
                       font-style: oblique;
                       text-decoration: overline"
                       for="userNo"/>
        </h2>
    </h:form>
</h:body>
```

The most important change is in the h:commandButton tag. The action attribute is removed from the tag, and f:ajax tag is added.

The f:ajax tag specifies that when the button is clicked, the h:inputText component with the id value userNo is executed. The components with the id values result and errors1 are then rendered. If that was all you did (as in the commented-out version of the tag), you would see the output from both the result and errors1 components, although only one output is valid; if a validation error occurs, the managed bean is not executed, so the result output is stale.

To solve this problem, the tag also calls the JavaScript function named msg, in the file ui.js, as described in the next section. The h:outputScript tag at the top of the form calls in this script.

The ui.js JavaScript File

The ui.js file specified in the h:outputScript tag of the ajaxgreeting.xhtml file is located in the web/resources directory of the application. The file contains just one function, msg:

```
var msg = function msg(data) {
    var resultArea = document.getElementById("AjaxGuess:result");
    var errorArea = document.getElementById("AjaxGuess:errors1");
    if (errorArea.innerHTML !== null && errorArea.innerHTML !== "") {
        resultArea.innerHTML="";
    }
};
```

The msg function obtains a handle to both the result and errors1 elements. If the errors1 element has any content, the function erases the content of the result element, so that the stale output does not appear in the page.

The UserNumberBean Managed Bean

A small change is also made in the UserNumberBean code, so that the output component does not display any message for the default (null) value of the property response. Here is the modified bean code:

```
public String getResponse() {
    if ((userNumber != null) && (userNumber.compareTo(randomInt) == 0)) {
        return "Yay! You got it!";
    }
    if (userNumber == null) {
        return null;
    } else {
        return "Sorry, " + userNumber + " is incorrect.";
    }
}
```

Building, Packaging, Deploying, and Running the ajaxguessnumber Example

You can build, package, deploy, and run the ajaxguessnumber application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the ajaxguessnumber Example Using NetBeans IDE

This procedure builds the application into the following directory:

tut-install/examples/web/ajaxguessnumber/build/web

The contents of this directory are deployed to the GlassFish Server.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install/examples/web/
3. **Select the ajaxguessnumber folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the ajaxguessnumber project and select Deploy.**

▼ To Build, Package, and Deploy the ajaxguessnumber Example Using Ant

1. **In a terminal window, go to:**

   tut-install/examples/web/ajaxguessnumber/
2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `ajaxguessnumber.war`, located in the `dist` directory.
3. **Type the following command:**

   ```
   ant deploy
   ```

   Typing this command deploys `ajaxguessnumber.war` to the GlassFish Server.

▼ To Run the ajaxguessnumber Example

1. **In a web browser, type the following URL:**

   ```
   http://localhost:8080/ajaxguessnumber
   ```
2. **Type a value in the input field and click Submit.**

   If the value is in the range 0 to 10, a message states whether the guess is correct or incorrect. If the value is outside that range, or if the value is not a number, an error message appears in red.

   To see what would happen if the JavaScript function were not included, remove the comment marks from the first `f:ajax` tag in `ajaxgreeting.xhtml` and place them around the second tag, as follows:

   ```
   <f:ajax execute="userNo" render="result errors1" />
                  <!--<f:ajax execute="userNo" render="result errors1"
                          onevent="msg"/>-->
   ```

If you then redeploy the application, you can see that stale output from valid guesses continues to appear if you type erroneous input.

Further Information about Ajax in JavaServer Faces

For more information on JavaServer Faces Technology, see

- JavaServer Faces 2.0 technology download web site:

  `http://www.oracle.com/technetwork/java/javaee/download-139288.html`

- JavaServer Faces JavaScript Library APIs are available in the Mojarra 2.x package in the following location:

  `<mojarra-2.0.2-FCS>/docs/jsdocs/symbols/jsf.ajax.html`

◆ ◆ ◆ CHAPTER 13

Advanced Composite Components

This chapter describes the advanced features of composite components in JavaServer Faces technology.

A composite component is a special type of JavaServer Faces template that acts as a component. If you are new to composite components, see "Composite Components" on page 121 before you proceed with this chapter.

The following topics are addressed here:

Attributes of a Composite Component

You define an attribute of a composite component by using the `composite:attribute` tag. Table 13–1 lists the commonly used attributes of this tag.

TABLE 13–1 Commonly Used Attributes of the `composite:attribute` Tag

Attribute	Description
`name`	Specifies the name of the composite component attribute to be used in the using page. Alternatively, the `name` attribute can specify standard event handlers such as action, `actionListener`, and managed bean.
`default`	Specifies the default value of the composite component attribute.
`required`	Specifies if it is mandatory to provide a value for the attribute.

TABLE 13–1 Commonly Used Attributes of the `composite:attribute` Tag *(Continued)*

Attribute	Description
`method-signature`	Specifies a subclass of `java.lang.Object` as the type of the composite component's attribute. The `method-signature` element declares that the composite component attribute is a method expression. The `type` attribute and the `method-signature` attribute are mutually exclusive. If you specify both, `method-signature` is ignored. The default type of an attribute is `java.lang.Object`. **Note –** Method expressions are similar to value expressions, but rather than supporting the dynamic retrieval and setting of properties, method expressions support the invocation of a method of an arbitrary object, passing a specified set of parameters, and returning the result from the called method (if any).
`type`	Specifies a fully qualified class name as the type of the attribute. The `type` attribute and the `method-signature` attribute are mutually exclusive. If you specify both, `method-signature` is ignored. The default type of an attribute is `java.lang.Object`.

The following code snippet defines a composite component attribute and assigns it a default value:

```
<composite:attribute name="username" default="admin"/>
```

The following code snippet uses the `method-signature` element:

```
<composite:attribute name="myaction" method-signature="java.lang.String action()"/>
```

The following code snippet uses the `type` element:

```
<composite:attribute name="dateofjoining" type="java.util.Date"/>
```

Invoking a Managed Bean

To enable a composite component to handle server-side data, you can invoke a managed bean in one of the following ways:

- Pass the reference of the managed bean to the composite component
- Directly use the properties of the managed bean

The example application described in "The `compositecomponentlogin` Example Application" on page 265 shows how to use a managed bean with a composite component by passing the reference of the managed bean to the component.

Validating Composite Component Values

JavaServer Faces provides the following tags for validating values of input components. These tags can be used with the `composite:ValueHolder` or with the `composite:EditableValueHolder` tags.

Table 13–2 lists commonly used validator tags.

TABLE 13–2 Validator Tags

Tag Name	Description
`f:validateBean`	Delegates the validation of the local value to the Bean Validation API.
`f:validateRegex`	Uses the `pattern` attribute to validate the wrapping component. The entire pattern is matched against the `String` value of the component. If it matches, it is valid.
`f:validateRequired`	Enforces the presence of a value. Has the same effect as setting the `required` element of a composite component's attribute to true.

The `compositecomponentlogin` Example Application

The `compositecomponentlogin` application creates a composite component that accepts a username and password. The component interacts with a managed bean. The component stores the username and password in the managed bean, retrieves the values from the bean, and displays these values on the Login page.

The `compositecomponentlogin` application has a composite component file, a using page, and a managed bean.

The Composite Component File

The composite component file is an XHTML file. It has a `composite:interface` section that declares the labels for the username, password, and login button. It also declares a managed bean, which defines properties for the username and password.

```
<composite:interface>

<composite:attribute name="namePrompt" default="username"/>
<composite:attribute name="passwordPrompt" default="password"/>
<composite:attribute name="loginButtonText" default="login"/>
<composite:attribute name="loginAction" method-signature="java.lang.String action()"/>

</composite:interface>
```

The composite component file accepts input values for the username and password properties of the managed bean.

```
<composite:implementation>

    <h:form id="form">

        <h:panelGrid columns="2">
            #{cc.attrs.namePrompt}
            <h:inputText id="name" value="#{cc.attrs.myloginBean.name}"
                         required="true"/>
            #{cc.attrs.passwordPrompt}
            <h:inputSecret id="password" value="#{cc.attrs.myloginBean.password}"
                           required="true"/>
        </h:panelGrid/>

        <p>
        <h:commandButton id="loginButton" value="#{cc.attrs.loginButtonText}"
                         action="#{cc.attrs.loginAction}"/>
        </p>

    </h:form>
</composite:implementation>
```

The Using Page

The using page in this example application is an XHTML file that invokes the login composite component file along with the managed bean.

```
<div id="compositecomponent">
<ez:LoginPanel myloginBean="#(myloginBean)" loginAction="#(myloginBean.login)">
</ez:LoginPanel>
</div>
```

The Managed Bean

The managed bean defines a method called `login`, which retrieves the values of the username and password.

```
@ManagedBean
@RequestScoped
public class myloginBean {

    private String name;
    private String password;

    public myloginBean() {
        this.name = "";
        this.password = "";
    }
```

```
    public myloginBean(String name, String password) {
        this.name = name;
        this.password = password;
    }

    public String getPassword() { return password; }
    public void setPassword(String newValue) { password = newValue; }

    public String getName() { return name; }
    public void setName(String newValue) { name = newValue; }

    public String login() {
        String msg = "Your username and password are " +
              " username: " + getName() +
              " password: " + getPassword();
        return msg;
    }
}
```

▼ To Build, Package, Deploy, and Run the `compositecomponentlogin` Example Application Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to** *tut-install*`/examples/web/`**.**
3. **Select the `compositecomponentlogin` folder.**
4. **Select the Open as Main Project checkbox.**
5. **Click Open Project.**
6. **In the Projects tab, right-click `compositecomponentlogin` and select Run.**

   The Login page opens in a browser window.

◆ ◆ ◆ CHAPTER 14

Creating Custom UI Components

JavaServer Faces technology offers a basic set of standard, reusable UI components that enable quick and easy construction of user interfaces s for web applications. But often an application requires a component that has additional functionality or requires a completely new component. JavaServer Faces technology allows extension of standard components to enhance their functionality or to create custom components.

Using the Composite Components feature of Facelets, you can combine and reuse the standard components and provide extended functionality. In some cases, however, it becomes necessary to create new components from scratch. For example, you may want to change the appearance of a component, provide a different renderer, or even alter listener behavior. For such cases, JavaServer Faces provides the ability to create custom components by extending the `UIComponent` class, the class that is the base class for all standard UI components.

This chapter explains how you can create simple custom components, custom renderers, custom converters, custom listeners, and associated custom tags, and take care of all the other details associated with using the components and renderers in an application.

The following topics are addressed here:

Determining Whether You Need a Custom Component or Renderer

The JavaServer Faces implementation supports a rich set of components and associated renderers, which are suitable enough for most simple applications. This section helps you to decide whether you can use standard components and renderers in your application or need a custom component or custom renderer.

When to Use a Custom Component

A component class defines the state and behavior of a UI component. This behavior includes converting the value of a component to the appropriate markup, queuing events on components, performing validation, and other functionality.

You need to create a custom component in the following situations:

- You need to add new behavior to a standard component, such as generating an additional type of event.
- You need a component that is supported by an HTML client but is not currently implemented by JavaServer Faces technology. The current release does not contain standard components for complex HTML components, such as frames; however, because of the extensibility of the component architecture, you can use JavaServer Faces technology to create components like these.
- You need to render to a non-HTML client that requires extra components not supported by HTML. Eventually, the standard HTML render kit will provide support for all standard HTML components. However, if you are rendering to a different client, such as a phone, you might need to create custom components to represent the controls uniquely supported by the client. For example, some component architectures for wireless clients include support for tickers and progress bars, which are not available on an HTML client. In this case, you might also need a custom renderer along with the component; or you might need only a custom renderer.

You do not need to create a custom component in these cases:

- You need to aggregate components to create a new component that has its own unique behavior. For this case, you can use a composite component to combine existing standard components. For more information on composite components, see "Composite Components" on page 121 and Chapter 13, "Advanced Composite Components."
- You simply need to manipulate data on the component or add application-specific functionality to it. In this situation, you should create a backing bean for this purpose and bind it to the standard component rather than create a custom component. See "Backing Beans" on page 183 for more information on backing beans.

- You need to convert a component's data to a type not supported by its renderer. See "Using the Standard Converters" on page 171 for more information about converting a component's data.
- You need to perform validation on the component data. Standard validators and custom validators can be added to a component by using the validator tags from the page. See "Using the Standard Validators" on page 178 and "Creating a Custom Validator" on page 288 for more information about validating a component's data.
- You need to register event listeners on components. You can either register event listeners on components using the `valueChangeListener` and `actionListener` tags, or you can point at an event-processing method on a backing bean using the component's `actionListener` or `valueChangeListener` attributes. See "Implementing an Event Listener" on page 286 and "Writing Backing Bean Methods" on page 194 for more information.

When to Use a Custom Renderer

If you are creating a custom component, you need to ensure, among other things, that your component class performs these operations:

- **Decoding**: Converting the incoming request parameters to the local value of the component
- **Encoding**: Converting the current local value of the component into the corresponding markup that represents it in the response

The JavaServer Faces specification supports two programming models for handling encoding and decoding:

- **Direct implementation**: The component class itself implements the decoding and encoding.
- **Delegated implementation**: The component class delegates the implementation of encoding and decoding to a separate renderer.

By delegating the operations to the renderer, you have the option of associating your custom component with different renderers so that you can represent the component in different ways on the page. If you don't plan to render a particular component in different ways, it's simpler to let the component class handle the rendering.

If you aren't sure whether you will need the flexibility offered by separate renderers but you want to use the simpler direct-implementation approach, you can actually use both models. Your component class can include some default rendering code, but it can delegate rendering to a renderer if there is one.

Component, Renderer, and Tag Combinations

When you create a custom component, you can create a custom renderer to go with it. To associate the component with the renderer and to reference the component from the page, you will also need a custom tag.

In rare situations, however, you might use a custom renderer with a standard component rather than a custom component. Or you might use a custom tag without a renderer or a component. This section gives examples of these situations and summarizes what's required for a custom component, renderer, and tag.

You would use a custom renderer without a custom component if you wanted to add some client-side validation on a standard component. You would implement the validation code with a client-side scripting language, such as JavaScript, and then render the JavaScript with the custom renderer. In this situation, you need a custom tag to go with the renderer so that its tag handler can register the renderer on the standard component.

Custom components as well as custom renderers need custom tags associated with them. However, you can have a custom tag without a custom renderer or custom component. For example, suppose that you need to create a custom validator that requires extra attributes on the validator tag. In this case, the custom tag corresponds to a custom validator and not to a custom component or custom renderer. In any case, you still need to associate the custom tag with a server-side object.

Table 14–1 summarizes what you must or can associate with a custom component, custom renderer, or custom tag.

TABLE 14–1 Requirements for Custom Components, Custom Renderers, and Custom Tags

Custom Item	Must Have	Can Have
Custom component	Custom tag	Custom renderer or standard renderer
Custom renderer	Custom tag	Custom component or standard component
Custom JavaServer Faces tag	Some server-side object, like a component, a custom renderer, or custom validator	Custom component or standard component associated with a custom renderer

Steps for Creating a Custom Component

You can apply the following steps while developing your own custom component.

1. Create a custom component class that does the following:
   a. Overrides the `getFamily` method to return the component family, which is used to look up renderers that can render the component.
   b. Includes the rendering code or delegates it to a renderer (explained in step 2).
   c. Enables component attributes to accept expressions.
   d. Queues an event on the component if the component generates events.
   e. Saves and restores the component state.
2. Delegate rendering to a renderer if your component does not handle the rendering. To do this:
   a. Create a custom renderer class by extending `javax.faces.render.Renderer`.
   b. Register the renderer to a render kit.
   c. Identify the renderer type in the component tag handler.
3. Register the component.
4. Create an event handler if your component generates events.
5. Write a tag handler class that extends `javax.faces.webapp.UIComponentELTag`. In this class, you need a `getRendererType` method, which returns the type of your custom renderer if you are using one (explained in step 2); a `getComponentType` method, which returns the type of the custom component; and a `setProperties` method, with which you set all the new attributes of your component.
6. Create a tag library descriptor (TLD) that defines the custom tag.

The section "Using a Custom Component" on page 297 discusses how to use the custom component in a JavaServer Faces page.

Creating Custom Component Classes

As explained in "When to Use a Custom Component" on page 270, a component class defines the state and behavior of a UI component. The state information includes the component's type, identifier, and local value. The behavior defined by the component class includes the following:

- Decoding (converting the request parameter to the component's local value)
- Encoding (converting the local value into the corresponding markup)
- Saving the state of the component
- Updating the bean value with the local value
- Processing validation on the local value
- Queueing events

The `UIComponentBase` class defines the default behavior of a component class. All the classes representing the standard components extend from `UIComponentBase`. These classes add their own behavior definitions, as your custom component class will do.

Your custom component class must either extend `UIComponentBase` directly or extend a class representing one of the standard components. These classes are located in the `javax.faces.component` package and their names begin with `UI`.

If your custom component serves the same purpose as a standard component, you should extend that standard component rather than directly extend `UIComponentBase`. For example, suppose you want to create an editable menu component. It makes sense to have this component extend `UISelectOne` rather than `UIComponentBase` because you can reuse the behavior already defined in `UISelectOne`. The only new functionality you need to define is to make the menu editable.

Whether you decide to have your component extend `UIComponentBase` or a standard component, you might also want your component to implement one or more of these behavioral interfaces:

- `ActionSource`: Indicates that the component can fire an `ActionEvent`.
- `ActionSource2`: Extends `ActionSource` and allows component properties referencing methods that handle action events to use method expressions as defined by the unified EL. This class was introduced in JavaServer Faces Technology 1.2.
- `EditableValueHolder`: Extends `ValueHolder` and specifies additional features for editable components, such as validation and emitting value-change events.
- `NamingContainer`: Mandates that each component rooted at this component have a unique ID.
- `StateHolder`: Denotes that a component has state that must be saved between requests.
- `ValueHolder`: Indicates that the component maintains a local value as well as the option of accessing data in the model tier.

If your component extends `UIComponentBase`, it automatically implements only `StateHolder`. Because all components directly or indirectly extend `UIComponentBase`, they all implement `StateHolder`.

If your component extends one of the other standard components, it might also implement other behavioral interfaces in addition to `StateHolder`. If your component extends `UICommand`, it automatically implements `ActionSource2`. If your component extends `UIOutput` or one of the component classes that extend `UIOutput`, it automatically implements `ValueHolder`. If your component extends `UIInput`, it automatically implements `EditableValueHolder` and `ValueHolder`. See the JavaServer Faces API documentation to find out what the other component classes implement.

You can also make your component explicitly implement a behavioral interface that it doesn't already by virtue of extending a particular standard component. For example, if you have a

component that extends `UIInput` and you want it to fire action events, you must make it explicitly implement `ActionSource2` because a `UIInput` component doesn't automatically implement this interface.

Specifying the Component Family

If your custom component class delegates rendering, it needs to override the `getFamily` method of `UIComponent` to return the identifier of a *component family*, which is used to refer to a component or set of components that can be rendered by a renderer or set of renderers. The component family is used along with the renderer type to look up renderers that can render the component:

```
public String getFamily() {
    return ("Map");
}
```

The component family identifier, `Map`, must match that defined by the `component-family` elements included in the component and renderer configurations in the application configuration resource file.

Performing Encoding

During the Render Response phase, the JavaServer Faces implementation processes the encoding methods of all components and their associated renderers in the view. The encoding methods convert the current local value of the component into the corresponding markup that represents it in the response.

The `UIComponentBase` class defines a set of methods for rendering markup: `encodeBegin`, `encodeChildren`, and `encodeEnd`. If the component has child components, you might need to use more than one of these methods to render the component; otherwise, all rendering should be done in `encodeEnd`. Alternatively, you can use the `encodeALL` method, which encompasses all the methods.

Here is an example of the `encodeBegin` and `encodeEnd` methods:

```
public void encodeBegin(FacesContext context,
     UIComponent component) throws IOException {
    if ((context == null)|| (component == null)){
        throw new NullPointerException();
    }
    MapComponent map = (MapComponent) component;
    ResponseWriter writer = context.getResponseWriter();
    writer.startElement("map", map);
    writer.writeAttribute("name", map.getId(),"id");
}
public void encodeEnd(FacesContext context) throws IOException {
```

```
    if ((context == null) || (component == null)){
        throw new NullPointerException();
    }
    MapComponent map = (MapComponent) component;
    ResponseWriter writer = context.getResponseWriter();
    writer.startElement("input", map);
    writer.writeAttribute("type", "hidden", null);
    writer.writeAttribute("name",
         getName(context,map), "clientId");(
    writer.endElement("input");
    writer.endElement("map");
}
```

The encoding methods accept a `UIComponent` argument and a `FacesContext` argument. The `FacesContext` instance contains all the information associated with the current request. The `UIComponent` argument is the component that needs to be rendered.

If you want your component to perform its own rendering but delegate to a renderer if there is one, include the following lines in the encoding method to check whether there is a renderer associated with this component.

```
if (getRendererType() != null) {
    super.encodeEnd(context);
    return;
}
```

If there is a renderer available, this method invokes the superclass's `encodeEnd` method, which does the work of finding the renderer.

In some custom component classes that extend standard components, you might need to implement other methods in addition to `encodeEnd`. For example, if you need to retrieve the component's value from the request parameters, you must also implement the `decode` method.

Performing Decoding

During the Apply Request Values phase, the JavaServer Faces implementation processes the `decode` methods of all components in the tree. The `decode` method extracts a component's local value from incoming request parameters and uses a `Converter` class to convert the value to a type that is acceptable to the component class.

A custom component class or its renderer must implement the `decode` method only if it must retrieve the local value or if it needs to queue events. The component queues the event by calling `queueEvent`.

Here is an example of the `decode` method:

```
public void decode(FacesContext context, UIComponent component) {
    if ((context == null) || (component == null)) {
        throw new NullPointerException();
```

```
    }
    MapComponent map = (MapComponent) component;
    String key = getName(context, map);
    String value = (String)context.getExternalContext().
        getRequestParameterMap().get(key);
    if (value != null)
         map.setCurrent(value);
    }
}
```

Enabling Component Properties to Accept Expressions

Nearly all the attributes of the standard JavaServer Faces tags can accept expressions, whether they are value expressions or method expressions. It is recommended that you also enable your component attributes to accept expressions because this is what page authors expect, and it gives page authors much more flexibility when authoring their pages.

"Creating the Component Tag Handler" on page 280 describes how a tag handler sets the component's values when processing the tag. It does this by providing the following:

- A method for each attribute that takes either a `ValueExpression` or `MethodExpression` object depending on what kind of expression the attribute accepts.
- A `setProperties` method that stores the `ValueExpression` or `MethodExpression` object for each component property so that the component class can retrieve the expression object later.

To retrieve the expression objects that `setProperties` stored, the component class must implement a method for each property that accesses the appropriate expression object, extracts the value from it and returns the value.

If your component extends `UICommand`, the `UICommand` class already does the work of getting the `ValueExpression` and `MethodExpression` instances associated with each of the attributes that it supports.

However, if you have a custom component class that extends `UIComponentBase`, you will need to implement the methods that get the `ValueExpression` and `MethodExpression` instances associated with those attributes that are enabled to accept expressions. For example, you could include a method that gets the `ValueExpression` instance for the `immediate` attribute:

```
public boolean isImmediate() {
    if (this.immediateSet) {
        return (this.immediate);
    }
    ValueExpression ve = getValueExpression("immediate");
    if (ve != null) {
        Boolean value = (Boolean) ve.getValue(
            getFacesContext().getELContext());
```

```
        return (value.booleanValue());
    } else {
        return (this.immediate);
    }
}
```

The properties corresponding to the component attributes that accept method expressions must accept and return a `MethodExpression` object. For example, if the component extended `UIComponentBase` instead of `UICommand`, it would need to provide an `action` property that returns and accepts a `MethodExpression` object:

```
public MethodExpression getAction() {
    return (this.action);
}
public void setAction(MethodExpression action) {
    this.action = action;
}
```

Saving and Restoring State

Because component classes implement `StateHolder`, they must implement the `saveState(FacesContext)` and `restoreState(FacesContext, Object)` methods to help the JavaServer Faces implementation save and restore the state of components across multiple requests.

To save a set of values, you must implement the `saveState(FacesContext)` method. This method is called during the Render Response phase, during which the state of the response is saved for processing on subsequent requests. Here is an example:

```
public Object saveState(FacesContext context) {
    Object values[] = new Object[2];
    values[0] = super.saveState(context);
    values[1] = current;
    return (values);
}
```

This method initializes an array, which will hold the saved state. It next saves all of the state associated with the component.

A component that implements `StateHolder` must also provide an implementation for `restoreState(FacesContext, Object)`, which restores the state of the component to that saved with the `saveState(FacesContext)` method. The `restoreState(FacesContext, Object)` method is called during the restore view phase, during which the JavaServer Faces implementation checks whether there is any state that was saved during the last render response phase and needs to be restored in preparation for the next postback. Here is an example of the `restoreState(FacesContext, Object)` method:

```
public void restoreState(FacesContext context, Object state) {
    Object values[] = (Object[]) state;
```

```
    super.restoreState(context, values[0]);
    current = (String) values[1];
}
```

This method takes a `FacesContext` and an `Object` instance, representing the array that is holding the state for the component. This method sets the component's properties to the values saved in the `Object` array.

When you implement these methods in your component class, be sure to specify in the deployment descriptor where you want the state to be saved: either client or server. If state is saved on the client, the state of the entire view is rendered to a hidden field on the page.

To specify where state is saved for a particular web application, you need to set the `javax.faces.STATE_SAVING_METHOD` context parameter to either client or server in your application's deployment descriptor.

Delegating Rendering to a Renderer

This section explains in detail the process of delegating rendering to a renderer.

To delegate rendering, you perform these tasks:

- Create the `Renderer` class.
- Identify the renderer type in the `FacesRenderer` annotation or in the component's tag handler.

Creating the Renderer Class

When delegating rendering to a renderer, you can delegate all encoding and decoding to the renderer, or you can choose to do part of it in the component class.

To perform the rendering for the component, the renderer must implement an `encodeEnd` method.

In addition to the `encodeEnd` method, the renderer contains an empty constructor. This is used to create an instance of the renderer so that it can be added to the render kit. Here is an example of creating a renderer class:

```
@FacesRenderer (componentFamily="javax.faces.Command",
rendererType="com.sun.bookstore6.bookstoreRenderer")
public class ImageRenderer extends Renderer{

}
```

The `@FacesRenderer` annotation registers the renderer class with the JavaServer Faces implementation as a renderer class. The annotation also identifies the component family as well as the renderer type.

Identifying the Renderer Type

During the render response phase, the JavaServer Faces implementation calls the `getRendererType` method of the component's tag handler to determine which renderer to invoke, if there is one.

The `getRendererType` method of the tag handler must return the type associated with the renderer.

"Creating the Component Tag Handler" on page 280 explains more about the `getRendererType` method.

Handling Events for Custom Components

As explained in "Implementing an Event Listener" on page 286, events are automatically queued on standard components that fire events. A custom component, on the other hand, must manually queue events from its `decode` method if it fires events.

In addition to the method that processes the event, you need the event class itself. This class is very simple to write: You have it extend `ActionEvent` and provide a constructor that takes the component on which the event is queued and a method that returns the component.

Creating the Component Tag Handler

After you create your component and renderer classes, you're ready to define how a tag handler processes the tag representing the component and renderer combination. If you've created your own JSP custom tags before, creating a component tag handler should be easy for you.

In JavaServer Faces applications, the tag handler class associated with a component drives the Render Response phase of the JavaServer Faces lifecycle. For more information on the JavaServer Faces lifecycle, see "The Lifecycle of a JavaServer Faces Application" on page 204.

The first thing that the tag handler does is to retrieve the type of the component associated with the tag. Next, it sets the component's attributes to the values given in the page. It then returns the type of the renderer (if there is one) to the JavaServer Faces implementation so that the component's encoding can be performed when the tag is processed. Finally, it releases resources used during the processing of the tag.

The class extends `UIComponentELTag`, which supports `javax.servlet.jsp.tagext.Tag` functionality as well as JavaServer Faces-specific functionality. `UIComponentELTag` is the base class for all JavaServer Faces tags that correspond to a component. Tags that need to process their tag bodies should instead subclass `UIComponentBodyELTag`.

Retrieving the Component Type

As explained earlier, the first thing the tag handler class does is to retrieve the type of the component. It does this by using the `getComponentType` method.

Setting Component Property Values

After retrieving the type of the component, the tag handler sets the component's property values to those supplied as tag attributes values in the page. This section assumes that your component properties are enabled to accept expressions, as explained in "Enabling Component Properties to Accept Expressions" on page 277.

Getting the Attribute Values

Before setting the values in the component class, the tag handler first gets the attribute values from the page by means of JavaBeans component properties that correspond to the attributes. The following code shows the property used to access the value of the `immediate` attribute.

```
private javax.el.ValueExpression immediate = null;

public void setImmediate(javax.el.ValueExpression immediate) {
    this.immediate = immediate;
}
```

As this code shows, the `setImmediate` method takes a `ValueExpression` object. This means that the `immediate` attribute of the tag accepts value expressions.

Similarly, the `setActionListener` and `setAction` methods take `MethodExpression` objects, which means that these attributes accept method expressions. The following code shows the properties used to access the values of the `actionListener` and the `action` attributes

```
private javax.el.MethodExpression actionListener = null;

public void setActionListener(
    javax.el.MethodExpression actionListener) {

    this.actionListener = actionListener;
}
private javax.el.MethodExpression action = null;

public void setAction(javax.el.MethodExpression action) {
        this.action = action;
}
```

Setting the Component Property Values

To pass the value of the tag attributes to the component, the tag handler implements the `setProperties` method. The way `setProperties` passes the attribute values to the component class depends on whether the values are value expressions or method expressions.

Setting Value Expressions on Component Properties

When the attribute value is a value expression, `setProperties` first checks if it is not a literal expression. If the expression is not a literal, `setProperties` stores the expression into a collection, from which the component class can retrieve it and resolve it at the appropriate time. If the expression is a literal, `setProperties` performs any required type conversion and then does one of the following:

- If the attribute is renderer-independent, meaning that it is defined by the component class, then `setProperties` calls the corresponding setter method of the component class.
- If the attribute is renderer-dependent, `setProperties` stores the converted value into the component's map of generic renderer attributes.

Setting Method Expressions on Component Properties

The process of setting the properties that accept method expressions is done differently depending on the purpose of the method. The `actionListener` attribute uses a method expression to reference a method that handles action events. The `action` attribute uses a method expression to either specify a logical outcome or to reference a method that returns a logical outcome, which is used for navigation purposes.

To handle the method expression referenced by `actionListener`, the `setProperties` method must wrap the expression in a special action listener object called `MethodExpressionActionListener`. This listener executes the method referenced by the expression when it receives the action event. The `setProperties` method then adds this `MethodExpressionActionListener` object to the list of listeners to be notified when an event occurs. The following piece of `setProperties` does all of this:

```
if (actionListener != null) {
    map.addActionListener(
        new MethodExpressionActionListener(actionListener));
}
```

If your component fires value change events, your tag handler's `setProperties` method does a similar thing, except it wraps the expression in a `MethodExpressionValueChangeListener` object and adds the listener using the `addValueChangeListener` method.

In the case of the method expression referenced by the `action` attribute, the `setProperties` method uses the `setActionExpression` method of `ActionSource2` to set the corresponding property on the component.

Providing the Renderer Type

After setting the component properties, the tag handler provides a renderer type (if there is a renderer associated with the component) to the JavaServer Faces implementation. It does this using the `getRendererType` method.

The renderer type that is returned is the name under which the renderer is registered with the application. See "Delegating Rendering to a Renderer" on page 279 for more information.

If your component does not have a renderer associated with it, `getRendererType` should return `null`. In this case, the `renderer-type` element in the application configuration file should also be set to `null`.

Releasing Resources

It's recommended practice that all tag handlers implement a `release` method, which releases resources allocated during the execution of the tag handler by first calling the `UIComponentTag.release` method, then setting the resource values to null.

Defining the Custom Component Tag in a Tag Library Descriptor

To use a custom tag, you declare it in a Tag Library Descriptor (TLD). The TLD file defines how the custom tag is used in a JavaServer Faces page. The web container uses the TLD to validate the tag. The set of tags that are part of the HTML render kit are defined in the HTML_BASIC TLD, available at `http://download.oracle.com/javaee/6/javaserverfaces/2.1/docs/renderkitdocs/`.

At a minimum, each tag must have a name and a namespace attached to it in the TLD. The TLD file name must end with `taglib.xml`. Here is an example TLD named `mytaglib.xml`, with name and namespace entries:

```
<facelet-taglib>
        <namespace>
            <tag>
                <tag-name> </tag-name>
                <component> </component>
            </tag>
        </namespace>
</facelet-taglib>
```

You can also add additional attributes and attribute types within a `tag` element for each custom component. Each attribute element defines one of the tag attributes. As described in "Defining a Tag Attribute Type" on page 134, the attribute element defines what kind of value the attribute accepts, which for JavaServer Faces tags is either a deferred value expression or a method expression.

Creating a Custom Converter

A JavaServer Faces converter class converts strings to objects and objects to strings as required. Several standard converters are provided by JavaServer Faces for this purpose. See for more information on these included converters.

If the standard converters included with JavaServer Faces cannot perform the data conversion that you need, you can create a custom converter to perform this specialized conversion.

All custom converters must implement the `Converter` interface. This section explains how to implement this interface to perform a custom data conversion.

The custom converter class is created as follows:

```
@FacesConverter("com.bookstore6.Card")
public class CredirCardConverter implements Converter{
.......
.......
}
```

The `@FacesConverter` annotation registers the custom converter class as a converter with the name of `com.bookstore6.Card` with JavaServer Faces implementation. Alternatively you can use the deprecated method of registering the converter with entries in the application configuration resource file as shown in the following example:

```
<converter>
<converter-id>com.bookstore6.Card</converter-id>
<converter-class>com.bookstore6.CreditCardConverter</converter-class>
</converter>
```

To define how the data is converted from the presentation view to the model view, the `Converter` implementation must implement the `getAsObject(FacesContext, UIComponent, String)` method from the `Converter` interface. Here is an implementation of this method:

```
public Object getAsObject(FacesContext context,
     UIComponent component, String newValue)
         throws ConverterException {

    String convertedValue = null;
    if ( newValue == null ) {
        return newValue;
    }
    // Since this is only a String to String conversion,
    // this conversion does not throw ConverterException.

    convertedValue = newValue.trim();
    if ( (convertedValue.contains("-")) ||
         (convertedValue.contains(" "))) {
        char[] input = convertedValue.toCharArray();
        StringBuffer buffer = new StringBuffer(input.length);
        for ( int i = 0; i < input.length; ++i ) {
            if ( input[i] == '-' || input[i] == ' '  ) {
```

```
                continue;
            } else {
                buffer.append(input[i]);
            }
        }
        convertedValue = buffer.toString();
    }
        return convertedValue;
}
```

During the apply request values phase, when the components' `decode` methods are processed, the JavaServer Faces implementation looks up the component's local value in the request and calls the `getAsObject` method. When calling this method, the JavaServer Faces implementation passes in the current `FacesContext` instance, the component whose data needs conversion, and the local value as a `String`. The method then writes the local value to a character array, trims the hyphens and blanks, adds the rest of the characters to a `String`, and returns the `String`.

To define how the data is converted from the model view to the presentation view, the `Converter` implementation must implement the `getAsString(FacesContext, UIComponent, Object)` method from the `Converter` interface. Here is an implementation of this method:

```
public String getAsString(FacesContext context,
     UIComponent component, Object value)
     throws ConverterException {

    String inputVal = null;
    if ( value == null ) {
        return null;
    }
    // value must be of the type that can be cast to a String.
    try {
        inputVal = (String)value;
    } catch (ClassCastException ce) {
        FacesMessage errMsg = MessageFactory.getMessage(
            CONVERSION_ERROR_MESSAGE_ID,
            (new Object[] { value, inputVal }));
        throw new ConverterException(errMsg.getSummary());
    }
    // insert spaces after every four characters for better
    // readability if it doesn't already exist.
    char[] input = inputVal.toCharArray();
    StringBuffer buffer = new StringBuffer(input.length + 3);
    for ( int i = 0; i < input.length; ++i ) {
        if ( (i % 4) == 0 && i != 0) {
            if (input[i] != ' ' || input[i] != '-'){
                buffer.append(" ");
                // if there are any "-"'s convert them to blanks.
            } else if (input[i] == '-') {
                buffer.append(" ");
            }
         }
         buffer.append(input[i]);
    }
    String convertedValue = buffer.toString();
    return convertedValue;
}
```

During the render response phase, in which the components' `encode` methods are called, the JavaServer Faces implementation calls the `getAsString` method in order to generate the appropriate output. When the JavaServer Faces implementation calls this method, it passes in the current `FacesContext`, the `UIComponent` whose value needs to be converted, and the bean value to be converted. Because this converter does a `String`-to-`String` conversion, this method can cast the bean value to a `String`.

If the value cannot be converted to a `String`, the method throws an exception, passing an error message from the resource bundle that is registered with the application. "Registering Custom Error Messages" on page 234 explains how to register custom error messages with the application.

If the value can be converted to a `String`, the method reads the `String` to a character array and loops through the array, adding a space after every four characters.

Implementing an Event Listener

The JavaServer Faces technology supports action events and value-change events for components.

Action events occur when the user activates a component that implements `ActionSource`. These events are represented by the class `javax.faces.event.ActionEvent`.

Value-change events occur when the user changes the value of a component that implements `EditableValueHolder`. These events are represented by the class `javax.faces.event.ValueChangeEvent`.

One way to handle events is to implement the appropriate listener classes. Listener classes that handle the action events in an application must implement the interface `javax.faces.event.ActionListener`. Similarly, listeners that handle the value-change events must implement the interface `javax.faces.event.ValueChangeListener`.

This section explains how to implement the two listener classes in backing beans.

To handle events generated by custom components, you must implement an event listener and an event handler and manually queue the event on the component. See "Handling Events for Custom Components" on page 280 for more information.

Note – You do not need to create an `ActionListener` implementation to handle an event that results solely in navigating to a page and does not perform any other application-specific processing. See "Writing a Method to Handle Navigation" on page 194 for information on how to manage page navigation.

Implementing Value-Change Listeners

A `ValueChangeListener` implementation must include a `processValueChange(ValueChangeEvent)` method. This method processes the specified value-change event and is invoked by the JavaServer Faces implementation when the value-change event occurs. The `ValueChangeEvent` instance stores the old and the new values of the component that fired the event.

Here is part of a listener implementation:

```
...
public class NameChanged extends Object implements
     ValueChangeListener {

     public void processValueChange(ValueChangeEvent event)
        throws AbortProcessingException {

        if (null != event.getNewValue()) {
            FacesContext.getCurrentInstance().
                getExternalContext().getSessionMap().
                    put("name", event.getNewValue());
        }
    }
}
```

The `NameChanged` listener implementation is registered on a `UIInput` component of a web page. This listener stores into session scope the name that the user entered in the text field corresponding to the `name` component.

When the user enters the name in the text field, a value-change event is generated, and the `processValueChange(ValueChangeEvent)` method of the `NameChanged` listener implementation is invoked. This method first gets the ID of the component that fired the event from the `ValueChangeEvent` object, and it puts the value, along with an attribute name, into the session map of the `FacesContext` instance.

"Registering a Value-Change Listener on a Component" on page 177 explains how to register this listener onto a component.

The custom converter is used by the Facelets page as follows:

```
<mystore:store>
    <f:valueChangeListener type="com.bookstore6.NameChanged">
</mystore:store>
```

Implementing Action Listeners

An `ActionListener` implementation must include a `processAction(ActionEvent)` method. The `processAction(ActionEvent)` method processes the specified action event. The JavaServer Faces implementation invokes the `processAction(ActionEvent)` method when the `ActionEvent` occurs.

For example, suppose you have a Facelets page that allows the user to select a locale for the application by clicking one of a set of hyperlinks. When the user clicks one of the hyperlinks, an action event is generated. The listener implementation would look like this:

```
...
public class LocaleChangeListener extends Object implements ActionListener {

    private HashMap<String, Locale> locales = null;

    public LocaleChangeListener() {
        locales = new HashMap<String, Locale>(4);
        locales.put("NAmerica", new Locale("en", "US"));
        locales.put("SAmerica", new Locale("es", "MX"));
        locales.put("Germany", new Locale("de", "DE"));
        locales.put("France", new Locale("fr", "FR"));
    }

    public void processAction(ActionEvent event)
        throws AbortProcessingException {

        String current = event.getComponent().getId();
        FacesContext context = FacesContext.getCurrentInstance();
        context.getViewRoot().setLocale((Locale)
         locales.get(current));
     }
}
```

"Registering an Action Listener on a Component" on page 178 explains how to register this listener onto a component.

Creating a Custom Validator

If the standard validators or Bean Validation don't perform the validation checking you need, you can create a custom validator to validate user input. There are two ways to implement validation code:

- Implement a backing bean method that performs the validation.
- Provide an implementation of the `Validator` interface to perform the validation.

"Writing a Method to Perform Validation" on page 196 explains how to implement a backing bean method to perform validation. The rest of this section explains how to implement the `Validator` interface.

If you choose to implement the `Validator` interface and you want to allow the page author to configure the validator's attributes from the page, you also must create a custom tag for registering the validator on a component.

If you prefer to configure the attributes in the `Validator` implementation, you can forgo creating a custom tag and instead let the page author register the validator on a component using the `validator` tag, as described in "Using a Custom Validator" on page 296.

You can also create a backing bean property that accepts and returns the `Validator` implementation you create, as described in "Writing Properties Bound to Converters, Listeners, or Validators" on page 193. You can use the `validator` tag's binding attribute to bind the `Validator` implementation to the backing bean property.

Usually, you will want to display an error message when data fails validation. You need to store these error messages in a resource bundle.

After creating the resource bundle, you have two ways to make the messages available to the application. You can queue the error messages onto the `FacesContext` programmatically, or you can register the error messages in the application configuration resource file, as explained in "Registering Custom Error Messages" on page 234.

For example, an e-commerce application might use a general-purpose custom validator called `FormatValidator.java` to validate input data against a format pattern that is specified in the custom validator tag. This validator would be used with a Credit Card Number field on a Facelets page. Here is the custom validator tag:

```
<mystore:formatValidator
     formatPatterns="9999999999999999|9999 9999 9999 9999|
        9999-9999-9999-9999"/>
```

According to this validator, the data entered in the field must be one of the following:

- A 16–digit number with no spaces
- A 16–digit number with a space between every four digits
- A 16–digit number with hyphens between every four digits

The rest of this section describes how this validator would be implemented and how to create a custom tag so that the page author can register the validator on a component.

Implementing the Validator Interface

A `Validator` implementation must contain a constructor, a set of accessor methods for any attributes on the tag, and a `validate` method, which overrides the `validate` method of the `Validator` interface.

The `FormatValidator` class also defines accessor methods for setting the `formatPatterns` attribute, which specifies the acceptable format patterns for input into the fields. In addition, the class overrides the `validate` method of the `Validator` interface. This method validates the input and also accesses the custom error messages to be displayed when the `String` is invalid.

The `validate` method performs the actual validation of the data. It takes the `FacesContext` instance, the component whose data needs to be validated, and the value that needs to be validated. A validator can validate only data of a component that implements `EditableValueHolder`.

Here is an implementation of the `validate` method:

```
@FacesValidator
public void validate(FacesContext context, UIComponent component, Object toValidate) {

    boolean valid = false;
    String value = null;
    if ((context == null) || (component == null)) {
        throw new NullPointerException();
    }
    if (!(component instanceof UIInput)) {
        return;
    }
    if ( null == formatPatternsList || null == toValidate) {
        return;
    }
    value = toValidate.toString();
    //validate the value against the list of valid patterns.
    Iterator patternIt = formatPatternsList.iterator();
    while (patternIt.hasNext()) {
        valid = isFormatValid(
            ((String)patternIt.next()), value);
        if (valid) {
            break;
        }
    }
    if ( !valid ) {
        FacesMessage errMsg =
            MessageFactory.getMessage(context,
                FORMAT_INVALID_MESSAGE_ID,
                     (new Object[] {formatPatterns}));
            throw new ValidatorException(errMsg);
    }
}
```

The `@FacesValidator` annotation registers the above method as a converter with the JavaServer Faces implementation. This method gets the local value of the component and converts it to a `String`. It then iterates over the `formatPatternsList` list, which is the list of acceptable patterns as specified in the `formatPatterns` attribute of the custom validator tag.

While iterating over the list, this method checks the pattern of the component's local value against the patterns in the list. If the pattern of the local value does not match any pattern in the list, this method generates an error message. It then passes the message to the constructor of `ValidatorException`. Eventually the message is queued onto the `FacesContext` instance so that the message is displayed on the page during the Render Response phase.

The error messages are retrieved from the `Application` instance by `MessageFactory`. An application that creates its own custom messages must provide a class, such as `MessageFactory`, that retrieves the messages from the `Application` instance.

The `getMessage(FacesContext, String, Object)` method of `MessageFactory` takes a `FacesContext`, a static `String` that represents the key into the `Properties` file, and the format pattern as an `Object`. The key corresponds to the static message ID in the `FormatValidator` class:

```
public static final String FORMAT_INVALID_MESSAGE_ID =
     "FormatInvalid";
}
```

When the error message is displayed, the format pattern will be substituted for the `{0}` in the error message, which, in English, is as follows:

```
Input must match one of the following patterns {0}
```

JavaServer Faces applications can save the state of validators and components on either the client or the server. "Specifying Where State Is Saved" on page 244 explains how to configure your application to save state on either the client or the server.

If your JavaServer Faces application saves state on the client (which is the default), you need to make the `Validator` implementation implement `StateHolder` as well as `Validator`. In addition to implementing `StateHolder`, the `Validator` implementation needs to implement the `saveState(FacesContext)` and `restoreState(FacesContext, Object)` methods of `StateHolder`. With these methods, the `Validator` implementation tells the JavaServer Faces implementation which attributes of the `Validator` implementation to save and restore across multiple requests.

To save a set of values, you must implement the `saveState(FacesContext)` method. This method is called during the Render Response phase, during which the state of the response is saved for processing on subsequent requests. When implementing the `saveState(FacesContext)` method, you need to create an array of objects and add the values of the attributes you want to save to the array. Here is the `saveState(FacesContext)` method from the custom validator class:

```
public Object saveState(FacesContext context) {
    Object values[] = new Object[2];
    values[0] = formatPatterns;
    values[1] = formatPatternsList;
    return (values);
}
```

To restore the state saved with the `saveState(FacesContext)` method in preparation for the next postback, the `Validator` implementation implements `restoreState(FacesContext, Object)`. The `restoreState(FacesContext, Object)` method takes the `FacesContext` instance and an `Object` instance, which represents the array that is holding the state for the `Validator` implementation. This method sets the `Validator` implementation's properties to the values saved in the `Object` array. Here is the `restoreState(FacesContext, Object)` method from `FormatValidator`:

```
public void restoreState(FacesContext context, Object state) {
    Object values[] = (Object[]) state;
    formatPatterns = (String) values[0];
    formatPatternsList = (ArrayList) values[1];
}
```

As part of implementing `StateHolder`, the custom `Validator` implementation must also override the `isTransient` and `setTransient(boolean)` methods of `StateHolder`. By default, `transientValue` is false, which means that the `Validator` implementation will have its state information saved and restored. Here are the `isTransient` and `setTransient(boolean)` methods of `FormatValidator`:

```
private boolean transientValue = false;

public boolean isTransient() {
    return (this.transientValue);
}

public void setTransient(boolean transientValue) {
    this.transientValue = transientValue;
}
```

"Saving and Restoring State" on page 278 describes how a custom component must implement the `saveState(FacesContext)` and `restoreState(FacesContext, Object)` methods.

Creating a Custom Tag

If you implemented a `Validator` interface rather than implementing a backing bean method that performs the validation, you need to do one of the following:

- Allow the page author to specify the `Validator` implementation to use with the `validator` tag. In this case, the `Validator` implementation must define its own properties. "Using a Custom Validator" on page 296 explains how to use the `validator` tag.
- Create a custom tag that provides attributes for configuring the properties of the validator from the page. Because the `Validator` implementation from the preceding section does not define its attributes, the application developer must create a custom tag so that the page author can define the format patterns in the tag.

To create a custom tag, you need to do two things:

- Write a tag handler to create and register the `Validator` implementation on the component.
- Write a TLD to define the tag and its attributes.

"Using a Custom Validator" on page 296 explains how to use the custom validator tag on the page.

Writing the Tag Handler

The tag handler associated with a custom validator tag must extend the `ValidatorELTag` class. This class is the base class for all custom tag handlers that create `Validator` instances and register them on UI components. The `FormatValidatorTag` class registers the `FormatValidator` instance onto the component.

The `FormatValidatorTag` tag handler class does the following:

- Sets the ID of the validator.
- Provides a set of accessor methods for each attribute defined on the tag.
- Implements the `createValidator` method of the `ValidatorELTag` class. This method creates an instance of the validator and sets the range of values accepted by the validator.

The `formatPatterns` attribute of the `formatValidator` tag supports literals and value expressions. Therefore, the accessor method for this attribute in the `FormatValidatorTag` class must accept and return an instance of `ValueExpression`:

```
protected ValueExpression formatPatterns = null;

public void setFormatPatterns(ValueExpression fmtPatterns){
    formatPatterns = fmtPatterns;
}
```

Finally, the `createValidator` method creates an instance of `FormatValidator`, extracts the value from the `formatPatterns` attribute's value expression and sets the `formatPatterns` property of `FormatValidator` to this value:

the `formatPatterns` property of `FormatValidator` to this value:

```
protected Validator createValidator() throws JspException {
    FacesContext facesContext =
         FacesContext.getCurrentInstance();
    FormatValidator result = null;
    if(validatorID != null){
        result = (FormatValidator) facesContext.getApplication()
            .createValidator(validatorID);
    }
    String patterns = null;
    if (formatPatterns != null) {
        if (!formatPatterns.isLiteralText()) {
            patterns = (String)
             formatPatterns.getValue(facesContext.getELContext());
        } else {
            patterns = formatPatterns.getExpressionString();
        }
```

Writing the Tag Library Descriptor

To define a tag, you declare it in a tag library descriptor (TLD), which is an XML document that describes a tag library. A TLD contains information about a library and each tag contained in it.

The custom validator tag is defined in a TLD that contains a tag definition for `formatValidator`:

```
<tag>
    <name>formatValidator</name>
    ...
```

```
    <tag-class>
        mystore.taglib.FormatValidatorTag</tag-class>
    <attribute>
        <name>formatPatterns</name>
        <required>true</required>
        <deferred-value>
            <type>String</type>
        </deferred-value>
    </attribute>
</tag>
```

The `name` element defines the name of the tag as it must be used in the page. The `tag-class` element defines the tag handler class. The attribute elements define each of the tag's attributes. The `formatPatterns` attribute is the only attribute that the tag supports. The `deferred-value` element indicates that the `formatPatterns` attribute accepts deferred value expressions. The `type` element says that the expression resolves to a property of type `String`.

Using Custom Objects

As a page author, you might need to use custom converters, validators, or components packaged with the application on your Facelets pages.

A custom converter is applied to a component in one of the following ways:

- Reference the converter from the component tag's `converter` attribute.
- Nest a `converter` tag inside the component's tag and reference the custom converter from one of the `converter` tag's attributes.

A custom validator is applied to a component in one of the following ways:

- Nest a `validator` tag inside the component's tag and reference the custom validator from the `validator` tag.
- Nest the validator's custom tag (if there is one) inside the component's tag.

To use a custom component, you add the custom tag associated with the component to the page.

As explained in "Setting Up a Page" on page 139, you must ensure that the TLD that defines any custom tags is packaged in the application if you intend to use the tags in your pages. TLD files are stored in the `WEB-INF/` directory or subdirectory of the WAR file or in the `META-INF/` directory or subdirectory of a tag library packaged in a JAR file.

The next three sections describe how to use custom converter, validator, and UI components.

Using a Custom Converter

As described in the previous section, to apply the data conversion performed by a custom converter to a particular component's value, you must either reference the custom converter from the component tag's `converter` attribute or from a `converter` tag nested inside the component tag.

If you are using the component tag's `converter` attribute, this attribute must reference the `Converter` implementation's identifier or the fully-qualified class name of the converter. "Creating a Custom Converter" on page 284 explains how a custom converter is implemented.

The identifier for the credit card converter is `CreditCardConverter`. The `CreditCardConverter` instance is registered on the `ccno` component, as shown in the following example:

```
<h:inputText id="ccno"
    size="19"
    converter="CreditCardConverter"
    required="true">
    ...
</h:inputText>
```

By setting the `converter` attribute of a component's tag to the converter's identifier or its class name, you cause that component's local value to be automatically converted according to the rules specified in the `Converter` implementation.

Instead of referencing the converter from the component tag's `converter` attribute, you can reference the converter from a `f:converter` tag nested inside the component's tag. To reference the custom converter using the `converter` tag, you do one of the following:

- Set the `f:converter` tag's `converterId` attribute to the `Converter` implementation's identifier defined in the `@FacesConverter` annotation or in the application configuration resource file. This method is shown in the following example:

  ```
  <h:inputText id="ccno"
      size="19">
      <f:converter converterId="CreditCardConverter"/>
   </h:inputText>
  ```

- Bind the `Converter` implementation to a backing bean property using the `converter` tag's `binding` attribute, as described in "Binding Converters, Listeners, and Validators to Backing Bean Properties" on page 302.

Using a Custom Validator

To register a custom validator on a component, you must do one of the following:

- Nest the validator's custom tag inside the tag of the component whose value you want to be validated.
- Nest the standard `validator` tag within the tag of the component and reference the custom `Validator` implementation from the `validator` tag.

Here is the custom `formatValidator` tag for the Credit Card Number field:

```
<h:inputText id="ccno" size="19"
    ...
    required="true">
    <mystore:formatValidator
         formatPatterns="9999999999999999|9999 9999 9999 9999|
        9999-9999-9999-9999" />
</h:inputText>
<h:message styleClass="validationMessage"  for="ccno"/>
```

This tag validates the input of the `ccno` field against the patterns defined by the page author in the `formatPatterns` attribute.

You can use the same custom validator for any similar component by simply nesting the custom validator tag within the component tag.

If the application developer who created the custom validator prefers to configure the attributes in the `Validator` implementation rather than allow the page author to configure the attributes from the page, the developer will not create a custom tag for use with the validator.

In this case, the page author must nest the `validator` tag inside the tag of the component whose data needs to be validated. Then the page author needs to do one of the following:

- Set the `validator` tag's `validatorId` attribute to the ID of the validator that is defined in the application configuration resource file.
- Bind the custom `Validator` implementation to a backing bean property using the `validator` tag's `binding` attribute, as described in "Binding Converters, Listeners, and Validators to Backing Bean Properties" on page 302.

The following tag registers a hypothetical validator on a component using a `validator` tag and references the ID of the validator:

```
<h:inputText id="name" value="#{CustomerBean.name}"
            size="10" ... >
    <f:validator validatorId="customValidator" />
    ...
</h:inputText>
```

Using a Custom Component

In order to use a custom component in a page, you need to declare the tag library that defines the custom tag that renders the custom component, as explained in "Using Custom Objects" on page 294, and you add the component's tag to the page.

The Duke's Bookstore application includes a custom image map component on the `chooselocale.jsp` page. This component allows you to select the locale for the application by clicking on a region of the image map:

```
...
<h:graphicImage id="mapImage" url="/template/world.jpg"
    alt="#{bundle.chooseLocale}"
    usemap="#worldMap" />
    <bookstore:map id="worldMap" current="NAmericas"
         immediate="true"
        action="bookstore"
        actionListener="#{localeBean.chooseLocaleFromMap}">
        <bookstore:area id="NAmerica" value="#{NA}"
             onmouseover="/template/world_namer.jpg"
             onmouseout="/template/world.jpg"
            targetImage="mapImage" />
        ...
        <bookstore:area id="France" value="#{fraA}"
            onmouseover="/template/world_france.jpg"
             onmouseout="/template/world.jpg"
            targetImage="mapImage" />
</bookstore:map>
```

The standard `graphicImage` tag associates an image (`world.jpg`) with an image map that is referenced in the `usemap` attribute value.

The custom `map` tag that represents the custom component, `MapComponent`, specifies the image map, and contains a set of `area` tags. Each custom `area` tag represents a custom `AreaComponent` and specifies a region of the image map.

On the page, the `onmouseover` and `onmouseout` attributes specify the image that is displayed when the user performs the actions described by the attributes. The page author defines what these images are. The custom renderer also renders an `onclick` attribute.

In the rendered HTML page, the `onmouseover`, `onmouseout`, and `onclick` attributes define which JavaScript code is executed when these events occur. When the user moves the mouse over a region, the `onmouseover` function associated with the region displays the map with that region highlighted. When the user moves the mouse out of a region, the `onmouseout` function redisplays the original image. When the user clicks a region, the `onclick` function sets the value of a hidden `input` tag to the ID of the selected area and submits the page.

When the custom renderer renders these attributes in HTML, it also renders the JavaScript code. The custom renderer also renders the entire `onclick` attribute rather than let the page author set it.

The custom renderer that renders the `map` tag also renders a hidden `input` component that holds the current area. The server-side objects retrieve the value of the hidden `input` field and set the locale in the `FacesContext` instance according to which region was selected.

Binding Component Values and Instances to External Data Sources

A component tag can wire its data to a back-end data object by one of the following methods:

- Binding its component's value to a bean property or other external data source
- Binding its component's instance to a bean property

A component tag's `value` attribute uses a EL value expression to bind the component's value to an external data source, such as a bean property. A component tag's `binding` attribute uses a value expression to bind a component instance to a bean property.

When a component instance is bound to a backing bean property, the property holds the component's local value. Conversely, when a component's value is bound to a backing bean property, the property holds the value stored in the backing bean. This value is updated with the local value during the update model values phase of the life cycle. There are advantages to both of these methods.

Binding a component instance to a bean property has these advantages:

- The backing bean can programmatically modify component attributes.
- The backing bean can instantiate components rather than let the page author do so.

Binding a component's value to a bean property has these advantages:

- The page author has more control over the component attributes.
- The backing bean has no dependencies on the JavaServer Faces API (such as the component classes), allowing for greater separation of the presentation layer from the model layer.
- The JavaServer Faces implementation can perform conversions on the data based on the type of the bean property without the developer needing to apply a converter.

In most situations, you will bind a component's value rather than its instance to a bean property. You'll need to use a component binding only when you need to change one of the component's attributes dynamically. For example, if an application renders a component only under certain conditions, it can set the component's `rendered` property accordingly by accessing the property to which the component is bound.

When referencing the property using the component tag's `value` attribute, you need to use the proper syntax. For example, suppose a backing bean called `MyBean` has this `int` property:

```
int currentOption = null;
int getCurrentOption(){...}
void setCurrentOption(int option){...}
```

The value attribute that references this property must have this value-binding expression:

```
#{MyBean.currentOption}
```

In addition to binding a component's value to a bean property, the `value` attribute can specify a literal value or can map the component's data to any primitive (such as `int`), structure (such as an array), or collection (such as a list), independent of a JavaBeans component. Table 14–2 lists some example value-binding expressions that you can use with the `value` attribute.

TABLE 14–2 Example Value-Binding Expressions

Value	Expression
A Boolean	`cart.numberOfItems > 0`
A property initialized from a context `init` parameter	`initParam.quantity`
A bean property	`CashierBean.name`
Value in an array	`books[3]`
Value in a collection	`books["fiction"]`
Property of an object in an array of objects	`books[3].price`

The next two sections explain how to use the `value` attribute to bind a component's value to a bean property or other external data sources, and how to use the `binding` attribute to bind a component instance to a bean property.

Binding a Component Value to a Property

To bind a component's value to a bean property, you specify the name of the bean and the property using the `value` attribute.

This means that the name of the bean in the EL value expression must match the `managed-bean-name` element of the managed bean declaration up to the first period (`.`) in the expression. Similarly, the part of the value expression after the period must match the name specified in the corresponding `property-name` element in the application configuration resource file.

This means that the first part of the EL value expression must match the name of the backing bean up to the first period (`.`) and the part of value expression after the period must match the property of the backing bean.

Much of the time you will not include definitions for a managed bean's properties when configuring it. You need to define a property and its value only when you want the property to be initialized with a value when the bean is initialized.

Binding a Component Value to an Implicit Object

One external data source that a `value` attribute can refer to is an implicit object.

The following example shows a reference to an implicit object:

```
<h:outputFormat title="thanks" value="#{bundle.ThankYouParam}">
    <f:param value="#{sessionScope.name}"/>
</h:outputFormat>
```

This tag gets the name of the customer from the session scope and inserts it into the parameterized message at the key `ThankYouParam` from the resource bundle. For example, if the name of the customer is Gwen Canigetit, this tag will render:

```
Thank you, Gwen Canigetit, for purchasing your books from us.
```

Retrieving values from other implicit objects is done in a similar way to the example shown in this section. Table 14–3 lists the implicit objects to which a value attribute can refer. All of the implicit objects, except for the scope objects, are read-only and therefore should not be used as a value for a `UIInput` component.

TABLE 14–3 Implicit Objects

Implicit Object	What It Is
`applicationScope`	A `Map` of the application scope attribute values, keyed by attribute name
`cookie`	A `Map` of the cookie values for the current request, keyed by cookie name
`facesContext`	The `FacesContext` instance for the current request
`header`	A `Map` of HTTP header values for the current request, keyed by header name
`headerValues`	A `Map` of `String` arrays containing all the header values for HTTP headers in the current request, keyed by header name
`initParam`	A `Map` of the context initialization parameters for this web application
`param`	A `Map` of the request parameters for this request, keyed by parameter name
`paramValues`	A `Map` of `String` arrays containing all the parameter values for request parameters in the current request, keyed by parameter name
`requestScope`	A `Map` of the request attributes for this request, keyed by attribute name
`sessionScope`	A `Map` of the session attributes for this request, keyed by attribute name

TABLE 14–3 Implicit Objects *(Continued)*

Implicit Object	What It Is
`view`	The root `UIComponent` in the current component tree stored in the `FacesRequest` for this request

Binding a Component Instance to a Bean Property

A component instance can be bound to a bean property using a value expression with the `binding` attribute of the component's tag. You usually bind a component instance rather than its value to a bean property if the bean must dynamically change the component's attributes.

Here are two tags that bind components to bean properties:

```
<h:selectBooleanCheckbox
    id="fanClub"
    rendered="false"
    binding="#{cashier.specialOffer}" />
<h:outputLabel for="fanClub"
    rendered="false"
    binding="#{cashier.specialOfferText}"  >
    <h:outputText id="fanClubLabel"
        value="#{bundle.DukeFanClub}"
    />
</h:outputLabel>
```

The `selectBooleanCheckbox` tag renders a check box and binds the `fanClub` `UISelectBoolean` component to the `specialOffer` property of the `cashier` bean. The `outputLabel` tag binds the component representing the check box's label to the `specialOfferText` property of the `cashier` bean.

The `rendered` attributes of both tags are set to `false`, which prevents the check box and its label from being rendered. If the customer makes a large order, the backing bean could set both components' `rendered` properties to `true`, causing the check box and its label to be rendered.

These tags use component bindings rather than value bindings, because the backing bean must dynamically set the values of the components' `rendered` properties.

If the tags were to use value bindings instead of component bindings, the backing bean would not have direct access to the components, and would therefore require additional code to access the components from the `FacesContext` instance to change the components' `rendered` properties.

Binding Converters, Listeners, and Validators to Backing Bean Properties

As described in "Adding Components to a Page Using HTML Tags" on page 140, a page author can bind converter, listener, and validator implementations to backing bean properties using the `binding` attributes of the tags which are used to register the implementations on components.

This technique has similar advantages to binding component instances to backing bean properties, as described in "Binding Component Values and Instances to External Data Sources" on page 298. In particular, binding a converter, listener, or validator implementation to a backing bean property yields the following benefits:

- The backing bean can instantiate the implementation instead of allowing the page author to do so.
- The backing bean can programmatically modify the attributes of the implementation. In the case of a custom implementation, the only other way to modify the attributes outside of the implementation class would be to create a custom tag for it and require the page author to set the attribute values from the page.

Whether you are binding a converter, listener, or validator to a backing bean property, the process is the same for any of the implementations:

- Nest the converter, listener, or validator tag within an appropriate component tag.
- Make sure that the backing bean has a property that accepts and returns the converter, listener, or validator implementation class that you want to bind to the property.
- Reference the backing bean property using a value expression from the `binding` attribute of the converter, listener, or validator tag.

For example, say that you want to bind the standard `DateTime` converter to a backing bean property because the application developer wants the backing bean to set the formatting pattern of the user's input rather than let the page author do it. First, the page author registers the converter onto the component by nesting the `convertDateTime` tag within the component tag. Then, the page author references the property with the `binding` attribute of the `convertDateTime` tag:

```
<h:inputText value="#{LoginBean.birthDate}">
    <f:convertDateTime binding="#{LoginBean.convertDate}" />
</h:inputText>
```

The `convertDate` property would look something like this:

```
private DateTimeConverter convertDate;
public DateTimeConverter getConvertDate() {
    ...
    return convertDate;
```

```
{
public void setConvertDate(DateTimeConverter convertDate) {
    convertDate.setPattern("EEEEEEEE, MMM dd, yyyy");
    this.convertDate = convertDate;
}
```

See "Writing Properties Bound to Converters, Listeners, or Validators" on page 193 for more information on writing backing bean properties for converter, listener, and validator implementations.

◆ ◆ ◆ CHAPTER 15

Java Servlet Technology

Shortly after the Web began to be used for delivering services, service providers recognized the need for dynamic content. Applets, one of the earliest attempts toward this goal, focused on using the client platform to deliver dynamic user experiences. At the same time, developers also investigated using the server platform for the same purpose. Initially, Common Gateway Interface (CGI) server-side scripts were the main technology used to generate dynamic content. Although widely used, CGI scripting technology had many shortcomings, including platform dependence and lack of scalability. To address these limitations, Java Servlet technology was created as a portable way to provide dynamic, user-oriented content.

The following topics are addressed here:

What Is a Servlet?

A servlet is a Java programming language class used to extend the capabilities of servers that host applications accessed by means of a request-response programming model. Although servlets can respond to any type of request, they are commonly used to extend the applications hosted by web servers. For such applications, Java Servlet technology defines HTTP-specific servlet classes.

The `javax.servlet` and `javax.servlet.http` packages provide interfaces and classes for writing servlets. All servlets must implement the `Servlet` interface, which defines lifecycle methods. When implementing a generic service, you can use or extend the `GenericServlet` class provided with the Java Servlet API. The `HttpServlet` class provides methods, such as `doGet` and `doPost`, for handling HTTP-specific services.

Servlet Lifecycle

The lifecycle of a servlet is controlled by the container in which the servlet has been deployed. When a request is mapped to a servlet, the container performs the following steps.

1. If an instance of the servlet does not exist, the web container
   a. Loads the servlet class.
   b. Creates an instance of the servlet class.
   c. Initializes the servlet instance by calling the `init` method. Initialization is covered in "Creating and Initializing a Servlet" on page 309.
2. Invokes the `service` method, passing request and response objects. Service methods are discussed in "Writing Service Methods" on page 310.

If it needs to remove the servlet, the container finalizes the servlet by calling the servlet's `destroy` method. For more information, see "Finalizing a Servlet" on page 320.

Handling Servlet Lifecycle Events

You can monitor and react to events in a servlet's lifecycle by defining listener objects whose methods get invoked when lifecycle events occur. To use these listener objects, you must define and specify the listener class.

Defining the Listener Class

You define a listener class as an implementation of a listener interface. Table 15–1 lists the events that can be monitored and the corresponding interface that must be implemented. When a listener method is invoked, it is passed an event that contains information appropriate to the event. For example, the methods in the `HttpSessionListener` interface are passed an `HttpSessionEvent`, which contains an `HttpSession`.

TABLE 15–1 Servlet Lifecycle Events

Object	Event	Listener Interface and Event Class
Web context (see "Accessing the Web Context" on page 317)	Initialization and destruction	`javax.servlet.ServletContextListener` and `ServletContextEvent`
	Attribute added, removed, or replaced	`javax.servlet.ServletContextAttributeListener` and `ServletContextAttributeEvent`
Session (See "Maintaining Client State" on page 318)	Creation, invalidation, activation, passivation, and timeout	`javax.servlet.http.HttpSessionListener`, `javax.servlet.http.HttpSessionActivationListener`, and `HttpSessionEvent`
	Attribute added, removed, or replaced	`javax.servlet.http.HttpSessionAttributeListener` and `HttpSessionBindingEvent`
Request	A servlet request has started being processed by web components	`javax.servlet.ServletRequestListener` and `ServletRequestEvent`
	Attribute added, removed, or replaced	`javax.servlet.ServletRequestAttributeListener` and `ServletRequestAttributeEvent`

Use the `@WebListener` annotation to define a listener to get events for various operations on the particular web application context. Classes annotated with `@WebListener` must implement one of the following interfaces:

```
javax.servlet.ServletContextListener
javax.servlet.ServletContextAttributeListener
javax.servlet.ServletRequestListener
javax.servlet.ServletRequestAttributeListener
javax.servlet..http.HttpSessionListener
javax.servlet..http.HttpSessionAttributeListener
```

For example, the following code snippet defines a listener that implements two of these interfaces:

```
import javax.servlet.ServletContextAttributeListener;
import javax.servlet.ServletContextListener;
import javax.servlet.annotation.WebListener;

@WebListener()
public class SimpleServletListener implements ServletContextListener,
        ServletContextAttributeListener {
    ...
```

Handling Servlet Errors

Any number of exceptions can occur when a servlet executes. When an exception occurs, the web container generates a default page containing the following message:

```
A Servlet Exception Has Occurred
```

But you can also specify that the container should return a specific error page for a given exception.

Sharing Information

Web components, like most objects, usually work with other objects to accomplish their tasks. Web components can do so by

- Using private helper objects (for example, JavaBeans components).
- Sharing objects that are attributes of a public scope.
- Using a database.
- Invoking other web resources. The Java Servlet technology mechanisms that allow a web component to invoke other web resources are described in "Invoking Other Web Resources" on page 316.

Using Scope Objects

Collaborating web components share information by means of objects that are maintained as attributes of four scope objects. You access these attributes by using the `getAttribute` and `setAttribute` methods of the class representing the scope. Table 15–2 lists the scope objects.

TABLE 15–2 Scope Objects

Scope Object	Class	Accessible from
Web context	`javax.servlet.ServletContext`	Web components within a web context. See "Accessing the Web Context" on page 317.
Session	`javax.servlet.http.HttpSession`	Web components handling a request that belongs to the session. See "Maintaining Client State" on page 318.
Request	Subtype of `javax.servlet.ServletRequest`	Web components handling the request.
Page	`javax.servlet.jsp.JspContext`	The JSP page that creates the object.

Controlling Concurrent Access to Shared Resources

In a multithreaded server, shared resources can be accessed concurrently. In addition to scope object attributes, shared resources include in-memory data, such as instance or class variables, and external objects, such as files, database connections, and network connections.

Concurrent access can arise in several situations:

- Multiple web components accessing objects stored in the web context.
- Multiple web components accessing objects stored in a session.
- Multiple threads within a web component accessing instance variables. A web container will typically create a thread to handle each request. To ensure that a servlet instance handles only one request at a time, a servlet can implement the `SingleThreadModel` interface. If a servlet implements this interface, no two threads will execute concurrently in the servlet's service method. A web container can implement this guarantee by synchronizing access to a single instance of the servlet or by maintaining a pool of web component instances and dispatching each new request to a free instance. This interface does not prevent synchronization problems that result from web components' accessing shared resources, such as static class variables or external objects.

When resources can be accessed concurrently, they can be used in an inconsistent fashion. You prevent this by controlling the access using the synchronization techniques described in the Threads lesson at `http://download.oracle.com/javase/tutorial/essential/concurrency/index.html` in *The Java Tutorial, Fourth Edition*, by Sharon Zakhour et al. (Addison-Wesley, 2006).

Creating and Initializing a Servlet

Use the `@WebServlet` annotation to define a servlet component in a web application. This annotation is specified on a class and contains metadata about the servlet being declared. The annotated servlet must specify at least one URL pattern. This is done by using the `urlPatterns` or `value` attribute on the annotation. All other attributes are optional, with default settings. Use the `value` attribute when the only attribute on the annotation is the URL pattern; otherwise use the `urlPatterns` attribute when other attributes are also used.

Classes annotated with `@WebServlet` must extend the `javax.servlet.http.HttpServlet` class. For example, the following code snippet defines a servlet with the URL pattern `/report`:

```
import javax.servlet.annotation.WebServlet;
import javax.servlet.http.HttpServlet;

@WebServlet("/report")
public class MoodServlet extends HttpServlet {
    ...
```

The web container initializes a servlet after loading and instantiating the servlet class and before delivering requests from clients. To customize this process to allow the servlet to read persistent configuration data, initialize resources, and perform any other one-time activities, you can either override the `init` method of the `Servlet` interface or specify the `initParams` attribute of the `@WebServlet` annotation. The `initParams` attribute contains a `@WebInitParam` annotation. If it cannot complete its initialization process, a servlet throws an `UnavailableException`.

Writing Service Methods

The service provided by a servlet is implemented in the `service` method of a `GenericServlet`, in the `do`*Method* methods (where *Method* can take the value `Get`, `Delete`, `Options`, `Post`, `Put`, or `Trace`) of an `HttpServlet` object, or in any other protocol-specific methods defined by a class that implements the `Servlet` interface. The term *service method* is used for any method in a servlet class that provides a service to a client.

The general pattern for a service method is to extract information from the request, access external resources, and then populate the response, based on that information. For HTTP servlets, the correct procedure for populating the response is to do the following:

1. Retrieve an output stream from the response.
2. Fill in the response headers.
3. Write any body content to the output stream.

Response headers must always be set before the response has been committed. The web container will ignore any attempt to set or add headers after the response has been committed. The next two sections describe how to get information from requests and generate responses.

Getting Information from Requests

A request contains data passed between a client and the servlet. All requests implement the `ServletRequest` interface. This interface defines methods for accessing the following information:

- Parameters, which are typically used to convey information between clients and servlets
- Object-valued attributes, which are typically used to pass information between the servlet container and a servlet or between collaborating servlets
- Information about the protocol used to communicate the request and about the client and server involved in the request
- Information relevant to localization

You can also retrieve an input stream from the request and manually parse the data. To read character data, use the `BufferedReader` object returned by the request's `getReader` method. To read binary data, use the `ServletInputStream` returned by `getInputStream`.

HTTP servlets are passed an HTTP request object, `HttpServletRequest`, which contains the request URL, HTTP headers, query string, and so on. An HTTP request URL contains the following parts:

`http://[host]:[port][request-path]?[query-string]`

The request path is further composed of the following elements:

- **Context path**: A concatenation of a forward slash (`/`) with the context root of the servlet's web application.
- **Servlet path**: The path section that corresponds to the component alias that activated this request. This path starts with a forward slash (`/`).
- **Path info**: The part of the request path that is not part of the context path or the servlet path.

You can use the `getContextPath`, `getServletPath`, and `getPathInfo` methods of the `HttpServletRequest` interface to access this information. Except for URL encoding differences between the request URI and the path parts, the request URI is always comprised of the context path plus the servlet path plus the path info.

Query strings are composed of a set of parameters and values. Individual parameters are retrieved from a request by using the `getParameter` method. There are two ways to generate query strings.

- A query string can explicitly appear in a web page.
- A query string is appended to a URL when a form with a `GET` HTTP method is submitted.

Constructing Responses

A response contains data passed between a server and the client. All responses implement the `ServletResponse` interface. This interface defines methods that allow you to

- Retrieve an output stream to use to send data to the client. To send character data, use the `PrintWriter` returned by the response's `getWriter` method. To send binary data in a Multipurpose Internet Mail Extensions (MIME) body response, use the `ServletOutputStream` returned by `getOutputStream`. To mix binary and text data, as in a multipart response, use a `ServletOutputStream` and manage the character sections manually.
- Indicate the content type (for example, `text/html`) being returned by the response with the `setContentType(String)` method. This method must be called before the response is committed. A registry of content type names is kept by the Internet Assigned Numbers Authority (IANA) at `http://www.iana.org/assignments/media-types/`.
- Indicate whether to buffer output with the `setBufferSize(int)` method. By default, any content written to the output stream is immediately sent to the client. Buffering allows content to be written before anything is sent back to the client, thus providing the servlet

with more time to set appropriate status codes and headers or forward to another web resource. The method must be called before any content is written or before the response is committed.

- Set localization information, such as locale and character encoding.

HTTP response objects, `javax.servlet.http.HttpServletResponse`, have fields representing HTTP headers, such as the following:

- Status codes, which are used to indicate the reason a request is not satisfied or that a request has been redirected.
- Cookies, which are used to store application-specific information at the client. Sometimes, cookies are used to maintain an identifier for tracking a user's session (see "Session Tracking" on page 319).

Filtering Requests and Responses

A *filter* is an object that can transform the header and content (or both) of a request or response. Filters differ from web components in that filters usually do not themselves create a response. Instead, a filter provides functionality that can be "attached" to any kind of web resource. Consequently, a filter should not have any dependencies on a web resource for which it is acting as a filter; this way, it can be composed with more than one type of web resource.

The main tasks that a filter can perform are as follows:

- Query the request and act accordingly.
- Block the request-and-response pair from passing any further.
- Modify the request headers and data. You do this by providing a customized version of the request.
- Modify the response headers and data. You do this by providing a customized version of the response.
- Interact with external resources.

Applications of filters include authentication, logging, image conversion, data compression, encryption, tokenizing streams, XML transformations, and so on.

You can configure a web resource to be filtered by a chain of zero, one, or more filters in a specific order. This chain is specified when the web application containing the component is deployed and is instantiated when a web container loads the component.

Programming Filters

The filtering API is defined by the `Filter`, `FilterChain`, and `FilterConfig` interfaces in the `javax.servlet` package. You define a filter by implementing the `Filter` interface.

Use the `@WebFilter` annotation to define a filter in a web application. This annotation is specified on a class and contains metadata about the filter being declared. The annotated filter must specify at least one URL pattern. This is done by using the `urlPatterns` or `value` attribute on the annotation. All other attributes are optional, with default settings. Use the `value` attribute when the only attribute on the annotation is the URL pattern; use the `urlPatterns` attribute when other attributes are also used.

Classes annotated with the `@WebFilter` annotation must implement the `javax.servlet.Filter` interface.

To add configuration data to the filter, specify the `initParams` attribute of the `@WebFilter` annotation. The `initParams` attribute contains a `@WebInitParam` annotation. The following code snippet defines a filter, specifying an initialization parameter:

```
import javax.servlet.Filter;
import javax.servlet.annotation.WebFilter;
import javax.servlet.annotation.WebInitParam;

@WebFilter(filterName = "TimeOfDayFilter",
urlPatterns = {"/*"},
initParams = {
    @WebInitParam(name = "mood", value = "awake")})
public class TimeOfDayFilter implements Filter {
    ....
```

The most important method in the `Filter` interface is `doFilter`, which is passed request, response, and filter chain objects. This method can perform the following actions:

- Examine the request headers.
- Customize the request object if the filter wishes to modify request headers or data.
- Customize the response object if the filter wishes to modify response headers or data.
- Invoke the next entity in the filter chain. If the current filter is the last filter in the chain that ends with the target web component or static resource, the next entity is the resource at the end of the chain; otherwise, it is the next filter that was configured in the WAR. The filter invokes the next entity by calling the `doFilter` method on the chain object, passing in the request and response it was called with or the wrapped versions it may have created. Alternatively, the filter can choose to block the request by not making the call to invoke the next entity. In the latter case, the filter is responsible for filling out the response.
- Examine response headers after invoking the next filter in the chain.
- Throw an exception to indicate an error in processing.

In addition to `doFilter`, you must implement the `init` and `destroy` methods. The `init` method is called by the container when the filter is instantiated. If you wish to pass initialization parameters to the filter, you retrieve them from the `FilterConfig` object passed to `init`.

Programming Customized Requests and Responses

There are many ways for a filter to modify a request or a response. For example, a filter can add an attribute to the request or can insert data in the response.

A filter that modifies a response must usually capture the response before it is returned to the client. To do this, you pass a stand-in stream to the servlet that generates the response. The stand-in stream prevents the servlet from closing the original response stream when it completes and allows the filter to modify the servlet's response.

To pass this stand-in stream to the servlet, the filter creates a response wrapper that overrides the `getWriter` or `getOutputStream` method to return this stand-in stream. The wrapper is passed to the `doFilter` method of the filter chain. Wrapper methods default to calling through to the wrapped request or response object.

To override request methods, you wrap the request in an object that extends either `ServletRequestWrapper` or `HttpServletRequestWrapper`. To override response methods, you wrap the response in an object that extends either `ServletResponseWrapper` or `HttpServletResponseWrapper`.

Specifying Filter Mappings

A web container uses filter mappings to decide how to apply filters to web resources. A filter mapping matches a filter to a web component by name or to web resources by URL pattern. The filters are invoked in the order in which filter mappings appear in the filter mapping list of a WAR. You specify a filter mapping list for a WAR in its deployment descriptor by either using NetBeans IDE or coding the list by hand with XML.

If you want to log every request to a web application, you map the hit counter filter to the URL pattern `/*`.

You can map a filter to one or more web resources, and you can map more than one filter to a web resource. This is illustrated in Figure 15–1, where filter F1 is mapped to servlets S1, S2, and S3; filter F2 is mapped to servlet S2; and filter F3 is mapped to servlets S1 and S2.

FIGURE 15–1 Filter-to-Servlet Mapping



Recall that a filter chain is one of the objects passed to the `doFilter` method of a filter. This chain is formed indirectly by means of filter mappings. The order of the filters in the chain is the same as the order in which filter mappings appear in the web application deployment descriptor.

When a filter is mapped to servlet S1, the web container invokes the `doFilter` method of F1. The `doFilter` method of each filter in S1's filter chain is invoked by the preceding filter in the chain by means of the `chain.doFilter` method. Because S1's filter chain contains filters F1 and F3, F1's call to `chain.doFilter` invokes the `doFilter` method of filter F3. When F3's `doFilter` method completes, control returns to F1's `doFilter` method.

▼ To Specify Filter Mappings Using NetBeans IDE

1. **Expand the application's project node in the Project pane.**
2. **Expand the Web Pages and WEB-INF nodes under the project node.**
3. **Double-click `web.xml`.**
4. **Click Filters at the top of the editor pane.**
5. **Expand the Servlet Filters node in the editor pane.**
6. **Click Add Filter Element to map the filter to a web resource by name or by URL pattern.**
7. **In the Add Servlet Filter dialog, enter the name of the filter in the Filter Name field.**
8. **Click Browse to locate the servlet class to which the filter applies.**
   You can include wildcard characters so that you can apply the filter to more than one servlet.

9. **Click OK.**

10. **To constrain how the filter is applied to requests, follow these steps.**

    a. **Expand the Filter Mappings node.**

    b. **Select the filter from the list of filters.**

    c. **Click Add.**

    d. **In the Add Filter Mapping dialog, select one of the following dispatcher types:**

    - `REQUEST`: Only when the request comes directly from the client
    - `ASYNC`: Only when the asynchronous request comes from the client
    - `FORWARD`: Only when the request has been forwarded to a component (see "Transferring Control to Another Web Component" on page 317)
    - `INCLUDE`: Only when the request is being processed by a component that has been included (see "Including Other Resources in the Response" on page 317)
    - `ERROR`: Only when the request is being processed with the error page mechanism (see "Handling Servlet Errors" on page 308)

    You can direct the filter to be applied to any combination of the preceding situations by selecting multiple dispatcher types. If no types are specified, the default option is `REQUEST`.

Invoking Other Web Resources

Web components can invoke other web resources both indirectly and directly. A web component indirectly invokes another web resource by embedding a URL that points to another web component in content returned to a client. While it is executing, a web component directly invokes another resource by either including the content of another resource or forwarding a request to another resource.

To invoke a resource available on the server that is running a web component, you must first obtain a `RequestDispatcher` object by using the `getRequestDispatcher("URL")` method. You can get a `RequestDispatcher` object from either a request or the web context; however, the two methods have slightly different behavior. The method takes the path to the requested resource as an argument. A request can take a relative path (that is, one that does not begin with a `/`), but the web context requires an absolute path. If the resource is not available or if the server has not implemented a `RequestDispatcher` object for that type of resource, `getRequestDispatcher` will return null. Your servlet should be prepared to deal with this condition.

Including Other Resources in the Response

It is often useful to include another web resource, such as banner content or copyright information) in the response returned from a web component. To include another resource, invoke the `include` method of a `RequestDispatcher` object:

```
include(request, response);
```

If the resource is static, the `include` method enables programmatic server-side includes. If the resource is a web component, the effect of the method is to send the request to the included web component, execute the web component, and then include the result of the execution in the response from the containing servlet. An included web component has access to the request object but is limited in what it can do with the response object.

- It can write to the body of the response and commit a response.
- It cannot set headers or call any method, such as `setCookie`, that affects the headers of the response.

Transferring Control to Another Web Component

In some applications, you might want to have one web component do preliminary processing of a request and have another component generate the response. For example, you might want to partially process a request and then transfer to another component, depending on the nature of the request.

To transfer control to another web component, you invoke the `forward` method of a `RequestDispatcher`. When a request is forwarded, the request URL is set to the path of the forwarded page. The original URI and its constituent parts are saved as request attributes `javax.servlet.forward.[`*request-uri*`|`*context-path*`|`*servlet-path*`|`*path-info*`|`*query-string*`]`.

The `forward` method should be used to give another resource responsibility for replying to the user. If you have already accessed a `ServletOutputStream` or `PrintWriter` object within the servlet, you cannot use this method; doing so throws an `IllegalStateException`.

Accessing the Web Context

The context in which web components execute is an object that implements the `ServletContext` interface. You retrieve the web context by using the `getServletContext` method. The web context provides methods for accessing

- Initialization parameters
- Resources associated with the web context
- Object-valued attributes
- Logging capabilities

The counter's access methods are synchronized to prevent incompatible operations by servlets that are running concurrently. A filter retrieves the counter object by using the context's `getAttribute` method. The incremented value of the counter is recorded in the log.

Maintaining Client State

Many applications require that a series of requests from a client be associated with one another. For example, a web application can save the state of a user's shopping cart across requests. Web-based applications are responsible for maintaining such state, called a *session*, because HTTP is stateless. To support applications that need to maintain state, Java Servlet technology provides an API for managing sessions and allows several mechanisms for implementing sessions.

Accessing a Session

Sessions are represented by an `HttpSession` object. You access a session by calling the `getSession` method of a request object. This method returns the current session associated with this request; or, if the request does not have a session, this method creates one.

Associating Objects with a Session

You can associate object-valued attributes with a session by name. Such attributes are accessible by any web component that belongs to the same web context *and* is handling a request that is part of the same session.

Recall that your application can notify web context and session listener objects of servlet lifecycle events ("Handling Servlet Lifecycle Events" on page 306). You can also notify objects of certain events related to their association with a session such as the following:

- When the object is added to or removed from a session. To receive this notification, your object must implement the `javax.servlet.http.HttpSessionBindingListener` interface.
- When the session to which the object is attached will be passivated or activated. A session will be passivated or activated when it is moved between virtual machines or saved to and restored from persistent storage. To receive this notification, your object must implement the `javax.servlet.http.HttpSessionActivationListener` interface.

Session Management

Because an HTTP client has no way to signal that it no longer needs a session, each session has an associated timeout so that its resources can be reclaimed. The timeout period can be accessed by using a session's `getMaxInactiveInterval` and `setMaxInactiveInterval` methods.

- To ensure that an active session is not timed out, you should periodically access the session by using service methods because this resets the session's time-to-live counter.
- When a particular client interaction is finished, you use the session's `invalidate` method to invalidate a session on the server side and remove any session data.

▼ To Set the Timeout Period Using NetBeans IDE

To set the timeout period in the deployment descriptor using NetBeans IDE, follow these steps.

1. **Open the project if you haven't already.**
2. **Expand the project's node in the Projects pane.**
3. **Expand the Web Pages node and then the WEB-INF node.**
4. **Double-click `web.xml`.**
5. **Click General at the top of the editor.**
6. **In the Session Timeout field, type an integer value.**

   The integer value represents the number of minutes of inactivity that must pass before the session times out.

Session Tracking

To associate a session with a user, a web container can use several methods, all of which involve passing an identifier between the client and the server. The identifier can be maintained on the client as a cookie, or the web component can include the identifier in every URL that is returned to the client.

If your application uses session objects, you must ensure that session tracking is enabled by having the application rewrite URLs whenever the client turns off cookies. You do this by calling the response's `encodeURL(URL)` method on all URLs returned by a servlet. This method includes the session ID in the URL only if cookies are disabled; otherwise, the method returns the URL unchanged.

Finalizing a Servlet

A servlet container may determine that a servlet should be removed from service (for example, when a container wants to reclaim memory resources or when it is being shut down). In such a case, the container calls the `destroy` method of the `Servlet` interface. In this method, you release any resources the servlet is using and save any persistent state. The `destroy` method releases the database object created in the `init` method .

A servlet's service methods should all be complete when a servlet is removed. The server tries to ensure this by calling the `destroy` method only after all service requests have returned or after a server-specific grace period, whichever comes first. If your servlet has operations that may run longer than the server's grace period, the operations could still be running when `destroy` is called. You must make sure that any threads still handling client requests complete.

The remainder of this section explains how to do the following:

- Keep track of how many threads are currently running the `service` method.
- Provide a clean shutdown by having the `destroy` method notify long-running threads of the shutdown and wait for them to complete.
- Have the long-running methods poll periodically to check for shutdown and, if necessary, stop working, clean up, and return.

Tracking Service Requests

To track service requests, include in your servlet class a field that counts the number of service methods that are running. The field should have synchronized access methods to increment, decrement, and return its value:

```
public class ShutdownExample extends HttpServlet {
    private int serviceCounter = 0;
    ...
    // Access methods for serviceCounter
    protected synchronized void enteringServiceMethod() {
        serviceCounter++;
    }
    protected synchronized void leavingServiceMethod() {
        serviceCounter--;
    }
    protected synchronized int numServices() {
        return serviceCounter;
    }
}
```

The `service` method should increment the service counter each time the method is entered and should decrement the counter each time the method returns. This is one of the few times that your `HttpServlet` subclass should override the `service` method. The new method should call `super.service` to preserve the functionality of the original `service` method:

```
protected void service(HttpServletRequest req,
                       HttpServletResponse resp)
                       throws ServletException,IOException {
    enteringServiceMethod();
    try {
        super.service(req, resp);
    } finally {
        leavingServiceMethod();
    }
}
```

Notifying Methods to Shut Down

To ensure a clean shutdown, your `destroy` method should not release any shared resources until all the service requests have completed. One part of doing this is to check the service counter. Another part is to notify the long-running methods that it is time to shut down. For this notification, another field is required. The field should have the usual access methods:

```
public class ShutdownExample extends HttpServlet {
    private boolean shuttingDown;
    ...
    //Access methods for shuttingDown
    protected synchronized void setShuttingDown(boolean flag) {
        shuttingDown = flag;
    }
    protected synchronized boolean isShuttingDown() {
        return shuttingDown;
    }
}
```

Here is an example of the `destroy` method using these fields to provide a clean shutdown:

```
public void destroy() {
    /* Check to see whether there are still service methods /*
    /* running, and if there are, tell them to stop. */
    if (numServices() > 0) {
        setShuttingDown(true);
    }

    /* Wait for the service methods to stop. */
    while(numServices() > 0) {
        try {
            Thread.sleep(interval);
        } catch (InterruptedException e) {
        }
    }
}
```

Creating Polite Long-Running Methods

The final step in providing a clean shutdown is to make any long-running methods behave politely. Methods that might run for a long time should check the value of the field that notifies them of shutdowns and should interrupt their work, if necessary:

```
public void doPost(...) {
    ...
    for(i = 0; ((i < lotsOfStuffToDo) &&
         !isShuttingDown()); i++) {
        try {
            partOfLongRunningOperation(i);
        } catch (InterruptedException e) {
            ...
        }
    }
}
```

The mood Example Application

The mood example application, located in *tut-install*/examples/web/mood, is a simple example that displays Duke's moods at different times during the day. The example shows how to develop a simple application by using the @WebServlet, @WebFilter, and @WebListener annotations to create a servlet, a listener, and a filter.

Components of the mood Example Application

The mood example application is comprised of three components: mood.web.MoodServlet, mood.web.TimeOfDayFilter, and mood.web.SimpleServletListener.

MoodServlet, the presentation layer of the application, displays Duke's mood in a graphic, based on the time of day. The @WebServlet annotation specifies the URL pattern:

```
@WebServlet("/report")
public class MoodServlet extends HttpServlet {
    ...
```

TimeOfDayFilter sets an initialization parameter indicating that Duke is awake:

```
@WebFilter(filterName = "TimeOfDayFilter",
urlPatterns = {"/*"},
initParams = {
    @WebInitParam(name = "mood", value = "awake")})
public class TimeOfDayFilter implements Filter {
    ...
```

The filter calls the doFilter method, which contains a switch statement that sets Duke's mood based on the current time.

SimpleServletListener logs changes in the servlet's lifecycle. The log entries appear in the server log.

Building, Packaging, Deploying, and Running the mood Example

You can use either NetBeans IDE or Ant to build, package, deploy, and run the mood example.

▼ To Build, Package, Deploy, and Run the mood Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install/examples/web/
3. **Select the mood folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the mood project and select Build.**
7. **Right-click the project and select Deploy.**
8. **In a web browser, open the URL `http://localhost:8080/mood/report`.**
   The URL specifies the context root, followed by the URL pattern specified for the servlet.

   A web page appears with the title "Servlet MoodServlet at /mood" a text string describing Duke's mood, and an illustrative graphic.

▼ To Build, Package, Deploy, and Run the mood Example Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/web/mood/
2. **Type the following command:**
   ```
   ant
   ```
   This target builds the WAR file and copies it to the *tut-install*/examples/web/mood/dist/ directory.
3. **Type `ant deploy`.**
   Ignore the URL shown in the deploy target output.

4. **In a web browser, open the URL `http://localhost:8080/mood/report`.**

   The URL specifies the context root, followed by the URL pattern.

   A web page appears with the title "Servlet MoodServlet at /mood" a text string describing Duke's mood, and an illustrative graphic.

Further Information about Java Servlet Technology

For more information on Java Servlet technology, see

- Java Servlet 3.0 specification:

  `http://jcp.org/en/jsr/detail?id=315`

- Java Servlet web site:

  `http://www.oracle.com/technetwork/java/index-jsp-135475.html`

◆ ◆ ◆ CHAPTER 16

Internationalizing and Localizing Web Applications

The process of preparing an application to support more than one language and data format is called *internationalization*. *Localization* is the process of adapting an internationalized application to support a specific region or locale. Examples of locale-dependent information include messages and user interface labels, character sets and encoding, and date and currency formats. Although all client user interfaces should be internationalized and localized, it is particularly important for web applications because of the global nature of the web.

The following topics are addressed here:

Java Platform Localization Classes

In the Java platform, java.util.Locale (`http://download.oracle.com/javase/6/docs/api/java/util/Locale.html`) represents a specific geographical, political, or cultural region. The string representation of a locale consists of the international standard two-character abbreviation for language and country and an optional variant, all separated by underscore (_) characters. Examples of locale strings include `fr` (French), `de_CH` (Swiss German), and `en_US_POSIX` (English on a POSIX-compliant platform).

Locale-sensitive data is stored in a java.util.ResourceBundle (`http://download.oracle.com/javase/6/docs/api/java/util/ResourceBundle.html`). A resource bundle contains key-value pairs, where the keys uniquely identify a locale-specific object in the bundle. A resource bundle can be backed by a text file (properties resource bundle) or a class (list resource bundle) containing the pairs. You construct resource bundle instance by appending a locale string representation to a base name.

The Duke's Tutoring application contains resource bundles with the base name `messages.properties` for the locales `pt` (Portuguese), `de` (German),`es` (Spanish), and `zh` (Chinese). The default locale, `en` (English), which is specified in the `faces-config.xml` file, uses the resource bundle with the base name, `messages.properties`.

For more details on internationalization and localization in the Java platform, see (`http://download.oracle.com/javase/tutorial/i18n/index.html`).

Providing Localized Messages and Labels

Messages and labels should be tailored according to the conventions of a user's language and region. There are two approaches to providing localized messages and labels in a web application:

- Provide a version of the web page in each of the target locales and have a controller servlet dispatch the request to the appropriate page depending on the requested locale. This approach is useful if large amounts of data on a page or an entire web application need to be internationalized.
- Isolate any locale-sensitive data on a page into resource bundles, and access the data so that the corresponding translated message is fetched automatically and inserted into the page. Thus, instead of creating strings directly in your code, you create a resource bundle that contains translations and read the translations from that bundle using the corresponding key.

The Duke's Tutoring application follows the second approach. Here are a few lines from the default resource bundle `messages.properties`:

```
nav.main=Main page
nav.status=View status
nav.current_session=View current tutoring session
nav.park=View students at the park
nav.admin=Administration

admin.nav.main=Administration main page
admin.nav.create_student=Create new student
admin.nav.edit_student=Edit student
admin.nav.create_guardian=Create new guardian
admin.nav.edit_guardian=Edit guardian
admin.nav.create_address=Create new address
admin.nav.edit_address=Edit address
admin.nav.activate_student=Activate student
```

Establishing the Locale

To get the correct strings for a given user, a web application either retrieves the locale (set by a browser language preference) from the request using the `getLocale` method, or allows the user to explicitly select the locale.

A component can explicitly set the locale by using the `fmt:setLocale` tag.

The `locale-config` element in the configuration file registers the default locale and also registers other supported locales. This element in Duke's Tutoring registers English as the default locale and indicates that German, Spanish, Portuguese, and Chinese are supported locales.

```
<locale-config>
    <default-locale>en</default-locale>
    <supported-locale>de</supported-locale>
    <supported-locale>es</supported-locale>
    <supported-locale>pt</supported-locale>
    <supported-locale>zh</supported-locale>
</locale-config>
```

The Status Manager in the Duke's Tutoring application uses the `getLocale` method to retrieve the locale and a `toString` method to return a localized translation of a student's status based on the locale.

```
public class StatusManager {

    private FacesContext ctx = FacesContext.getCurrentInstance();
    private Locale locale;

    /** Creates a new instance of StatusManager */
    public StatusManager() {
        locale = ctx.getViewRoot().getLocale();
    }

    public String getLocalizedStatus(StatusType status) {
        return status.toString(locale);
    }

}
```

Setting the Resource Bundle

The resource bundle is set with the `resource-bundle` element in the configuration file. The setting for Duke's Tutoring looks like this:

```
<resource-bundle>
    <base-name>dukestutoring.web.messages.Messages</base-name>
    <var>bundle</var>
</resource-bundle>
```

After the locale is set, the controller of a web application could retrieve the resource bundle for that locale and save it as a session attribute (see "Associating Objects with a Session" on page 318) for use by other components or simply be used to return a text string appropriate for the selected locale:

```
public String toString(Locale locale) {
    ResourceBundle res =
        ResourceBundle.getBundle("dukestutoring.web.messages.Messages", locale);
    return res.getString(name() + ".string");
}
```

Alternatively, an application could use the `f:loadBundle` tag to set the resource bundle. This tag loads the correct resource bundle according to the locale stored in `FacesContext`.

```
<f:loadBundle basename="dukestutoring.web.messages.Messages"
    var="bundle"/>
```

Resource bundles containing messages that are explicitly referenced from a JavaServer Faces tag attribute using a value expression must be registered using the `resource-bundle` element of the configuration file.

For more information on using this element, see "Registering Custom Localized Static Text" on page 237.

Retrieving Localized Messages

A web component written in the Java programming language retrieves the resource bundle from the session:

```
ResourceBundle messages = (ResourceBundle)session.getAttribute("messages");
```

Then it looks up the string associated with the key `person.lastName` as follows:

```
messages.getString("person.lastName");
```

You can only use a `message` or `messages` tag to display messages that are queued onto a component as a result of a converter or validator being registered on the component. The following example shows a `message` tag that displays the error message queued on the `userNo` input component if the validator registered on the component fails to validate the value the user enters into the component.

```
<h:inputText id="userNo" value="#{UserNumberBean.userNumber}">
    <f:validateLongRange minimum="0" maximum="10" />
     ...
<h:message
     style="color: red;
     text-decoration: overline" id="errors1" for="userNo"/>
```

For more information on using the `message` or `messages` tags, see "Displaying Error Messages with the `h:message` and `h:messages` Tags" on page 163.

Messages that are not queued on a component and are therefore not loaded automatically are referenced using a value expression. You can reference a localized message from almost any JavaServer Faces tag attribute.

The value expression that references a message has the same notation whether you loaded the resource bundle with the `loadBundle` tag or registered it with the `resource-bundle` element in the configuration file.

The value expression notation is `var.message`, in which `var` matches the `var` attribute of the `loadBundle` tag or the `var` element defined in the `resource-bundle` element of the configuration file, and `message` matches the key of the message contained in the resource bundle, referred to by the `var` attribute.

Here is an example from `editAddress.xhtml` in Duke's Tutoring:

```
<h:outputLabel for="country" value="#{bundle['address.country']}:" />
```

Notice that `bundle` matches the `var` element from the configuration file and that `country` matches the key in the resource bundle.

For information on using localized messages in JavaServer Faces applications, see "Displaying Components for Selecting Multiple Values" on page 157.

Date and Number Formatting

Java programs use the `DateFormat.getDateInstance(int, locale)` to parse and format dates in a locale-sensitive manner. Java programs use the `NumberFormat.get`*XXX*`Instance(locale)` method, where *XXX* can be `Currency`, `Number`, or `Percent`, to parse and format numerical values in a locale-sensitive manner.

An application can use date/time and number converters to format dates and numbers in a locale-sensitive manner. For example, a shipping date could be converted as follows:

```
<h:outputText value="#{cashier.shipDate}">
    <f:convertDateTime dateStyle="full"/>
</h:outputText>
```

For information on JavaServer Faces converters, see "Using the Standard Converters" on page 171.

Character Sets and Encodings

The following sections describe character sets and character encodings.

Character Sets

A *character set* is a set of textual and graphic symbols, each of which is mapped to a set of nonnegative integers.

The first character set used in computing was US-ASCII. It is limited in that it can represent only American English. US-ASCII contains uppercase and lowercase Latin alphabets, numerals, punctuation, a set of control codes, and a few miscellaneous symbols.

Unicode defines a standardized, universal character set that can be extended to accommodate additions. When the Java program source file encoding doesn't support Unicode, you can represent Unicode characters as escape sequences by using the notation `\u`*XXXX*, where *XXXX* is the character's 16-bit representation in hexadecimal. For example, the Spanish version of the Duke's Tutoring message file uses Unicode for non-ASCII characters:

```
nav.main=P\u00e1gina Principal
nav.status=Mirar el estado
nav.current_session=Ver sesi\u00f3n actual del tutorial
nav.park=Ver estudiantes en el Parque
nav.admin=Administraci\u00f3n

admin.nav.main=P\u00e1gina principal de administraci\u00f3n
admin.nav.create_student=Crear un nuevo estudiante
admin.nav.edit_student=Editar informaci\u00f3n del estudiante
admin.nav.create_guardian=Crear un nuevo guardia
admin.nav.edit_guardian=Editar guardia
admin.nav.create_address=Crear una nueva direcci\u00f3n
admin.nav.edit_address=Editar direcci\u00f3n
admin.nav.activate_student=Activar estudiante
```

Character Encoding

A *character encoding* maps a character set to units of a specific width and defines byte serialization and ordering rules. Many character sets have more than one encoding. For example, Java programs can represent Japanese character sets using the `EUC-JP` or `Shift-JIS` encodings, among others. Each encoding has rules for representing and serializing a character set.

The ISO 8859 series defines 13 character encodings that can represent texts in dozens of languages. Each ISO 8859 character encoding can have up to 256 characters. ISO-8859-1 (Latin-1) comprises the ASCII character set, characters with diacritics (accents, diaereses, cedillas, circumflexes, and so on), and additional symbols.

UTF-8 (Unicode Transformation Format, 8-bit form) is a variable-width character encoding that encodes 16-bit Unicode characters as one to four bytes. A byte in UTF-8 is equivalent to 7-bit ASCII if its high-order bit is zero; otherwise, the character comprises a variable number of bytes.

UTF-8 is compatible with the majority of existing web content and provides access to the Unicode character set. Current versions of browsers and email clients support UTF-8. In addition, many new web standards specify UTF-8 as their character encoding. For example, UTF-8 is one of the two required encodings for XML documents (the other is UTF-16).

Web components usually use `PrintWriter` to produce responses; `PrintWriter` automatically encodes using ISO-8859-1. Servlets can also output binary data using `OutputStream` classes, which perform no encoding. An application that uses a character set that cannot use the default encoding must explicitly set a different encoding.

PART III

Web Services

Part III explores web services. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 17

Introduction to Web Services

Part III of the tutorial discusses Java EE 6 web services technologies. For this book, these technologies include Java API for XML Web Services (JAX-WS) and Java API for RESTful Web Services (JAX-RS).

The following topics are addressed here:

What Are Web Services?

Web services are client and server applications that communicate over the World Wide Web's (WWW) HyperText Transfer Protocol (HTTP). As described by the World Wide Web Consortium (W3C), web services provide a standard means of interoperating between software applications running on a variety of platforms and frameworks. Web services are characterized by their great interoperability and extensibility, as well as their machine-processable descriptions, thanks to the use of XML. Web services can be combined in a loosely coupled way to achieve complex operations. Programs providing simple services can interact with each other to deliver sophisticated added-value services.

Types of Web Services

On the conceptual level, a service is a software component provided through a network-accessible endpoint. The service consumer and provider use messages to exchange invocation request and response information in the form of self-containing documents that make very few assumptions about the technological capabilities of the receiver.

On a technical level, web services can be implemented in various ways. The two types of web services discussed in this section can be distinguished as "big" web services and "RESTful" web services.

"Big" Web Services

In Java EE 6, JAX-WS provides the functionality for "big" web services, which are described in Chapter 18, "Building Web Services with JAX-WS." Big web services use XML messages that follow the Simple Object Access Protocol (SOAP) standard, an XML language defining a message architecture and message formats. Such systems often contain a machine-readable description of the operations offered by the service, written in the Web Services Description Language (WSDL), an XML language for defining interfaces syntactically.

The SOAP message format and the WSDL interface definition language have gained widespread adoption. Many development tools, such as NetBeans IDE, can reduce the complexity of developing web service applications.

A SOAP-based design must include the following elements.

- A formal contract must be established to describe the interface that the web service offers. WSDL can be used to describe the details of the contract, which may include messages, operations, bindings, and the location of the web service. You may also process SOAP messages in a JAX-WS service without publishing a WSDL.
- The architecture must address complex nonfunctional requirements. Many web service specifications address such requirements and establish a common vocabulary for them. Examples include transactions, security, addressing, trust, coordination, and so on.
- The architecture needs to handle asynchronous processing and invocation. In such cases, the infrastructure provided by standards, such as Web Services Reliable Messaging (WSRM), and APIs, such as JAX-WS, with their client-side asynchronous invocation support, can be leveraged out of the box.

RESTful Web Services

In Java EE 6, JAX-RS provides the functionality for Representational State Transfer (RESTful) web services. REST is well suited for basic, ad hoc integration scenarios. RESTful web services, often better integrated with HTTP than SOAP-based services are, do not require XML messages or WSDL service–API definitions.

Project Jersey is the production-ready reference implementation for the JAX-RS specification. Jersey implements support for the annotations defined in the JAX-RS specification, making it easy for developers to build RESTful web services with Java and the Java Virtual Machine (JVM).

Because RESTful web services use existing well-known W3C and Internet Engineering Task Force (IETF) standards (HTTP, XML, URI, MIME) and have a lightweight infrastructure that allows services to be built with minimal tooling, developing RESTful web services is inexpensive and thus has a very low barrier for adoption. You can use a development tool such as NetBeans IDE to further reduce the complexity of developing RESTful web services.

A RESTful design may be appropriate when the following conditions are met.

- The web services are completely stateless. A good test is to consider whether the interaction can survive a restart of the server.
- A caching infrastructure can be leveraged for performance. If the data that the web service returns is not dynamically generated and can be cached, the caching infrastructure that web servers and other intermediaries inherently provide can be leveraged to improve performance. However, the developer must take care because such caches are limited to the HTTP `GET` method for most servers.
- The service producer and service consumer have a mutual understanding of the context and content being passed along. Because there is no formal way to describe the web services interface, both parties must agree out of band on the schemas that describe the data being exchanged and on ways to process it meaningfully. In the real world, most commercial applications that expose services as RESTful implementations also distribute so-called value-added toolkits that describe the interfaces to developers in popular programming languages.
- Bandwidth is particularly important and needs to be limited. REST is particularly useful for limited-profile devices, such as PDAs and mobile phones, for which the overhead of headers and additional layers of SOAP elements on the XML payload must be restricted.
- Web service delivery or aggregation into existing web sites can be enabled easily with a RESTful style. Developers can use such technologies as JAX-RS and Asynchronous JavaScript with XML (AJAX) and such toolkits as Direct Web Remoting (DWR) to consume the services in their web applications. Rather than starting from scratch, services can be exposed with XML and consumed by HTML pages without significantly refactoring the existing web site architecture. Existing developers will be more productive because they are adding to something they are already familiar with rather than having to start from scratch with new technology.

RESTful web services are discussed in Chapter 19, "Building RESTful Web Services with JAX-RS." This chapter contains information about generating the skeleton of a RESTful web service using both NetBeans IDE and the Maven project management tool.

Deciding Which Type of Web Service to Use

Basically, you would want to use RESTful web services for integration over the web and use big web services in enterprise application integration scenarios that have advanced quality of service (QoS) requirements.

- **JAX-WS**: addresses advanced QoS requirements commonly occurring in enterprise computing. When compared to JAX-RS, JAX-WS makes it easier to support the WS-* set of protocols, which provide standards for security and reliability, among other things, and interoperate with other WS-* conforming clients and servers.
- **JAX-RS**: makes it easier to write web applications that apply some or all of the constraints of the REST style to induce desirable properties in the application, such as loose coupling (evolving the server is easier without breaking existing clients), scalability (start small and grow), and architectural simplicity (use off-the-shelf components, such as proxies or HTTP routers). You would choose to use JAX-RS for your web application because it is easier for many types of clients to consume RESTful web services while enabling the server side to evolve and scale. Clients can choose to consume some or all aspects of the service and mash it up with other web-based services.

Note – For an article that provides more in-depth analysis of this issue, see "RESTful Web Services vs. "Big" Web Services: Making the Right Architectural Decision," by Cesare Pautasso, Olaf Zimmermann, and Frank Leymann from *WWW '08: Proceedings of the 17th International Conference on the World Wide Web* (2008), pp. 805–814 (`http://www2008.org/papers/pdf/p805-pautassoA.pdf`).

◆ ◆ ◆ CHAPTER 18

Building Web Services with JAX-WS

Java API for XML Web Services (JAX-WS) is a technology for building web services and clients that communicate using XML. JAX-WS allows developers to write message-oriented as well as Remote Procedure Call-oriented (RPC-oriented) web services.

In JAX-WS, a web service operation invocation is represented by an XML-based protocol, such as SOAP. The SOAP specification defines the envelope structure, encoding rules, and conventions for representing web service invocations and responses. These calls and responses are transmitted as SOAP messages (XML files) over HTTP.

Although SOAP messages are complex, the JAX-WS API hides this complexity from the application developer. On the server side, the developer specifies the web service operations by defining methods in an interface written in the Java programming language. The developer also codes one or more classes that implement those methods. Client programs are also easy to code. A client creates a proxy (a local object representing the service) and then simply invokes methods on the proxy. With JAX-WS, the developer does not generate or parse SOAP messages. It is the JAX-WS runtime system that converts the API calls and responses to and from SOAP messages.

With JAX-WS, clients and web services have a big advantage: the platform independence of the Java programming language. In addition, JAX-WS is not restrictive: A JAX-WS client can access a web service that is not running on the Java platform, and vice versa. This flexibility is possible because JAX-WS uses technologies defined by the W3C: HTTP, SOAP, and WSDL. WSDL specifies an XML format for describing a service as a set of endpoints operating on messages.

Note – Several files in the JAX-WS examples depend on the port that you specified when you installed the GlassFish Server. These tutorial examples assume that the server runs on the default port, 8080. They do not run with a nondefault port setting.

The following topics are addressed here:

Creating a Simple Web Service and Clients with JAX-WS

This section shows how to build and deploy a simple web service and two clients: an application client and a web client. The source code for the service is in the directory *tut-install*`/examples/jaxws/helloservice/`, and the clients are in the directories *tut-install*`/examples/jaxws/appclient/` and *tut-install*`/examples/jaxws/webclient/`.

Figure 18–1 illustrates how JAX-WS technology manages communication between a web service and a client.

FIGURE 18–1 Communication between a JAX-WS Web Service and a Client

The starting point for developing a JAX-WS web service is a Java class annotated with the `javax.jws.WebService` annotation. The `@WebService` annotation defines the class as a web service endpoint.

A *service endpoint interface* or *service endpoint implementation* (SEI) is a Java interface or class, respectively, that declares the methods that a client can invoke on the service. An interface is not required when building a JAX-WS endpoint. The web service implementation class implicitly defines an SEI.

You may specify an explicit interface by adding the `endpointInterface` element to the `@WebService` annotation in the implementation class. You must then provide an interface that defines the public methods made available in the endpoint implementation class.

The basic steps for creating a web service and client are as follows:

1. Code the implementation class.
2. Compile the implementation class.
3. Package the files into a WAR file.

4. Deploy the WAR file. The web service artifacts, which are used to communicate with clients, are generated by the GlassFish Server during deployment.
5. Code the client class.
6. Use a `wsimport` Ant task to generate and compile the web service artifacts needed to connect to the service.
7. Compile the client class.
8. Run the client.

If you use NetBeans IDE to create a service and client, the IDE performs the `wsimport` task for you.

The sections that follow cover these steps in greater detail.

Requirements of a JAX-WS Endpoint

JAX-WS endpoints must follow these requirements.

- The implementing class must be annotated with either the `javax.jws.WebService` or the `javax.jws.WebServiceProvider` annotation.
- The implementing class may explicitly reference an SEI through the `endpointInterface` element of the `@WebService` annotation but is not required to do so. If no `endpointInterface` is specified in `@WebService`, an SEI is implicitly defined for the implementing class.
- The business methods of the implementing class must be public and must not be declared `static` or `final`.
- Business methods that are exposed to web service clients must be annotated with `javax.jws.WebMethod`.
- Business methods that are exposed to web service clients must have JAXB-compatible parameters and return types. See the list of JAXB default data type bindings at `http://download.oracle.com/javaee/5/tutorial/doc/bnazq.html#bnazs`.
- The implementing class must not be declared `final` and must not be `abstract`.
- The implementing class must have a default public constructor.
- The implementing class must not define the `finalize` method.
- The implementing class may use the `javax.annotation.PostConstruct` or the `javax.annotation.PreDestroy` annotations on its methods for lifecycle event callbacks.

  The `@PostConstruct` method is called by the container before the implementing class begins responding to web service clients.

  The `@PreDestroy` method is called by the container before the endpoint is removed from operation.

Coding the Service Endpoint Implementation Class

In this example, the implementation class, `Hello`, is annotated as a web service endpoint using the `@WebService` annotation. `Hello` declares a single method named `sayHello`, annotated with the `@WebMethod` annotation, which exposes the annotated method to web service clients. The `sayHello` method returns a greeting to the client, using the name passed to it to compose the greeting. The implementation class also must define a default, public, no-argument constructor.

```
package helloservice.endpoint;

import javax.jws.WebService;
import javax.jws.webMethod;

@WebService
public class Hello {
    private String message = new String("Hello, ");

    public void Hello() {
    }

    @WebMethod
    public String sayHello(String name) {
        return message + name + ".";
    }
}
```

Building, Packaging, and Deploying the Service

You can build, package, and deploy the `helloservice` application by using either NetBeans IDE or Ant.

▼ To Build, Package, and Deploy the Service Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/jaxws/`
3. **Select the `helloservice` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**

6. **In the Projects tab, right-click the `helloservice` project and select Deploy.**

   This command builds and packages the application into `helloservice.war`, located in *tut-install*`/examples/jaxws/helloservice/dist/`, and deploys this WAR file to the GlassFish Server.

Next Steps You can view the WSDL file of the deployed service by requesting the URL `http://localhost:8080/helloservice/HelloService?wsdl` in a web browser. Now you are ready to create a client that accesses this service.

▼ To Build, Package, and Deploy the Service Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/jaxws/helloservice/`

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `helloservice.war`, located in the `dist` directory.

3. **Make sure that the GlassFish Server is started.**

4. **Type the following:**

   ```
   ant deploy
   ```

Next Steps You can view the WSDL file of the deployed service by requesting the URL `http://localhost:8080/helloservice/HelloService?wsdl` in a web browser. Now you are ready to create a client that accesses this service.

Testing the Methods of a Web Service Endpoint

GlassFish Server allows you to test the methods of a web service endpoint.

▼ To Test the Service without a Client

To test the `sayHello` method of `HelloService`, follow these steps.

1. **Open the web service test interface by typing the following URL in a web browser:**

   `http://localhost:8080/helloservice/HelloService?Tester`

2. **Under Methods, type a name as the parameter to the `sayHello` method.**

3 **Click the `sayHello` button.**

This takes you to the `sayHello` Method invocation page.

Under Method returned, you'll see the response from the endpoint.

A Simple JAX-WS Application Client

The `HelloAppClient` class is a stand-alone application client that accesses the `sayHello` method of `HelloService`. This call is made through a port, a local object that acts as a proxy for the remote service. The port is created at development time by the `wsimport` task, which generates JAX-WS portable artifacts based on a WSDL file.

Coding the Application Client

When invoking the remote methods on the port, the client performs these steps:

1. Uses the generated `helloservice.endpoint.HelloService` class, which represents the service at the URI of the deployed service's WSDL file:

```
import helloservice.endpoint.HelloService;
import javax.xml.ws.WebServiceRef;

public class HelloAppClient {
    @WebServiceRef(wsdlLocation =
      "META-INF/wsdl/localhost_8080/helloservice/HelloService.wsdl")
    private static HelloService service;
```

2. Retrieves a proxy to the service, also known as a port, by invoking `getHelloPort` on the service:

```
helloservice.endpoint.Hello port = service.getHelloPort();
```

   The port implements the SEI defined by the service.

3. Invokes the port's `sayHello` method, passing a string to the service:

```
return port.sayHello(arg0);
```

Here is the full source of `HelloAppClient`, which is located in the following directory:

tut-install`/examples/jaxws/appclient/src/appclient/`

```
package appclient;

import helloservice.endpoint.HelloService;
import javax.xml.ws.WebServiceRef;

public class HelloAppClient {
    @WebServiceRef(wsdlLocation =
      "META-INF/wsdl/localhost_8080/helloservice/HelloService.wsdl")
    private static HelloService service;
```

```
    /**
     * @param args the command line arguments
     */
    public static void main(String[] args) {
       System.out.println(sayHello("world"));
    }

    private static String sayHello(java.lang.String arg0) {
        helloservice.endpoint.Hello port = service.getHelloPort();
        return port.sayHello(arg0);
    }
}
```

Building, Packaging, Deploying, and Running the Application Client

You can build, package, deploy, and run the `appclient` application by using either NetBeans IDE or Ant. To build the client, you must first have deployed `helloservice`, as described in "Building, Packaging, and Deploying the Service" on page 342.

▼ To Build, Package, Deploy, and Run the Application Client Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/jaxws/`
3. **Select the `appclient` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `appclient` project and select Run.**

   You will see the output of the application client in the Output pane.

▼ To Build, Package, Deploy, and Run the Application Client Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/jaxws/appclient/`
2. **Type the following command:**

   `ant`

   This command calls the `default` target, which runs the `wsimport` task and builds and packages the application into a JAR file, `appclient.jar`, located in the `dist` directory.

3 **Type the following command:**

```
ant getclient
```

This command deploys the `appclient.jar` file and retrieves the client stubs.

4 **To run the client, type the following command:**

```
ant run
```

A Simple JAX-WS Web Client

`HelloServlet` is a servlet that, like the Java client, calls the `sayHello` method of the web service. Like the application client, it makes this call through a port.

Coding the Servlet

To invoke the method on the port, the client performs these steps:

1. Imports the `HelloService` endpoint and the `WebServiceRef` annotation:

```
import helloservice.endpoint.HelloService;
...
import javax.xml.ws.WebServiceRef;
```

2. Defines a reference to the web service by specifying the WSDL location:

```
@WebServiceRef(wsdlLocation =
  "WEB-INF/wsdl/localhost_8080/helloservice/HelloService.wsdl")
```

3. Declares the web service, then defines a private method that calls the `sayHello` method on the port:

```
private HelloService service;
...
private String sayHello(java.lang.String arg0) {
    helloservice.endpoint.Hello port = service.getHelloPort();
    return port.sayHello(arg0);
}
```

4. In the servlet, calls this private method:

```
out.println("<p>" + sayHello("world") + "</p>");
```

The significant parts of the `HelloServlet` code follow. The code is located in the *tut-install*`/examples/jaxws/src/java/webclient` directory.

```
package webclient;

import helloservice.endpoint.HelloService;
import java.io.IOException;
import java.io.PrintWriter;
import javax.servlet.ServletException;
import javax.servlet.annotation.WebServlet;
import javax.servlet.http.HttpServlet;
import javax.servlet.http.HttpServletRequest;
```

```
import javax.servlet.http.HttpServletResponse;
import javax.xml.ws.WebServiceRef;

@WebServlet(name="HelloServlet", urlPatterns={"/HelloServlet"})
public class HelloServlet extends HttpServlet {
    @WebServiceRef(wsdlLocation =
      "WEB-INF/wsdl/localhost_8080/helloservice/HelloService.wsdl")
    private HelloService service;

    /**
     * Processes requests for both HTTP <code>GET</code>
     *   and <code>POST</code> methods.
     * @param request servlet request
     * @param response servlet response
     * @throws ServletException if a servlet-specific error occurs
     * @throws IOException if an I/O error occurs
     */
    protected void processRequest(HttpServletRequest request,
            HttpServletResponse response)
    throws ServletException, IOException {
        response.setContentType("text/html;charset=UTF-8");
        PrintWriter out = response.getWriter();
        try {

            out.println("<html>");
            out.println("<head>");
            out.println("<title>Servlet HelloServlet</title>");
            out.println("</head>");
            out.println("<body>");
            out.println("<h1>Servlet HelloServlet at " +
                request.getContextPath () + "</h1>");
            out.println("<p>" + sayHello("world") + "</p>");
            out.println("</body>");
            out.println("</html>");

        } finally {
            out.close();
        }
    }

    // doGet and doPost methods, which call processRequest, and
    //   getServletInfo method

    private String sayHello(java.lang.String arg0) {
        helloservice.endpoint.Hello port = service.getHelloPort();
        return port.sayHello(arg0);
    }
}
```

Building, Packaging, Deploying, and Running the Web Client

You can build, package, deploy, and run the `webclient` application by using either NetBeans IDE or Ant. To build the client, you must first have deployed `helloservice`, as described in "Building, Packaging, and Deploying the Service" on page 342.

▼ To Build, Package, Deploy, and Run the Web Client Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/jaxws/`
3. **Select the `webclient` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `webclient` project and select Deploy.**
   This task runs the `wsimport` tasks, builds and packages the application into a WAR file, `webclient.war`, located in the `dist` directory, and deploys it to the server.
7. **In a web browser, navigate to the following URL:**
   `http://localhost:8080/webclient/HelloServlet`
   The output of the `sayHello` method appears in the window.

▼ To Build, Package, Deploy, and Run the Web Client Using Ant

1. **In a terminal window, go to:**
   tut-install`/examples/jaxws/webclient/`
2. **Type the following command:**
   ```
   ant
   ```
   This command calls the `default` target, which runs the `wsimport` tasks, then builds and packages the application into a WAR file, `webclient.war`, located in the `dist` directory.
3. **Type the following command:**
   ```
   ant deploy
   ```
   This task deploys the WAR file to the server.
4. **In a web browser, navigate to the following URL:**
   `http://localhost:8080/webclient/HelloServlet`
   The output of the `sayHello` method appears in the window.

Types Supported by JAX-WS

JAX-WS delegates the mapping of Java programming language types to and from XML definitions to JAXB. Application developers don't need to know the details of these mappings but should be aware that not every class in the Java language can be used as a method parameter or return type in JAX-WS.

The following sections explain the default schema-to-Java and Java-to-schema data type bindings.

Schema-to-Java Mapping

The Java language provides a richer set of data type than XML schema. Table 18–1 lists the mapping of XML data types to Java data types in JAXB.

TABLE 18–1 JAXB Mapping of XML Schema Built-in Data Types

XML Schema Type	Java Data Type
xsd:string	java.lang.String
xsd:integer	java.math.BigInteger
xsd:int	int
xsd.long	long
xsd:short	short
xsd:decimal	java.math.BigDecimal
xsd:float	float
xsd:double	double
xsd:boolean	boolean
xsd:byte	byte
xsd:QName	javax.xml.namespace.QName
xsd:dateTime	javax.xml.datatype.XMLGregorianCalendar
xsd:base64Binary	byte[]
xsd:hexBinary	byte[]
xsd:unsignedInt	long
xsd:unsignedShort	int
xsd:unsignedByte	short

TABLE 18–1 JAXB Mapping of XML Schema Built-in Data Types *(Continued)*

XML Schema Type	Java Data Type
xsd:time	javax.xml.datatype.XMLGregorianCalendar
xsd:date	javax.xml.datatype.XMLGregorianCalendar
xsd:g	javax.xml.datatype.XMLGregorianCalendar
xsd:anySimpleType	java.lang.Object
xsd:anySimpleType	java.lang.String
xsd:duration	javax.xml.datatype.Duration
xsd:NOTATION	javax.xml.namespace.QName

Java-to-Schema Mapping

Table 18–2 shows the default mapping of Java classes to XML data types.

TABLE 18–2 JAXB Mapping of XML Data Types to Java Classes

Java Class	XML Data Type
java.lang.String	xs:string
java.math.BigInteger	xs:integer
java.math.BigDecimal	xs:decimal
java.util.Calendar	xs:dateTime
java.util.Date	xs:dateTime
javax.xml.namespace.QName	xs:QName
java.net.URI	xs:string
javax.xml.datatype.XMLGregorianCalendar	xs:anySimpleType
javax.xml.datatype.Duration	xs:duration
java.lang.Object	xs:anyType
java.awt.Image	xs:base64Binary
javax.activation.DataHandler	xs:base64Binary
javax.xml.transform.Source	xs:base64Binary
java.util.UUID	xs:string

Web Services Interoperability and JAX-WS

JAX-WS supports the Web Services Interoperability (WS-I) Basic Profile Version 1.1. The WS-I Basic Profile is a document that clarifies the SOAP 1.1 and WSDL 1.1 specifications to promote SOAP interoperability. For links related to WS-I, see "Further Information about JAX-WS" on page 351.

To support WS-I Basic Profile Version 1.1, the JAX-WS runtime supports doc/literal and rpc/literal encodings for services, static ports, dynamic proxies, and the Dynamic Invocation Interface (DII).

Further Information about JAX-WS

For more information about JAX-WS and related technologies, see

- Java API for XML Web Services 2.2 specification:

  `http://jax-ws.java.net/spec-download.html`
- JAX-WS home:

  `http://jax-ws.java.net/`
- Simple Object Access Protocol (SOAP) 1.2 W3C Note:

  `http://www.w3.org/TR/soap/`
- Web Services Description Language (WSDL) 1.1 W3C Note:

  `http://www.w3.org/TR/wsdl`
- WS-I Basic Profile 1.1:

  `http://www.ws-i.org`

◆ ◆ ◆ CHAPTER 19

Building RESTful Web Services with JAX-RS

This chapter describes the REST architecture, RESTful web services, and the Java API for RESTful Web Services (JAX-RS, defined in JSR 311).

Jersey, the reference implementation of JAX-RS, implements support for the annotations defined in JSR 311, making it easy for developers to build RESTful web services by using the Java programming language.

If you are developing with GlassFish Server, you can install the Jersey samples and documentation by using the Update Tool. Instructions for using the Update Tool can be found in "Java EE 6 Tutorial Component" on page 68. The Jersey samples and documentation are provided in the Available Add-ons area of the Update Tool.

The following topics are addressed here:

What Are RESTful Web Services?

RESTful web services are built to work best on the Web. Representational State Transfer (REST) is an architectural style that specifies constraints, such as the uniform interface, that if applied to a web service induce desirable properties, such as performance, scalability, and modifiability, that enable services to work best on the Web. In the REST architectural style, data and functionality are considered resources and are accessed using *Uniform Resource Identifiers (URIs)*, typically links on the Web. The resources are acted upon by using a set of simple, well-defined operations. The REST architectural style constrains an architecture to a client/server architecture and is designed to use a stateless communication protocol, typically HTTP. In the REST architecture style, clients and servers exchange representations of resources by using a standardized interface and protocol.

The following principles encourage RESTful applications to be simple, lightweight, and fast:

- **Resource identification through URI**: A RESTful web service exposes a set of resources that identify the targets of the interaction with its clients. Resources are identified by URIs, which provide a global addressing space for resource and service discovery. See "The `@Path` Annotation and URI Path Templates" on page 357 for more information.
- **Uniform interface**: Resources are manipulated using a fixed set of four create, read, update, delete operations: `PUT`, `GET`, `POST`, and `DELETE`. `PUT` creates a new resource, which can be then deleted by using `DELETE`. `GET` retrieves the current state of a resource in some representation. `POST` transfers a new state onto a resource. See "Responding to HTTP Resources" on page 359 for more information.
- **Self-descriptive messages**: Resources are decoupled from their representation so that their content can be accessed in a variety of formats, such as HTML, XML, plain text, PDF, JPEG, JSON, and others. Metadata about the resource is available and used, for example, to control caching, detect transmission errors, negotiate the appropriate representation format, and perform authentication or access control. See "Responding to HTTP Resources" on page 359 and "Using Entity Providers to Map HTTP Response and Request Entity Bodies" on page 361 for more information.
- **Stateful interactions through hyperlinks**: Every interaction with a resource is stateless; that is, request messages are self-contained. Stateful interactions are based on the concept of explicit state transfer. Several techniques exist to exchange state, such as URI rewriting, cookies, and hidden form fields. State can be embedded in response messages to point to valid future states of the interaction. See "Using Entity Providers to Map HTTP Response and Request Entity Bodies" on page 361 and "Building URIs" in the JAX-RS Overview document for more information.

Creating a RESTful Root Resource Class

Root resource classes are POJOs that are either annotated with `@Path` or have at least one method annotated with `@Path` or a *request method designator*, such as `@GET`, `@PUT`, `@POST`, or `@DELETE`. *Resource methods* are methods of a resource class annotated with a request method designator. This section explains how to use JAX-RS to annotate Java classes to create RESTful web services.

Developing RESTful Web Services with JAX-RS

JAX-RS is a Java programming language API designed to make it easy to develop applications that use the REST architecture.

The JAX-RS API uses Java programming language annotations to simplify the development of RESTful web services. Developers decorate Java programming language class files with JAX-RS annotations to define resources and the actions that can be performed on those resources. JAX-RS annotations are runtime annotations; therefore, runtime reflection will generate the

helper classes and artifacts for the resource. A Java EE application archive containing JAX-RS resource classes will have the resources configured, the helper classes and artifacts generated, and the resource exposed to clients by deploying the archive to a Java EE server.

Table 19–1 lists some of the Java programming annotations that are defined by JAX-RS, with a brief description of how each is used. Further information on the JAX-RS APIs can be viewed at `http://download.oracle.com/javaee/6/api/`.

TABLE 19–1 Summary of JAX-RS Annotations

Annotation	Description
`@Path`	The `@Path` annotation's value is a relative URI path indicating where the Java class will be hosted: for example, `/helloworld`. You can also embed variables in the URIs to make a URI path template. For example, you could ask for the name of a user and pass it to the application as a variable in the URI: `/helloworld/{username}`.
`@GET`	The `@GET` annotation is a request method designator and corresponds to the similarly named HTTP method. The Java method annotated with this request method designator will process HTTP GET requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
`@POST`	The `@POST` annotation is a request method designator and corresponds to the similarly named HTTP method. The Java method annotated with this request method designator will process HTTP POST requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
`@PUT`	The `@PUT` annotation is a request method designator and corresponds to the similarly named HTTP method. The Java method annotated with this request method designator will process HTTP PUT requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
`@DELETE`	The `@DELETE` annotation is a request method designator and corresponds to the similarly named HTTP method. The Java method annotated with this request method designator will process HTTP DELETE requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
`@HEAD`	The `@HEAD` annotation is a request method designator and corresponds to the similarly named HTTP method. The Java method annotated with this request method designator will process HTTP HEAD requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
`@PathParam`	The `@PathParam` annotation is a type of parameter that you can extract for use in your resource class. URI path parameters are extracted from the request URI, and the parameter names correspond to the URI path template variable names specified in the `@Path` class-level annotation.
`@QueryParam`	The `@QueryParam` annotation is a type of parameter that you can extract for use in your resource class. Query parameters are extracted from the request URI query parameters.

TABLE 19–1 Summary of JAX-RS Annotations *(Continued)*

Annotation	Description
`@Consumes`	The `@Consumes` annotation is used to specify the MIME media types of representations a resource can consume that were sent by the client.
`@Produces`	The `@Produces` annotation is used to specify the MIME media types of representations a resource can produce and send back to the client: for example, `"text/plain"`.
`@Provider`	The `@Provider` annotation is used for anything that is of interest to the JAX-RS runtime, such as `MessageBodyReader` and `MessageBodyWriter`. For HTTP requests, the `MessageBodyReader` is used to map an HTTP request entity body to method parameters. On the response side, a return value is mapped to an HTTP response entity body by using a `MessageBodyWriter`. If the application needs to supply additional metadata, such as HTTP headers or a different status code, a method can return a `Response` that wraps the entity and that can be built using `Response.ResponseBuilder`.

Overview of a JAX-RS Application

The following code sample is a very simple example of a root resource class that uses JAX-RS annotations:

```
package com.sun.jersey.samples.helloworld.resources;

import javax.ws.rs.GET;
import javax.ws.rs.Produces;
import javax.ws.rs.Path;

// The Java class will be hosted at the URI path "/helloworld"
@Path("/helloworld")
public class HelloWorldResource {

    // The Java method will process HTTP GET requests
    @GET
    // The Java method will produce content identified by the MIME Media
    // type "text/plain"
    @Produces("text/plain")
    public String getClichedMessage() {
        // Return some cliched textual content
        return "Hello World";
    }
}
```

The following sections describe the annotations used in this example.

- The `@Path` annotation's value is a relative URI path. In the preceding example, the Java class will be hosted at the URI path `/helloworld`. This is an extremely simple use of the `@Path` annotation, with a static URI path. Variables can be embedded in the URIs. *URI path templates* are URIs with variables embedded within the URI syntax.
- The `@GET` annotation is a request method designator, along with `@POST`, `@PUT`, `@DELETE`, and `@HEAD`, defined by JAX-RS and corresponding to the similarly named HTTP methods. In the example, the annotated Java method will process HTTP `GET` requests. The behavior of a resource is determined by the HTTP method to which the resource is responding.
- The `@Produces` annotation is used to specify the MIME media types a resource can produce and send back to the client. In this example, the Java method will produce representations identified by the MIME media type "`text/plain`".
- The `@Consumes` annotation is used to specify the MIME media types a resource can consume that were sent by the client. The example could be modified to set the message returned by the `getClichedMessage` method, as shown in this code example:

```
@POST
@Consumes("text/plain")
public void postClichedMessage(String message) {
    // Store the message
}
```

The `@Path` Annotation and URI Path Templates

The `@Path` annotation identifies the URI path template to which the resource responds and is specified at the class or method level of a resource. The `@Path` annotation's value is a partial URI path template relative to the base URI of the server on which the resource is deployed, the context root of the application, and the URL pattern to which the JAX-RS runtime responds.

URI path templates are URIs with variables embedded within the URI syntax. These variables are substituted at runtime in order for a resource to respond to a request based on the substituted URI. Variables are denoted by braces ({ and }). For example, look at the following `@Path` annotation:

```
@Path("/users/{username}")
```

In this kind of example, a user is prompted to type his or her name, and then a JAX-RS web service configured to respond to requests to this URI path template responds. For example, if the user types the user name "Galileo," the web service responds to the following URL:

```
http://example.com/users/Galileo
```

To obtain the value of the user name, the `@PathParam` annotation may be used on the method parameter of a request method, as shown in the following code example:

```
@Path("/users/{username}")
public class UserResource {

    @GET
    @Produces("text/xml")
    public String getUser(@PathParam("username") String userName) {
        ...
    }
}
```

By default, the URI variable must match the regular expression `"[^/]+?"`. This variable may be customized by specifying a different regular expression after the variable name. For example, if a user name must consist only of lowercase and uppercase alphanumeric characters, override the default regular expression in the variable definition:

```
@Path("users/{username: [a-zA-Z][a-zA-Z_0-9]}")
```

In this example the `username` variable will match only user names that begin with one uppercase or lowercase letter and zero or more alphanumeric characters and the underscore character. If a user name does not match that template, a 404 (Not Found) response will be sent to the client.

A `@Path` value isn't required to have leading or trailing slashes (/). The JAX-RS runtime parses URI path templates the same whether or not they have leading or trailing spaces.

A URI path template has one or more variables, with each variable name surrounded by braces: `{` to begin the variable name and `}` to end it. In the preceding example, `username` is the variable name. At runtime, a resource configured to respond to the preceding URI path template will attempt to process the URI data that corresponds to the location of `{username}` in the URI as the variable data for `username`.

For example, if you want to deploy a resource that responds to the URI path template `http://example.com/myContextRoot/resources/{name1}/{name2}/`, you must deploy the application to a Java EE server that responds to requests to the `http://example.com/myContextRoot` URI and then decorate your resource with the following `@Path` annotation:

```
@Path("/{name1}/{name2}/")
public class SomeResource {
    ...
}
```

In this example, the URL pattern for the JAX-RS helper servlet, specified in `web.xml`, is the default:

```
<servlet-mapping>
      <servlet-name>My JAX-RS Resource</servlet-name>
      <url-pattern>/resources/*</url-pattern>
</servlet-mapping>
```

A variable name can be used more than once in the URI path template.

If a character in the value of a variable would conflict with the reserved characters of a URI, the conflicting character should be substituted with percent encoding. For example, spaces in the value of a variable should be substituted with `%20`.

When defining URI path templates, be careful that the resulting URI after substitution is valid.

Table 19–2 lists some examples of URI path template variables and how the URIs are resolved after substitution. The following variable names and values are used in the examples:

- `name1`: `james`
- `name2`: `gatz`
- `name3`:
- `location`: `Main%20Street`
- `question`: `why`

Note – The value of the `name3` variable is an empty string.

TABLE 19–2 Examples of URI Path Templates

URI Path Template	URI After Substitution
`http://example.com/{name1}/{name2}/`	`http://example.com/james/gatz/`
`http://example.com/{question}/{question}/{question}/`	`http://example.com/why/why/why/`
`http://example.com/maps/{location}`	`http://example.com/maps/Main%20Street`
`http://example.com/{name3}/home/`	`http://example.com//home/`

Responding to HTTP Resources

The behavior of a resource is determined by the HTTP methods (typically, `GET`, `POST`, `PUT`, `DELETE`) to which the resource is responding.

The Request Method Designator Annotations

Request method designator annotations are runtime annotations, defined by JAX-RS, that correspond to the similarly named HTTP methods. Within a resource class file, HTTP methods are mapped to Java programming language methods by using the request method designator annotations. The behavior of a resource is determined by which HTTP method the resource is responding to. JAX-RS defines a set of request method designators for the common HTTP methods `@GET`, `@POST`, `@PUT`, `@DELETE`, and `@HEAD`; you can also create your own custom request method designators. Creating custom request method designators is outside the scope of this document.

The following example, an extract from the storage service sample, shows the use of the PUT method to create or update a storage container:

```
@PUT
public Response putContainer() {
    System.out.println("PUT CONTAINER " + container);

    URI uri =  uriInfo.getAbsolutePath();
    Container c = new Container(container, uri.toString());

    Response r;
    if (!MemoryStore.MS.hasContainer(c)) {
        r = Response.created(uri).build();
    } else {
        r = Response.noContent().build();
    }

    MemoryStore.MS.createContainer(c);
    return r;
}
```

By default, the JAX-RS runtime will automatically support the methods HEAD and OPTIONS if not explicitly implemented. For HEAD, the runtime will invoke the implemented GET method, if present, and ignore the response entity, if set. For OPTIONS, the Allow response header will be set to the set of HTTP methods supported by the resource. In addition, the JAX-RS runtime will return a Web Application Definition Language (WADL) document describing the resource; see http://wadl.java.net/ for more information.

Methods decorated with request method designators must return void, a Java programming language type, or a javax.ws.rs.core.Response object. Multiple parameters may be extracted from the URI by using the PathParam or QueryParam annotations as described in "Extracting Request Parameters" on page 364. Conversion between Java types and an entity body is the responsibility of an entity provider, such as MessageBodyReader or MessageBodyWriter. Methods that need to provide additional metadata with a response should return an instance of the Response class. The ResponseBuilder class provides a convenient way to create a Response instance using a builder pattern. The HTTP PUT and POST methods expect an HTTP request body, so you should use a MessageBodyReader for methods that respond to PUT and POST requests.

Both @PUT and @POST can be used to create or update a resource. POST can mean anything, so when using POST, it is up to the application to define the semantics. PUT has well-defined semantics. When using PUT for creation, the client declares the URI for the newly created resource.

PUT has very clear semantics for creating and updating a resource. The representation the client sends must be the same representation that is received using a GET, given the same media type. PUT does not allow a resource to be partially updated, a common mistake when attempting to use the PUT method. A common application pattern is to use POST to create a resource and return a 201 response with a location header whose value is the URI to the newly created resource. In this pattern, the web service declares the URI for the newly created resource.

Using Entity Providers to Map HTTP Response and Request Entity Bodies

Entity providers supply mapping services between representations and their associated Java types. The two types of entity providers are `MessageBodyReader` and `MessageBodyWriter`. For HTTP requests, the `MessageBodyReader` is used to map an HTTP request entity body to method parameters. On the response side, a return value is mapped to an HTTP response entity body by using a `MessageBodyWriter`. If the application needs to supply additional metadata, such as HTTP headers or a different status code, a method can return a `Response` that wraps the entity and that can be built by using `Response.ResponseBuilder`.

Table 19–3 shows the standard types that are supported automatically for entities. You need to write an entity provider only if you are not choosing one of these standard types.

TABLE 19–3 Types Supported for Entities

Java Type	Supported Media Types
`byte[]`	All media types (`*/*`)
`java.lang.String`	All text media types (`text/*`)
`java.io.InputStream`	All media types (`*/*`)
`java.io.Reader`	All media types (`*/*`)
`java.io.File`	All media types (`*/*`)
`javax.activation.DataSource`	All media types (`*/*`)
`javax.xml.transform.Source`	XML media types (`text/xml`, `application/xml`, and `application/*+xml`)
`javax.xml.bind.JAXBElement` and application-supplied JAXB classes	XML media types (`text/xml`, `application/xml`, and `application/*+xml`)
`MultivaluedMap<String, String>`	Form content (`application/x-www-form-urlencoded`)
`StreamingOutput`	All media types (`*/*`), `MessageBodyWriter` only

The following example shows how to use `MessageBodyReader` with the `@Consumes` and `@Provider` annotations:

```
@Consumes("application/x-www-form-urlencoded")
@Provider
public class FormReader implements MessageBodyReader<NameValuePair> {
```

The following example shows how to use `MessageBodyWriter` with the `@Produces` and `@Provider` annotations:

```
@Produces("text/html")
@Provider
public class FormWriter implements
        MessageBodyWriter<Hashtable<String, String>> {
```

The following example shows how to use `ResponseBuilder`:

```
@GET
public Response getItem() {
    System.out.println("GET ITEM " + container + " " + item);

    Item i = MemoryStore.MS.getItem(container, item);
    if (i == null)
        throw new NotFoundException("Item not found");
    Date lastModified = i.getLastModified().getTime();
    EntityTag et = new EntityTag(i.getDigest());
    ResponseBuilder rb = request.evaluatePreconditions(lastModified, et);
    if (rb != null)
        return rb.build();

    byte[] b = MemoryStore.MS.getItemData(container, item);
    return Response.ok(b, i.getMimeType()).
            lastModified(lastModified).tag(et).build();
}
```

Using `@Consumes` and `@Produces` to Customize Requests and Responses

The information sent to a resource and then passed back to the client is specified as a MIME media type in the headers of an HTTP request or response. You can specify which MIME media types of representations a resource can respond to or produce by using the following annotations:

- `javax.ws.rs.Consumes`
- `javax.ws.rs.Produces`

By default, a resource class can respond to and produce all MIME media types of representations specified in the HTTP request and response headers.

The `@Produces` Annotation

The `@Produces` annotation is used to specify the MIME media types or representations a resource can produce and send back to the client. If `@Produces` is applied at the class level, all the methods in a resource can produce the specified MIME types by default. If applied at the method level, the annotation overrides any `@Produces` annotations applied at the class level.

If no methods in a resource are able to produce the MIME type in a client request, the JAX-RS runtime sends back an HTTP "406 Not Acceptable" error.

The value of `@Produces` is an array of `String` of MIME types. For example:

```
@Produces({"image/jpeg,image/png"})
```

The following example shows how to apply `@Produces` at both the class and method levels:

```
@Path("/myResource")
@Produces("text/plain")
public class SomeResource {
    @GET
    public String doGetAsPlainText() {
        ...
    }

    @GET
    @Produces("text/html")
    public String doGetAsHtml() {
        ...
    }
}
```

The `doGetAsPlainText` method defaults to the MIME media type of the `@Produces` annotation at the class level. The `doGetAsHtml` method's `@Produces` annotation overrides the class-level `@Produces` setting and specifies that the method can produce HTML rather than plain text.

If a resource class is capable of producing more than one MIME media type, the resource method chosen will correspond to the most acceptable media type as declared by the client. More specifically, the `Accept` header of the HTTP request declares what is most acceptable. For example, if the `Accept` header is `Accept: text/plain`, the `doGetAsPlainText` method will be invoked. Alternatively, if the `Accept` header is `Accept: text/plain;q=0.9, text/html`, which declares that the client can accept media types of `text/plain` and `text/html` but prefers the latter, the `doGetAsHtml` method will be invoked.

More than one media type may be declared in the same `@Produces` declaration. The following code example shows how this is done:

```
@Produces({"application/xml", "application/json"})
public String doGetAsXmlOrJson() {
    ...
}
```

The `doGetAsXmlOrJson` method will get invoked if either of the media types `application/xml` and `application/json` is acceptable. If both are equally acceptable, the former will be chosen because it occurs first. The preceding examples refer explicitly to MIME media types for clarity. It is possible to refer to constant values, which may reduce typographical errors. For more information, see the constant field values of `MediaType` at `http://jsr311.java.net/nonav/releases/1.0/javax/ws/rs/core/MediaType.html`.

The `@Consumes` Annotation

The `@Consumes` annotation is used to specify which MIME media types of representations a resource can accept, or consume, from the client. If `@Consumes` is applied at the class level, all the response methods accept the specified MIME types by default. If applied at the method level, `@Consumes` overrides any `@Consumes` annotations applied at the class level.

If a resource is unable to consume the MIME type of a client request, the JAX-RS runtime sends back an HTTP 415 ("Unsupported Media Type") error.

The value of `@Consumes` is an array of `String` of acceptable MIME types. For example:

```
@Consumes({"text/plain,text/html"})
```

The following example shows how to apply `@Consumes` at both the class and method levels:

```
@Path("/myResource")
@Consumes("multipart/related")
public class SomeResource {
    @POST
    public String doPost(MimeMultipart mimeMultipartData) {
        ...
    }

    @POST
    @Consumes("application/x-www-form-urlencoded")
    public String doPost2(FormURLEncodedProperties formData) {
        ...
    }
}
```

The `doPost` method defaults to the MIME media type of the `@Consumes` annotation at the class level. The `doPost2` method overrides the class level `@Consumes` annotation to specify that it can accept URL-encoded form data.

If no resource methods can respond to the requested MIME type, an HTTP 415 ("Unsupported Media Type") error is returned to the client.

The `HelloWorld` example discussed previously in this section can be modified to set the message by using `@Consumes`, as shown in the following code example:

```
@POST
@Consumes("text/plain")
public void postClichedMessage(String message) {
    // Store the message
}
```

In this example, the Java method will consume representations identified by the MIME media type `text/plain`. Note that the resource method returns `void`. This means that no representation is returned and that a response with a status code of HTTP 204 ("No Content") will be returned.

Extracting Request Parameters

Parameters of a resource method may be annotated with parameter-based annotations to extract information from a request. A previous example presented the use of the `@PathParam` parameter to extract a path parameter from the path component of the request URL that matched the path declared in `@Path`.

You can extract the following types of parameters for use in your resource class:

- Query
- URI path
- Form
- Cookie
- Header
- Matrix

Query parameters are extracted from the request URI query parameters and are specified by using the `javax.ws.rs.QueryParam` annotation in the method parameter arguments. The following example, from the `sparklines` sample application, demonstrates using `@QueryParam` to extract query parameters from the `Query` component of the request URL:

```
@Path("smooth")
@GET
public Response smooth(
        @DefaultValue("2") @QueryParam("step") int step,
        @DefaultValue("true") @QueryParam("min-m") boolean hasMin,
        @DefaultValue("true") @QueryParam("max-m") boolean hasMax,
        @DefaultValue("true") @QueryParam("last-m") boolean hasLast,
        @DefaultValue("blue") @QueryParam("min-color") ColorParam minColor,
        @DefaultValue("green") @QueryParam("max-color") ColorParam maxColor,
        @DefaultValue("red") @QueryParam("last-color") ColorParam lastColor
        ) { ... }
```

If the query parameter `step` exists in the query component of the request URI, the value of `step` will be extracted and parsed as a 32-bit signed integer and assigned to the `step` method parameter. If `step` does not exist, a default value of 2, as declared in the `@DefaultValue` annotation, will be assigned to the `step` method parameter. If the `step` value cannot be parsed as a 32-bit signed integer, an HTTP 400 (“Client Error”) response is returned.

User-defined Java programming language types may be used as query parameters. The following code example shows the `ColorParam` class used in the preceding query parameter example:

```
public class ColorParam extends Color {
    public ColorParam(String s) {
        super(getRGB(s));
    }

    private static int getRGB(String s) {
        if (s.charAt(0) == '#') {
            try {
                Color c = Color.decode("0x" + s.substring(1));
                return c.getRGB();
            } catch (NumberFormatException e) {
                throw new WebApplicationException(400);
            }
        } else {
            try {
                Field f = Color.class.getField(s);
```

```
                return ((Color)f.get(null)).getRGB();
            } catch (Exception e) {
                throw new WebApplicationException(400);
            }
        }
    }
}
```

The constructor for `ColorParam` takes a single `String` parameter.

Both `@QueryParam` and `@PathParam` can be used only on the following Java types:

- All primitive types except `char`
- All wrapper classes of primitive types except `Character`
- Any class with a constructor that accepts a single `String` argument
- Any class with the static method named `valueOf(String)` that accepts a single `String` argument
- `List<T>`, `Set<T>`, or `SortedSet<T>`, where *T* matches the already listed criteria. Sometimes, parameters may contain more than one value for the same name. If this is the case, these types may be used to obtain all values

If `@DefaultValue` is not used in conjunction with `@QueryParam`, and the query parameter is not present in the request, the value will be an empty collection for `List`, `Set`, or `SortedSet`; null for other object types; and the default for primitive types.

URI path parameters are extracted from the request URI, and the parameter names correspond to the URI path template variable names specified in the `@Path` class-level annotation. URI parameters are specified using the `javax.ws.rs.PathParam` annotation in the method parameter arguments. The following example shows how to use `@Path` variables and the `@PathParam` annotation in a method:

```
@Path("/{username}")
public class MyResourceBean {
    ...
    @GET
    public String printUsername(@PathParam("username") String userId) {
        ...
    }
}
```

In the preceding snippet, the URI path template variable name `username` is specified as a parameter to the `printUsername` method. The `@PathParam` annotation is set to the variable name `username`. At runtime, before `printUsername` is called, the value of `username` is extracted from the URI and cast to a `String`. The resulting `String` is then available to the method as the `userId` variable.

If the URI path template variable cannot be cast to the specified type, the JAX-RS runtime returns an HTTP 400 (“Bad Request”) error to the client. If the `@PathParam` annotation cannot be cast to the specified type, the JAX-RS runtime returns an HTTP 404 (“Not Found”) error to the client.

The `@PathParam` parameter and the other parameter-based annotations (`@MatrixParam`, `@HeaderParam`, `@CookieParam`, and `@FormParam`) obey the same rules as `@QueryParam`.

Cookie parameters, indicated by decorating the parameter with `javax.ws.rs.CookieParam`, extract information from the cookies declared in cookie-related HTTP headers. *Header parameters*, indicated by decorating the parameter with `javax.ws.rs.HeaderParam`, extract information from the HTTP headers. *Matrix parameters*, indicated by decorating the parameter with `javax.ws.rs.MatrixParam`, extract information from URL path segments.

Form parameters, indicated by decorating the parameter with `javax.ws.rs.FormParam`, extract information from a request representation that is of the MIME media type `application/x-www-form-urlencoded` and conforms to the encoding specified by HTML forms, as described in `http://www.w3.org/TR/html401/interact/forms.html#h-17.13.4.1`. This parameter is very useful for extracting information sent by `POST` in HTML forms.

The following example extracts the `name` form parameter from the `POST` form data:

```
@POST
@Consumes("application/x-www-form-urlencoded")
public void post(@FormParam("name") String name) {
    // Store the message
}
```

To obtain a general map of parameter names and values for query and path parameters, use the following code:

```
@GET
public String get(@Context UriInfo ui) {
    MultivaluedMap<String, String> queryParams = ui.getQueryParameters();
    MultivaluedMap<String, String> pathParams = ui.getPathParameters();
}
```

The following method extracts header and cookie parameter names and values into a map:

```
@GET
public String get(@Context HttpHeaders hh) {
    MultivaluedMap<String, String> headerParams = ui.getRequestHeaders();
    Map<String, Cookie> pathParams = ui.getCookies();
}
```

In general, `@Context` can be used to obtain contextual Java types related to the request or response.

For form parameters, it is possible to do the following:

```
@POST
@Consumes("application/x-www-form-urlencoded")
public void post(MultivaluedMap<String, String> formParams) {
    // Store the message
}
```

Example Applications for JAX-RS

This section provides an introduction to creating, deploying, and running your own JAX-RS applications. This section demonstrates the steps that are needed to create, build, deploy, and test a very simple web application that uses JAX-RS annotations.

A RESTful Web Service

This section explains how to use NetBeans IDE to create a RESTful web service. NetBeans IDE generates a skeleton for the application, and you simply need to implement the appropriate methods. If you do not use an IDE, try using one of the example applications that ship with Jersey as a template to modify.

You can find a version of this application at *tut-install*`/examples/jaxrs/HelloWorldApplication`.

▼ To Create a RESTful Web Service Using NetBeans IDE

1 In NetBeans IDE, create a simple web application. This example creates a very simple "Hello, World" web application.

a. From the File menu, choose New Project.

b. From Categories, select Java Web. From Projects, select Web Application. Click Next.

Note – For this step, you could also create a RESTful web service in a Maven web project by selecting Maven as the category and Maven Web Project as the project. The remaining steps would be the same.

---

c. Type a project name, `HelloWorldApplication`, and click Next.

d. Make sure that the Server is GlassFish Server (or similar wording.)

e. Click Finish.

The project is created. The file `index.jsp` appears in the Source pane.

2 Right-click the project and select New; then select RESTful Web Services from Patterns.

a. Select Simple Root Resource and click Next.

b. Type a Resource Package name, such as `helloWorld`.

c. **Type `helloworld` in the Path field. Type `HelloWorld` in the Class Name field. For MIME Type, select `text/html`.**

d. **Click Finish.**

The REST Resources Configuration page appears.

e. **Click OK.**

A new resource, `HelloWorld.java`, is added to the project and appears in the Source pane. This file provides a template for creating a RESTful web service.

3 **In `HelloWorld.java`, find the `getHtml()` method. Replace the `//TODO` comment and the exception with the following text, so that the finished product resembles the following method.**

Note – Because the MIME type produced is HTML, you can use HTML tags in your return statement.

```
/**
 * Retrieves representation of an instance of helloWorld.HelloWorld
 * @return an instance of java.lang.String
 */
@GET
@Produces("text/html")
public String getHtml() {
    return "<html><body><h1>Hello, World!!</body></h1></html>";
}
```

4 **Test the web service. To do this, right-click the project node and click Test RESTful Web Services.**

This step deploys the application and brings up a test client in the browser.

5 **When the test client appears, select the `helloworld` resource in the left pane, and click the Test button in the right pane.**

The words `Hello, World!!` appear in the Response window below.

6 **Set the Run Properties:**

a. **Right-click the project node and select Properties.**

b. **In the dialog, select the Run category.**

c. **Set the Relative URL to the location of the RESTful web service relative to the Context Path, which for this example is `resources/helloworld`.**

Tip – You can find the value for the Relative URL in the Test RESTful Web Services browser window. In the top of the right pane, after Resource, is the URL for the RESTful web service being tested. The part following the Context Path (`http://localhost:8080/HelloWorldApp`) is the Relative URL that needs to be entered here.

If you don't set this property, the file `index.jsp` will appear by default when the application is run. As this file also contains `Hello World` as its default value, you might not notice that your RESTful web service isn't running, so just be aware of this default and the need to set this property, or update `index.jsp` to provide a link to the RESTful web service.

7. **Right-click the project and select Deploy.**

8. **Right-click the project and select Run.**

   A browser window opens and displays the return value of `Hello, World!!`

See Also For other sample applications that demonstrate deploying and running JAX-RS applications using NetBeans IDE, see "The `rsvp` Example Application" on page 370 and *Your First Cup: An Introduction to the Java EE Platform* at `http://download.oracle.com/javaee/6/firstcup/doc/`. You may also look at the tutorials on the NetBeans IDE tutorial site, such as the one titled "Getting Started with RESTful Web Services" at `http://www.netbeans.org/kb/docs/websvc/rest.html`. This tutorial includes a section on creating a CRUD application from a database. Create, read, update, and delete (CRUD) are the four basic functions of persistent storage and relational databases.

The `rsvp` Example Application

The `rsvp` example application, located in *tut-install*`/examples/jaxrs/rsvp`, allows invitees to an event to indicate whether they will attend. The events, people invited to the event, and the responses to the invite are stored in a Java DB database using the Java Persistence API. The JAX-RS resources in `rsvp` are exposed in a stateless session enterprise bean.

Components of the `rsvp` Example Application

The three enterprise beans in the `rsvp` example application are `rsvp.ejb.ConfigBean`, `rsvp.ejb.StatusBean`, and `rsvp.ejb.ResponseBean`.

`ConfigBean` is a singleton session bean that initializes the data in the database.

`StatusBean` exposes a JAX-RS resource for displaying the current status of all invitees to an event. The URI path template is declared as follows:

```
@Path("/status/{eventId}/")
```

The URI path variable `eventId` is a `@PathParam` variable in the `getResponse` method, which responds to HTTP `GET` requests and has been annotated with `@GET`. The `eventId` variable is used to look up all the current responses in the database for that particular event.

`ResponseBean` exposes a JAX-RS resource for setting an invitee's response to a particular event. The URI path template for `ResponseBean` is declared as follows:

```
@Path("/{eventId}/{inviteId}")
```

Two URI path variables are declared in the path template: `eventId` and `inviteId`. As in `StatusBean`, `eventId` is the unique ID for a particular event. Each invitee to that event has a unique ID for the invitation, and that is the `inviteId`. Both of these path variables are used in two JAX-RS methods in `ResponseBean`: `getResponse` and `putResponse`. The `getResponse` method responds to HTTP `GET` requests and displays the invitee's current response and a form to change the response.

An invitee who wants to change his or her response selects the new response and submits the form data, which is processed as an HTTP `PUT` request by the `putResponse` method. One of the parameters to the `putResponse` method, the `userResponse` string, is annotated with `@FormParam("attendeeResponse")`. The HTML form created by `getResponse` stores the changed response in the select list with an ID of `attendeeResponse`. The annotation `@FormParam("attendeeResponse")` indicates that the value of the select response is extracted from the HTTP `PUT` request and stored as the `userResponse` string. The `putResponse` method uses `userResponse`, `eventId`, and `inviteId` to update the invitee's response in the database.

The events, people, and responses in `rsvp` are encapsulated in Java Persistence API entities. The `rsvp.entity.Event`, `rsvp.entity.Person`, and `rsvp.entity.Response` entities respectively represent events, invitees, and responses to an event.

The `rsvp.util.ResponseEnum` class declares an enumerated type that represents all the possible response statuses an invitee may have.

Running the `rsvp` Example Application

Both NetBeans IDE and Ant can be used to deploy and run the `rsvp` example application.

▼ To Run the `rsvp` Example Application in NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/jaxrs/`
3. **Select the `rsvp` folder.**
4. **Select the Open as Main Project check box.**

5. **Click Open Project.**

6. **Right-click the `rsvp` project in the left pane and select Run.**

   The project will be compiled, assembled, and deployed to GlassFish Server. A web browser window will open to `http://localhost:8080/rsvp`.

7. **In the web browser window, click the Event Status link for the Duke's Birthday event.**

   You'll see the current invitees and their responses.

8. **Click on the name of one of the invitees, select a response, and click Submit response; then click Back to event page.**

   The invitee's new status should now be displayed in the table of invitees and their response statuses.

▼ To Run the `rsvp` Example Application Using Ant

Before You Begin You must have started the Java DB database before running `rsvp`.

1. **In a terminal window, go to:**

   tut-install`/examples/jaxrs/rsvp`

2. **Type the following command:**

   ```
   ant all
   ```

   This command builds, assembles, and deploys `rsvp` to GlassFish Server.

3. **Open a web browser window to `http://localhost:8080/rsvp`.**

4. **In the web browser window, click the Event Status link for the Duke's Birthday event.**

   You'll see the current invitees and their responses.

5. **Click on the name of one of the invitees, select a response, and click Submit response, then click Back to event page.**

   The invitee's new status should now be displayed in the table of invitees and their response statuses.

Real-World Examples

Most blog sites use RESTful web services. These sites involve downloading XML files, in RSS or Atom format, that contain lists of links to other resources. Other web sites and web applications that use REST-like developer interfaces to data include Twitter and Amazon S3 (Simple Storage Service). With Amazon S3, buckets and objects can be created, listed, and retrieved using either a REST-style HTTP interface or a SOAP interface. The examples that ship with Jersey include a

storage service example with a RESTful interface. The tutorial at `http://netbeans.org/kb/docs/websvc/twitter-swing.html` uses NetBeans IDE to create a simple, graphical, REST-based client that displays Twitter public timeline messages and lets you view and update your Twitter status.

Further Information about JAX-RS

For more information about RESTful web services and JAX-RS, see

- "RESTful Web Services vs. 'Big' Web Services: Making the Right Architectural Decision":

  `http://www2008.org/papers/pdf/p805-pautassoA.pdf`
- The Community Wiki for Project Jersey, the JAX-RS reference implementation:

  `http://wikis.sun.com/display/Jersey/Main`
- "Fielding Dissertation: Chapter 5: Representational State Transfer (REST)":

  `http://www.ics.uci.edu/~fielding/pubs/dissertation/rest_arch_style.htm`
- *RESTful Web Services*, by Leonard Richardson and Sam Ruby, available from O'Reilly Media at `http://oreilly.com/catalog/9780596529260/`
- JSR 311: JAX-RS: The Java API for RESTful Web Services:

  `http://jcp.org/en/jsr/detail?id=311`
- JAX-RS project:

  `http://jsr311.java.net/`
- Jersey project:

  `http://jersey.java.net/`
- JAX-RS Overview document:

  `http://wikis.sun.com/display/Jersey/Overview+of+JAX-RS+1.0+Features`

◆ ◆ ◆ CHAPTER 20

Advanced JAX-RS Features

The Java API for RESTful Web Services (JAX-RS, defined in JSR 311) is designed to make it easy to develop applications that use the REST architecture. This chapter describes advanced features of JAX-RS. If you are new to JAX-RS, see Chapter 19, "Building RESTful Web Services with JAX-RS," before you proceed with this chapter.

JAX-RS is part of the Java EE 6 full profile. JAX-RS is integrated with Contexts and Dependency Injection for the Java EE Platform (CDI), Enterprise JavaBeans (EJB) technology, and Java Servlet technology.

The following topics are addressed here:

Annotations for Field and Bean Properties of Resource Classes

JAX-RS annotations for resource classes let you extract specific parts or values from a Uniform Resource Identifier (URI) or request header.

JAX-RS provides the annotations listed in the following table.

TABLE 20–1 Advanced JAX-RS Annotations

Annotation	Description
`@Context`	Injects information into a class field, bean property, or method parameter

TABLE 20–1 Advanced JAX-RS Annotations *(Continued)*

Annotation	Description
`@CookieParam`	Extracts information from cookies declared in the cookie request header
`@FormParam`	Extracts information from a request representation whose content type is `application/x-www-form-urlencoded`
`@HeaderParam`	Extracts the value of a header
`@MatrixParam`	Extracts the value of a URI matrix parameter
`@PathParam`	Extracts the value of a URI template parameter
`@QueryParam`	Extracts the value of a URI query parameter

Extracting Path Parameters

URI path templates are URIs with variables embedded within the URI syntax. The `@PathParam` annotation lets you use variable URI path fragments when you call a method.

The following code snippet shows how to extract the last name of an employee when the employee's email address is provided:

```
@Path(/employees/{"firstname}.{lastname}@{domain}.com")
public class EmpResource {

    @GET
    @Produces("text/xml")
    public String getEmployeelastname(@PathParam("lastname") String lastName) {
     ...
    }
}
```

In this example, the `@Path` annotation defines the URI variables (or path parameters) `{firstname}` , `{lastname}`, and `{domain}`. The `@PathParam` in the method parameter of the request method extracts the last name from the email address.

If your HTTP request is GET `/employees/john.doe@mycompany.com`, the value, "`doe`" is injected into `{lastname}`.

You can specify several path parameters in one URI.

You can declare a regular expression with a URI variable. For example, if it is required that the last name must only consist of lower and upper case characters, you can declare the following regular expression:

```
@Path(/employees/{"firstname}.{lastname[a-zA-Z]*}@{domain}.com")
```

If the last name does not match the regular expression, a 404 response is returned.

Extracting Query Parameters

Use the `@QueryParam` annotation to extract query parameters from the query component of the request URI.

For instance, to query all employees who have joined within a specific range of years, use a method signature like the following:

```
@Path(/employees/")
@GET
public Response getEmployees(
        @DefaultValue("2002") @QueryParam("minyear") int minyear,
        @DefaultValue("2010") @QueryParam("maxyear") int maxyear)
    {...}
```

This code snippet defines two query parameters, `minyear` and `maxyear`. The following HTTP request would query for all employees who have joined between 1999 and 2009:

```
GET /employees?maxyear=2009&minyear=1999
```

The `@DefaultValue` annotation defines a default value, which is to be used if no values are provided for the query parameters. By default, JAX-RS assigns a null value for `Object` values and zero for primitive data types. You can use the `@DefaultValue` annotation to eliminate null or zero values and define your own default values for a parameter.

Extracting Form Data

Use the `@FormParam` annotation to extract form parameters from HTML forms. For example, the following form accepts the name, address, and manager's name of an employee:

```
<FORM action="http://example.com/employees/" method="post">
<p>
<fieldset>
Employee name: <INPUT type="text" name="empname" tabindex="1">
Employee address: <INPUT type="text" name="empaddress" tabindex="2">
Manager name: <INPUT type="text" name="managername" tabindex="3">
</fieldset>
</p>
</FORM>
```

Use the following code snippet to extract the manager name from this HTML form:

```
@POST
@Consumes("application/x-www-form-urlencoded")
public void post(@FormParam("managername") String managername) {
    // Store the value
    ...
}
```

To obtain a map of form parameter names to values, use a code snippet like the following:

```
@POST
@Consumes("application/x-www-form-urlencoded")
public void post(MultivaluedMap<String. String> formParams) {
    // Store the message
}
```

Extracting the Java Type of a Request or Response

The `javax.ws.rs.core.Context` annotation retrieves the Java types related to a request or response.

The `javax.ws.rs.core.UriInfo` interface provides information about the components of a request URI. The following code snippet shows how to obtain a map of query and path parameter names to values:

```
@GET
public String getParams(@Context UriInfo ui) {
    MultivaluedMap<String, String> queryParams = ui.getQueryParameters();
    MultivaluedMap<String, String> pathParams = ui.getPathParameters();
}
```

The `javax.ws.rs.core` `HttpHeaders` interface provides information about a request headers and cookies. The following code snippet shows how to obtain a map of header and cookie parameter names to values:

```
@GET
public String getHeaders(@Context HttpHeaders hh) {
    MultivaluedMap<String, String> headerParams = hh.getRequestHeaders();
    MultivaluedMap<String, Cookie> pathParams = hh.getCookies();
}
```

Subresources and Runtime Resource Resolution

You can use a resource class to process only a part of the URI request. A root resource can then implement subresources that can process the remainder of the URI path.

A resource class method that is annotated with `@Path` is either a subresource method or a subresource locator:

- A subresource method is used to handle requests on a subresource of the corresponding resource.
- A subresource locator is used to locate subresources of the corresponding resource (requests on the subresource are then handled by something else ...).

Subresource Methods

A *subresource method* handles an HTTP request directly. The method must be annotated with a request method designator such as `@GET` or `@POST`, in addition to `@Path`. The method is invoked for request URIs that match a URI template created by concatenating the URI template of the resource class with the URI template of the method.

The following code snippet shows how a subresource method can be used to extract the last name of an employee, when the employee's email address is provided:

```
@Path("/employeeinfo")
Public class EmployeeInfo {

    public employeeinfo() {}

    @GET
    @Path("/employees/{firstname}.{lastname}@{domain}.com")
    @Produces("text/xml")
    public String getEmployeeLastName(@PathParam("lastname") String lastName) {
       ...
    }

}
```

The `getEmployeeLastName` method returns `doe` for the following GET request:

```
GET /employeeinfo/employees/john.doe@oracle.com
```

Subresource Locators

A *subresource locator* returns an object that will handle a HTTP request. The method must not be annotated with a request method designator. You must declare a subresource locator within a subresource class, and only subresource locators are used for runtime resource resolution.

The following code snippet shows a subresource locator:

```
// Root resource class
@Path("/employeeinfo")
public class EmployeeInfo {

    // Subresource locator: obtains the subresource Employee
    // from the path /employeeinfo/employees/{empid}
    @Path("/employees/{empid}")
    public Employee getEmployee(@PathParam("id") String id) {
        // Find the Employee based on the id path parameter
        Employee emp = ...;
        ...
        return emp;
    }
}
```

```
// Subresource class
public class Employee {

    // Subresource method: returns the employee's last name
    @GET
    @Path("/lastname")
    public String getEmployeeLastName() {
        ...
        return lastName
    }
}
```

In this code snippet, the `getEmployee` method is the subresource locator that provides the `Employee` object, which services requests for `lastname`.

If your HTTP request is `GET /employeeinfo/employees/as209/`, the `getEmployee` method returns an `Employee` object whose id is `as209`. At runtime, JAX-RS sends a `GET /employeeinfo/employees/as209/lastname` request to the `getEmployeeLastName` method . The `getEmployeeLastName` method retrieves and returns the last name of the employee whose id is `as209`.

Integrating JAX-RS with EJB Technology and CDI

JAX-RS works with Enterprise JavaBeans technology (enterprise beans) and Contexts and Dependency Injection for the Java EE Platform (CDI).

In general, for JAX-RS to work with enterprise beans, you need to annotate the class of a bean with `@Path` to convert it to a root resource class. You can use the `@Path` annotation with stateless session beans and singleton POJO beans.

The following code snippet shows enterprise beans that have been converted to JAX-RS root resource classes.

```
@Stateless
@Path{"stateless-bean")
public class StatelessResource {...}

@Singleton
@Path{"singleton-bean")
public class SingletonResource {...}
```

Session beans can also be used for subresources.

JAX-RS and CDI have slightly different component models. By default, JAX-RS root resource classes are managed in the request scope, and no annotations are required for specifying the scope. CDI managed beans annotated with `@RequestScoped` or `@ApplicationScoped` can be converted to JAX-RS resource classes.

The following code snippet shows a JAX-RS resource class.

```
@Path("/employee/{id}")
public class Employee {
    public Employee(@PathParam("id") String id) {...}
}

@Path("{lastname}")
public final class EmpDetails {...}
```

The following code snippet shows this JAX-RS resource class converted to a CDI bean. The beans must be proxyable, so the `Employee` class requires a non-private constructor with no parameters, and the `EmpDetails` class must not be `final`.

```
@Path("/employee/{id}")
@RequestScoped
public class Employee {
    public Employee() {...}

    @Inject
    public Employee(@PathParam("id") String id) {...}
}

@Path("{lastname}")
@RequestScoped
public class EmpDetails {...}
```

Conditional HTTP Requests

JAX-RS provides support for conditional GET and PUT HTTP requests. Conditional GET requests help save bandwidth by improving the efficiency of client processing.

A GET request can return a Not Modified (304) response if the representation has not changed since the previous request. For example, a web site can return 304 responses for all its static images that have not changed since the previous request.

A PUT request can return a Precondition Failed (412) response if the representation has been modified since the last request. The conditional PUT can help avoid the lost update problem.

Conditional HTTP requests can be used with the `Last-Modified` and `ETag` headers. The `Last-Modified` header can represent dates with granularity of one second.

```
@Path("/employee/{joiningdate}")
public class Employee {

    Date joiningdate;

    @GET
    @Produces("application/xml")
    public Employee(@PathParam("joiningdate") Date joiningdate, @Context Request req,
            @Context UriInfo ui) {

        this.joiningdate = joiningdate;
```

```
        ...
        this.tag = computeEntityTag(ui.getRequestUri());
        if (req.getMethod().equals("GET")) {
            Response.ResponseBuilder rb = req.evaluatePreconditions(tag);
            if (rb != null) {
                throw new WebApplicationException(rb.build());
            }
        }
    }
}
```

In this code snippet, the constructor of the `Employee` class computes the entity tag from the request URI and calls the `request.evaluatePreconditions` method with that tag. If a client request returns an `If-none-match` header with a value that has the same entity tag that was computed, `evaluate.Preconditions` returns a pre-filled out response with a 304 status code and an entity tag set that may be built and returned.

Runtime Content Negotiation

The `@Produces` and `@Consumes` annotations handle static content negotiation in JAX-RS. These annotations specify the content preferences of the server. HTTP headers such as `Accept`, `Content-Type`, and `Accept-Language` define the content negotiation preferences of the client.

For more details on the HTTP headers for content negotiation, see HTTP /1.1 - Content Negotiation (`http://www.w3.org/Protocols/rfc2616/rfc2616-sec12.html`).

The following code snippet shows the server content preferences:

```
@Produces("text/plain")
@Path("/employee")
public class Employee {

    @GET
    public String getEmployeeAddressText(String address) { ... }

    @Produces("text/xml")
    @GET
    public String getEmployeeAddressXml(Address address) { ... }
}
```

The `getEmployeeAddressText` method is called for an HTTP request that looks as follows:

```
GET /employee
content-type: text/plain
500 Oracle Parkway, Redwood Shores, CA
```

The `getEmployeeAddressXml` method is called for an HTTP request that looks as follows:

```
GET /employee
content-type: text/xml
<address street="500 Oracle Parkway, Redwood Shores, CA" country="USA"/>
```

With static content negotiation, you can also define multiple content and media types for the client and server.

```
@Produces("text/plain", "text/xml")
```

In addition to supporting static content negotiation, JAX-RS also supports runtime content negotiation using the `javax.ws.rs.core.Variant` class and `Request` objects. The `Variant` class specifies the resource representation of content negotiation. Each instance of the `Variant` class may contain a media type, a language, and an encoding. The `Variant` object defines the resource representation that is supported by the server. The `Variant.VariantListBuilder` class is used to build a list of representation variants.

The following code snippet shows how to create a list of resource representation variants:

```
List<Variant> vs =
    Variant.mediatypes("application/xml", "application/json")
           .languages("en", "fr").build();
```

This code snippet calls the `build` method of the `VariantListBuilder` class. The `VariantListBuilder` class is invoked when you call the `mediatypes`,`encodings`, or `languages` methods. The `build` method builds a series of resource representations. The `Variant` list created by the `build` method has all possible combinations of items specified in the `mediatypes`, `languages`, and `encodings` methods. In this example, the size of the `vs` object as defined in this code snippet is 4 and the contents are as follows:

```
[["application/xml","en"], ["application/json","en"],
    ["application/xml","fr"],["application/json","fr"]]
```

The `javax.ws.rs.core.Request.selectVariant` method accepts a list of `Variant` objects and chooses the `Variant` object that matches the HTTP request. This method compares its list of `Variant` objects with the `Accept`, `Accept-Encoding`, `Accept-Language`, and `Accept-Charset` headers of the HTTP request.

The following code snippet shows how to use the `selectVariant` method to select the most acceptable `Variant` from the values in the client request.

```
@GET
public Response get(@Context Request r) {
    List<Variant> vs = ...;
    Variant v = r.selectVariant(vs);
    if (v == null) {
        return Response.notAcceptable(vs).build();
    } else {
        Object rep = selectRepresentation(v);
        return Response.ok(rep, v);
    }
}
```

The `selectVariant` method returns the `Variant` object that matches the request, or null if no matches are found. In this code snippet, if the method returns null, a `Response` object for a

non-acceptable response is built. Otherwise, a `Response` object with an OK status and containing a representation in the form of an `Object` entity and a `Variant` is returned.

Using JAX-RS With JAXB

Java Architecture for XML Binding (JAXB) enables you to access XML documents from Java applications. JAXB provides annotations to map Java classes into XML.

JAX-RS has built-in support for JAXB. You can add JAXB annotations to the JPA entity manager, and there is no need to use converter classes. The JAXB annotations within a RESTful web service indicate the XML structure that should be generated from that code.

◆ ◆ ◆ CHAPTER 21

Running the Advanced JAX-RS Example Application

This chapter describes how to build and run the `customer` sample application. This example application is a RESTful web service that uses JAXB to perform the Create, Read, Update, Delete (CRUD) operations for a specific entity.

The `customer` Example Application

The `customer` sample application is in the *tut-install*`/examples/jaxrs/customer` directory. See Chapter 2, "Using the Tutorial Examples," for basic information on building and running sample applications.

The `customer` Application Source Files

The source files of this application are at *tut-install*`/examples/jaxrs/customer/src/java`. This application has the following source files:

The `CustomerService` Class

```
@Path("/Customer")
public class CustomerService {
    public static final String DATA_STORE = "CustomerDATA.txt";
    public static final Logger logger =
            Logger.getLogger(CustomerService.class.getCanonicalName());

    @POST
    @Consumes("application/xml")
    public Response createCustomer(CustomerType customer) {
        try {
```

```
            long customerId = persist(customer);
            return Response.created(URI.create("/" + customerId)).build();
        } catch (Exception e) {
          throw new WebApplicationException(e, Response.Status.INTERNAL_SERVER_ERROR);
        }
    }

    private long persist(CustomerType customer) throws IOException {
        File dataFile = new File(DATA_STORE);
        if (!dataFile.exists()) {
            dataFile.createNewFile();
        }
        long customerId = customer.getId();
        Properties properties = new Properties();
        properties.load(new FileInputStream(dataFile));
        properties.setProperty(String.valueOf(customerId),
                customer.getFirstName() + "," + customer.getLastName()
                + "," + customer.getEmail() + "," + customer.getCity()
                + "," + customer.getCountry());
        properties.store(new FileOutputStream(DATA_STORE),null);
        return customerId;
    }
}
```

The `CustomerService` class has a `createCustomer` method that creates a customer resource based on the `CustomerType` and returns a URI for the new resource. The `persist` method emulates the behavior of the JPA entity manager. This example uses a `java.util.Properties` file to store data. If you are using the default configuration of GlassFish, the properties file is at *as-install*`/glassfish/domains/domain1/CustomerDATA.txt`.

The response that is returned to the client has a URI to the newly created resource. The return type is an entity body mapped from the property of the response with the status code specified by the status property of the response. The `WebApplicationException` is a `RuntimeException` that is used to wrap the appropriate HTTP error status code, such as 404, 406, 415, or 500.

The `@Consumes("application/xml")` and `@Produces("application/xml")` annotations set the request and response media types to use the appropriate MIME client. These annotations can be applied to a resource method, a resource class, or even to an entity provider. If you do not use these annotations, JAX-RS allows the use of any media type (`"*/*"`).

The following code snippet shows the implementation of the `getCustomer` and `findbyId` methods. The `getCustomer` method uses the `@Produces`annotation and returns a `JAXBElement` with a `CustomerType` object, which is a JAXB XML based entity, generated through the `xjc` binding compiler.

```
@GET
@Path("{id}")
@Produces("application/xml")
public JAXBElement<CustomerType> getCustomer(@PathParam("id") String customerId) {
    CustomerType customer = null;
    try {
        customer = findById(customerId);
    } catch (Exception ex) {
```

```
            logger.log(Level.SEVERE,
                       "Error calling searchCustomer() for customerId {0}. {1}",
                       new Object[]{customerId, ex.getMessage()});
        }
        return new ObjectFactory().createCustomer(customer);
    }

    private CustomerType findById(String customerId) throws IOException {
        properties properties = new Properties();
        properties.load(new FileInputStream(DATA_STORE));
        String rawData = properties.getProperty(customerId);
        if (rawData != null) {
            final String[] field = rawData.split(",");
            ObjectFactory objFactory = new ObjectFactory();
            CustomerType customer = objFactory.createCustomerType();
            customer.setFirstName(field[0]);
            customer.setLastName(field[1]);
            customer.setEmail(field[2]);
            customer.setCity(field[3]);
            customer.setCountry(field[4]);
            customer.setId(Integer.parseInt(customerId));
            return customer;
        }
        return null;
    }
```

The XSD Schema for the `customer` Application

A sample XSD schema for the `Customer` entity is as follows:

```
<?xml version="1.0"?>
<xs:schema targetNamespace="http://examples.oracle.com"
           xmlns:xs="http://www.w3.org/2001/XMLSchema"
           elementFormDefault="qualified"
           xmlns:ora="http://examples.oracle.com">
    <xs:element name="customer" type="ora:CustomerType"/>
    <xs:complexType name="CustomerType">
        <xs:sequence>
            <xs:element name="id" type="xs:int"/>
            <xs:element name="firstName" type="xs:string"/>
            <xs:element name="lastName" type="xs:string"/>
            <xs:element name="city" type="xs:string"/>
            <xs:element name="country" type="xs:string"/>
        </xs:sequence>
    </xs:complexType>
</xs:schema>
```

The `CustomerClient` Class

Jersey is the reference implementation of JAX-RS (JSR 311). You can use the Jersey client API to write a test client for the `customer` example application. You can find the Jersey APIs at `http://jersey.java.net/nonav/apidocs/latest/jersey/`.

The `CustomerClient` class calls Jersey APIs to test the `CustomerService` web service:

```
package customer.rest.client;

import com.oracle.examples.CustomerType;
import com.oracle.examples.ObjectFactory;
import com.sun.jersey.api.client.Client;
import com.sun.jersey.api.client.ClientResponse;
import com.sun.jersey.api.client.WebResource;
import java.util.logging.Level;
import java.util.logging.Logger;
import javax.ws.rs.core.MediaType;
import javax.xml.bind.JAXBElement;

public class CustomerClient {
    public static final Logger logger =
            Logger.getLogger(CustomerClient.class.getCanonicalName());

    public static void main(String[] args) {

        Client client = Client.create();
        // Define the URL for testing the example application
        WebResource webResource =
            client.resource("http://localhost:8080/customer/Customer");

        ObjectFactory factory = new ObjectFactory();

        // Test the POST method
        CustomerType customerType = new CustomerType();

        customerType.setId(1);
        customerType.setFirstName("Duke");
        customerType.setLastName("OfJava");
        customerType.setCity("JavaTown");
        customerType.setCountry("USA");

        JAXBElement<CustomerType> customer = factory.createCustomer(customerType);

        ClientResponse response =
            webResource.type("application/xml").post(ClientResponse.class,
                customer);

        logger.info("POST status: {0}" + response.getStatus());
        if (response.getStatus() == 201) {
            logger.info("POST succeeded");
        } else {
            logger.info("POST failed");
        }

        // Test the GET method using content negotiation
        response = webResource.path("1").accept(MediaType.APPLICATION_XML)
                                        .get(ClientResponse.class);
        CustomerType entity = response.getEntity(CustomerType.class);

        logger.info("GET status: " + response.getStatus());
        if (response.getStatus() == 200) {
            logger.info("GET succeeded, city is " + entity.getCity());
        } else {
            logger.info("GET failed");
        }
```

```
        // Test the DELETE method
        response = webResource.path("1").delete(ClientResponse.class);

        logger.info("DELETE status: " + response.getStatus());
        if (response.getStatus() == 204) {
            logger.info("DELETE succeeded (no content)");
        } else {
            logger.info("DELETE failed");
        }

        response = webResource.path("1").accept(MediaType.APPLICATION_XML)
                              .get(ClientResponse.class);
        entity = response.getEntity(CustomerType.class);

        logger.info("GET status: " + response.getStatus());

        try {
            logger.info(entity.getCity());
        } catch (NullPointerException ne) {
            // as expected, returns null because you have deleted the customer
            logger.info("After DELETE, city is: " + ne.getCause());
        }
    }
}
```

This Jersey client tests the POST, GET, and DELETE methods.

All of these HTTP status codes indicate success: 201 for POST, 200 for GET, and 204 for DELETE. For details about the meanings of HTTP status codes, see http://www.w3.org/Protocols/rfc2616/rfc2616-sec10.html.

Building, Packaging, Deploying, and Running the `customer` Example

You can build, package, deploy, and run the `customer` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the `customer` Example Using NetBeans IDE

This procedure builds the application into the following directory:

tut-install`/examples/jax-rs/customer/build/web`

The contents of this directory are deployed to the GlassFish Server.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/jaxrs/`

3. **Select the `customer` folder.**

4. **Select the Open as Main Project check box.**

5. **Click Open Project.**

   It may appear that there are errors in the source files, because the files refer to JAXB classes that will be generated when you build the application. You can ignore these errors.

6. **In the Projects tab, right-click the `customer` project and select Deploy.**

▼ To Build, Package, and Deploy the `customer` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/jaxrs/customer/`

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `customer.war`, located in the `dist` directory.

3. **Type the following command:**

   ```
   ant deploy
   ```

   Typing this command deploys `customer.war` to the GlassFish Server.

▼ To Run the `customer` Example Using the Jersey Client

1. **In NetBeans IDE, expand the Source Packages node.**

2. **Expand the `customer.rest.client` node.**

3. **Right-click the `CustomerClient.java` file and click Run File.**

   The output of the client looks like this:

   ```
   run:
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   INFO: POST status: 201
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   INFO: POST succeeded
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   INFO: GET status: 200
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   INFO: GET succeeded, city is JavaTown
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   INFO: DELETE status: 204
   Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
   ```

```
INFO: DELETE succeeded (no content)
Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
INFO: GET status: 200
Jan 18, 2011 2:40:20 PM customer.rest.client.CustomerClient main
INFO: After DELETE, city is: null
BUILD SUCCESSFUL (total time: 5 seconds)
```

▼ To Run the `customer` Example Using the Web Services Tester

1 In NetBeans IDE, right-click the customer node and click Test RESTful Web Services.

The step deploys the application and brings up a test client in the browser.

2 When the test client appears, select the Customer resource node in the left pane.

3 Paste the following XML code into the Content text box, replacing "Insert content here":

```
<?xml version="1.0" encoding="UTF-8"?>
<ora:customer xmlns:ora="http://examples.oracle.com"
  xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
  xsi:schemaLocation="http://examples.oracle.com Customer.xsd">
<ora:id>1</ora:id>
<ora:firstName>Duke</ora:firstName>
<ora:lastName>OfJava</ora:lastName>
<ora:city>JavaTown</ora:city>
<ora:country>USA</ora:country>
</ora:customer>
```

You can find the code in the file `customer/sample-input.txt`.

4 Click Test.

The following message appears in the window below:

```
Status: 201 (Created)
```

Below it is a POST `RequestFailed` message, which you can ignore.

5 Expand the Customer node and click `{id}`.

6 Type `1` in the id field and click Test to test the GET method.

The following status message appears:

```
Status: 200 (OK)
```

The XML output for the resource appears in the Response window:

```
<?xml version="1.0" encoding="UTF-8"?>
    <customer xmlns="http://examples.oracle.com">
        <id>1</id>
        <firstName>Duke</firstName>
        <lastName>OfJava</lastName>
        <city>JavaTown</city>
        <country>USA</country>
    </customer>
```

A GET for a nonexistent ID also returns a 200 (OK) status, but the output in the Response window shows no content:

```
<?xml version="1.0" encoding="UTF-8"?>
   <customer xmlns="http://examples.oracle.com"
     xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance" xsi:nil="true"/>
```

You can test other methods as follows:

- Click PUT, type the input for an existing customer, modify any content except the id value, and click Test to update the customer fields. A successful update returns the following status message:

  ```
  Status: 303 (See Other)
  ```

- Click DELETE, type the ID for an existing customer, and click Test to remove the customer. A successful delete returns the following status message:

  ```
  Status: 303 (See Other)
  ```

Using Curl to Run the customer Example Application

Curl is a command-line tool that you can use to run the customer application on UNIX platforms. You can download Curl from http://curl.haxx.se or add it to a Cygwin installation.

To add a new customer and test the POST method, use the following command:

```
curl -i --data @sample-input.txt \
--header Content-type:application/xml http://localhost:8080/customer/Customer
```

A successful POST returns an HTTP Status: 201 (Created) status.

To retrieve the details of the customer whose id is 1, use the following command:

```
curl -i -X GET http://localhost:8080/customer/Customer/1
```

A successful GET returns an HTTP Status: 200 (OK) status.

To delete a customer record, use the following command:

```
curl -i -X DELETE http://localhost:8080/customer/Customer/1
```

A successful DELETE returns an HTTP Status: 303 status.

PART IV

Enterprise Beans

Part IV explores Enterprise JavaBeans components. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 22

Enterprise Beans

Enterprise beans are Java EE components that implement Enterprise JavaBeans (EJB) technology. Enterprise beans run in the EJB container, a runtime environment within the GlassFish Server (see "Container Types" on page 46). Although transparent to the application developer, the EJB container provides system-level services, such as transactions and security, to its enterprise beans. These services enable you to quickly build and deploy enterprise beans, which form the core of transactional Java EE applications.

The following topics are addressed here:

What Is an Enterprise Bean?

Written in the Java programming language, an enterprise bean is a server-side component that encapsulates the business logic of an application. The business logic is the code that fulfills the purpose of the application. In an inventory control application, for example, the enterprise beans might implement the business logic in methods called `checkInventoryLevel` and `orderProduct`. By invoking these 32–bit methods, clients can access the inventory services provided by the application.

Benefits of Enterprise Beans

For several reasons, enterprise beans simplify the development of large, distributed applications. First, because the EJB container provides system-level services to enterprise beans, the bean developer can concentrate on solving business problems. The EJB container, rather than the bean developer, is responsible for system-level services, such as transaction management and security authorization.

Second, because the beans rather than the clients contain the application's business logic, the client developer can focus on the presentation of the client. The client developer does not have to code the routines that implement business rules or access databases. As a result, the clients are thinner, a benefit that is particularly important for clients that run on small devices.

Third, because enterprise beans are portable components, the application assembler can build new applications from existing beans. Provided that they use the standard APIs, these applications can run on any compliant Java EE server.

When to Use Enterprise Beans

You should consider using enterprise beans if your application has any of the following requirements.

- The application must be scalable. To accommodate a growing number of users, you may need to distribute an application's components across multiple machines. Not only can the enterprise beans of an application run on different machines, but also their location will remain transparent to the clients.
- Transactions must ensure data integrity. Enterprise beans support transactions, the mechanisms that manage the concurrent access of shared objects.
- The application will have a variety of clients. With only a few lines of code, remote clients can easily locate enterprise beans. These clients can be thin, various, and numerous.

Types of Enterprise Beans

Table 22–1 summarizes the two types of enterprise beans. The following sections discuss each type in more detail.

TABLE 22–1 Enterprise Bean Types

Enterprise Bean Type	Purpose
Session	Performs a task for a client; optionally, may implement a web service
Message-driven	Acts as a listener for a particular messaging type, such as the Java Message Service API

What Is a Session Bean?

A *session bean* encapsulates business logic that can be invoked programmatically by a client over local, remote, or web service client views. To access an application that is deployed on the server, the client invokes the session bean's methods. The session bean performs work for its client, shielding it from complexity by executing business tasks inside the server.

A session bean is not persistent. (That is, its data is not saved to a database.)

For code samples, see Chapter 24, "Running the Enterprise Bean Examples."

Types of Session Beans

Session beans are of three types: stateful, stateless, and singleton.

Stateful Session Beans

The state of an object consists of the values of its instance variables. In a *stateful session bean*, the instance variables represent the state of a unique client/bean session. Because the client interacts ("talks") with its bean, this state is often called the *conversational state*.

As its name suggests, a session bean is similar to an interactive session. A session bean is not shared; it can have only one client, in the same way that an interactive session can have only one user. When the client terminates, its session bean appears to terminate and is no longer associated with the client.

The state is retained for the duration of the client/bean session. If the client removes the bean, the session ends and the state disappears. This transient nature of the state is not a problem, however, because when the conversation between the client and the bean ends, there is no need to retain the state.

Stateless Session Beans

A *stateless session bean* does not maintain a conversational state with the client. When a client invokes the methods of a stateless bean, the bean's instance variables may contain a state specific to that client but only for the duration of the invocation. When the method is finished, the

client-specific state should not be retained. Clients may, however, change the state of instance variables in pooled stateless beans, and this state is held over to the next invocation of the pooled stateless bean. Except during method invocation, all instances of a stateless bean are equivalent, allowing the EJB container to assign an instance to any client. That is, the state of a stateless session bean should apply across all clients.

Because they can support multiple clients, stateless session beans can offer better scalability for applications that require large numbers of clients. Typically, an application requires fewer stateless session beans than stateful session beans to support the same number of clients.

A stateless session bean can implement a web service, but a stateful session bean cannot.

Singleton Session Beans

A *singleton session bean* is instantiated once per application and exists for the lifecycle of the application. Singleton session beans are designed for circumstances in which a single enterprise bean instance is shared across and concurrently accessed by clients.

Singleton session beans offer similar functionality to stateless session beans but differ from them in that there is only one singleton session bean per application, as opposed to a pool of stateless session beans, any of which may respond to a client request. Like stateless session beans, singleton session beans can implement web service endpoints.

Singleton session beans maintain their state between client invocations but are not required to maintain their state across server crashes or shutdowns.

Applications that use a singleton session bean may specify that the singleton should be instantiated upon application startup, which allows the singleton to perform initialization tasks for the application. The singleton may perform cleanup tasks on application shutdown as well, because the singleton will operate throughout the lifecycle of the application.

When to Use Session Beans

Stateful session beans are appropriate if any of the following conditions are true.

- The bean's state represents the interaction between the bean and a specific client.
- The bean needs to hold information about the client across method invocations.
- The bean mediates between the client and the other components of the application, presenting a simplified view to the client.
- Behind the scenes, the bean manages the work flow of several enterprise beans.

To improve performance, you might choose a stateless session bean if it has any of these traits.

- The bean's state has no data for a specific client.
- In a single method invocation, the bean performs a generic task for all clients. For example, you might use a stateless session bean to send an email that confirms an online order.
- The bean implements a web service.

Singleton session beans are appropriate in the following circumstances.

- State needs to be shared across the application.
- A single enterprise bean needs to be accessed by multiple threads concurrently.
- The application needs an enterprise bean to perform tasks upon application startup and shutdown.
- The bean implements a web service.

What Is a Message-Driven Bean?

A *message-driven bean* is an enterprise bean that allows Java EE applications to process messages asynchronously. This type of bean normally acts as a JMS message listener, which is similar to an event listener but receives JMS messages instead of events. The messages can be sent by any Java EE component (an application client, another enterprise bean, or a web component) or by a JMS application or system that does not use Java EE technology. Message-driven beans can process JMS messages or other kinds of messages.

What Makes Message-Driven Beans Different from Session Beans?

The most visible difference between message-driven beans and session beans is that clients do not access message-driven beans through interfaces. Interfaces are described in the section "Accessing Enterprise Beans" on page 401. Unlike a session bean, a message-driven bean has only a bean class.

In several respects, a message-driven bean resembles a stateless session bean.

- A message-driven bean's instances retain no data or conversational state for a specific client.
- All instances of a message-driven bean are equivalent, allowing the EJB container to assign a message to any message-driven bean instance. The container can pool these instances to allow streams of messages to be processed concurrently.
- A single message-driven bean can process messages from multiple clients.

The instance variables of the message-driven bean instance can contain some state across the handling of client messages, such as a JMS API connection, an open database connection, or an object reference to an enterprise bean object.

Client components do not locate message-driven beans and invoke methods directly on them. Instead, a client accesses a message-driven bean through, for example, JMS by sending messages to the message destination for which the message-driven bean class is the `MessageListener`. You assign a message-driven bean's destination during deployment by using GlassFish Server resources.

Message-driven beans have the following characteristics.

- They execute upon receipt of a single client message.
- They are invoked asynchronously.
- They are relatively short-lived.
- They do not represent directly shared data in the database, but they can access and update this data.
- They can be transaction-aware.
- They are stateless.

When a message arrives, the container calls the message-driven bean's `onMessage` method to process the message. The `onMessage` method normally casts the message to one of the five JMS message types and handles it in accordance with the application's business logic. The `onMessage` method can call helper methods or can invoke a session bean to process the information in the message or to store it in a database.

A message can be delivered to a message-driven bean within a transaction context, so all operations within the `onMessage` method are part of a single transaction. If message processing is rolled back, the message will be redelivered. For more information, see Chapter 43, "Transactions."

When to Use Message-Driven Beans

Session beans allow you to send JMS messages and to receive them synchronously but not asynchronously. To avoid tying up server resources, do not to use blocking synchronous

receives in a server-side component; in general, JMS messages should not be sent or received synchronously. To receive messages asynchronously, use a message-driven bean.

Accessing Enterprise Beans

Note – The material in this section applies only to session beans and not to message-driven beans. Because they have a different programming model, message-driven beans do not have interfaces or no-interface views that define client access.

Clients access enterprise beans either through a *no-interface view* or through a *business interface*. A no-interface view of an enterprise bean exposes the public methods of the enterprise bean implementation class to clients. Clients using the no-interface view of an enterprise bean may invoke any public methods in the enterprise bean implementation class or any superclasses of the implementation class. A business interface is a standard Java programming language interface that contains the business methods of the enterprise bean.

A client can access a session bean only through the methods defined in the bean's business interface or through the public methods of an enterprise bean that has a no-interface view. The business interface or no-interface view defines the client's view of an enterprise bean. All other aspects of the enterprise bean (method implementations and deployment settings) are hidden from the client.

Well-designed interfaces and no-interface views simplify the development and maintenance of Java EE applications. Not only do clean interfaces and no-interface views shield the clients from any complexities in the EJB tier, but they also allow the enterprise beans to change internally without affecting the clients. For example, if you change the implementation of a session bean business method, you won't have to alter the client code. But if you were to change the method definitions in the interfaces, you might have to modify the client code as well. Therefore, it is important that you design the interfaces and no-interface views carefully to isolate your clients from possible changes in the enterprise beans.

Session beans can have more than one business interface. Session beans should, but are not required to, implement their business interface or interfaces.

Using Enterprise Beans in Clients

The client of an enterprise bean obtains a reference to an instance of an enterprise bean through either *dependency injection*, using Java programming language annotations, or *JNDI lookup*, using the Java Naming and Directory Interface syntax to find the enterprise bean instance.

Dependency injection is the simplest way of obtaining an enterprise bean reference. Clients that run within a Java EE server-managed environment, JavaServer Faces web applications, JAX-RS web services, other enterprise beans, or Java EE application clients, support dependency injection using the `javax.ejb.EJB` annotation.

Applications that run outside a Java EE server-managed environment, such as Java SE applications, must perform an explicit lookup. JNDI supports a global syntax for identifying Java EE components to simplify this explicit lookup.

Portable JNDI Syntax

Three JNDI namespaces are used for portable JNDI lookups: `java:global`, `java:module`, and `java:app`.

- The `java:global` JNDI namespace is the portable way of finding remote enterprise beans using JNDI lookups. JNDI addresses are of the following form:

  `java:global[/`*application name*`]/`*module name*`/`*enterprise bean name*`[/`*interface name*`]`

  Application name and module name default to the name of the application and module minus the file extension. Application names are required only if the application is packaged within an EAR. The interface name is required only if the enterprise bean implements more than one business interface.
- The `java:module` namespace is used to look up local enterprise beans within the same module. JNDI addresses using the `java:module` namespace are of the following form:

  `java:module/`*enterprise bean name*`/[`*interface name*`]`

  The interface name is required only if the enterprise bean implements more than one business interface.
- The `java:app` namespace is used to look up local enterprise beans packaged within the same application. That is, the enterprise bean is packaged within an EAR file containing multiple Java EE modules. JNDI addresses using the `java:app` namespace are of the following form:

  `java:app[/`*module name*`]/`*enterprise bean name*`[/`*interface name*`]`

  The module name is optional. The interface name is required only if the enterprise bean implements more than one business interface.

For example, if an enterprise bean, `MyBean`, is packaged within the web application archive `myApp.war`, the module name is `myApp`. The portable JNDI name is `java:module/MyBean` An equivalent JNDI name using the `java:global` namespace is `java:global/myApp/MyBean`.

Deciding on Remote or Local Access

When you design a Java EE application, one of the first decisions you make is the type of client access allowed by the enterprise beans: remote, local, or web service.

Whether to allow local or remote access depends on the following factors.

- **Tight or loose coupling of related beans**: Tightly coupled beans depend on one another. For example, if a session bean that processes sales orders calls a session bean that emails a confirmation message to the customer, these beans are tightly coupled. Tightly coupled beans are good candidates for local access. Because they fit together as a logical unit, they typically call each other often and would benefit from the increased performance that is possible with local access.
- **Type of client**: If an enterprise bean is accessed by application clients, it should allow remote access. In a production environment, these clients almost always run on machines other than those on which the GlassFish Server is running. If an enterprise bean's clients are web components or other enterprise beans, the type of access depends on how you want to distribute your components.
- **Component distribution**: Java EE applications are scalable because their server-side components can be distributed across multiple machines. In a distributed application, for example, the server that the web components run on may not be the one on which the enterprise beans they access are deployed. In this distributed scenario, the enterprise beans should allow remote access.
- **Performance**: Owing to such factors as network latency, remote calls may be slower than local calls. On the other hand, if you distribute components among different servers, you may improve the application's overall performance. Both of these statements are generalizations; performance can vary in different operational environments. Nevertheless, you should keep in mind how your application design might affect performance.

If you aren't sure which type of access an enterprise bean should have, choose remote access. This decision gives you more flexibility. In the future, you can distribute your components to accommodate the growing demands on your application.

Although it is uncommon, it is possible for an enterprise bean to allow both remote and local access. If this is the case, either the business interface of the bean must be explicitly designated as a business interface by being decorated with the `@Remote` or `@Local` annotations, or the bean class must explicitly designate the business interfaces by using the `@Remote` and `@Local` annotations. The same business interface cannot be both a local and a remote business interface.

Local Clients

A local client has these characteristics.

- It must run in the same application as the enterprise bean it accesses.
- It can be a web component or another enterprise bean.
- To the local client, the location of the enterprise bean it accesses is not transparent.

The no-interface view of an enterprise bean is a local view. The public methods of the enterprise bean implementation class are exposed to local clients that access the no-interface view of the enterprise bean. Enterprise beans that use the no-interface view do not implement a business interface.

The *local business interface* defines the bean's business and lifecycle methods. If the bean's business interface is not decorated with `@Local` or `@Remote`, and if the bean class does not specify the interface using `@Local` or `@Remote`, the business interface is by default a local interface.

To build an enterprise bean that allows only local access, you may, but are not required to, do one of the following:

- Create an enterprise bean implementation class that does not implement a business interface, indicating that the bean exposes a no-interface view to clients. For example:

```
@Session
public class MyBean { ... }
```

- Annotate the business interface of the enterprise bean as a `@Local` interface. For example:

```
@Local
public interface InterfaceName { ... }
```

- Specify the interface by decorating the bean class with `@Local` and specify the interface name. For example:

```
@Local(InterfaceName.class)
public class BeanName implements InterfaceName { ... }
```

Accessing Local Enterprise Beans Using the No-Interface View

Client access to an enterprise bean that exposes a local, no-interface view is accomplished through either dependency injection or JNDI lookup.

- To obtain a reference to the no-interface view of an enterprise bean through dependency injection, use the `javax.ejb.EJB` annotation and specify the enterprise bean's implementation class:

```
@EJB
ExampleBean exampleBean;
```

- To obtain a reference to the no-interface view of an enterprise bean through JNDI lookup, use the `javax.naming.InitialContext` interface's `lookup` method:

```
ExampleBean exampleBean = (ExampleBean)
        InitialContext.lookup("java:module/ExampleBean");
```

Clients *do not* use the `new` operator to obtain a new instance of an enterprise bean that uses a no-interface view.

Accessing Local Enterprise Beans That Implement Business Interfaces

Client access to enterprise beans that implement local business interfaces is accomplished through either dependency injection or JNDI lookup.

- To obtain a reference to the local business interface of an enterprise bean through dependency injection, use the `javax.ejb.EJB` annotation and specify the enterprise bean's local business interface name:

```
@EJB
Example example;
```

- To obtain a reference to a local business interface of an enterprise bean through JNDI lookup, use the `javax.naming.InitialContext` interface's `lookup` method:

```
ExampleLocal example = (ExampleLocal)
        InitialContext.lookup("java:module/ExampleLocal");
```

Remote Clients

A remote client of an enterprise bean has the following traits.

- It can run on a different machine and a different JVM from the enterprise bean it accesses. (It is not required to run on a different JVM.)
- It can be a web component, an application client, or another enterprise bean.
- To a remote client, the location of the enterprise bean is transparent.
- The enterprise bean must implement a business interface. That is, remote clients *may not* access an enterprise bean through a no-interface view.

To create an enterprise bean that allows remote access, you must either

- Decorate the business interface of the enterprise bean with the `@Remote` annotation:

```
@Remote
public interface InterfaceName { ... }
```

- Decorate the bean class with `@Remote`, specifying the business interface or interfaces:

```
@Remote(InterfaceName.class)
public class BeanName implements InterfaceName { ... }
```

The *remote interface* defines the business and lifecycle methods that are specific to the bean. For example, the remote interface of a bean named `BankAccountBean` might have business methods named `deposit` and `credit`. Figure 22–1 shows how the interface controls the client's view of an enterprise bean.

FIGURE 22–1 Interfaces for an Enterprise Bean with Remote Access



Client access to an enterprise bean that implements a remote business interface is accomplished through either dependency injection or JNDI lookup.

- To obtain a reference to the remote business interface of an enterprise bean through dependency injection, use the `javax.ejb.EJB` annotation and specify the enterprise bean's remote business interface name:

```
@EJB
Example example;
```

- To obtain a reference to a remote business interface of an enterprise bean through JNDI lookup, use the `javax.naming.InitialContext` interface's `lookup` method:

```
ExampleRemote example = (ExampleRemote)
        InitialContext.lookup("java:global/myApp/ExampleRemote");
```

Web Service Clients

A web service client can access a Java EE application in two ways. First, the client can access a web service created with JAX-WS. (For more information on JAX-WS, see Chapter 18, "Building Web Services with JAX-WS.") Second, a web service client can invoke the business methods of a stateless session bean. Message beans cannot be accessed by web service clients.

Provided that it uses the correct protocols (SOAP, HTTP, WSDL), any web service client can access a stateless session bean, whether or not the client is written in the Java programming language. The client doesn't even "know" what technology implements the service: stateless session bean, JAX-WS, or some other technology. In addition, enterprise beans and web components can be clients of web services. This flexibility enables you to integrate Java EE applications with web services.

A web service client accesses a stateless session bean through the bean's web service endpoint implementation class. By default, all public methods in the bean class are accessible to web service clients. The `@WebMethod` annotation may be used to customize the behavior of web service methods. If the `@WebMethod` annotation is used to decorate the bean class's methods, only those methods decorated with `@WebMethod` are exposed to web service clients.

For a code sample, see "A Web Service Example: `helloservice`" on page 435.

Method Parameters and Access

The type of access affects the parameters of the bean methods that are called by clients. The following sections apply not only to method parameters but also to method return values.

Isolation

The parameters of remote calls are more isolated than those of local calls. With remote calls, the client and the bean operate on different copies of a parameter object. If the client changes the value of the object, the value of the copy in the bean does not change. This layer of isolation can help protect the bean if the client accidentally modifies the data.

In a local call, both the client and the bean can modify the same parameter object. In general, you should not rely on this side effect of local calls. Perhaps someday you will want to distribute your components, replacing the local calls with remote ones.

As with remote clients, web service clients operate on different copies of parameters than does the bean that implements the web service.

Granularity of Accessed Data

Because remote calls are likely to be slower than local calls, the parameters in remote methods should be relatively coarse-grained. A coarse-grained object contains more data than a fine-grained one, so fewer access calls are required. For the same reason, the parameters of the methods called by web service clients should also be coarse-grained.

The Contents of an Enterprise Bean

To develop an enterprise bean, you must provide the following files:

- **Enterprise bean class**: Implements the business methods of the enterprise bean and any lifecycle callback methods.
- **Business interfaces**: Define the business methods implemented by the enterprise bean class. A business interface is not required if the enterprise bean exposes a local, no-interface view.
- **Helper classes**: Other classes needed by the enterprise bean class, such as exception and utility classes.

Package the programming artifacts in the preceding list either into an EJB JAR file (a stand-alone module that stores the enterprise bean) or within a web application archive (WAR) module.

Packaging Enterprise Beans in EJB JAR Modules

An EJB JAR file is portable and can be used for various applications.

To assemble a Java EE application, package one or more modules, such as EJB JAR files, into an EAR file, the archive file that holds the application. When deploying the EAR file that contains the enterprise bean's EJB JAR file, you also deploy the enterprise bean to the GlassFish Server. You can also deploy an EJB JAR that is not contained in an EAR file. Figure 22–2 shows the contents of an EJB JAR file.

FIGURE 22–2 Structure of an Enterprise Bean JAR



Packaging Enterprise Beans in WAR Modules

Enterprise beans often provide the business logic of a web application. In these cases, packaging the enterprise bean within the web application's WAR module simplifies deployment and application organization. Enterprise beans may be packaged within a WAR module as Java programming language class files or within a JAR file that is bundled within the WAR module.

To include enterprise bean class files in a WAR module, the class files should be in the `WEB-INF/classes` directory.

To include a JAR file that contains enterprise beans in a WAR module, add the JAR to the `WEB-INF/lib` directory of the WAR module.

WAR modules that contain enterprise beans do not require an `ejb-jar.xml` deployment descriptor. If the application uses `ejb-jar.xml`, it must be located in the WAR module's `WEB-INF` directory.

JAR files that contain enterprise bean classes packaged within a WAR module are not considered EJB JAR files, even if the bundled JAR file conforms to the format of an EJB JAR file.

The enterprise beans contained within the JAR file are semantically equivalent to enterprise beans located in the WAR module's `WEB-INF/classes` directory, and the environment namespace of all the enterprise beans are scoped to the WAR module.

For example, suppose that a web application consists of a shopping cart enterprise bean, a credit card processing enterprise bean, and a Java servlet front end. The shopping cart bean exposes a local, no-interface view and is defined as follows:

```
package com.example.cart;

@Stateless
public class CartBean { ... }
```

The credit card processing bean is packaged within its own JAR file, `cc.jar`, exposes a local, no-interface view, and is defined as follows:

```
package com.example.cc;

@Stateless
public class CreditCardBean { ... }
```

The servlet, `com.example.web.StoreServlet`, handles the web front end and uses both `CartBean` and `CreditCardBean`. The WAR module layout for this application looks as follows:

```
WEB-INF/classes/com/example/cart/CartBean.class
WEB-INF/classes/com/example/web/StoreServlet
WEB-INF/lib/cc.jar
WEB-INF/ejb-jar.xml
WEB-INF/web.xml
```

Naming Conventions for Enterprise Beans

Because enterprise beans are composed of multiple parts, it's useful to follow a naming convention for your applications. Table 22–2 summarizes the conventions for the example beans in this tutorial.

TABLE 22–2 Naming Conventions for Enterprise Beans

Item	Syntax	Example
Enterprise bean name	*name*`Bean`	`AccountBean`
Enterprise bean class	*name*`Bean`	`AccountBean`
Business interface	*name*	`Account`

The Lifecycles of Enterprise Beans

An enterprise bean goes through various stages during its lifetime, or lifecycle. Each type of enterprise bean (stateful session, stateless session, singleton session, or message-driven) has a different lifecycle.

The descriptions that follow refer to methods that are explained along with the code examples in the next two chapters. If you are new to enterprise beans, you should skip this section and run the code examples first.

The Lifecycle of a Stateful Session Bean

Figure 22–3 illustrates the stages that a session bean passes through during its lifetime. The client initiates the lifecycle by obtaining a reference to a stateful session bean. The container performs any dependency injection and then invokes the method annotated with `@PostConstruct`, if any. The bean is now ready to have its business methods invoked by the client.

FIGURE 22–3 Lifecycle of a Stateful Session Bean



While in the ready stage, the EJB container may decide to deactivate, or *passivate*, the bean by moving it from memory to secondary storage. (Typically, the EJB container uses a least-recently-used algorithm to select a bean for passivation.) The EJB container invokes the method annotated `@PrePassivate`, if any, immediately before passivating it. If a client invokes a business method on the bean while it is in the passive stage, the EJB container activates the bean, calls the method annotated `@PostActivate`, if any, and then moves it to the ready stage.

At the end of the lifecycle, the client invokes a method annotated `@Remove`, and the EJB container calls the method annotated `@PreDestroy`, if any. The bean's instance is then ready for garbage collection.

Your code controls the invocation of only one lifecycle method: the method annotated `@Remove`. All other methods in Figure 22–3 are invoked by the EJB container. See Chapter 44, "Resource Connections," for more information.

The Lifecycle of a Stateless Session Bean

Because a stateless session bean is never passivated, its lifecycle has only two stages: nonexistent and ready for the invocation of business methods. Figure 22–4 illustrates the stages of a stateless session bean.

FIGURE 22–4 Lifecycle of a Stateless Session Bean



The EJB container typically creates and maintains a pool of stateless session beans, beginning the stateless session bean's lifecycle. The container performs any dependency injection and then invokes the method annotated `@PostConstruct`, if it exists. The bean is now ready to have its business methods invoked by a client.

At the end of the lifecycle, the EJB container calls the method annotated `@PreDestroy`, if it exists. The bean's instance is then ready for garbage collection.

The Lifecycle of a Singleton Session Bean

Like a stateless session bean, a singleton session bean is never passivated and has only two stages, nonexistent and ready for the invocation of business methods, as shown in Figure 22–5.

FIGURE 22–5 Lifecycle of a Singleton Session Bean



The EJB container initiates the singleton session bean lifecycle by creating the singleton instance. This occurs upon application deployment if the singleton is annotated with the `@Startup` annotation The container performs any dependency injection and then invokes the method annotated `@PostConstruct`, if it exists. The singleton session bean is now ready to have its business methods invoked by the client.

At the end of the lifecycle, the EJB container calls the method annotated `@PreDestroy`, if it exists. The singleton session bean is now ready for garbage collection.

The Lifecycle of a Message-Driven Bean

Figure 22–6 illustrates the stages in the lifecycle of a message-driven bean.

FIGURE 22–6 Lifecycle of a Message-Driven Bean



The EJB container usually creates a pool of message-driven bean instances. For each instance, the EJB container performs these tasks.

1. If the message-driven bean uses dependency injection, the container injects these references before instantiating the instance.
2. The container calls the method annotated `@PostConstruct`, if any.

Like a stateless session bean, a message-driven bean is never passivated and has only two states: nonexistent and ready to receive messages.

At the end of the lifecycle, the container calls the method annotated `@PreDestroy`, if any. The bean's instance is then ready for garbage collection.

Further Information about Enterprise Beans

For more information on Enterprise JavaBeans technology, see

- Enterprise JavaBeans 3.1 specification:

  `http://jcp.org/en/jsr/summary?id=318`
- Enterprise JavaBeans web site:

  `http://www.oracle.com/technetwork/java/ejb-141389.html`

◆ ◆ ◆ CHAPTER 23

Getting Started with Enterprise Beans

This chapter shows how to develop, deploy, and run a simple Java EE application named `converter`. The purpose of `converter` is to calculate currency conversions between Japanese yen and Eurodollars. The `converter` application consists of an enterprise bean, which performs the calculations, and a web client.

Here's an overview of the steps you'll follow in this chapter:

1. Create the enterprise bean: `ConverterBean`.
2. Create the web client.
3. Deploy `converter` onto the server.
4. Using a browser, run the web client.

Before proceeding, make sure that you've done the following:

- Read Chapter 1, "Overview"
- Become familiar with enterprise beans (see Chapter 22, "Enterprise Beans")
- Started the server (see "Starting and Stopping the GlassFish Server" on page 71)

The following topics are addressed here:

Creating the Enterprise Bean

The enterprise bean in our example is a stateless session bean called `ConverterBean`. The source code for `ConverterBean` is in the *tut-install*`/examples/ejb/converter/src/java/` directory.

Creating `ConverterBean` requires these steps:

1. Coding the bean's implementation class (the source code is provided)
2. Compiling the source code

Coding the Enterprise Bean Class

The enterprise bean class for this example is called `ConverterBean`. This class implements two business methods: `dollarToYen` and `yenToEuro`. Because the enterprise bean class doesn't implement a business interface, the enterprise bean exposes a local, no-interface view. The public methods in the enterprise bean class are available to clients that obtain a reference to `ConverterBean`. The source code for the `ConverterBean` class is as follows:

```
package com.sun.tutorial.javaee.ejb;

import java.math.BigDecimal;
import javax.ejb.*;

@Stateless
public class ConverterBean {
    private BigDecimal yenRate = new BigDecimal("83.0602");
    private BigDecimal euroRate = new BigDecimal("0.0093016");

    public BigDecimal dollarToYen(BigDecimal dollars) {
        BigDecimal result = dollars.multiply(yenRate);
        return result.setScale(2, BigDecimal.ROUND_UP);
    }

    public BigDecimal yenToEuro(BigDecimal yen) {
        BigDecimal result = yen.multiply(euroRate);
        return result.setScale(2, BigDecimal.ROUND_UP);
    }
}
```

Note the `@Stateless` annotation decorating the enterprise bean class. This annotation lets the container know that `ConverterBean` is a stateless session bean.

Creating the `converter` Web Client

The web client is contained in the following servlet class:

tut-install`/examples/ejb/converter/src/java/converter/web/ConverterServlet.java`

A Java servlet is a web component that responds to HTTP requests.

The `ConverterServlet` class uses dependency injection to obtain a reference to `ConverterBean`. The `javax.ejb.EJB` annotation is added to the declaration of the private member variable `converterBean`, which is of type `ConverterBean`. `ConverterBean` exposes a local, no-interface view, so the enterprise bean implementation class is the variable type:

```
@WebServlet
public class ConverterServlet extends HttpServlet {
  @EJB
  ConverterBean converterBean;
  ...
}
```

When the user enters an amount to be converted to yen and euro, the amount is retrieved from the request parameters; then the `ConverterBean.dollarToYen` and the `ConverterBean.yenToEuro` methods are called:

```
...
try {
  String amount = request.getParameter("amount");
  if (amount != null && amount.length() > 0) {
    // convert the amount to a BigDecimal from the request parameter
    BigDecimal d = new BigDecimal(amount);
    // call the ConverterBean.dollarToYen() method to get the amount
    // in Yen
    BigDecimal yenAmount = converter.dollarToYen(d);

    // call the ConverterBean.yenToEuro() method to get the amount
    // in Euros
    BigDecimal euroAmount = converter.yenToEuro(yenAmount);
    ...
  }
  ...
}
```

The results are displayed to the user.

Building, Packaging, Deploying, and Running the `converter` Example

Now you are ready to compile the enterprise bean class (`ConverterBean.java`) and the servlet class (`ConverterServlet.java`) and to package the compiled classes into a WAR file.

▼ To Build, Package, and Deploy the `converter` Example in NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/ejb/`
3. **Select the `converter` folder.**
4. **Select the Open as Main Project and Open Required Projects check boxes.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `converter` project and select Deploy.**

   A web browser window opens the URL `http://localhost:8080/converter`.

▼ To Build, Package, and Deploy the `converter` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/ejb/converter/`

2. **Type the following command:**

   ```
   ant all
   ```

   This command calls the `default` task, which compiles the source files for the enterprise bean and the servlet, placing the class files in the `build` subdirectory (not the `src` directory) of the project. The default task packages the project into a WAR module: `converter.war`. For more information about the Ant tool, see "Building the Examples" on page 73.

Note – When compiling the code, the `ant` task includes the Java EE API JAR files in the classpath. These JARs reside in the `modules` directory of your GlassFish Server installation. If you plan to use other tools to compile the source code for Java EE components, make sure that the classpath includes the Java EE API JAR files.

▼ To Run the `converter` Example

1. **Open a web browser to the following URL:**

   `http://localhost:8080/converter`

   The screen shown in Figure 23–1 appears.

FIGURE 23–1 The `converter` Web Client

2. **Type `100` in the input field and click Submit.**

   A second page appears, showing the converted values.

Modifying the Java EE Application

The GlassFish Server supports iterative development. Whenever you make a change to a Java EE application, you must redeploy the application.

▼ To Modify a Class File

To modify a class file in an enterprise bean, you change the source code, recompile it, and redeploy the application. For example, to update the exchange rate in the `dollarToYen` business method of the `ConverterBean` class, you would follow these steps.

To modify `ConverterServlet`, the procedure is the same.

1. **Edit `ConverterBean.java` and save the file.**

2. **Recompile the source file.**

   - **To recompile `ConverterBean.java` in NetBeans IDE, right-click the `converter` project and select Run.**

     This recompiles the `ConverterBean.java` file, replaces the old class file in the build directory, and redeploys the application to GlassFish Server.

   - **Recompile `ConverterBean.java` using Ant:**

     a. **In a terminal window, go to the *tut-install*`/examples/ejb/converter/` subdirectory.**

     b. **Type the following command:**

        ```
        ant all
        ```

        This command repackages, deploys, and runs the application.

◆ ◆ ◆ CHAPTER 24

Running the Enterprise Bean Examples

Session beans provide a simple but powerful way to encapsulate business logic within an application. They can be accessed from remote Java clients, web service clients, and components running in the same server.

In Chapter 23, "Getting Started with Enterprise Beans," you built a stateless session bean named `ConverterBean`. This chapter examines the source code of four more session beans:

- `CartBean`: a stateful session bean that is accessed by a remote client
- `CounterBean`: a singleton session bean
- `HelloServiceBean`: a stateless session bean that implements a web service
- `TimerSessionBean`: a stateless session bean that sets a timer

The following topics are addressed here:

The `cart` Example

The `cart` example represents a shopping cart in an online bookstore and uses a stateful session bean to manage the operations of the shopping cart. The bean's client can add a book to the cart, remove a book, or retrieve the cart's contents. To assemble `cart`, you need the following code:

- Session bean class (`CartBean`)
- Remote business interface (`Cart`)

All session beans require a session bean class. All enterprise beans that permit remote access must have a remote business interface. To meet the needs of a specific application, an enterprise

bean may also need some helper classes. The `CartBean` session bean uses two helper classes, `BookException` and `IdVerifier`, which are discussed in the section "Helper Classes" on page 426.

The source code for this example is in the *tut-install*`/examples/ejb/cart/` directory.

The Business Interface

The `Cart` business interface is a plain Java interface that defines all the business methods implemented in the bean class. If the bean class implements a single interface, that interface is assumed to the business interface. The business interface is a local interface unless it is annotated with the `javax.ejb.Remote` annotation; the `javax.ejb.Local` annotation is optional in this case.

The bean class may implement more than one interface. In that case, the business interfaces must either be explicitly annotated `@Local` or `@Remote` or be specified by decorating the bean class with `@Local` or `@Remote`. However, the following interfaces are excluded when determining whether the bean class implements more than one interface:

- `java.io.Serializable`
- `java.io.Externalizable`
- Any of the interfaces defined by the `javax.ejb` package

The source code for the `Cart` business interface follows:

```
package com.sun.tutorial.javaee.ejb;

import java.util.List;
import javax.ejb.Remote;

@Remote
public interface Cart {
    public void initialize(String person) throws BookException;
    public void initialize(String person, String id)
         throws BookException;
    public void addBook(String title);
    public void removeBook(String title) throws BookException;
    public List<String> getContents();
    public void remove();
}
```

Session Bean Class

The session bean class for this example is called `CartBean`. Like any stateful session bean, the `CartBean` class must meet the following requirements.

- The class is annotated `@Stateful`.
- The class implements the business methods defined in the business interface.

Stateful session beans also may

- Implement the business interface, a plain Java interface. It is good practice to implement the bean's business interface.
- Implement any optional lifecycle callback methods, annotated `@PostConstruct`, `@PreDestroy`, `@PostActivate`, and `@PrePassivate`.
- Implement any optional business methods annotated `@Remove`.

The source code for the `CartBean` class follows:

```
package com.sun.tutorial.javaee.ejb;

import java.util.ArrayList;
import java.util.List;
import javax.ejb.Remove;
import javax.ejb.Stateful;

@Stateful
public class CartBean implements Cart {
    String customerName;
    String customerId;
    List<String> contents;

    public void initialize(String person) throws BookException {
        if (person == null) {
            throw new BookException("Null person not allowed.");
        } else {
            customerName = person;
        }

        customerId = "0";
        contents = new ArrayList<String>();
    }

    public void initialize(String person, String id)
                throws BookException {
        if (person == null) {
            throw new BookException("Null person not allowed.");
        } else {

            customerName = person;
        }

        IdVerifier idChecker = new IdVerifier();

        if (idChecker.validate(id)) {
            customerId = id;
        } else {
            throw new BookException("Invalid id: " + id);
        }

        contents = new ArrayList<String>();
    }

    public void addBook(String title) {
        contents.add(title);
```

```
    }

    public void removeBook(String title) throws BookException {
        boolean result = contents.remove(title);
        if (result == false) {
            throw new BookException(title + " not in cart.");
        }
    }

    public List<String> getContents() {
        return contents;
    }

    @Remove
    public void remove() {
        contents = null;
    }
}
```

Lifecycle Callback Methods

A method in the bean class may be declared as a lifecycle callback method by annotating the method with the following annotations:

- `javax.annotation.PostConstruct`: Methods annotated with `@PostConstruct` are invoked by the container on newly constructed bean instances after all dependency injection has completed and before the first business method is invoked on the enterprise bean.
- `javax.annotation.PreDestroy`: Methods annotated with `@PreDestroy` are invoked after any method annotated `@Remove` has completed and before the container removes the enterprise bean instance.
- `javax.ejb.PostActivate`: Methods annotated with `@PostActivate` are invoked by the container after the container moves the bean from secondary storage to active status.
- `javax.ejb.PrePassivate`: Methods annotated with `@PrePassivate` are invoked by the container before it passivates the enterprise bean, meaning that the container temporarily removes the bean from the environment and saves it to secondary storage.

Lifecycle callback methods must return `void` and have no parameters.

Business Methods

The primary purpose of a session bean is to run business tasks for the client. The client invokes business methods on the object reference it gets from dependency injection or JNDI lookup. From the client's perspective, the business methods appear to run locally, although they run remotely in the session bean. The following code snippet shows how the `CartClient` program invokes the business methods:

```
cart.create("Duke DeEarl", "123");
...
cart.addBook("Bel Canto");
 ...
```

```
List<String> bookList = cart.getContents();
...
cart.removeBook("Gravity's Rainbow");
```

The `CartBean` class implements the business methods in the following code:

```
public void addBook(String title) {
   contents.addElement(title);
}

public void removeBook(String title) throws BookException {
   boolean result = contents.remove(title);
   if (result == false) {
      throw new BookException(title + "not in cart.");
   }
}

public List<String> getContents() {
   return contents;
}
```

The signature of a business method must conform to these rules.

- The method name must not begin with `ejb`, to avoid conflicts with callback methods defined by the EJB architecture. For example, you cannot call a business method `ejbCreate` or `ejbActivate`.
- The access control modifier must be `public`.
- If the bean allows remote access through a remote business interface, the arguments and return types must be legal types for the Java Remote Method Invocation (RMI) API.
- If the bean is a web service endpoint, the arguments and return types for the methods annotated `@WebMethod` must be legal types for JAX-WS.
- The modifier must not be `static` or `final`.

The `throws` clause can include exceptions that you define for your application. The `removeBook` method, for example, throws a `BookException` if the book is not in the cart.

To indicate a system-level problem, such as the inability to connect to a database, a business method should throw a `javax.ejb.EJBException`. The container will not wrap application exceptions, such as `BookException`. Because `EJBException` is a subclass of `RuntimeException`, you do not need to include it in the `throws` clause of the business method.

The `@Remove` Method

Business methods annotated with `javax.ejb.Remove` in the stateful session bean class can be invoked by enterprise bean clients to remove the bean instance. The container will remove the enterprise bean after a `@Remove` method completes, either normally or abnormally.

In `CartBean`, the `remove` method is a `@Remove` method:

```
@Remove
public void remove() {
    contents = null;
}
```

Helper Classes

The `CartBean` session bean has two helper classes: `BookException` and `IdVerifier`. The `BookException` is thrown by the `removeBook` method, and the `IdVerifier` validates the `customerId` in one of the `create` methods. Helper classes may reside in an EJB JAR file that contains the enterprise bean class, a WAR file if the enterprise bean is packaged within a WAR, or in an EAR that contains an EJB JAR or a WAR file that contains an enterprise bean.

Building, Packaging, Deploying, and Running the `cart` Example

Now you are ready to compile the remote interface (`Cart.java`), the home interface (`CartHome.java`), the enterprise bean class (`CartBean.java`), the client class (`CartClient.java`), and the helper classes (`BookException.java` and `IdVerifier.java`). Follow these steps.

You can build, package, deploy, and run the `cart` application using either NetBeans IDE or the Ant tool.

▼ To Build, Package, Deploy, and Run the `cart` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/ejb/`
3. **Select the `cart` folder.**
4. **Select the Open as Main Project and Open Required Projects check boxes.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `cart` project and select Deploy.**
   This builds and packages the application into `cart.ear`, located in *tut-install*`/examples/ejb/cart/dist/`, and deploys this EAR file to your GlassFish Server instance.

7. **From the Run menu, choose Run Main Project.**

   You will see the output of the `cart` application client in the Output pane:

```
...
Retrieving book title from cart: Infinite Jest
Retrieving book title from cart: Bel Canto
Retrieving book title from cart: Kafka on the Shore
Removing "Gravity's Rainbow" from cart.
Caught a BookException: "Gravity's Rainbow" not in cart.
Java Result: 1
run-cart-app-client:
run-nb:
BUILD SUCCESSFUL (total time: 14 seconds)
```

▼ To Build, Package, Deploy, and Run the `cart` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/ejb/cart/`

2. **Type the following command:**

   `ant`

   This command calls the `default` target, which builds and packages the application into an EAR file, `cart.ear`, located in the `dist` directory.

3. **Type the following command:**

   `ant deploy`

   The `cart.ear` file is deployed to the GlassFish Server.

4. **Type the following command:**

   `ant run`

   This task retrieves the application client JAR, `cartClient.jar`, and runs the application client. The client JAR, `cartClient.jar`, contains the application client class, the helper class `BookException`, and the `Cart` business interface.

   This task is equivalent to running the following command:

   `appclient -client cartClient.jar`

   When you run the client, the application client container injects any component references declared in the application client class, in this case the reference to the `Cart` enterprise bean.

The `all` Task

As a convenience, the `all` task will build, package, deploy, and run the application. To do this, enter the following command:

`ant all`

A Singleton Session Bean Example: counter

The counter example demonstrates how to create a singleton session bean.

Creating a Singleton Session Bean

The javax.ejb.Singleton annotation is used to specify that the enterprise bean implementation class is a singleton session bean:

```
@Singleton
public class SingletonBean { ... }
```

Initializing Singleton Session Beans

The EJB container is responsible for determining when to initialize a singleton session bean instance unless the singleton session bean implementation class is annotated with the javax.ejb.Startup annotation. In this case, sometimes called *eager initialization*, the EJB container must initialize the singleton session bean upon application startup. The singleton session bean is initialized before the EJB container delivers client requests to any enterprise beans in the application. This allows the singleton session bean to perform, for example, application startup tasks.

The following singleton session bean stores the status of an application and is eagerly initialized:

```
@Startup
@Singleton
public class StatusBean {
  private String status;

  @PostConstruct
  void init {
    status = "Ready";
  }
  ...
}
```

Sometimes multiple singleton session beans are used to initialize data for an application and therefore must be initialized in a specific order. In these cases, use the javax.ejb.DependsOn annotation to declare the startup dependencies of the singleton session bean. The @DependsOn annotation's value attribute is one or more strings that specify the name of the target singleton session bean. If more than one dependent singleton bean is specified in @DependsOn, the order in which they are listed is not necessarily the order in which the EJB container will initialize the target singleton session beans.

The following singleton session bean, PrimaryBean, should be started up first:

```
@Singleton
public class PrimaryBean { ... }
```

SecondaryBean depends on PrimaryBean:

```
@Singleton
@DependsOn("PrimaryBean")
public class SecondaryBean { ... }
```

This guarantees that the EJB container will initialize PrimaryBean before SecondaryBean.

The following singleton session bean, TertiaryBean, depends on PrimaryBean and SecondaryBean:

```
@Singleton
@DependsOn("PrimaryBean", "SecondaryBean")
public class TertiaryBean { ... }
```

SecondaryBean explicitly requires PrimaryBean to be initialized before it is initialized, through its own @DependsOn annotation. In this case, the EJB container will first initialize PrimaryBean, then SecondaryBean, and finally TertiaryBean.

If, however, SecondaryBean did not explicitly depend on PrimaryBean, the EJB container may initialize either PrimaryBean or SecondaryBean first. That is, the EJB container could initialize the singletons in the following order: SecondaryBean, PrimaryBean, TertiaryBean.

Managing Concurrent Access in a Singleton Session Bean

Singleton session beans are designed for *concurrent access*, situations in which many clients need to access a single instance of a session bean at the same time. A singleton's client needs only a reference to a singleton in order to invoke any business methods exposed by the singleton and doesn't need to worry about any other clients that may be simultaneously invoking business methods on the same singleton.

When creating a singleton session bean, concurrent access to the singleton's business methods can be controlled in two ways: *container-managed concurrency* and *bean-managed concurrency*.

The javax.ejb.ConcurrencyManagement annotation is used to specify container-managed or bean-managed concurrency for the singleton. With @ConcurrencyManagement, a type attribute must be set to either javax.ejb.ConcurrencyManagementType.CONTAINER or javax.ejb.ConcurrencyManagementType.BEAN. If no @ConcurrencyManagement annotation is present on the singleton implementation class, the EJB container default of container-managed concurrency is used.

Container-Managed Concurrency

If a singleton uses container-managed concurrency, the EJB container controls client access to the business methods of the singleton. The javax.ejb.Lock annotation and a javax.ejb.LockType type are used to specify the access level of the singleton's business methods or @Timeout methods.

Annotate a singleton's business or timeout method with `@Lock(READ)` if the method can be concurrently accessed, or shared, with many clients. Annotate the business or timeout method with `@Lock(WRITE)` if the singleton session bean should be locked to other clients while a client is calling that method. Typically, the `@Lock(WRITE)` annotation is used when clients are modifying the state of the singleton.

Annotating a singleton class with `@Lock` specifies that all the business methods and any timeout methods of the singleton will use the specified lock type unless they explicitly set the lock type with a method-level `@Lock` annotation. If no `@Lock` annotation is present on the singleton class, the default lock type, `@Lock(WRITE)`, is applied to all business and timeout methods.

The following example shows how to use the `@ConcurrencyManagement`, `@Lock(READ)`, and `@Lock(WRITE)` annotations for a singleton that uses container-managed concurrency.

Although by default, singletons use container-managed concurrency, the `@ConcurrencyManagement(CONTAINER)` annotation may be added at the class level of the singleton to explicitly set the concurrency management type:

```
@ConcurrencyManagement(CONTAINER)
@Singleton
public class ExampleSingletonBean {
  private String state;

  @Lock(READ)
  public String getState() {
    return state;
  }

  @Lock(WRITE)
  public void setState(String newState) {
    state = newState;
  }
}
```

The `getState` method can be accessed by many clients at the same time because it is annotated with `@Lock(READ)`. When the `setState` method is called, however, all the methods in `ExampleSingletonBean` will be locked to other clients because `setState` is annotated with `@Lock(WRITE)`. This prevents two clients from attempting to simultaneously change the `state` variable of `ExampleSingletonBean`.

The `getData` and `getStatus` methods in the following singleton are of type `READ`, and the `setStatus` method is of type `WRITE`:

```
@Singleton
@Lock(READ)
public class SharedSingletonBean {
  private String data;
  private String status;

  public String getData() {
    return data;
```

```
  }

  public String getStatus() {
    return status;
  }

  @Lock(WRITE)
  public void setStatus(String newStatus) {
    status = newStatus;
  }
}
```

If a method is of locking type `WRITE`, client access to all the singleton's methods is blocked until the current client finishes its method call or an access timeout occurs. When an access timeout occurs, the EJB container throws a `javax.ejb.ConcurrentAccessTimeoutException`. The `javax.ejb.AccessTimeout` annotation is used to specify the number of milliseconds before an access timeout occurs. If added at the class level of a singleton, `@AccessTimeout` specifies the access timeout value for all methods in the singleton unless a method explicitly overrides the default with its own `@AccessTimeout` annotation.

The `@AccessTimeout` annotation can be applied to both `@Lock(READ)` and `@Lock(WRITE)` methods. The `@AccessTimeout` annotation has one required element, `value`, and one optional element, `unit`. By default, the `value` is specified in milliseconds. To change the `value` unit, set `unit` to one of the `java.util.concurrent.TimeUnit` constants: `NANOSECONDS`, `MICROSECONDS`, `MILLISECONDS`, or `SECONDS`.

The following singleton has a default access timeout value of 120,000 milliseconds, or 2 minutes. The `doTediousOperation` method overrides the default access timeout and sets the value to 360,000 milliseconds, or 6 minutes.

```
@Singleton
@AccessTimeout(value=120000)
public class StatusSingletonBean {
  private String status;

  @Lock(WRITE)
  public void setStatus(String new Status) {
    status = newStatus;
  }

  @Lock(WRITE)
  @AccessTimeout(value=360000)
  public void doTediousOperation {
    ...
  }
}
```

The following singleton has a default access timeout value of 60 seconds, specified using the `TimeUnit.SECONDS` constant:

```
@Singleton
@AccessTimeout(value=60, timeUnit=SECONDS)
public class StatusSingletonBean { ... }
```

Bean-Managed Concurrency

Singletons that use bean-managed concurrency allow full concurrent access to all the business and timeout methods in the singleton. The developer of the singleton is responsible for ensuring that the state of the singleton is synchronized across all clients. Developers who create singletons with bean-managed concurrency are allowed to use the Java programming language synchronization primitives, such as `synchronization` and `volatile`, to prevent errors during concurrent access.

Add a `@ConcurrencyManagement` annotation at the class level of the singleton to specify bean-managed concurrency:

```
@ConcurrencyManagement(BEAN)
@Singleton
public class AnotherSingletonBean { ... }
```

Handling Errors in a Singleton Session Bean

If a singleton session bean encounters an error when initialized by the EJB container, that singleton instance will be destroyed.

Unlike other enterprise beans, once a singleton session bean instance is initialized, it is not destroyed if the singleton's business or lifecycle methods cause system exceptions. This ensures that the same singleton instance is used throughout the application lifecycle.

The Architecture of the `counter` Example

The `counter` example consists of a singleton session bean, `CounterBean`, and a JavaServer Faces Facelets web front end.

`CounterBean` is a simple singleton with one method, `getHits`, that returns an integer representing the number of times a web page has been accessed. Here is the code of `CounterBean`:

```
package counter.ejb;

import javax.ejb.Singleton;

/**
 * CounterBean is a simple singleton session bean that records the number
 * of hits to a web page.
 */
@Singleton
public class CounterBean {
    private int hits = 1;

    // Increment and return the number of hits
    public int getHits() {
        return hits++;
    }
}
```

The @Singleton annotation marks CounterBean as a singleton session bean. CounterBean uses a local, no-interface view.

CounterBean uses the EJB container's default metadata values for singletons to simplify the coding of the singleton implementation class. There is no @ConcurrencyManagement annotation on the class, so the default of container-managed concurrency access is applied. There is no @Lock annotation on the class or business method, so the default of @Lock(WRITE) is applied to the only business method, getHits.

The following version of CounterBean is functionally equivalent to the preceding version:

```
package counter.ejb;

import javax.ejb.Singleton;
import javax.ejb.ConcurrencyManagement;
import static javax.ejb.ConcurrencyManagementType.CONTAINER;
import javax.ejb.Lock;
import javax.ejb.LockType.WRITE;

/**
 * CounterBean is a simple singleton session bean that records the number
 * of hits to a web page.
 */
@Singleton
@ConcurrencyManagement(CONTAINER)
public class CounterBean {
    private int hits = 1;

    // Increment and return the number of hits
    @Lock(WRITE)
    public int getHits() {
        return hits++;
    }
}
```

The web front end of counter consists of a JavaServer Faces managed bean, Count.java, that is used by the Facelets XHTML files template.xhtml and template-client.xhtml. The Count JavaServer Faces managed bean obtains a reference to CounterBean through dependency injection. Count defines a hitCount JavaBeans property. When the getHitCount getter method is called from the XHTML files, CounterBean's getHits method is called to return the current number of page hits.

Here's the Count managed bean class:

```
@ManagedBean
@SessionScoped
public class Count {
    @EJB
    private CounterBean counterBean;

    private int hitCount;

    public Count() {
```

```
        this.hitCount = 0;
    }

    public int getHitCount() {
        hitCount = counterBean.getHits();
        return hitCount;
    }
    public void setHitCount(int newHits) {
        this.hitCount = newHits;
    }
}
```

The `template.xhtml` and `template-client.xhtml` files are used to render a Facelets view that displays the number of hits to that view. The `template-client.xhtml` file uses an expression language statement, `#{count.hitCount}`, to access the `hitCount` property of the `Count` managed bean. Here is the content of `template-client.xhtml`:

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
    "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:ui="http://java.sun.com/jsf/facelets"
      xmlns:h="http://java.sun.com/jsf/html">
    <body>

        This text above will not be displayed.

        <ui:composition template="/template.xhtml">

            This text will not be displayed.

            <ui:define name="title">
                This page has been accessed #{count.hitCount} time(s).
            </ui:define>

            This text will also not be displayed.

            <ui:define name="body">
                Hooray!
            </ui:define>

            This text will not be displayed.

        </ui:composition>

        This text below will also not be displayed.

    </body>
</html>
```

Building, Packaging, Deploying, and Running the `counter` Example

The `counter` example application can be built, deployed, and run using NetBeans IDE or Ant.

▼ To Build, Package, Deploy, and Run the counter Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install/examples/ejb/
3. **Select the counter folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the counter project and select Run.**
   A web browser will open the URL http://localhost:8080/counter, which displays the number of hits.
7. **Click the browser's Refresh button to see the hit count increment.**

▼ To Build, Package, Deploy, and Run the counter Example Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/ejb/counter
2. **Type the following command:**
   ```
   ant all
   ```
   This will build and deploy counter to your GlassFish Server instance.
3. **In a web browser, type the following URL:**
   ```
   http://localhost:8080/counter
   ```
4. **Click the browser's Refresh button to see the hit count increment.**

A Web Service Example: helloservice

This example demonstrates a simple web service that generates a response based on information received from the client. HelloServiceBean is a stateless session bean that implements a single method: sayHello. This method matches the sayHello method invoked by the client described in "A Simple JAX-WS Application Client" on page 344.

The Web Service Endpoint Implementation Class

HelloServiceBean is the endpoint implementation class, typically the primary programming artifact for enterprise bean web service endpoints. The web service endpoint implementation class has the following requirements.

- The class must be annotated with either the javax.jws.WebService or the javax.jws.WebServiceProvider annotation.
- The implementing class may explicitly reference an SEI through the endpointInterface element of the @WebService annotation but is not required to do so. If no endpointInterface is specified in @WebService, an SEI is implicitly defined for the implementing class.
- The business methods of the implementing class must be public and must not be declared static or final.
- Business methods that are exposed to web service clients must be annotated with javax.jws.WebMethod.
- Business methods that are exposed to web service clients must have JAXB-compatible parameters and return types. See the list of JAXB default data type bindings at "Types Supported by JAX-WS" on page 349.
- The implementing class must not be declared final and must not be abstract.
- The implementing class must have a default public constructor.
- The endpoint class must be annotated @Stateless.
- The implementing class must not define the finalize method.
- The implementing class may use the javax.annotation.PostConstruct or javax.annotation.PreDestroy annotations on its methods for lifecycle event callbacks.

  The @PostConstruct method is called by the container before the implementing class begins responding to web service clients.

  The @PreDestroy method is called by the container before the endpoint is removed from operation.

Stateless Session Bean Implementation Class

The HelloServiceBean class implements the sayHello method, which is annotated @WebMethod. The source code for the HelloServiceBean class follows:

```
package com.sun.tutorial.javaee.ejb;

import javax.ejb.Stateless;
import javax.jws.WebMethod;
import javax.jws.WebService;
```

```
@Stateless
@WebService
public class HelloServiceBean {
    private String message = "Hello, ";

    public void HelloServiceBean() {}

    @WebMethod
    public String sayHello(String name) {
        return message + name + ".";
    }
}
```

Building, Packaging, Deploying, and Testing the `helloservice` Example

You can build, package, and deploy the `helloservice` example using either NetBeans IDE or Ant. You can then use the Administration Console to test the web service endpoint methods.

▼ To Build, Package, and Deploy the `helloservice` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/ejb/`
3. **Select the `helloservice` folder.**
4. **Select the Open as Main Project and Open Required Projects check boxes.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `helloservice` project and select Deploy.**

   This builds and packages the application into `helloservice.ear`, located in *tut-install*`/examples/ejb/helloservice/dist`, and deploys this EAR file to the GlassFish Server.

▼ To Build, Package, and Deploy the `helloservice` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/ejb/helloservice/`
2. **Type the following command:**

   `ant`

This runs the `default` task, which compiles the source files and packages the application into a JAR file located at *tut-install*`/examples/ejb/helloservice/dist/helloservice.jar`.

3 **To deploy `helloservice`, type the following command:**

```
ant deploy
```

Upon deployment, the GlassFish Server generates additional artifacts required for web service invocation, including the WSDL file.

▼ To Test the Service without a Client

The GlassFish Server Administration Console allows you to test the methods of a web service endpoint. To test the `sayHello` method of `HelloServiceBean`, follow these steps.

1 **Open the Administration Console by opening the following URL in a web browser:**

```
http://localhost:4848/
```

2 **In the left pane of the Administration Console, select the Applications node.**

3 **In the Applications table, click `helloservice`.**

4 **In the Modules and Components table, click View Endpoint.**

5 **On the Web Service Endpoint Information page, click the Tester link:**

```
/HelloServiceBeanService/HelloServiceBean?Tester
```

A Web Service Test Links page opens.

6 **On the Web Service Test Links page, click the non-secure link (the one that specifies port 8080).**

A HelloServiceBeanService Web Service Tester page opens.

7 **Under Methods, type a name as the parameter to the `sayHello` method.**

8 **Click the `sayHello` button.**

The `sayHello` Method invocation page opens. Under Method returned, you'll see the response from the endpoint.

Using the Timer Service

Applications that model business work flows often rely on timed notifications. The timer service of the enterprise bean container enables you to schedule timed notifications for all types of enterprise beans except for stateful session beans. You can schedule a timed notification to

occur according to a calendar schedule, at a specific time, after a duration of time, or at timed intervals. For example, you could set timers to go off at 10:30 a.m. on May 23, in 30 days, or every 12 hours.

Enterprise bean timers are either *programmatic timers* or *automatic timers*. Programmatic timers are set by explicitly calling one of the timer creation methods of the `TimerService` interface. Automatic timers are created upon the successful deployment of an enterprise bean that contains a method annotated with the `java.ejb.Schedule` or `java.ejb.Schedules` annotations.

Creating Calendar-Based Timer Expressions

Timers can be set according to a calendar-based schedule, expressed using a syntax similar to the UNIX `cron` utility. Both programmatic and automatic timers can use calendar-based timer expressions. Table 24–1 shows the calendar-based timer attributes.

TABLE 24–1 Calendar-Based Timer Attributes

Attribute	Description	Allowable Values	Default Value	Examples
`second`	One or more seconds within a minute	`0` to `59`	`0`	`second="30"`
`minute`	One or more minutes within an hour	`0` to `59`	`0`	`minute="15"`
`hour`	One or more hours within a day	`0` to `23`	`0`	`hour="13"`
`dayOfWeek`	One or more days within a week	`0` to `7` (both 0 and 7 refer to Sunday) `Sun`, `Mon`, `Tue`, `Wed`, `Thu`, `Fri`, `Sat`	*	`dayOfWeek="3"` `dayOfWeek="Mon"`

`dayOfMonth`	One or more days within a month	`1` to `31`
		–7 to –1 (a negative number means the *n*th day or days before the end of the month)
		`Last`
		[`1st`, `2nd`, `3rd`, `4th`, `5th`, `Last`] [`Sun`, `Mon`, `Tue`, `Wed`, `Thu`, `Fri`, `Sat`]
			*	`dayOfMonth="15"`
				`dayOfMonth="–3"`
				`dayOfMonth="Last"`
				`dayOfMonth="2nd Fri"`

`month`	One or more months within a year	`1` to `12` `Jan`, `Feb`, `Mar`, `Apr`, `May`, `Jun`, `Jul`, `Aug`, `Sep`, `Oct`, `Nov`, `Dec`	*	`month="7"` `month="July"`

TABLE 24–1 Calendar-Based Timer Attributes *(Continued)*

Attribute	Description	Allowable Values	Default Value	Examples
`year`	A particular calendar year	A four–digit calendar year	*	`year="2010"`

Specifying Multiple Values in Calendar Expressions

You can specify multiple values in calendar expressions, as described in the following sections.

Using Wildcards in Calendar Expressions

Setting an attribute to an asterisk symbol (*) represents all allowable values for the attribute.

The following expression represents every minute:

```
minute="*"
```

The following expression represents every day of the week:

```
dayOfWeek="*"
```

Specifying a List of Values

To specify two or more values for an attribute, use a comma (`,`) to separate the values. A range of values is allowed as part of a list. Wildcards and intervals, however, are not allowed.

Duplicates within a list are ignored.

The following expression sets the day of the week to Tuesday and Thursday:

```
dayOfWeek="Tue, Thu"
```

The following expression represents 4:00 a.m., every hour from 9:00 a.m. to 5:00 p.m. using a range, and 10:00 p.m.:

```
hour="4,9–17,22"
```

Specifying a Range of Values

Use a dash character (–) to specify an inclusive range of values for an attribute. Members of a range cannot be wildcards, lists, or intervals. A range of the form x–x, is equivalent to the single-valued expression x. A range of the form x–y where x is greater than y is equivalent to the expression x–*maximum value*`,` *minimum value*–y. That is, the expression begins at x, rolls over to the beginning of the allowable values, and continues up to y.

The following expression represents 9:00 a.m. to 5:00 p.m.:

```
hour="9–17"
```

The following expression represents Friday through Monday:

```
dayOfWeek="5–1"
```

The following expression represents the twenty-fifth day of the month to the end of the month, and the beginning of the month to the fifth day of the month:

```
dayOfMonth="25–5"
```

It is equivalent to the following expression:

```
dayOfMonth="25–Last,1–5"
```

Specifying Intervals

The forward slash (`/`) constrains an attribute to a starting point and an interval and is used to specify every `N` seconds, minutes, or hours within the minute, hour, or day. For an expression of the form `x/y`, `x` represents the starting point and `y` represents the interval. The wildcard character may be used in the `x` position of an interval and is equivalent to setting `x` to `0`.

Intervals may be set only for `second`, `minute`, and `hour` attributes.

The following expression represents every 10 minutes within the hour:

```
minute="*/10"
```

It is equivalent to:

```
minute="0,10,20,30,40,50"
```

The following expression represents every 2 hours starting at noon:

```
hour="12/2"
```

Programmatic Timers

When a programmatic timer expires (goes off), the container calls the method annotated `@Timeout` in the bean's implementation class. The `@Timeout` method contains the business logic that handles the timed event.

The `@Timeout` Method

Methods annotated `@Timeout` in the enterprise bean class must return `void` and optionally take a `javax.ejb.Timer` object as the only parameter. They may not throw application exceptions.

```
@Timeout
public void timeout(Timer timer) {
    System.out.println("TimerBean: timeout occurred");
}
```

Creating Programmatic Timers

To create a timer, the bean invokes one of the `create` methods of the `TimerService` interface. These methods allow single-action, interval, or calendar-based timers to be created.

For single-action or interval timers, the expiration of the timer can be expressed as either a duration or an absolute time. The duration is expressed as a the number of milliseconds before a timeout event is triggered. To specify an absolute time, create a `java.util.Date` object and pass it to the `TimerService.createSingleActionTimer` or the `TimerService.createTimer` method.

The following code sets a programmatic timer that will expire in 1 minute (6,000 milliseconds):

```
long duration = 6000;
Timer timer =
    timerService.createSingleActionTimer(duration, new TimerConfig());
```

The following code sets a programmatic timer that will expire at 12:05 p.m. on May 1, 2010, specified as a `java.util.Date`:

```
SimpleDateFormatter formatter =
    new SimpleDateFormatter("MM/dd/yyyy 'at' HH:mm");
Date date = formatter.parse("05/01/2010 at 12:05");
Timer timer = timerService.createSingleActionTimer(date, new TimerConfig());
```

For calendar-based timers, the expiration of the timer is expressed as a `javax.ejb.ScheduleExpression` object, passed as a parameter to the `TimerService.createCalendarTimer` method. The `ScheduleExpression` class represents calendar-based timer expressions and has methods that correspond to the attributes described in "Creating Calendar-Based Timer Expressions" on page 439.

The following code creates a programmatic timer using the `ScheduleExpression` helper class:

```
ScheduleExpression schedule = new ScheduleExpression();
schedule.dayOfWeek("Mon");
schedule.hour("12-17, 23");
Timer timer = timerService.createCalendarTimer(schedule);
```

For details on the method signatures, see the `TimerService` API documentation at `http://download.oracle.com/javaee/6/api/javax/ejb/TimerService.html`.

The bean described in "The `timersession` Example" on page 445 creates a timer as follows:

```
Timer timer = timerService.createTimer(intervalDuration,
        "Created new programmatic timer");
```

In the `timersession` example, `createTimer` is invoked in a business method, which is called by a client.

Timers are persistent by default. If the server is shut down or crashes, persistent timers are saved and will become active again when the server is restarted. If a persistent timer expires while the server is down, the container will call the `@Timeout` method when the server is restarted.

Nonpersistent programmatic timers are created by calling `TimerConfig.setPersistent(false)` and passing the `TimerConfig` object to one of the timer-creation methods.

The `Date` and `long` parameters of the `createTimer` methods represent time with the resolution of milliseconds. However, because the timer service is not intended for real-time applications, a callback to the `@Timeout` method might not occur with millisecond precision. The timer service is for business applications, which typically measure time in hours, days, or longer durations.

Automatic Timers

Automatic timers are created by the EJB container when an enterprise bean that contains methods annotated with the `@Schedule` or `@Schedules` annotations is deployed. An enterprise bean can have multiple automatic timeout methods, unlike a programmatic timer, which allows only one method annotated with the `@Timeout` annotation in the enterprise bean class.

Automatic timers can be configured through annotations or through the `ejb-jar.xml` deployment descriptor.

Adding a `@Schedule` annotation on an enterprise bean marks that method as a timeout method according to the calendar schedule specified in the attributes of `@Schedule`.

The `@Schedule` annotation has elements that correspond to the calendar expressions detailed in "Creating Calendar-Based Timer Expressions" on page 439 and the `persistent`, `info`, and `timezone` elements.

The optional `persistent` element takes a Boolean value and is used to specify whether the automatic timer should survive a server restart or crash. By default, all automatic timers are persistent.

The optional `timezone` element is used to specify that the automatic timer is associated with a particular time zone. If set, this element will evaluate all timer expressions in relation to the specified time zone, regardless of the time zone in which the EJB container is running. By default, all automatic timers set are in relation to the default time zone of the server.

The optional `info` element is used to set an informational description of the timer. A timer's information can be retrieved later by using `Timer.getInfo`.

The following timeout method uses `@Schedule` to set a timer that will expire every Sunday at midnight:

```
@Schedule(dayOfWeek="Sun", hour="0")
public void cleanupWeekData() { ... }
```

The `@Schedules` annotation is used to specify multiple calendar-based timer expressions for a given timeout method.

The following timeout method uses the `@Schedules` annotation to set multiple calendar-based timer expressions. The first expression sets a timer to expire on the last day of every month. The second expression sets a timer to expire every Friday at 11:00 p.m.

```
@Schedules ({
    @Schedule(dayOfMonth="Last"),
    @Schedule(dayOfWeek="Fri", hour="23")
})
public void doPeriodicCleanup() { ... }
```

Canceling and Saving Timers

Timers can be canceled by the following events.

- When a single-event timer expires, the EJB container calls the associated timeout method and then cancels the timer.
- When the bean invokes the `cancel` method of the `Timer` interface, the container cancels the timer.

If a method is invoked on a canceled timer, the container throws the `javax.ejb.NoSuchObjectLocalException`.

To save a `Timer` object for future reference, invoke its `getHandle` method and store the `TimerHandle` object in a database. (A `TimerHandle` object is serializable.) To reinstantiate the `Timer` object, retrieve the handle from the database and invoke `getTimer` on the handle. A `TimerHandle` object cannot be passed as an argument of a method defined in a remote or web service interface. In other words, remote clients and web service clients cannot access a bean's `TimerHandle` object. Local clients, however, do not have this restriction.

Getting Timer Information

In addition to defining the `cancel` and `getHandle` methods, the `Timer` interface defines methods for obtaining information about timers:

```
public long getTimeRemaining();
public java.util.Date getNextTimeout();
public java.io.Serializable getInfo();
```

The `getInfo` method returns the object that was the last parameter of the `createTimer` invocation. For example, in the `createTimer` code snippet of the preceding section, this information parameter is a `String` object with the value `created timer`.

To retrieve all of a bean's active timers, call the `getTimers` method of the `TimerService` interface. The `getTimers` method returns a collection of `Timer` objects.

Transactions and Timers

An enterprise bean usually creates a timer within a transaction. If this transaction is rolled back, the timer creation also is rolled back. Similarly, if a bean cancels a timer within a transaction that gets rolled back, the timer cancellation is rolled back. In this case, the timer's duration is reset as if the cancellation had never occurred.

In beans that use container-managed transactions, the `@Timeout` method usually has the `Required` or `RequiresNew` transaction attribute to preserve transaction integrity. With these attributes, the EJB container begins the new transaction before calling the `@Timeout` method. If the transaction is rolled back, the container will call the `@Timeout` method at least one more time.

The `timersession` Example

The source code for this example is in the *tut-install*`/examples/ejb/timersession/src/java/` directory.

`TimerSessionBean` is a singleton session bean that shows how to set both an automatic timer and a programmatic timer. In the source code listing of `TimerSessionBean` that follows, the `setTimer` and `@Timeout` methods are used to set a programmatic timer. A `TimerService` instance is injected by the container when the bean is created. Because it's a business method, `setTimer` is exposed to the local, no-interface view of `TimerSessionBean` and can be invoked by the client. In this example, the client invokes `setTimer` with an interval duration of 30,000 milliseconds. The `setTimer` method creates a new timer by invoking the `createTimer` method of `TimerService`. Now that the timer is set, the EJB container will invoke the `programmaticTimeout` method of `TimerSessionBean` when the timer expires, in about 30 seconds.

```
...
    public void setTimer(long intervalDuration) {
        logger.info("Setting a programmatic timeout for " +
                intervalDuration + " milliseconds from now.");
        Timer timer = timerService.createTimer(intervalDuration,
                "Created new programmatic timer");
    }

    @Timeout
    public void programmaticTimeout(Timer timer) {
        this.setLastProgrammaticTimeout(new Date());
        logger.info("Programmatic timeout occurred.");
    }
...
```

`TimerSessionBean` also has an automatic timer and timeout method, `automaticTimeout`. The automatic timer is set to expire every 3 minutes and is set by using a calendar-based timer expression in the `@Schedule` annotation:

```
...
    @Schedule(minute="*/3", hour="*")
    public void automaticTimeout() {
        this.setLastAutomaticTimeout(new Date());
        logger.info("Automatic timeout occured");
    }
...
```

`TimerSessionBean` also has two business methods: `getLastProgrammaticTimeout` and `getLastAutomaticTimeout`. Clients call these methods to get the date and time of the last timeout for the programmatic timer and automatic timer, respectively.

Here's the source code for the `TimerSessionBean` class:

```
package timersession.ejb;

import java.util.Date;
import java.util.logging.Logger;
import javax.annotation.Resource;
import javax.ejb.Schedule;
import javax.ejb.Stateless;
import javax.ejb.Timeout;
import javax.ejb.Timer;
import javax.ejb.TimerService;

@Singleton
public class TimerSessionBean {
    @Resource
    TimerService timerService;

    private Date lastProgrammaticTimeout;
    private Date lastAutomaticTimeout;

    private Logger logger = Logger.getLogger(
            "com.sun.tutorial.javaee.ejb.timersession.TimerSessionBean");

    public void setTimer(long intervalDuration) {
        logger.info("Setting a programmatic timeout for "
                + intervalDuration + " milliseconds from now.");
        Timer timer = timerService.createTimer(intervalDuration,
                "Created new programmatic timer");
    }

    @Timeout
    public void programmaticTimeout(Timer timer) {
        this.setLastProgrammaticTimeout(new Date());
        logger.info("Programmatic timeout occurred.");
    }

    @Schedule(minute="*/3", hour="*")
    public void automaticTimeout() {
        this.setLastAutomaticTimeout(new Date());
```

```
        logger.info("Automatic timeout occured");
    }

    public String getLastProgrammaticTimeout() {
        if (lastProgrammaticTimeout != null) {
            return lastProgrammaticTimeout.toString();
        } else {
            return "never";
        }

    }

    public void setLastProgrammaticTimeout(Date lastTimeout) {
        this.lastProgrammaticTimeout = lastTimeout;
    }

    public String getLastAutomaticTimeout() {
        if (lastAutomaticTimeout != null) {
            return lastAutomaticTimeout.toString();
        } else {
            return "never";
        }
    }

    public void setLastAutomaticTimeout(Date lastAutomaticTimeout) {
        this.lastAutomaticTimeout = lastAutomaticTimeout;
    }
}
```

Note – GlassFish Server has a default minimum timeout value of 1,000 milliseconds, or 1 second. If you need to set the timeout value lower than 1,000 milliseconds, change the value of the `minimum-delivery-interval-in-millis` element in *domain-dir*`/config/domain.xml`. The lowest practical value for `minimum-delivery-interval-in-millis` is around 10 milliseconds, owing to virtual machine constraints.

Building, Packaging, Deploying, and Running the `timersession` Example

You can build, package, deploy, and run the `timersession` example by using either NetBeans IDE or Ant.

▼ To Build, Package, Deploy, and Run the `timersession` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/ejb/`

3. **Select the `timersession` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **From the Run menu, choose Run Main Project.**

   This builds and packages the application into `timersession.war`, located in *tut-install*`/examples/ejb/timersession/dist/`, deploys this WAR file to your GlassFish Server instance, and then runs the web client.

▼ To Build, Package, and Deploy the `timersession` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/ejb/timersession/`
2. **Type the following command:**

   ```
   ant
   ```

   This runs the `default` task, which compiles the source files and packages the application into a WAR file located at *tut-install*`/examples/ejb/timersession/dist/timersession.war`.
3. **To deploy the application, type the following command:**

   ```
   ant deploy
   ```

▼ To Run the Web Client

1. **Open a web browser to `http://localhost:8080/timersession`.**
2. **Click the Set Timer button to set a programmatic timer.**
3. **Wait for a while and click the browser's Refresh button.**

   You will see the date and time of the last programmatic and automatic timeouts.

   To see the messages that are logged when a timeout occurs, open the `server.log` file located in *domain-dir*`/server/logs/`.

Handling Exceptions

The exceptions thrown by enterprise beans fall into two categories: system and application.

A *system exception* indicates a problem with the services that support an application. For example, a connection to an external resource cannot be obtained, or an injected resource cannot be found. If it encounters a system-level problem, your enterprise bean should throw a `javax.ejb.EJBException`. Because the `EJBException` is a subclass of the `RuntimeException`, you do not have to specify it in the `throws` clause of the method declaration. If a system exception is thrown, the EJB container might destroy the bean instance. Therefore, a system exception cannot be handled by the bean's client program, but instead requires intervention by a system administrator.

An *application exception* signals an error in the business logic of an enterprise bean. Application exceptions are typically exceptions that you've coded yourself, such as the `BookException` thrown by the business methods of the `CartBean` example. When an enterprise bean throws an application exception, the container does not wrap it in another exception. The client should be able to handle any application exception it receives.

If a system exception occurs within a transaction, the EJB container rolls back the transaction. However, if an application exception is thrown within a transaction, the container does not roll back the transaction.

◆ ◆ ◆ CHAPTER 25

A Message-Driven Bean Example

Message-driven beans can implement any messaging type. Most commonly, they implement the Java Message Service (JMS) technology. The example in this chapter uses JMS technology, so you should be familiar with basic JMS concepts such as queues and messages. To learn about these concepts, see Chapter 45, "Java Message Service Concepts."

This chapter describes the source code of a simple message-driven bean example. Before proceeding, you should read the basic conceptual information in the section "What Is a Message-Driven Bean?" on page 399 as well as "Using Message-Driven Beans to Receive Messages Asynchronously" on page 785.

The following topics are addressed here:

`simplemessage` Example Application Overview

The `simplemessage` application has the following components:

- `SimpleMessageClient`: An application client that sends several messages to a queue
- `SimpleMessageBean`: A message-driven bean that asynchronously receives and processes the messages that are sent to the queue

Figure 25–1 illustrates the structure of this application. The application client sends messages to the queue, which was created administratively using the Administration Console. The JMS provider (in this case, the GlassFish Server) delivers the messages to the instances of the message-driven bean, which then processes the messages.

FIGURE 25–1 The simplemessage Application



The source code for this application is in the *tut-install*/examples/ejb/simplemessage/ directory.

The simplemessage Application Client

The SimpleMessageClient sends messages to the queue that the SimpleMessageBean listens to. The client starts by injecting the connection factory and queue resources:

```
@Resource(mappedName="jms/ConnectionFactory")
private static ConnectionFactory connectionFactory;

@Resource(mappedName="jms/Queue")
private static Queue queue;
```

Next, the client creates the connection, session, and message producer:

```
connection = connectionFactory.createConnection();
session = connection.createSession(false, Session.AUTO_ACKNOWLEDGE);
messageProducer = session.createProducer(queue);
```

Finally, the client sends several messages to the queue:

```
message = session.createTextMessage();

for (int i = 0; i < NUM_MSGS; i++) {
    message.setText("This is message " + (i + 1));
    System.out.println("Sending message: " + message.getText());
    messageProducer.send(message);
}
```

The Message-Driven Bean Class

The code for the `SimpleMessageBean` class illustrates the requirements of a message-driven bean class:

- It must be annotated with the `@MessageDriven` annotation if it does not use a deployment descriptor.
- The class must be defined as `public`.
- The class cannot be defined as `abstract` or `final`.
- It must contain a public constructor with no arguments.
- It must not define the `finalize` method.

It is recommended, but not required, that a message-driven bean class implement the message listener interface for the message type it supports. A bean that supports the JMS API implements the `javax.jms.MessageListener` interface.

Unlike session beans and entities, message-driven beans do not have the remote or local interfaces that define client access. Client components do not locate message-driven beans and invoke methods on them. Although message-driven beans do not have business methods, they may contain helper methods that are invoked internally by the `onMessage` method.

For the GlassFish Server, the `@MessageDriven` annotation typically contains a `mappedName` element that specifies the JNDI name of the destination from which the bean will consume messages. For complex message-driven beans, there can also be an `activationconfig` element containing `@ActivationConfigProperty` annotations used by the bean.

A message-driven bean can also inject a `MessageDrivenContext` resource. Commonly you use this resource to call the `setRollbackOnly` method to handle exceptions for a bean that uses container-managed transactions.

Therefore, the first few lines of the `SimpleMessageBean` class look like this:

```
@MessageDriven(mappedName="jms/Queue", activationConfig =  {
        @ActivationConfigProperty(propertyName = "acknowledgeMode",
                                  propertyValue = "Auto-acknowledge"),
        @ActivationConfigProperty(propertyName = "destinationType",
                                  propertyValue = "javax.jms.Queue")
    })
public class SimpleMessageBean implements MessageListener {
    @Resource
    private MessageDrivenContext mdc;
    ...
```

NetBeans IDE typically creates a message-driven bean with a default set of `@ActivationConfigProperty` settings. You can delete those you do not need, or add others. Table 25–1 lists commonly used properties.

TABLE 25–1 `@ActivationConfigProperty` Settings for Message-Driven Beans

Property Name	Description
`acknowledgeMode`	Acknowledgment mode; see "Controlling Message Acknowledgment" on page 775 for information
`destinationType`	Either `javax.jms.Queue` or `javax.jms.Topic`
`subscriptionDurability`	For durable subscribers, set to `Durable`; see "Creating Durable Subscriptions" on page 779 for information
`clientId`	For durable subscribers, the client ID for the connection
`subscriptionName`	For durable subscribers, the name of the subscription
`messageSelector`	A string that filters messages; see "JMS Message Selectors" on page 770 for information, and see "An Application That Uses the JMS API with a Session Bean" on page 829 for an example
`addressList`	Remote system or systems to communicate with; see "An Application Example That Consumes Messages from a Remote Server" on page 841 for an example

The `onMessage` Method

When the queue receives a message, the EJB container invokes the message listener method or methods. For a bean that uses JMS, this is the `onMessage` method of the `MessageListener` interface.

A message listener method must follow these rules:

- The method must be declared as `public`.
- The method must not be declared as `final` or `static`.

The `onMessage` method is called by the bean's container when a message has arrived for the bean to service. This method contains the business logic that handles the processing of the message. It is the message-driven bean's responsibility to parse the message and perform the necessary business logic.

The `onMessage` method has a single argument: the incoming message.

The signature of the `onMessage` method must follow these rules:

- The return type must be `void`.
- The method must have a single argument of type `javax.jms.Message`.

In the `SimpleMessageBean` class, the `onMessage` method casts the incoming message to a `TextMessage` and displays the text:

```
public void onMessage(Message inMessage) {
    TextMessage msg = null;

    try {
        if (inMessage instanceof TextMessage) {
            msg = (TextMessage) inMessage;
            logger.info("MESSAGE BEAN: Message received: " +
                msg.getText());
        } else {
            logger.warning("Message of wrong type: " +
                inMessage.getClass().getName());
        }
    } catch (JMSException e) {
        e.printStackTrace();
        mdc.setRollbackOnly();
    } catch (Throwable te) {
        te.printStackTrace();
    }
}
```

Packaging, Deploying, and Running the `simplemessage` Example

To package, deploy and run this example, go to the *tut-install*`/examples/ejb/simplemessage/` directory.

Creating the Administered Objects for the `simplemessage` Example

This example requires the following:

- A JMS connection factory resource
- A JMS destination resource

If you have run the simple JMS examples in Chapter 45, "Java Message Service Concepts," and have not deleted the resources, you already have these resources and do not need to perform these steps.

You can use Ant targets to create the resources. The Ant targets, which are defined in the `build.xml` file for this example, use the `asadmin` command. To create the resources needed for this example, use the following commands:

```
ant create-cf
ant create-queue
```

These commands do the following:

- Create a connection factory resource named jms/ConnectionFactory
- Create a destination resource named jms/Queue

The Ant targets for these commands refer to other targets that are defined in the *tut-install*/examples/bp-project/app-server-ant.xml file.

▼ To Build, Deploy, and Run the simplemessage Application Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install/examples/ejb/
3. **Select the simplemessage folder.**
4. **Select the Open as Main Project check box and the Open Required Projects check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the simplemessage project and choose Build.**

   This task packages the application client and the message-driven bean, then creates a file named simplemessage.ear in the dist directory.
7. **Right-click the project and choose Run.**

   This command deploys the project, returns a JAR file named simplemessageClient.jar, and then executes it.

   The output of the application client in the Output pane looks like this (preceded by application client container output):

```
Sending message: This is message 1
Sending message: This is message 2
Sending message: This is message 3
To see if the bean received the messages,
 check <install_dir>/domains/domain1/logs/server.log.
```

   The output from the message-driven bean appears in the server log (*domain-dir*/logs/server.log), wrapped in logging information.

```
MESSAGE BEAN: Message received: This is message 1
MESSAGE BEAN: Message received: This is message 2
MESSAGE BEAN: Message received: This is message 3
```

   The received messages may appear in a different order from the order in which they were sent.

▼ To Build, Deploy, and Run the `simplemessage` Application Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/ejb/simplemessage/`

2. **To compile the source files and package the application, use the following command:**

   ```
   ant
   ```

   This target packages the application client and the message-driven bean, then creates a file named `simplemessage.ear` in the `dist` directory.

   By using resource injection and annotations, you avoid having to create deployment descriptor files for the message-driven bean and application client. You need to use deployment descriptors only if you want to override the values specified in the annotated source files.

3. **To deploy the application and run the client using Ant, use the following command:**

   ```
   ant run
   ```

   Ignore the message that states that the application is deployed at a URL.

   The output in the terminal window looks like this (preceded by application client container output):

   ```
   Sending message: This is message 1
   Sending message: This is message 2
   Sending message: This is message 3
   To see if the bean received the messages,
    check <install_dir>/domains/domain1/logs/server.log.
   ```

   In the server log file, the following lines appear, wrapped in logging information:

   ```
   MESSAGE BEAN: Message received: This is message 1
   MESSAGE BEAN: Message received: This is message 2
   MESSAGE BEAN: Message received: This is message 3
   ```

   The received messages may appear in a different order from the order in which they were sent.

Removing the Administered Objects for the `simplemessage` Example

After you run the example, you can use the following Ant targets to delete the connection factory and queue:

```
ant delete-cf
ant delete-queue
```

◆ ◆ ◆ CHAPTER 26

Using the Embedded Enterprise Bean Container

This chapter demonstrates how to use the embedded enterprise bean container to run enterprise bean applications in the Java SE environment, outside of a Java EE server.

The following topics are addressed here:

Overview of the Embedded Enterprise Bean Container

The embedded enterprise bean container is used to access enterprise bean components from client code executed in a Java SE environment. The container and the client code are executed within the same virtual machine. The embedded enterprise bean container is typically used for testing enterprise beans without having to deploy them to a server.

Most of the services present in the enterprise bean container in a Java EE server are available in the embedded enterprise bean container, including injection, container-managed transactions, and security. Enterprise bean components execute similarly in both embedded and Java EE environments, and therefore the same enterprise bean can be easily reused in both standalone and networked applications.

Developing Embeddable Enterprise Bean Applications

All embeddable enterprise bean containers support the features listed in Table 26–1.

TABLE 26–1 Required Enterprise Bean Features in the Embeddable Container

Enterprise Bean Feature	Description
Local session beans	Local and no-interface view stateless, stateful, and singleton session beans. All method access is synchronous. Session beans must not be web service endpoints.
Transactions	Container-managed and bean-managed transactions.
Security	Declarative and programmatic security.
Interceptors	Class-level and method-level interceptors for session beans.
Deployment descriptor	The optional `ejb-jar.xml` deployment descriptor, with the same overriding rules for the enterprise bean container in Java EE servers.

Container providers are allowed to support the full set of features in enterprise beans, but applications that use the embedded container will not be portable if they use enterprise bean features not listed in Table 26–1, such as the timer service, session beans as web service endpoints, or remote business interfaces.

Running Embedded Applications

The embedded container, the enterprise bean components, and the client all are executed in the same virtual machine using the same classpath. As a result, developers can run an application that uses the embedded container just like a typical Java SE application as follows:

```
java -classpath mySessionBean.jar:containerProviderRuntime.jar:myClient.jar
com.example.ejb.client.Main
```

In the above example, `mySessionBean.jar` is an EJB JAR containing a local stateless session bean, `containerProviderRuntime.jar` is a JAR file supplied by the enterprise bean provider that contains the needed runtime classes for the embedded container, and `myClient.jar` is a JAR file containing a Java SE application that calls the business methods in the session bean through the embedded container.

Creating the Enterprise Bean Container

The `javax.ejb.embedded.EJBContainer` abstract class represents an instance of the enterprise bean container and includes factory methods for creating a container instance. The `EJBContainer.createEJBContainer` method is used to create and initialize an embedded container instance.

The following code snippet shows how to create an embedded container that is initialized with the container provider's default settings:

```
EJBContainer ec = EJBContainer.createEJBContainer();
```

By default, the embedded container will search the virtual machine classpath for enterprise bean modules: directories containing a `META-INF/ejb-jar.xml` deployment descriptor, directories containing a class file with one of the enterprise bean component annotations (such as `@Stateless`), or JAR files containing an `ejb-jar.xml` deployment descriptor or class file with an enterprise bean annotation. Any matching entries are considered enterprise bean modules within the same application. Once all the valid enterprise bean modules have been found in the classpath, the container will begin initializing the modules. When the `createEJBContainer` method successfully returns, the client application can obtain references to the client view of any enterprise bean module found by the embedded container.

An alternate version of the `EJBContainer.createEJBContainer` method takes a `Map` of properties and settings for customizing the embeddable container instance:

```
Properties props = new Properties();
props.setProperty(...);
...
EJBContainer ec = EJBContainer.createEJBContainer(props);
```

Explicitly Specifying Enterprise Bean Modules to be Initialized

Developers can specify exactly which enterprise bean modules the embedded container will initialize. To explicitly specify the enterprise bean modules initialized by the embedded container, set the `EJBContainer.MODULES` property.

The modules may be located either in the virtual machine classpath in which the embedded container and client code run, or alternately outside the virtual machine classpath.

To specify modules in the virtual machine classpath, set `EJBContainer.MODULES` to a `String` to specify a single module name, or a `String` array containing the module names. The embedded container searches the virtual machine classpath for enterprise bean modules matching the specified names.

```
Properties props = new Properties();
props.setProperty(EJBContainer.MODULES, "mySessionBean");
EJBContainer ec = EJBContainer.createEJBContainer(props);
```

To specify enterprise bean modules outside the virtual machine classpath, set `EJBContainer.MODULES` to a `java.io.File` object or an array of `File` objects. Each `File` object refers to an EJB JAR file, or a directory containing an expanded EJB JAR.

```
Properties props = new Properties();
File ejbJarFile = new File(...);
props.setProperty(EJBContainer.MODULES, ejbJarFile);
EJBContainer ec = EJBContainer.createEJBContainer(props);
```

Looking Up Session Bean References

To look up session bean references in an application using the embedded container, use an instance of `EJBContainer` to retrieve a `javax.naming.Context` object. Call the `EJBContainer.getContext` method to retrieve the `Context` object.

```
EJBContainer ec = EJBContainer.createEJBContainer();
Context ctx = ec.getContext();
```

References to session beans can then be obtained using the portable JNDI syntax detailed in "Portable JNDI Syntax" on page 402. For example, to obtain a reference to `MySessionBean`, a local session bean with a no-interface view, use the following code:

```
MySessionBean msb = (MySessionBean)
            ctx.lookup("java:global/mySessionBean/MySessionBean");
```

Shutting Down the Enterprise Bean Container

From the client, call the `close` method of the instance of `EJBContainer` to shut down the embedded container:

```
EJBContainer ec = EJBContainer.createEJBContainer();
...
ec.close();
```

While clients are not required to shut down `EJBContainer` instances, doing so frees resources consumed by the embedded container. This is particularly important when the virtual machine under which the client application is running has a longer lifetime than the client application.

The `standalone` Example Application

The `standalone` example application demonstrates how to create an instance of the embedded enterprise bean container in a JUnit test class and call a session bean business method. Testing the business methods of an enterprise bean in a unit test allows developers to exercise the business logic of an application separately from the other application layers, such as the presentation layer, and without having to deploy the application to a Java EE server.

The `standalone` example has two main components: `StandaloneBean`, a stateless session bean, and `StandaloneBeanTest`, a JUnit test class that acts as a client to `StandaloneBean` using the embedded container.

`StandaloneBean` is a simple session bean exposing a local, no-interface view with a single business method, `returnMessage`, which returns "Greetings!" as a `String`.

```
@Stateless
public class StandaloneBean {
```

```
    private static final String message = "Greetings!";

    public String returnMessage() {
        return message;
    }

}
```

`StandaloneBeanTest` calls `StandaloneBean.returnMessage` and tests that the returned message is correct. First, an embedded container instance and initial context are created within the `setUp` method, which is annotated with `org.junit.Before` to indicate that the method should be executed before the test methods.

```
@Before
public void setUp() {
    ec = EJBContainer.createEJBContainer();
    ctx = ec.getContext();
}
```

The `testReturnMessage` method, annotated with `org.junit.Test` to indicate that the method includes a unit test, obtains a reference to `StandaloneBean` through the `Context` instance, and calls `StandaloneBean.returnMessage`. The result is compared with the expected result using a JUnit assertion, `assertEquals`. If the string returned from `StandaloneBean.returnMessage` is equal to "Greetings!" the test passes.

```
@Test
public void testReturnMessage() throws Exception {
    logger.info("Testing standalone.ejb.StandalonBean.returnMessage()");
    StandaloneBean instance = (StandaloneBean)
            ctx.lookup("java:global/classes/StandaloneBean");
    String expResult = "Greetings!";
    String result = instance.returnMessage();
    assertEquals(expResult, result);
}
```

Finally, the `tearDown` method, annotated with `org.junit.After` to indicate that the method should be executed after all the unit tests have run, closes the embedded container instance.

```
@After
public void tearDown() {
    if (ec != null) {
        ec.close();
    }
}
```

▼ Running the `standalone` Example Application

Before You Begin You must run the `standalone` example application within NetBeans IDE.

1 From the File menu, choose Open Project.

2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/ejb/`

3. **Select the `standalone` folder and click Open Project.**

4. **In the Projects tab, right-click `standalone` and select Test.**

   This will execute the JUnit test class `StandaloneBeanTest`. The Output tab shows the progress of the test and the output log.

◆ ◆ ◆ CHAPTER 27

Using Asynchronous Method Invocation in Session Beans

Discusses how to implement asynchronous business methods in session beans, and call them from enterprise bean clients.

The following topics are addressed here:

Asynchronous Method Invocation

Session beans can implement *asynchronous methods*, business methods where control is returned to the client by the enterprise bean container before the method is invoked on the session bean instance. Clients may then use the Java SE concurrency API to retrieve the result, cancel the invocation, and check for exceptions. Asynchronous methods are typically used for long-running operations, for processor-intensive tasks, for background tasks, to increase application throughput, or to improve application response time if the method invocation result isn't required immediately.

When a session bean client invokes a typical non-asynchronous business method, control is not returned to the client until the method has completed. Clients calling asynchronous methods, however, immediately have control returned to them by the enterprise bean container. This allows the client to perform other tasks while the method invocation completes. If the method returns a result, the result is an implementation of the `java.util.concurrent.Future<V>` interface, where "V" is the result value type. The `Future<V>` interface defines methods the client may use to check if the computation is completed, wait for the invocation to complete, retrieve the final result, and cancel the invocation.

Creating an Asynchronous Business Method

Annotate a business method with `javax.ejb.Asynchronous` to mark that method as an asynchronous method, or apply `@Asynchronous` at the class level to mark all the business methods of the session bean as asynchronous methods. Session bean methods that expose web services can't be asynchronous.

Asynchronous methods must return either `void` or an implementation of the `Future<V>` interface. Asynchronous methods that return `void` can't declare application exceptions, but if they return `Future<V>`, they may declare application exceptions. For example:

```
@Asynchronous
public Future<String> processPayment(Order order) throws PaymentException { ... }
```

This method will attempt to process the payment of an order, and return the status as a `String`. Even if the payment processor takes a long time, the client can continue working, and display the result when the processing finally completes.

The `javax.ejb.AsyncResult<V>` class is a concrete implementation of the `Future<V>` interface provided as a helper class for returning asynchronous results. `AsyncResult` has a constructor with the result as a parameter, making it easy to create `Future<V>` implementations. For example, the `processPayment` method would use `AsyncResult` to return the status as a `String`:

```
@Asynchronous
public Future<String> processPayment(Order order) throws PaymentException {
  ...
  String status = ...;
  return new AsyncResult<String>(status);
}
```

The result is returned to the enterprise bean container, not directly to the client, and the enterprise bean container makes the result available to the client. The session bean can check if the client requested that the invocation be cancelled by calling the `javax.ejb.SessionContext.wasCancelled` method. For example:

```
@Asynchronous
public Future<String> processPayment(Order order) throws PaymentException {
  ...
  if (SessionContext.wasCancelled()) {
    // clean up
  } else {
    // process the payment
  }
  ...
}
```

Calling Asynchronous Methods from Enterprise Bean Clients

Session bean clients call asynchronous methods just like non-asynchronous business methods. If the asynchronous method returns a result, the client receives a `Future<V>` instance as soon as the method is invoked. This instance can be used to retrieve the final result, cancel the invocation, check whether the invocation has completed, check if there were any exceptions thrown during processing, and check if the invocation was cancelled.

Retrieving the Final Result from an Asynchronous Method Invocation

The client may retrieve the result using one of the `Future<V>.get` methods. If processing hasn't completed by the session bean handling the invocation, calling one of the `get` methods will result in the client halting execution until the invocation completes. Use the `Future<V>.isDone` method to determine if processing has completed before calling one of the `get` methods.

The `get()` method returns the result as the type specified in the type value of the `Future<V>` instance. For example, calling `Future<String>.get()` will return a `String` object. If the method invocation was cancelled, calls to `get()` result in a `java.util.concurrent.CancellationException` being thrown. If the invocation resulted in an exception during processing by the session bean, calls to `get()` result in a `java.util.concurrent.ExecutionException` being thrown. The cause of the `ExecutionException` may be retrieved by calling the `ExecutionException.getCause` method.

The `get(long timeout, java.util.concurrent.TimeUnit unit)` method is similar to the `get()` method, but allows the client to set a timeout value. If the timeout value is exceeded, a `java.util.concurrent.TimeoutException` is thrown. See the Javadoc for the `TimeUnit` class for the available units of time to specify the timeout value.

Cancelling an Asynchronous Method Invocation

Call the `cancel(boolean mayInterruptIfRunning)` method on the `Future<V>` instance to attempt to cancel the method invocation. The `cancel` method returns `true` if the cancellation was successful, and `false` if the method invocation cannot be cancelled.

When the invocation cannot be cancelled, the `mayInterruptIfRunning` parameter is used to alert the session bean instance on which the method invocation is running that the client attempted to cancel the invocation. If `mayInterruptIfRunning` is set to `true`, calls to `SessionContext.wasCancelled` by the session bean instance will return `true`. If `mayInterruptIfRunning` is to set `false`, calls to `SessionContext.wasCancelled` by the session bean instance will return `false`.

The `Future<V>.isCancelled` method is used to check if the method invocation was cancelled before the asynchronous method invocation completed by calling `Future<V>.cancel`. The `isCancelled` method returns `true` if the invocation was cancelled.

Checking the Status of an Asynchronous Method Invocation

The `Future<V>.isDone` method returns `true` if the session bean instance completed processing the method invocation. The `isDone` method returns `true` if the asynchronous method invocation completed normally, was cancelled, or resulted in an exception. That is, `isDone` only indicates whether the session bean has completed processing the invocation.

The `async` Example Application

The `async` example demonstrates how to define an asynchronous business method on a session bean, and call it from a web client. The `MailerBean` stateless session bean defines an asynchronous method, `sendMessage`, which uses the JavaMail API to send an email to a specified email address.

Note – This example needs to be configured for your environment before it runs correctly, and requires access to an SMTPS server.

Architecture of the `async` Example Application

The `async` application consists of a single stateless session bean, `MailerBean`, and a JavaServer Faces web application front-end that uses Facelets tags in XHTML files to display a form for users to enter the email address for the recipient of an email. The status of the email is updated when the email is finally sent.

The `MailerBean` session bean injects a JavaMail resource used to send an email message to an address specified by the user. The message is created, modified, and sent using the JavaMail API. The injected JavaMail resource is configured through the GlassFish Server Administration Console, or through a resource configuration file packaged with the application. The resource configuration can be modified at runtime by GlassFish Server administrator to use a different mail server or transport protocol.

```
@Asynchronous
public Future<String> sendMessage(String email) {
    String status;
    try {
        Message message = new MimeMessage(session);
        message.setFrom();
        message.setRecipients(Message.RecipientType.TO,
                InternetAddress.parse(email, false));
        message.setSubject("Test message from async example");
        message.setHeader("X-Mailer", "JavaMail");
        DateFormat dateFormatter = DateFormat
                .getDateTimeInstance(DateFormat.LONG, DateFormat.SHORT);
        Date timeStamp = new Date();
        String messageBody = "This is a test message from the async example "
```

```
                + "of the Java EE Tutorial. It was sent on "
                + dateFormatter.format(timeStamp)
                + ".";
            message.setText(messageBody);
            message.setSentDate(timeStamp);
            Transport.send(message);
            status = "Sent";
            logger.log(Level.INFO, "Mail sent to {0}", email);
        } catch (MessagingException ex) {
            logger.severe("Error in sending message.");
            status = "Encountered an error";
            logger.severe(ex.getMessage() + ex.getNextException().getMessage());
            logger.severe(ex.getCause().getMessage());
        }
        return new AsyncResult<String>(status);
    }
```

The web client consists of a Facelets template, `template.xhtml`, two Facelets clients, `index.xhtml` and `response.xhtml`, and a JavaServer Faces managed bean, `MailerManagedBean`. The `index.xhtml` file contains a form for the target email address. When the user submits the form, the `MailerManagedBean.send` method is called. This method uses an injected instance of the `MailerBean` session bean to call `MailerBean.sendMessage`. The result is sent to the `response.xhtml` Facelets view.

Configuring the Keystore and Truststore in GlassFish Server

The GlassFish Server domain needs to be configured with the server's master password to access the keystore and truststore used to initiate secure communications using the SMTPS transport protocol.

1. **Open the GlassFish Server Administration Console in a web browser at `http://localhost:4848`.**
2. **Expand Configurations, then expand server-config, then click JVM Settings.**
3. **Click JVM Options, then click Add JVM Option and enter `-Djavax.net.ssl.keyStorePassword=`*master password*, replacing *master password* `with the keystore master password`. The default master password is `changeit`.**
4. **Click Add JVM Option and enter `-Djavax.net.ssl.trustStorePassword=`*master password*, replacing *master password* `with the truststore master password`. The default master password is `changeit`.**
5. **Click Save, then restart GlassFish Server.**

▼ Running the async Example Application in NetBeans IDE

Follow these instructions for running the async example application in NetBeans IDE.

Before You Begin Before running this example, you must configure your GlassFish Server instance to access the keystore and truststore used by GlassFish Server to create a secure connection to the target SMTPS server.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install/examples/ejb/
3. **Select the async folder and click Open Project.**
4. **Under async in the project pane, expand the Server Resources node and double-click glassfish-resources.xml.**
5. **Enter the configuration settings for your SMTPS server in glassfish-resources.xml.**

   The SMTPS server host name is set in the host attribute, email address from which you want the message sent is the from attribute, the SMTPS user name is the user attribute. Set the mail-smtps-password property value to the password for the SMTPS server user. The following code snippet shows an example resource configuration. Lines in bold need to be modified.

```
<resources>
    <mail-resource debug="false"
            enabled="true"
            from="user@example.com"
            host="smtp.example.com"
            jndi-name="mail/myExampleSession"
            object-type="user" store-protocol="imap"
            store-protocol-class="com.sun.mail.imap.IMAPStore"
            transport-protocol="smtps"
            transport-protocol-class="com.sun.mail.smtp.SMTPSSLTransport"
            user="user@example.com">
        <description/>
        <property name="mail-smtps-auth" value="true"/>
        <property name="mail-smtps-password" value="mypassword"/>
    </mail-resource>
</resources>
```

6. **Right-click async in the project pane and select Run.**

   This will compile, assemble, and deploy the application, and start a web browser at the following URL: http://localhost:8080/async.

7 **In the web browser window, enter the email to which you want the test message sent and click Send email.**

If your configuration settings are correct, a test email will be sent, and the status message will read `Sent` in the web client. The test message should appear momentarily in the inbox of the recipient.

If an error occurs, the status will read `Encountered an error`. Check the `server.log` file for your domain to find the cause of the error.

▼ Running the `async` Example Application Using Ant

Follow these instructions for running the `async` example application using Ant.

1 **In a terminal window, navigate to *tut-install*`/examples/ejb/async/`.**

2 **In a text editor, open `setup/glassfish-resources.xml` and enter the configuration settings for your SMTPS server.**

The SMTPS server host name is set in the `host` attribute, email address from which you want the message sent is the `from` attribute, the SMTPS user name is the `user` attribute. Set the `mail-smtps-password` property value to the password for the SMTPS server user. The following code snippet shows an example resource configuration. Lines in bold need to be modified.

```
<resources>
    <mail-resource debug="false"
            enabled="true"
            from="user@example.com"
            host="smtp.example.com"
            jndi-name="mail/myExampleSession"
            object-type="user" store-protocol="imap"
            store-protocol-class="com.sun.mail.imap.IMAPStore"
            transport-protocol="smtps"
            transport-protocol-class="com.sun.mail.smtp.SMTPSSLTransport"
            user="user@example.com">
        <description/>
        <property name="mail-smtps-auth" value="true"/>
        <property name="mail-smtps-password" value="mypassword"/>
    </mail-resource>
</resources>
```

3 **Enter the following command:**

```
ant all
```

This will compile, assemble, and deploy the application, and start a web browser at the following URL: `http://localhost:8080/async`.

Note – If your build system isn't configured to automatically open a web browser, open the above URL in a browser window.

4 **In the web browser window, enter the email to which you want the test message sent and click Send email.**

If your configuration settings are correct, a test email will be sent, and the status message will read `Sent` in the web client. The test message should appear momentarily in the inbox of the recipient.

If an error occurs, the status will read `Encountered an error`. Check the `server.log` file for your domain to find the cause of the error.

PART V

Contexts and Dependency Injection for the Java EE Platform

Part V explores Contexts and Dependency Injection for the Java EE Platform. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 28

Introduction to Contexts and Dependency Injection for the Java EE Platform

Contexts and Dependency Injection (CDI) for the Java EE platform is one of several Java EE 6 features that help to knit together the web tier and the transactional tier of the Java EE platform. CDI is a set of services that, used together, make it easy for developers to use enterprise beans along with JavaServer Faces technology in web applications. Designed for use with stateful objects, CDI also has many broader uses, allowing developers a great deal of flexibility to integrate various kinds of components in a loosely coupled but typesafe way.

CDI is specified by JSR 299, formerly known as Web Beans. Related specifications that CDI uses include the following:

- JSR 330, Dependency Injection for Java
- The Managed Beans specification, which is an offshoot of the Java EE 6 platform specification (JSR 316)

The following topics are addressed here:

Overview of CDI

The most fundamental services provided by CDI are as follows:

- **Contexts**: The ability to bind the lifecycle and interactions of stateful components to well-defined but extensible lifecycle contexts
- **Dependency injection**: The ability to inject components into an application in a typesafe way, including the ability to choose at deployment time which implementation of a particular interface to inject

In addition, CDI provides the following services:

- Integration with the Expression Language (EL), which allows any component to be used directly within a JavaServer Faces page or a JavaServer Pages page
- The ability to decorate injected components
- The ability to associate interceptors with components using typesafe interceptor bindings
- An event-notification model
- A web conversation scope in addition to the three standard scopes (request, session, and application) defined by the Java Servlet specification
- A complete Service Provider Interface (SPI) that allows third-party frameworks to integrate cleanly in the Java EE 6 environment

A major theme of CDI is loose coupling. CDI does the following:

- Decouples the server and the client by means of well-defined types and qualifiers, so that the server implementation may vary
- Decouples the lifecycles of collaborating components by doing the following:
  - Making components contextual, with automatic lifecycle management
  - Allowing stateful components to interact like services, purely by message passing
- Completely decouples message producers from consumers, by means of events
- Decouples orthogonal concerns by means of Java EE interceptors

Along with loose coupling, CDI provides strong typing by

- Eliminating lookup using string-based names for wiring and correlations, so that the compiler will detect typing errors
- Allowing the use of declarative Java annotations to specify everything, largely eliminating the need for XML deployment descriptors, and making it easy to provide tools that introspect the code and understand the dependency structure at development time

About Beans

CDI redefines the concept of a *bean* beyond its use in other Java technologies, such as the JavaBeans and Enterprise JavaBeans (EJB) technologies. In CDI, a bean is a source of contextual objects that define application state and/or logic. A Java EE component is a bean if the lifecycle of its instances may be managed by the container according to the lifecycle context model defined in the CDI specification.

More specifically, a bean has the following attributes:

- A (nonempty) set of bean types
- A (nonempty) set of qualifiers (see "Using Qualifiers" on page 479)
- A scope (see "Using Scopes" on page 480)
- Optionally, a bean EL name (see "Giving Beans EL Names" on page 482)
- A set of interceptor bindings
- A bean implementation

A bean type defines a client-visible type of the bean. Almost any Java type may be a bean type of a bean.

- A bean type may be an interface, a concrete class, or an abstract class and may be declared final or have final methods.
- A bean type may be a parameterized type with type parameters and type variables.
- A bean type may be an array type. Two array types are considered identical only if the element type is identical.
- A bean type may be a primitive type. Primitive types are considered to be identical to their corresponding wrapper types in `java.lang`.
- A bean type may be a raw type.

About Managed Beans

A *managed bean* is implemented by a Java class, which is called its bean class. A top-level Java class is a managed bean if it is defined to be a managed bean by any other Java EE technology specification, such as the JavaServer Faces technology specification, or if it meets all the following conditions:

- It is not a nonstatic inner class.
- It is a concrete class or is annotated `@Decorator`.
- It is not annotated with an EJB component-defining annotation or declared as an EJB bean class in `ejb-jar.xml`.

- It has an appropriate constructor. That is, one of the following is the case:
  - The class has a constructor with no parameters.
  - The class declares a constructor annotated `@Inject`.

No special declaration, such as an annotation, is required to define a managed bean.

Beans as Injectable Objects

The concept of injection has been part of Java technology for some time. Since the Java EE 5 platform was introduced, annotations have made it possible to inject resources and some other kinds of objects into container-managed objects. CDI makes it possible to inject more kinds of objects and to inject them into objects that are not container-managed.

The following kinds of objects can be injected:

- (Almost) any Java class
- Session beans
- Java EE resources: data sources, Java Message Service topics, queues, connection factories, and the like
- Persistence contexts (JPA `EntityManager` objects)
- Producer fields
- Objects returned by producer methods
- Web service references
- Remote enterprise bean references

For example, suppose that you create a simple Java class with a method that returns a string:

```
package greetings;

public class Greeting {
    public String greet(String name) {
        return "Hello, " + name + ".";
    }
}
```

This class becomes a bean that you can then inject into another class. This bean is not exposed to the EL in this form. "Giving Beans EL Names" on page 482 explains how you can make a bean accessible to the EL.

Using Qualifiers

You can use qualifiers to provide various implementations of a particular bean type. A qualifier is an annotation that you apply to a bean. A qualifier type is a Java annotation defined as `@Target({METHOD, FIELD, PARAMETER, TYPE})` and `@Retention(RUNTIME)`.

For example, you could declare an `@Informal` qualifier type and apply it to another class that extends the `Greeting` class. To declare this qualifier type, you would use the following code:

```
package greetings;

import static java.lang.annotation.ElementType.FIELD;
import static java.lang.annotation.ElementType.METHOD;
import static java.lang.annotation.ElementType.PARAMETER;
import static java.lang.annotation.ElementType.TYPE;
import static java.lang.annotation.RetentionPolicy.RUNTIME;

import java.lang.annotation.Retention;
import java.lang.annotation.Target;

import javax.inject.Qualifier;

@Qualifier
@Retention(RUNTIME)
@Target({TYPE, METHOD, FIELD, PARAMETER})
public @interface Informal {}
```

You can then define a bean class that extends the `Greeting` class and uses this qualifier:

```
package greetings;

@Informal
public class InformalGreeting extends Greeting {
    public String greet(String name) {
        return "Hi, " + name + "!";
    }
}
```

Both implementations of the bean can now be used in the application.

If you define a bean with no qualifier, the bean automatically has the qualifier `@Default`. The unannotated `Greeting` class could be declared as follows:

```
package greetings;

import javax.enterprise.inject.Default;

@Default
public class Greeting {
    public String greet(String name) {
        return "Hello, " + name + ".";
    }
}
```

Injecting Beans

In order to use the beans you create, you inject them into yet another bean that can then be used by an application, such as a JavaServer Faces application. For example, you might create a bean called `Printer` into which you would inject one of the `Greeting` beans:

```
import javax.inject.Inject;

public class Printer {

    @Inject Greeting greeting;
    ...
```

This code injects the `@Default Greeting` implementation into the bean. The following code injects the `@Informal` implementation:

```
import javax.inject.Inject;

public class Printer {

    @Inject @Informal Greeting greeting;
    ...
```

More is needed for the complete picture of this bean. Its use of scope needs to be understood. In addition, for a JavaServer Faces application, the bean needs to be accessible through the EL.

Using Scopes

For a web application to use a bean that injects another bean class, the bean needs to be able to hold state over the duration of the user's interaction with the application. The way to define this state is to give the bean a scope. You can give an object any of the scopes described in Table 28–1, depending on how you are using it.

TABLE 28–1 Scopes

Scope	Annotation	Duration
Request	`@RequestScoped`	A user's interaction with a web application in a single HTTP request.
Session	`@SessionScoped`	A user's interaction with a web application across multiple HTTP requests.
Application	`@ApplicationScoped`	Shared state across all users' interactions with a web application.
Dependent	`@Dependent`	The default scope if none is specified; it means that an object exists to serve exactly one client (bean) and has the same lifecycle as that client (bean).

TABLE 28–1 Scopes *(Continued)*

Scope	Annotation	Duration
Conversation	`@ConversationScoped`	A user's interaction with a JavaServer Faces application, within explicit developer-controlled boundaries that extend the scope across multiple invocations of the JavaServer Faces lifecycle. All long-running conversations are scoped to a particular HTTP servlet session and may not cross session boundaries.

The first three scopes are defined by both JSR 299 and the JavaServer Faces API. The last two are defined by JSR 299.

You can also define and implement custom scopes, but that is an advanced topic. Custom scopes are likely to be used by those who implement and extend the CDI specification.

A scope gives an object a well-defined lifecycle context. A scoped object can be automatically created when it is needed and automatically destroyed when the context in which it was created ends. Moreover, its state is automatically shared by any clients that execute in the same context.

Java EE components, such as servlets and enterprise beans, and JavaBeans components do not by definition have a well-defined scope. These components are one of the following:

- Singletons, such as Enterprise JavaBeans singleton beans, whose state is shared among all clients
- Stateless objects, such as servlets and stateless session beans, which do not contain client-visible state
- Objects that must be explicitly created and destroyed by their client, such as JavaBeans components and stateful session beans, whose state is shared by explicit reference passing between clients

If, however, you create a Java EE component that is a managed bean, it becomes a scoped object, which exists in a well-defined lifecycle context.

The web application for the `Printer` bean will use a simple request and response mechanism, so the managed bean can be annotated as follows:

```
import javax.inject.Inject;
import javax.enterprise.context.RequestScoped;

@RequestScoped
public class Printer {

       @Inject @Informal Greeting greeting;
    ...
```

Beans that use session, application, or conversation scope must be serializable, but beans that use request scope do not have to be serializable.

Giving Beans EL Names

To make a bean accessible through the EL, use the `@Named` built-in qualifier:

```
import javax.inject.Inject;
import javax.enterprise.context.RequestScoped;
import javax.inject.Named;

@Named
@RequestScoped
public class Printer {

    @Inject @Informal Greeting greeting;
    ...
```

The `@Named` qualifier allows you to access the bean by using the bean name, with the first letter in lowercase. For example, a Facelets page would refer to the bean as `printer`.

You can specify an argument to the `@Named` qualifier to use a nondefault name:

```
@Named("MyPrinter")
```

With this annotation, the Facelets page would refer to the bean as `MyPrinter`.

Adding Setter and Getter Methods

To make the state of the managed bean accessible, you need to add setter and getter methods for that state. The `createSalutation` method calls the bean's `greet` method, and the `getSalutation` method retrieves the result.

Once the setter and getter methods have been added, the bean is complete. The final code looks like this:

```
package greetings;

import javax.inject.Inject;
import javax.enterprise.context.RequestScoped;
import javax.inject.Named;

@Named
@RequestScoped
public class Printer {

    @Inject @Informal Greeting greeting;

    private String name;
    private String salutation;

    public void createSalutation() {
        this.salutation = greeting.greet(name);
    }
```

```
    public String getSalutation() {
        return salutation;
    }
    public String setName(String name) {
       this.name = name;
    }

    public String getName() {
       return name;
    }
}
```

Using a Managed Bean in a Facelets Page

To use the managed bean in a Facelets page, you typically create a form that uses user interface elements to call its methods and display their results. This example provides a button that asks the user to type a name, retrieves the salutation, and then displays the text in a paragraph below the button:

```
<h:form id="greetme">
   <p><h:outputLabel value="Enter your name: " for="name"/>
      <h:inputText id="name" value="#{printer.name}"/></p>
   <p><h:commandButton value="Say Hello"
                       action="#{printer.createSalutation}"/></p>
   <p><h:outputText value="#{printer.salutation}"/></p>
</h:form>
```

Injecting Objects by Using Producer Methods

Producer methods provide a way to inject objects that are not beans, objects whose values may vary at runtime, and objects that require custom initialization. For example, if you want to initialize a numeric value defined by a qualifier named `@MaxNumber`, you can define the value in a managed bean and then define a producer method, `getMaxNumber`, for it:

```
private int maxNumber = 100;
...
@Produces @MaxNumber int getMaxNumber() {
    return maxNumber;
}
```

When you inject the object in another managed bean, the container automatically invokes the producer method, initializing the value to 100:

```
@Inject @MaxNumber private int maxNumber;
```

If the value can vary at runtime, the process is slightly different. For example, the following code defines a producer method that generates a random number defined by a qualifier called `@Random`:

```
private java.util.Random random =
    new java.util.Random( System.currentTimeMillis() );

java.util.Random getRandom() {
        return random;
}

@Produces @Random int next() {
    return getRandom().nextInt(maxNumber);
}
```

When you inject this object in another managed bean, you declare a contextual instance of the object:

```
@Inject @Random Instance<Integer> randomInt;
```

You then call the `get` method of the `Instance`:

```
this.number = randomInt.get();
```

Configuring a CDI Application

An application that uses CDI must have a file named `beans.xml`. The file can be completely empty (it has content only in certain limited situations), but it must be present. For a web application, the `beans.xml` file can be in either the `WEB-INF` directory or the `WEB-INF/classes/META-INF` directory. For EJB modules or JAR files, the `beans.xml` file must be in the `META-INF` directory.

Further Information about CDI

For more information about CDI for the Java EE platform, see

- Contexts and Dependency Injection for the Java EE platform specification:

  `http://jcp.org/en/jsr/detail?id=299`
- An introduction to Contexts and Dependency Injection for the Java EE platform:

  `http://docs.jboss.org/weld/reference/latest/en-US/html/`
- Dependency Injection for Java specification:

  `http://jcp.org/en/jsr/detail?id=330`

◆ ◆ ◆ CHAPTER 29

Running the Basic Contexts and Dependency Injection Examples

This chapter describes in detail how to build and run simple examples that use CDI. The examples are in the following directory:

tut-install`/examples/cdi/`

To build and run the examples, you will do the following:

1. Use NetBeans IDE or the Ant tool to compile and package the example.
2. Use NetBeans IDE or the Ant tool to deploy the example.
3. Run the example in a web browser.

Each example has a `build.xml` file that refers to files in the following directory:

tut-install`/examples/bp-project/`

See Chapter 2, "Using the Tutorial Examples," for basic information on installing, building, and running the examples.

The following topics are addressed here:

The `simplegreeting` CDI Example

The `simplegreeting` example illustrates some of the most basic features of CDI: scopes, qualifiers, bean injection, and accessing a managed bean in a JavaServer Faces application. When you run the example, you click a button that presents either a formal or an informal greeting, depending on how you edited one of the classes. The example includes four source files, a Facelets page and template, and configuration files.

The simplegreeting Source Files

The four source files for the simplegreeting example are

- The default Greeting class, shown in "Beans as Injectable Objects" on page 478
- The @Informal qualifier interface definition and the InformalGreeting class that implements the interface, both shown in "Using Qualifiers" on page 479
- The Printer managed bean class, which injects one of the two interfaces, shown in full in "Adding Setter and Getter Methods" on page 482

The source files are located in the following directory:

tut-install/examples/cdi/simplegreeting/src/java/greetings

The Facelets Template and Page

To use the managed bean in a simple Facelets application, you can use a very simple template file and index.xhtml page. The template page, template.xhtml, looks like this:

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
          "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html"
      xmlns:ui="http://java.sun.com/jsf/facelets">
    <h:head>
        <meta http-equiv="Content-Type"
              content="text/html; charset=UTF-8"/>
        <link href="resources/css/default.css"
              rel="stylesheet" type="text/css"/>
        <title>
            <ui:insert name="title">Default Title</ui:insert>
        </title>
    </h:head>

    <body>
        <div id="container">
            <div id="header">
                <h2><ui:insert name="head">Head</ui:insert></h2>
            </div>

            <div id="space">
                <p></p>
            </div>

            <div id="content">
                <ui:insert name="content"/>
            </div>
        </div>
    </body>
</html>
```

To create the Facelets page, you can redefine the title and head, then add a small form to the content:

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
          "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:ui="http://java.sun.com/jsf/facelets"
      xmlns:h="http://java.sun.com/jsf/html"
      xmlns:f="http://java.sun.com/jsf/core">
    <ui:composition template="/template.xhtml">

        <ui:define name="title">Simple Greeting</ui:define>
        <ui:define name="head">Simple Greeting</ui:define>
        <ui:define name="content">
            <h:form id="greetme">
               <p><h:outputLabel value="Enter your name: " for="name"/>
                  <h:inputText id="name" value="#{printer.name}"/></p>
               <p><h:commandButton value="Say Hello"
                                   action="#{printer.createSalutation}"/></p>
               <p><h:outputText value="#{printer.salutation}"/> </p>
            </h:form>
        </ui:define>

    </ui:composition>
</html>
```

The form asks the user to type a name. The button is labeled Say Hello, and the action defined for it is to call the `createSalutation` method of the `Printer` managed bean. This method in turn calls the `greet` method of the defined `Greeting` class.

The output text for the form is the value of the greeting returned by the setter method. Depending on whether the default or the `@Informal` version of the greeting is injected, this is one of the following, where *name* is the name typed by the user:

`Hello, `*name*`.`

`Hi, `*name*`!`

The Facelets page and template are located in the following directory:

tut-install`/examples/cdi/simplegreeting/web`

The simple CSS file that is used by the Facelets page is in the following location:

tut-install`/examples/cdi/simplegreeting/web/resources/css/default.css`

Configuration Files

You must create an empty `beans.xml` file to indicate to GlassFish Server that your application is a CDI application. This file can have content in some situations, but not in simple applications like this one.

Your application also needs the basic web application deployment descriptors `web.xml` and `glassfish-web.xml`. These configuration files are located in the following directory:

tut-install`/examples/cdi/simplegreeting/web/WEB-INF`

Building, Packaging, Deploying, and Running the `simplegreeting` CDI Example

You can build, package, deploy, and run the `simplegreeting` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the `simplegreeting` Example Using NetBeans IDE

This procedure builds the application into the following directory:

tut-install`/examples/cdi/simplegreeting/build/web`

The contents of this directory are deployed to the GlassFish Server.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/cdi/`
3. **Select the `simplegreeting` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **(Optional) To modify the `Printer.java` file, perform these steps:**
   a. **Expand the Source Packages node.**
   b. **Expand the `greetings` node.**
   c. **Double-click the `Printer.java` file.**
   d. **In the edit pane, comment out the `@Informal` annotation:**

```
//@Informal
@Inject
Greeting greeting;
```

   e. **Save the file.**

7. **In the Projects tab, right-click the `simplegreeting` project and select Deploy.**

▼ To Build, Package, and Deploy the `simplegreeting` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/cdi/simplegreeting/`

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `simplegreeting.war`, located in the `dist` directory.

3. **Type the following command:**

   ```
   ant deploy
   ```

   Typing this command deploys `simplegreeting.war` to the GlassFish Server.

▼ To Run the `simplegreeting` Example

1. **In a web browser, type the following URL:**

   ```
   http://localhost:8080/simplegreeting
   ```

   The Simple Greeting page opens.

2. **Type a name in the text field.**

   For example, suppose that you type **`Duke`**.

3. **Click the Say Hello button.**

   If you did not modify the `Printer.java` file, the following text string appears below the button:

   ```
   Hi, Duke!
   ```

   If you commented out the `@Informal` annotation in the `Printer.java` file, the following text string appears below the button:

   ```
   Hello, Duke.
   ```

   Figure 29–1 shows what the application looks like if you did not modify the `Printer.java` file.

FIGURE 29–1 Simple Greeting Application



The guessnumber CDI Example

The guessnumber example, somewhat more complex than the simplegreeting example, illustrates the use of producer methods and of session and application scope. The example is a game in which you try to guess a number in fewer than ten attempts. It is similar to the guessnumber example described in Chapter 5, "Introduction to Facelets," except that you can keep guessing until you get the right answer or until you use up your ten attempts.

The example includes four source files, a Facelets page and template, and configuration files. The configuration files and the template are the same as those used for the simplegreeting example.

The guessnumber Source Files

The four source files for the guessnumber example are

- The @MaxNumber qualifier interface
- The @Random qualifier interface
- The Generator managed bean, which defines producer methods
- The UserNumberBean managed bean

The source files are located in the following directory:

tut-install/examples/cdi/guessnumber/src/java/guessnumber

The @MaxNumber and @Random Qualifier Interfaces

The @MaxNumber qualifier interface is defined as follows:

```
package guessnumber;

import static java.lang.annotation.ElementType.FIELD;
```

```
import static java.lang.annotation.ElementType.METHOD;
import static java.lang.annotation.ElementType.PARAMETER;
import static java.lang.annotation.ElementType.TYPE;
import static java.lang.annotation.RetentionPolicy.RUNTIME;

import java.lang.annotation.Documented;
import java.lang.annotation.Retention;
import java.lang.annotation.Target;

import javax.inject.Qualifier;

@Target( { TYPE, METHOD, PARAMETER, FIELD })
@Retention(RUNTIME)
@Documented
@Qualifier
public @interface MaxNumber {

}
```

The `@Random` qualifier interface is defined as follows:

```
package guessnumber;

import static java.lang.annotation.ElementType.FIELD;
import static java.lang.annotation.ElementType.METHOD;
import static java.lang.annotation.ElementType.PARAMETER;
import static java.lang.annotation.ElementType.TYPE;
import static java.lang.annotation.RetentionPolicy.RUNTIME;

import java.lang.annotation.Documented;
import java.lang.annotation.Retention;
import java.lang.annotation.Target;

import javax.inject.Qualifier;

@Target( { TYPE, METHOD, PARAMETER, FIELD })
@Retention(RUNTIME)
@Documented
@Qualifier
public @interface Random {

}
```

The `Generator` Managed Bean

The `Generator` managed bean contains the two producer methods for the application. The bean has the `@ApplicationScoped` annotation to specify that its context extends for the duration of the user's interaction with the application:

```
package guessnumber;

import java.io.Serializable;

import javax.enterprise.context.ApplicationScoped;
import javax.enterprise.inject.Produces;
```

```
@ApplicationScoped
public class Generator implements Serializable {

    private static final long serialVersionUID = -7213673465118041882L;

    private java.util.Random random =
        new java.util.Random( System.currentTimeMillis() );

    private int maxNumber = 100;

    java.util.Random getRandom() {
        return random;
    }

    @Produces @Random int next() {
        return getRandom().nextInt(maxNumber);
    }

    @Produces @MaxNumber int getMaxNumber() {
        return maxNumber;
    }

}
```

The `UserNumberBean` Managed Bean

The `UserNumberBean` managed bean, the backing bean for the JavaServer Faces application, provides the basic logic for the game. This bean does the following:

- Implements setter and getter methods for the bean fields
- Injects the two qualifier objects
- Provides a `reset` method that allows you to begin a new game after you complete one
- Provides a `check` method that determines whether the user has guessed the number
- Provides a `validateNumberRange` method that determines whether the user's input is correct

The bean is defined as follows:

```
package guessnumber;

import java.io.Serializable;

import javax.annotation.PostConstruct;
import javax.enterprise.context.SessionScoped;
import javax.enterprise.inject.Instance;
import javax.inject.Inject;
import javax.inject.Named;
import javax.faces.application.FacesMessage;
import javax.faces.component.UIComponent;
import javax.faces.component.UIInput;
import javax.faces.context.FacesContext;

@Named
```

```
@SessionScoped
public class UserNumberBean implements Serializable {

    private static final long serialVersionUID = 1L;
    private int number;
    private Integer userNumber;
    private int minimum;
    private int remainingGuesses;

    @MaxNumber
    @Inject
    private int maxNumber;

    private int maximum;

    @Random
    @Inject
    Instance<Integer> randomInt;

    public UserNumberBean() {
    }

    public int getNumber() {
        return number;
    }

    public void setUserNumber(Integer user_number) {
        userNumber = user_number;
    }

    public Integer getUserNumber() {
        return userNumber;
    }

    public int getMaximum() {
        return (this.maximum);
    }

    public void setMaximum(int maximum) {
        this.maximum = maximum;
    }

    public int getMinimum() {
        return (this.minimum);
    }

    public void setMinimum(int minimum) {
        this.minimum = minimum;
    }

    public int getRemainingGuesses() {
        return remainingGuesses;
    }

    public String check() throws InterruptedException {
        if (userNumber > number) {
            maximum = userNumber - 1;
        }
        if (userNumber < number) {
```

```
            minimum = userNumber + 1;
        }
        if (userNumber == number) {
            FacesContext.getCurrentInstance().addMessage(null,
                new FacesMessage("Correct!"));
        }
        remainingGuesses--;
        return null;
    }

    @PostConstruct
    public void reset() {
        this.minimum = 0;
        this.userNumber = 0;
        this.remainingGuesses = 10;
        this.maximum = maxNumber;
        this.number = randomInt.get();
    }

    public void validateNumberRange(FacesContext context,
                                    UIComponent toValidate,
                                    Object value) {
        if (remainingGuesses <= 0) {
            FacesMessage message = new FacesMessage("No guesses left!");
            context.addMessage(toValidate.getClientId(context), message);
            ((UIInput) toValidate).setValid(false);
            return;
        }
        int input = (Integer) value;

        if (input < minimum || input > maximum) {
            ((UIInput) toValidate).setValid(false);

            FacesMessage message = new FacesMessage("Invalid guess");
            context.addMessage(toValidate.getClientId(context), message);
        }
    }
}
```

The Facelets Page

This example uses the same template that the `simplegreeting` example uses. The `index.xhtml` file, however, is more complex.

```
<?xml version='1.0' encoding='UTF-8' ?>
<!DOCTYPE html PUBLIC "-//W3C//DTD XHTML 1.0 Transitional//EN"
          "http://www.w3.org/TR/xhtml1/DTD/xhtml1-transitional.dtd">
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:ui="http://java.sun.com/jsf/facelets"
      xmlns:h="http://java.sun.com/jsf/html"
      xmlns:f="http://java.sun.com/jsf/core">
    <ui:composition template="/template.xhtml">

        <ui:define name="title">Guess My Number</ui:define>
        <ui:define name="head">Guess My Number</ui:define>
        <ui:define name="content">
            <h:form id="GuessMain">
                <div style="color: black; font-size: 24px;">
                    <p>I'm thinking of a number between
                    <span style="color: blue">#{userNumberBean.minimum}</span> and
                    <span style="color: blue">#{userNumberBean.maximum}</span>. You have
                    <span style="color: blue">#{userNumberBean.remainingGuesses}</span>
                    guesses.</p>
                </div>
                <h:panelGrid border="0" columns="5" style="font-size: 18px;">
                    Number:
                    <h:inputText id="inputGuess"
                       value="#{userNumberBean.userNumber}"
                       required="true" size="3"
                       disabled="#{userNumberBean.number eq userNumberBean.userNumber}"
                       validator="#{userNumberBean.validateNumberRange}">
                    </h:inputText>
                    <h:commandButton id="GuessButton" value="Guess"
                       action="#{userNumberBean.check}"
                       disabled="#{userNumberBean.number eq userNumberBean.userNumber}"/>
                    <h:commandButton id="RestartButton" value="Reset"
                       action="#{userNumberBean.reset}"
                       immediate="true" />
                    <h:outputText id="Higher" value="Higher!"
rendered="#{userNumberBean.number gt userNumberBean.userNumber and userNumberBean.userNumber ne 0}"
                       style="color: red"/>
                    <h:outputText id="Lower" value="Lower!"
rendered="#{userNumberBean.number lt userNumberBean.userNumber and userNumberBean.userNumber ne 0}"
                       style="color: red"/>
                </h:panelGrid>
                <div style="color: red; font-size: 14px;">
                    <h:messages id="messages" globalOnly="false"/>
                </div>
            </h:form>
        </ui:define>

    </ui:composition>
</html>
```

The Facelets page presents the user with the minimum and maximum values and the number of guesses remaining. The user's interaction with the game takes place within the `panelGrid` table, which contains an input field, Guess and Reset buttons, and a text field that appears if the guess is higher or lower than the correct number. Every time the user clicks the Guess button, the `userNumberBean.check` method is called to reset the maximum or minimum value or, if the guess is correct, to generate a `FacesMessage` to that effect. The method that determines whether each guess is valid is `userNumberBean.validateNumberRange`.

Building, Packaging, Deploying, and Running the guessnumber CDI Example

You can build, package, deploy, and run the guessnumber application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the guessnumber Example Using NetBeans IDE

This procedure builds the application into the following directory:

tut-install/examples/cdi/guessnumber/build/web

The contents of this directory are deployed to the GlassFish Server.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install/examples/cdi/
3. **Select the guessnumber folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the guessnumber project and select Deploy.**

▼ To Build, Package, and Deploy the guessnumber Example Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/cdi/guessnumber/
2. **Type the following command:**
   ant

   This command calls the default target, which builds and packages the application into a WAR file, guessnumber.war, located in the dist directory.

3 **Type the following command:**

```
ant deploy
```

The `guessnumber.war` file will be deployed to the GlassFish Server.

▼ To Run the `guessnumber` Example

1 **In a web browser, type the following URL:**

```
http://localhost:8080/guessnumber
```

The Guess My Number page opens, as shown in Figure 29–2.

FIGURE 29–2 Guess My Number Example



2 **Type a number in the Number text field and click Guess.**

The minimum and maximum values are modified, along with the remaining number of guesses.

3 **Keep guessing numbers until you get the right answer or run out of guesses.**

If you get the right answer, the input field and Guess button are grayed out, as shown in Figure 29–3.

FIGURE 29–3 Guess My Number at End of Game



4 Click the Reset button to play the game again with a new random number.

◆ ◆ ◆ CHAPTER 30

Contexts and Dependency Injection for the Java EE Platform: Advanced Topics

This chapter describes more advanced features of Contexts and Dependency Injection for the Java EE Platform. Specifically, it covers additional features that CDI provides to enable loose coupling of components with strong typing, as described in "Overview of CDI" on page 476.

The following topics are addressed here:

Using Alternatives

When you have more than one version of a bean that you use for different purposes, you can choose between them during the development phase by injecting one qualifier or another, as shown in "The `simplegreeting` CDI Example" on page 485.

Instead of having to change the source code of your application, however, you can make the choice at deployment time by using alternatives.

Alternatives are commonly used for purposes like the following:

- To handle client-specific business logic that is determined at runtime
- To specify beans that are valid for a particular deployment scenario (for example, when country-specific sales tax laws require country-specific sales tax business logic)
- To create dummy (mock) versions of beans to be used for testing

To make a bean available for lookup, injection, or EL resolution using this mechanism, give it a `javax.enterprise.inject.Alternative` annotation and then use the `alternative` element to specify it in the `beans.xml` file.

For example, you might want to create a full version of a bean and also a simpler version that you use only for certain kinds of testing. The example described in "The encoder Example: Using Alternatives" on page 512 contains two such beans, `CoderImpl` and `TestCoderImpl`. The test bean is annotated as follows:

```
@Alternative
public class TestCoderImpl implements Coder { ... }
```

The full version is not annotated:

```
public class CoderImpl implements Coder { ... }
```

The managed bean injects an instance of the `Coder` interface:

```
@Inject
Coder coder;
```

The alternative version of the bean is used by the application only if that version is declared as follows in the `beans.xml` file:

```
<beans ... >
    <alternatives>
        <class>encoder.TestCoderImpl</class>
    </alternatives>
</beans>
```

If the `alternatives` element is commented out in the `beans.xml` file, the `CoderImpl` class is used.

You can also have several beans that implement the same interface and are all annotated `@Alternative`. In this case, you must specify in the `beans.xml` file which of these alternative beans you want to use. If `CoderImpl` were also annotated `@Alternative`, one of the two beans would always have to be specified in the `beans.xml` file.

Using Specialization

Specialization has a function similar to that of alternatives, in that it allows you to substitute one bean for another. However, you might want to make one bean override the other in all cases. Suppose that you defined the following two beans:

```
@Default @Asynchronous
public class AsynchronousService implements Service { ... }

@Alternative
public class MockAsynchronousService extends AsynchronousService { ... }
```

If you then declared `MockAsynchronousService` as an alternative in your `beans.xml` file, the following injection point would resolve to `MockAsynchronousService`:

```
@Inject Service service;
```

The following, however, would resolve to `AsynchronousService` rather than `MockAsynchronousService`, because `MockAsynchronousService` does not have the `@Asynchronous` qualifier:

```
@Inject @Asynchronous Service service;
```

To make sure that `MockAsynchronousService` is always injected, you would have to implement all bean types and bean qualifiers of `AsynchronousService`. However, if `AsynchronousService` declared a producer method or observer method, even this cumbersome mechanism would not ensure that the other bean is never invoked. Specialization provides a simpler mechanism.

Specialization happens at development time as well as at runtime. If you declare that one bean *specializes* another, it extends the other bean class, and at runtime the specialized bean completely replaces the other bean. If the first bean is produced by means of a producer method, you must also override the producer method.

You specialize a bean by giving it the `javax.enterprise.inject.Specializes` annotation. For example, you might declare a bean as follows:

```
@Specializes
public class MockAsynchronousService extends AsynchronousService { ... }
```

In this case, the `MockAsynchronousService` class will always be invoked instead of the `AsynchronousService` class.

Usually, a bean marked with the `@Specializes` annotation is also an alternative and is declared as an alternative in the `beans.xml` file. Such a bean is meant to stand in as a replacement for the default implementation, and the alternative implementation automatically inherits all qualifiers of the default implementation as well as its EL name, if it has one.

Using Producer Methods and Fields

A *producer method* is a method that generates an object that can then be injected. Typically, you use producer methods in the following situations:

- When you want to inject an object that is not itself a bean
- When the concrete type of the object to be injected may vary at runtime
- When the object requires some custom initialization that the bean constructor does not perform

For more information on producer methods, see "Injecting Objects by Using Producer Methods" on page 483.

A *producer field* is a simpler alternative to a producer method; it is a field of a bean that generates an object. It can be used instead of a simple getter method. Producer fields are particularly useful for declaring Java EE resources.

A producer method or field is annotated with the `javax.enterprise.inject.Produces` annotation.

A producer method can allow you to select a bean implementation at runtime, instead of at development time or deployment time. For example, in the example described in "The `producermethods` Example: Using a Producer Method To Choose a Bean Implementation" on page 517, the managed bean defines the following producer method:

```
@Produces
@Chosen
@RequestScoped
public Coder getCoder(@New TestCoderImpl tci,
        @New CoderImpl ci) {

    switch (coderType) {
        case TEST:
            return tci;
        case SHIFT:
            return ci;
        default:
            return null;
    }
}
```

The `javax.enterprise.inject.New` qualifier instructs the CDI runtime to instantiate both of the coder implementations and provide them as arguments to the producer method. Here, `getCoder` becomes in effect a getter method, and when the `coder` property is injected with the same qualifier and other annotations as the method, the selected version of the interface is used.

```
@Inject
@Chosen
@RequestScoped
Coder coder;
```

Specifying the qualifier is essential: it tells CDI which `Coder` to inject. Without it, the CDI implementation would not be able to choose between `CoderImpl`, `TestCoderImpl`, and the one returned by `getCoder`, and would abort deployment, informing the user of the ambiguous dependency.

A common use of a producer field is to generate an object such as a JDBC `DataSource` or a Java Persistence API `EntityManager`. The object can then be managed by the container. For example, you could create a `@UserDatabase` qualifier and then declare a producer field for an entity manager as follows:

```
@Produces
@UserDatabase
@PersistenceContext
private EntityManager em;
```

The `@UserDatabase` qualifier can be used when you inject the object into another bean, `RequestBean`, elsewhere in the application:

```
    @Inject
    @UserDatabase
    EntityManager em;
    ...
```

"The `producerfields` Example: Using Producer Fields to Generate Resources" on page 519 shows how to use producer fields to generate an entity manager.

You can use a producer method to generate an object that needs to be removed when its work is completed. If you do, you need a corresponding disposer method, annotated with a `@Disposes` annotation. For example, if you used a producer method instead of a producer field to create the entity manager, you would create and close it as follows:

```
@PersistenceContext
private EntityManager em;

@Produces
@UserDatabase
public EntityManager create() {
    return em;
}

public void close(@Disposes @UserDatabase EntityManager em) {
    em.close();
}
```

The disposer method is called automatically when the context ends (in this case, at the end of the conversation, because `RequestBean` has conversation scope), and the parameter in the `close` method receives the object produced by the producer method, `create`.

Using Events

Events allow beans to communicate without any compile-time dependency. One bean can define an event, another bean can fire the event, and yet another bean can handle the event. The beans can be in separate packages and even in separate tiers of the application.

Defining Events

An event consists of the following:

- The event object, a Java object
- Zero or more qualifier types, the event qualifiers

For example, in the `billpayment` example described in "The `billpayment` Example: Using Events and Interceptors" on page 525, a `PaymentEvent` bean defines an event using three properties, which have setter and getter methods:

```
    public String paymentType;
    public BigDecimal value;
    public Date datetime;

    public PaymentEvent() {
    }
```

The example also defines qualifiers that distinguish between two kinds of `PaymentEvent`. Every event also has the default qualifier `@Any`.

Using Observer Methods to Handle Events

An event handler uses an *observer method* to consume events.

Each observer method takes as a parameter an event of a specific event type that is annotated with the `@Observes` annotation and with any qualifiers for that event type. The observer method is notified of an event if the event object matches the event type and if all the qualifiers of the event match the observer method event qualifiers.

The observer method can take other parameters in addition to the event parameter. The additional parameters are injection points and can declare qualifiers.

The event handler for the `billpayment` example, `PaymentHandler`, defines two observer methods, one for each type of `PaymentEvent`:

```
public void creditPayment(@Observes @Credit PaymentEvent event) {
    ...
}

public void debitPayment(@Observes @Debit PaymentEvent event) {
    ...
}
```

Observer methods can also be conditional or transactional:

- A conditional observer method is notified of an event only if an instance of the bean that defines the observer method already exists in the current context. To declare a conditional observer method, specify `notifyObserver=IF_EXISTS` as an argument to `@Observes`:

  ```
  @Observes(notifyObserver=IF_EXISTS)
  ```

  To obtain the default unconditional behavior, you can specify `@Observes(notifyObserver=ALWAYS)`.
- A transactional observer method is notified of an event during the before completion or after completion phase of the transaction in which the event was fired. You can also specify that the notification is to occur only after the transaction has completed successfully or unsuccessfully. To specify a transactional observer method, use any of the following arguments to `@Observes`:

```
@Observes(during=BEFORE_COMPLETION)

@Observes(during=AFTER_COMPLETION)

@Observes(during=AFTER_SUCCESS)

@Observes(during=AFTER_FAILURE)
```

To obtain the default non-transactional behavior, specify `@Observes(during=IN_PROGRESS)`.

An observer method that is called before completion of a transaction may call the `setRollbackOnly` method on the transaction instance to force a transaction rollback.

Observer methods may throw exceptions. If a transactional observer method throws an exception, the exception is caught by the container. If the observer method is non-transactional, the exception aborts processing of the event, and no other observer methods for the event are called.

Firing Events

To activate an event, call the `javax.enterprise.event.Event.fire` method. This method fires an event and notifies any observer methods.

In the `billpayment` example, a managed bean called `PaymentBean` fires the appropriate event by using information that it receives from the user interface. There are actually four event beans, two for the event object and two for the payload. The managed bean injects the two event beans. The `pay` method uses a `switch` statement to choose which event to fire, using `new` to create the payload.

```
@Inject
@Credit
Event<PaymentEvent> creditEvent;

@Inject
@Debit
Event<PaymentEvent> debitEvent;

public static final int DEBIT = 1;
public static final int CREDIT = 2;
private int paymentOption = DEBIT;
...

@Logged
public String pay() {
    ...
    switch (paymentOption) {
        case DEBIT:
            PaymentEvent debitPayload = new PaymentEvent();
            // populate payload ...
            debitEvent.fire(debitPayload);
```

```
                break;
            case CREDIT:
                PaymentEvent creditPayload = new PaymentEvent();
                // populate payload ...
                creditEvent.fire(creditPayload);
                break;
            default:
                logger.severe("Invalid payment option!");
        }
        ...
    }
```

The argument to the `fire` method is a `PaymentEvent` that contains the payload. The fired event is then consumed by the observer methods.

Using Interceptors

An *interceptor* is a class that is used to interpose in method invocations or lifecycle events that occur in an associated target class. The interceptor performs tasks, such as logging or auditing, that are separate from the business logic of the application and that are repeated often within an application. Such tasks are often called *cross-cutting* tasks. Interceptors allow you to specify the code for these tasks in one place for easy maintenance. When interceptors were first introduced to the Java EE platform, they were specific to enterprise beans. You can now use them with Java EE managed objects of all kinds, including managed beans.

For information on Java EE interceptors, see Chapter 48, "Using Java EE Interceptors."

An interceptor class often contains a method annotated `@AroundInvoke`, which specifies the tasks the interceptor will perform when intercepted methods are invoked. It can also contain a method annotated `@PostConstruct`, `@PreDestroy`, `@PrePassivate`, or `@PostActivate`, to specify lifecycle callback interceptors, and a method annotated `@AroundTimeout`, to specify EJB timeout interceptors. An interceptor class can contain more than one interceptor method, but it must have no more than one method of each type.

Along with an interceptor, an application defines one or more *interceptor binding types*, which are annotations that associate an interceptor with target beans or methods. For example, the `billpayment` example contains an interceptor binding type named `@Logged` and an interceptor named `LoggedInterceptor`. The interceptor binding type declaration looks something like a qualifier declaration, but it is annotated with `javax.interceptor.InterceptorBinding`:

```
@Inherited
@InterceptorBinding
@Retention(RUNTIME)
@Target({METHOD, TYPE})
public @interface Logged {
}
```

An interceptor binding also has the `java.lang.annotation.Inherited` annotation, to specify that the annotation can be inherited from superclasses. The `@Inherited` annotation also applies to custom scopes (not discussed in this tutorial), but does not apply to qualifiers.

An interceptor binding type may declare other interceptor bindings.

The interceptor class is annotated with the interceptor binding as well as with the `@Interceptor` annotation. For an example, see "The `LoggedInterceptor` Interceptor Class" on page 529.

Every `@AroundInvoke` method takes a `javax.interceptor.InvocationContext` argument, returns a `java.lang.Object`, and throws an `Exception`. It can call `InvocationContext` methods. The `@AroundInvoke` method must call the `proceed` method, which causes the target class method to be invoked.

Once an interceptor and binding type are defined, you can annotate beans and individual methods with the binding type to specify that the interceptor is to be invoked either on all methods of the bean or on specific methods. For example, in the `billpayment` example, the `PaymentHandler` bean is annotated `@Logged`, which means that any invocation of its business methods will cause the interceptor's `@AroundInvoke` method to be invoked:

```
@Logged
@SessionScoped
public class PaymentHandler implements Serializable {...}
```

However, in the `PaymentBean` bean, only the `pay` and `reset` methods have the `@Logged` annotation, so the interceptor is invoked only when these methods are invoked:

```
@Logged
public String pay() {...}

@Logged
public void reset() {...}
```

In order for an interceptor to be invoked in a CDI application, it must, like an alternative, be specified in the `beans.xml` file. For example, the `LoggedInterceptor` class is specified as follows:

```
<interceptors>
    <class>billpayment.interceptors.LoggedInterceptor</class>
</interceptors>
```

If an application uses more than one interceptor, the interceptors are invoked in the order specified in the `beans.xml` file.

Using Decorators

A *decorator* is a Java class that is annotated `javax.decorator.Decorator` and that has a corresponding `decorators` element in the `beans.xml` file.

A decorator bean class must also have a delegate injection point, which is annotated `javax.decorator.Delegate`. This injection point can be a field, a constructor parameter, or an initializer method parameter of the decorator class.

Decorators are outwardly similar to interceptors. However, they actually perform tasks complementary to those performed by interceptors. Interceptors perform cross-cutting tasks associated with method invocation and with the lifecycles of beans, but cannot perform any business logic. Decorators, on the other hand, do perform business logic by intercepting business methods of beans. This means that instead of being reusable for different kinds of applications as interceptors are, their logic is specific to a particular application.

For example, instead of using an alternative `TestCoderImpl` class for the `encoder` example, you could create a decorator as follows:

```
@Decorator
public abstract class CoderDecorator implements Coder {

    @Inject
    @Delegate
    @Any
    Coder coder;

    public String codeString(String s, int tval) {
        int len = s.length();

        return "\"" + s + "\" becomes " + "\"" + coder.codeString(s, tval)
                + "\", " + len + " characters in length";
    }
}
```

See "The `decorators` Example: Decorating a Bean" on page 532 for an example that uses this decorator.

This simple decorator returns more detailed output than the encoded string returned by the `CoderImpl.codeString` method. A more complex decorator could store information in a database or perform some other business logic.

A decorator can be declared as an abstract class, so that it does not have to implement all the business methods of the interface.

In order for a decorator to be invoked in a CDI application, it must, like an interceptor or an alternative, be specified in the `beans.xml` file. For example, the `CoderDecorator` class is specified as follows:

```
<decorators>
    <class>decorators.CoderDecorator</class>
</decorators>
```

If an application uses more than one decorator, the decorators are invoked in the order in which they are specified in the `beans.xml` file.

If an application has both interceptors and decorators, the interceptors are invoked first. This means, in effect, that you cannot intercept a decorator.

Using Stereotypes

A *stereotype* is a kind of annotation, applied to a bean, that incorporates other annotations. Stereotypes can be particularly useful in large applications where you have a number of beans that perform similar functions. A stereotype is a kind of annotation that specifies the following:

- A default scope
- Zero or more interceptor bindings
- Optionally, a `@Named` annotation, guaranteeing default EL naming
- Optionally, an `@Alternative` annotation, specifying that all beans with this stereotype are alternatives

A bean annotated with a particular stereotype will always use the specified annotations, so that you do not have to apply the same annotations to many beans.

For example, you might create a stereotype named `Action`, using the `javax.enterprise.inject.Stereotype` annotation:

```
@RequestScoped
@Secure
@Transactional
@Named
@Stereotype
@Target(TYPE)
@Retention(RUNTIME)
public @interface Action {}
```

All beans annotated `@Action` will have request scope, use default EL naming, and have the interceptor bindings `@Transactional` and `@Secure`:

You could also create a stereotype named `Mock`:

```
@Alternative
@Stereotype
@Target(TYPE)
@Retention(RUNTIME)
public @interface Mock {}
```

All beans with this annotation are alternatives.

It is possible to apply multiple stereotypes to the same bean, so you can annotate a bean as follows:

```
@Action
@Mock
public class MockLoginAction extends LoginAction { ... }
```

It is also possible to override the scope specified by a stereotype, simply by specifying a different scope for the bean. The following declaration gives the `MockLoginAction` bean session scope instead of request scope:

```
@SessionScoped
@Action
@Mock
public class MockLoginAction extends LoginAction { ... }
```

CDI makes available a built-in stereotype called `Model`, which is intended for use with beans that define the model layer of a model-view-controller application architecture. This stereotype specifies that a bean is both `@Named` and `@RequestScoped`:

```
@Named
@RequestScoped
@Stereotype
@Target({TYPE, METHOD, FIELD})
@Retention(RUNTIME)
public @interface Model {}
```

◆ ◆ ◆ CHAPTER 31

Running the Advanced Contexts and Dependency Injection Examples

This chapter describes in detail how to build and run several advanced examples that use CDI. The examples are in the following directory:

tut-install/examples/cdi/

To build and run the examples, you will do the following:

1. Use NetBeans IDE or the Ant tool to compile, package, and deploy the example.
2. Run the example in a web browser.

Each example has a `build.xml` file that refers to files in the following directory:

tut-install/examples/bp-project/

See Chapter 2, "Using the Tutorial Examples," for basic information on installing, building, and running the examples.

The following topics are addressed here:

The encoder Example: Using Alternatives

The encoder example shows how to use alternatives to choose between two beans at deployment time, as described in "Using Alternatives" on page 499. The example includes an interface and two implementations of it, a managed bean, a Facelets page, and configuration files.

The Coder Interface and Implementations

The Coder interface contains just one method, codeString, that takes two arguments: a string, and an integer value that specifies how the letters in the string should be transposed.

```
public interface Coder {

    public String codeString(String s, int tval);
}
```

The interface has two implementation classes, CoderImpl and TestCoderImpl. The implementation of codeString in CoderImpl shifts the string argument forward in the alphabet by the number of letters specified in the second argument; any characters that are not letters are left unchanged. (This simple shift code is known as a Caesar cipher, for Julius Caesar, who reportedly used it to communicate with his generals.) The implementation in TestCoderImpl merely displays the values of the arguments. The TestCoderImpl implementation is annotated @Alternative:

```
import javax.enterprise.inject.Alternative;

@Alternative
public class TestCoderImpl implements Coder {

    public String codeString(String s, int tval) {
        return ("input string is " + s + ", shift value is " + tval);
    }
}
```

The beans.xml file for the encoder example contains an alternatives element for the TestCoderImplclass, but by default the element is commented out:

```
<beans ... >
    <!--<alternatives>
        <class>encoder.TestCoderImpl</class>
    </alternatives>-->
</beans>
```

This means that by default, the TestCoderImpl class, annotated @Alternative, will not be used. Instead, the CoderImpl class will be used.

The encoder Facelets Page and Managed Bean

The simple Facelets page for the encoder example, index.xhtml, asks the user to type the string and integer values and passes them to the managed bean, CoderBean, as coderBean.inputString and coderBean.transVal:

```
<html xmlns="http://www.w3.org/1999/xhtml"
      xmlns:h="http://java.sun.com/jsf/html">
    <h:head>
        <title>String Encoder</title>
        <link href="resources/css/default.css"
              rel="stylesheet" type="text/css"/>
    </h:head>
    <h:body>
        <h2>String Encoder</h2>
        <p>Type a string and an integer, then click Encode.</p>
        <p>Depending on which alternative is enabled, the coder bean
            will either display the argument values or return a string that
            shifts the letters in the original string by the value you specify.
            The value must be between 0 and 26.</p>
        <h:form id="encodeit">
            <p><h:outputLabel value="Type a string: " for="inputString"/>
                <h:inputText id="inputString"
                             value="#{coderBean.inputString}"/>
                <h:outputLabel value="Type the number of letters to shift by: "
                               for="transVal"/>
                <h:inputText id="transVal" value="#{coderBean.transVal}"/></p>
            <p><h:commandButton value="Encode"
                                action="#{coderBean.encodeString()}"/></p>
            <p><h:outputLabel value="Result: " for="outputString"/>
                <h:outputText id="outputString" value="#{coderBean.codedString}"
                              style="color:blue"/> </p>
            <p><h:commandButton value="Reset" action="#{coderBean.reset}"/></p>
        </h:form>
    </h:body>
</html>
```

When the user clicks the Encode button, the page invokes the managed bean's encodeString method and displays the result, coderBean.codedString, in blue. The page also has a Reset button that clears the fields.

The managed bean, CoderBean, is a @RequestScoped bean that declares its input and output properties. The transVal property has three Bean Validation constraints that enforce limits on the integer value, so that if the user types an invalid value, a default error message appears on the Facelets page. The bean also injects an instance of the Coder interface:

```
@Named
@RequestScoped
public class CoderBean {

    private String inputString;
    private String codedString;
    @Max(26)
    @Min(0)
```

```
@NotNull
private int transVal;

@Inject
Coder coder;
...
```

In addition to simple getter and setter methods for the three properties, the bean defines the `encodeString` action method called by the Facelets page. This method sets the `codedString` property to the value returned by a call to the `codeString` method of the `Coder` implementation:

```
public void encodeString() {
    setCodedString(coder.codeString(inputString, transVal));
}
```

Finally, the bean defines the `reset` method to empty the fields of the Facelets page:

```
public void reset() {
    setInputString("");
    setTransVal(0);
}
```

Building, Packaging, Deploying, and Running the `encoder` Example

You can build, package, deploy, and run the `encoder` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the `encoder` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/cdi/`
3. **Select the `encoder` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `encoder` project and select Deploy.**

▼ To Run the encoder Example Using NetBeans IDE

1. **In a web browser, type the following URL:**

   ```
   http://localhost:8080/encoder
   ```

   The String Encoder page opens.

2. **Type a string and the number of letters to shift by, then click Encode.**

   The encoded string appears in blue on the Result line. For example, if you type `Java` and `4`, the result is `Neze`.

3. **Now, edit the `beans.xml` file to enable the alternative implementation of `Coder`.**

   a. **In the Projects tab, under the `encoder` project, expand the Web Pages node, then the WEB-INF node.**

   b. **Double-click the `beans.xml` file to open it.**

   c. **Remove the comment characters that surround the `alternatives` element, so that it looks like this:**

   ```
   <alternatives>
       <class>encoder.TestCoderImpl</class>
   </alternatives>
   ```

   d. **Save the file.**

4. **Right-click the `encoder` project and select Deploy.**

5. **In the web browser, retype the URL to show the String Encoder page for the redeployed project:**

   ```
   http://localhost:8080/encoder/
   ```

6. **Type a string and the number of letters to shift by, then click Encode.**

   This time, the Result line displays your arguments. For example, if you type `Java` and `4`, the result is:

   ```
   Result: input string is Java, shift value is 4
   ```

▼ To Build, Package, and Deploy the encoder Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/cdi/encoder/`

2. **Type the following command:**

   ```
   ant
   ```

This command calls the `default` target, which builds and packages the application into a WAR file, `encoder.war`, located in the `dist` directory.

3 **Type the following command:**

```
ant deploy
```

▼ To Run the `encoder` Example Using Ant

1 **In a web browser, type the following URL:**

```
http://localhost:8080/encoder/
```

The String Encoder page opens.

2 **Type a string and the number of letters to shift by, then click Encode.**

The encoded string appears in blue on the Result line. For example, if you type `Java` and 4, the result is `Neze`.

3 **Now, edit the `beans.xml` file to enable the alternative implementation of `Coder`.**

a. **In a text editor, open the following file:**

tut-install`/examples/cdi/encoder/web/WEB-INF/beans.xml`

b. **Remove the comment characters that surround the `alternatives` element, so that it looks like this:**

```
<alternatives>
    <class>encoder.TestCoderImpl</class>
</alternatives>
```

c. **Save and close the file.**

4 **Type the following command:**

```
ant deploy
```

5 **In the web browser, retype the URL to show the String Encoder page for the redeployed project:**

```
http://localhost:8080/encoder
```

6 **Type a string and the number of letters to shift by, then click Encode.**

This time, the Result line displays your arguments. For example, if you type `Java` and 4, the result is:

```
Result: input string is Java, shift value is 4
```

The producermethods Example: Using a Producer Method To Choose a Bean Implementation

The producermethods example shows how to use a producer method to choose between two beans at runtime, as described in "Using Producer Methods and Fields" on page 501. It is very similar to the encoder example described in "The encoder Example: Using Alternatives" on page 512. The example includes the same interface and two implementations of it, a managed bean, a Facelets page, and configuration files. It also contains a qualifier type. When you run it, you do not need to edit the beans.xml file and redeploy the application to change its behavior.

Components of the producermethods Example

The components of producermethods are very much like those for encoder, with some significant differences.

Neither implementation of the Coder bean is annotated @Alternative, and the beans.xml file does not contain an alternatives element.

The Facelets page and the managed bean, CoderBean, have an additional property, coderType, that allows the user to specify at runtime which implementation to use. In addition, the managed bean has a producer method that selects the implementation using a qualifier type, @Chosen.

The bean declares two constants that specify whether the coder type is the test implementation or the implementation that actually shifts letters:

```
private final static int TEST = 1;
private final static int SHIFT = 2;
private int coderType = SHIFT; // default value
```

The producer method, annotated with @Produces and @Chosen as well as @RequestScoped (so that it lasts only for the duration of a single request and response), takes both implementations as arguments, then returns one or the other, based on the coderType supplied by the user.

```
@Produces
@Chosen
@RequestScoped
public Coder getCoder(@New TestCoderImpl tci,
        @New CoderImpl ci) {

    switch (coderType) {
        case TEST:
            return tci;
        case SHIFT:
            return ci;
        default:
            return null;
    }
}
```

Finally, the managed bean injects the chosen implementation, specifying the same qualifier as that returned by the producer method to resolve ambiguities:

```
@Inject
@Chosen
@RequestScoped
Coder coder;
```

The Facelets page contains modified instructions and a pair of radio buttons whose selected value is assigned to the property `coderBean.coderType`:

```
<h2>String Encoder</h2>
    <p>Select Test or Shift, type a string and an integer, then click
        Encode.</p>
    <p>If you select Test, the TestCoderImpl bean will display the
        argument values.</p>
    <p>If you select Shift, the CoderImpl bean will return a string that
        shifts the letters in the original string by the value you specify.
        The value must be between 0 and 26.</p>
    <h:form id="encodeit">
        <h:selectOneRadio id="coderType"
                          required="true"
                          value="#{coderBean.coderType}">
            <f:selectItem
                itemValue="1"
                itemLabel="Test"/>
            <f:selectItem
                itemValue="2"
                itemLabel="Shift Letters"/>
        </h:selectOneRadio>
        ...
```

Building, Packaging, Deploying, and Running the producermethods Example

You can build, package, deploy, and run the `producermethods` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the producermethods Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/cdi/`
3. **Select the `producermethods` folder.**
4. **Select the Open as Main Project check box.**

5. **Click Open Project.**
6. **In the Projects tab, right-click the `producermethods` project and select Deploy.**

▼ To Build, Package, and Deploy the `producermethods` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/cdi/producermethods/`
2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `producermethods.war`, located in the `dist` directory.
3. **Type the following command:**

   ```
   ant deploy
   ```

▼ To Run the `producermethods` Example

1. **In a web browser, type the following URL:**

   ```
   http://localhost:8080/producermethods
   ```

   The String Encoder page opens.
2. **Select either the Test or Shift Letters radio button, type a string and the number of letters to shift by, then click Encode.**

   Depending on your selection, the Result line displays either the encoded string or the input values you specified.

The `producerfields` Example: Using Producer Fields to Generate Resources

The `producerfields` example, which allows you to create a to-do list, shows how to use a producer field to generate objects that can then be managed by the container. This example generates an `EntityManager` object, but resources such as JDBC connections and datasources can also be generated this way.

The `producerfields` example is the simplest possible entity example. It also contains a qualifier and a class that generates the entity manager. It also contains a single entity, a stateful session bean, a Facelets page, and a managed bean.

The Producer Field for the producerfields Example

The most important component of the producerfields example is the smallest, the db.UserDatabaseEntityManager class, which isolates the generation of the EntityManager object so that it can easily be used by other components in the application. The class uses a producer field to inject an EntityManager that is annotated with the @UserDatabase qualifier, also defined in the db package:

```
@Singleton
public class UserDatabaseEntityManager {

    @Produces
    @PersistenceContext
    @UserDatabase
    private EntityManager em;
    ...
}
```

The class does not explicitly produce a persistence unit field, but the application has a persistence.xml file that specifies a persistence unit. The class is annotated javax.inject.Singleton to specify that the injector should instantiate it only once.

The db.UserDatabaseEntityManager class also contains commented-out code that uses create and close methods to generate and remove the producer field:

```
 /* @PersistenceContext
    private EntityManager em;

    @Produces
    @UserDatabase
    public EntityManager create() {
        return em;
    } */

    public void close(@Disposes @UserDatabase EntityManager em) {
        em.close();
    }
```

You can remove the comments from this code and place them around the field declaration to test how the methods work. The behavior of the application is the same with either mechanism.

The advantage of producing the EntityManager in a separate class rather than simply injecting it into an enterprise bean is that the object can easily be reused in a typesafe way. Also, a more complex application may want to create multiple entity managers using multiple persistence units, and this mechanism isolates this code for easy maintenance, as in the following example:

```
@Singleton
public class JPAResourceProducer {
    @Produces
    @PersistenceUnit(unitName="pu3")
    @TestDatabase
    EntityManagerFactory customerDatabasePersistenceUnit;
```

```
    @Produces
    @PersistenceContext(unitName="pu3")
    @TestDatabase
    EntityManager customerDatabasePersistenceContext;

    @Produces
    @PersistenceUnit(unitName="pu4")
    @Documents
    EntityManagerFactory customerDatabasePersistenceUnit;

    @Produces
    @PersistenceContext(unitName="pu4")
    @Documents
    EntityManager docDatabaseEntityManager;"
}
```

The `EntityManagerFactory` declarations also allow applications to use an application-managed entity manager.

The `producerfields` Entity and Session Bean

The `producerfields` example contains a simple entity class, `entity.ToDo`, and a stateful session bean, `ejb.RequestBean`, that uses it.

The entity class contains three fields: an autogenerated id field, a string specifying the task, and a timestamp. The timestamp field, `timeCreated`, is annotated with `@Temporal`, which is required for persistent `Date` fields.

```
@Entity
public class ToDo implements Serializable {

    private static final long serialVersionUID = 1L;
    @Id
    @GeneratedValue(strategy = GenerationType.AUTO)
    private Long id;
    protected String taskText;
    @Temporal(TIMESTAMP)
    protected Date timeCreated;

    public ToDo() {
    }

    public ToDo(Long id, String taskText, Date timeCreated) {
        this.id = id;
        this.taskText = taskText;
        this.timeCreated = timeCreated;
    }
    ...
```

The remainder of the `ToDo` class contains the usual getters, setters, and other entity methods.

The `RequestBean` class injects the `EntityManager` generated by the producer method, annotated with the `@UserDatabase` qualifier:

```
@ConversationScoped
@Stateful
public class RequestBean {

    @Inject
    @UserDatabase
    EntityManager em;
```

It then defines two methods, one that creates and persists a single ToDo list item, and another that retrieves all the ToDo items created so far by creating a query:

```
    public ToDo createToDo(String inputString) {
        ToDo toDo = null;
        Date currentTime = Calendar.getInstance().getTime();

        try {
            toDo = new ToDo();
            toDo.setTaskText(inputString);
            toDo.setTimeCreated(currentTime);
            em.persist(toDo);
            return toDo;
        } catch (Exception e) {
            throw new EJBException(e.getMessage());
        }
    }

    public List<ToDo> getToDos() {
        try {
             List<ToDo> toDos =
                    (List<ToDo>) em.createQuery(
                    "SELECT t FROM ToDo t ORDER BY t.timeCreated").getResultList();
            return toDos;
        } catch (Exception e) {
            throw new EJBException(e.getMessage());
        }
    }
}
```

The producerfields Facelets Pages and Managed Bean

The producerfields example has two Facelets pages, index.xhtml and todolist.xhtml. The simple form on the index.xhtml page asks the user only for the task. When the user clicks the Submit button, the listBean.createTask method is called. When the user clicks the Show Items button, the action specifies that the todolist.xhtml file should be displayed:

```
    <h:body>
        <h2>To Do List</h2>
        <p>Type a task to be completed.</p>
        <h:form id="todolist">
            <p><h:outputLabel value="Type a string: " for="inputString"/>
                <h:inputText id="inputString"
                             value="#{listBean.inputString}"/></p>
```

```
            <p><h:commandButton value="Submit"
                                action="#{listBean.createTask()}"/></p>
            <p><h:commandButton value="Show Items"
                                action="todolist"/></p>
        </h:form>
    </h:body>
```

The managed bean, `web.ListBean`, injects the `ejb.RequestBean` session bean. It declares the `entity.ToDo` entity and a list of the entity, along with the input string that it passes to the session bean. The `inputString` is annotated with the `@NotNull` Bean Validation constraint, so that an attempt to submit an empty string results in an error.

```
@Named
@ConversationScoped
public class ListBean implements Serializable {

    private static final long serialVersionUID = 1L;
    @EJB
    private RequestBean request;
    @NotNull
    private String inputString;
    private ToDo toDo;
    private List<ToDo> toDos;
```

The `createTask` method called by the Submit button calls the `createToDo` method of `RequestBean`:

```
    public void createTask() {
        this.toDo = request.createToDo(inputString);
    }
```

The `getToDos` method, which is called by the `todolist.xhtml` page, calls the `getToDos` method of `RequestBean`:

```
public List<ToDo> getToDos() {
        return request.getToDos();
    }
```

To force the Facelets page to recognize an empty string as a null value and return an error, the `web.xml` file sets the context parameter `javax.faces.INTERPRET_EMPTY_STRING_SUBMITTED_VALUES_AS_NULL` to `true`:

```
<context-param>
  <param-name>javax.faces.INTERPRET_EMPTY_STRING_SUBMITTED_VALUES_AS_NULL</param-name>
  <param-value>true</param-value>
</context-param>
```

The `todolist.xhtml` page is a little more complicated than the `index.html` page. It contains a `dataTable` element that displays the contents of the `ToDo` list. The body of the page looks like this:

```
    <body>
        <h2>To Do List</h2>
        <h:form id="showlist">
```

```
            <h:dataTable var="toDo"
                         value="#{listBean.toDos}"
                         rules="all"
                         border="1"
                         cellpadding="5">
                <h:column>
                    <f:facet name="header">
                        <h:outputText value="Time Stamp" />
                    </f:facet>
                    <h:outputText value="#{toDo.timeCreated}" />
                </h:column>
                <h:column>
                    <f:facet name="header">
                        <h:outputText value="Task" />
                    </f:facet>
                    <h:outputText value="#{toDo.taskText}" />
                </h:column>
            </h:dataTable>
            <p><h:commandButton id="back" value="Back" action="index" /></p>
        </h:form>
    </body>
```

The value of the `dataTable` is `listBean.toDos`, the list returned by the managed bean's `getToDos` method, which in turn calls the session bean's `getToDos` method. Each row of the table displays the `timeCreated` and `taskText` fields of the individual task. Finally, a Back button returns the user to the `index.xhtml` page.

Building, Packaging, Deploying, and Running the `producerfields` Example

You can build, package, deploy, and run the `producerfields` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the `producerfields` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/cdi/`
3. **Select the `producerfields` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `producerfields` project and select Deploy.**

▼ To Build, Package, and Deploy the producerfields Example Using Ant

1. **In a terminal window, go to:**

   tut-install/examples/cdi/producerfields/

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the default target, which builds and packages the application into a WAR file, producerfields.war, located in the dist directory.

3. **Type the following command:**

   ```
   ant deploy
   ```

▼ To Run the producerfields Example

1. **In a web browser, type the following URL:**

   http://localhost:8080/producerfields

   The Create To Do List page opens.

2. **Type a string in the text field and click Submit.**

   You can type additional strings and click Submit to create a task list with multiple items.

3. **Click the Show Items button.**

   The To Do List page opens, showing the timestamp and text for each item you created.

4. **Click the Back button to return to the Create To Do List page.**

   On this page, you can enter more items in the list.

The billpayment Example: Using Events and Interceptors

The billpayment example shows how to use both events and interceptors.

The example simulates paying an amount using a debit card or credit card. When the user chooses a payment method, the managed bean creates an appropriate event, supplies its payload, and fires it. A simple event listener handles the event using observer methods.

The example also defines an interceptor that is set on a class and on two methods of another class.

The PaymentEvent Event Class

The event class, event.PaymentEvent, is a simple bean class that contains a no-argument constructor. It also has a toString method and getter and setter methods for the payload components: a String for the payment type, a BigDecimal for the payment amount, and a Date for the time stamp.

```
public class PaymentEvent implements Serializable {

    private static final long serialVersionUID = 1L;
    public String paymentType;
    public BigDecimal value;
    public Date datetime;

    public PaymentEvent() {
    }
    @Override
    public String toString() {
        return this.paymentType
                + " = $" + this.value.toString()
                + " at " + this.datetime.toString();
    }
    ...
```

The event class is a simple bean that is instantiated by the managed bean using new and then populated. For this reason, the CDI container cannot intercept the creation of the bean, and hence it cannot allow interception of its getter and setter methods.

The PaymentHandler Event Listener

The event listener, listener.PaymentHandler, contains two observer methods, one for each of the two event types:

```
@Logged
@SessionScoped
public class PaymentHandler implements Serializable {

    ...
    public void creditPayment(@Observes @Credit PaymentEvent event) {
        logger.log(Level.INFO, "PaymentHandler - Credit Handler: {0}",
                event.toString());

        // call a specific Credit handler class...
    }

    public void debitPayment(@Observes @Debit PaymentEvent event) {
        logger.log(Level.INFO, "PaymentHandler - Debit Handler: {0}",
                event.toString());

        // call a specific Debit handler class...
    }
}
```

Each observer method takes as an argument the event, annotated with `@Observes` and the qualifier for the type of payment. In a real application, the observer methods would pass the event information on to another component that would perform business logic on the payment.

The qualifiers are defined in the `payment` package, described in "The billpayment Facelets Pages and Managed Bean" on page 527.

Like `PaymentEvent`, the `PaymentHandler` bean is annotated `@Logged`, so that all its methods can be intercepted.

The billpayment Facelets Pages and Managed Bean

The `billpayment` example contains two Facelets pages, `index.xhtml` and the very simple `response.xhtml`. The body of `index.xhtml` looks like this:

```
<h:body>
    <h3>Bill Payment Options</h3>
    <p>Type an amount, select Debit Card or Credit Card, then click Pay.</p>
    <h:form>
        <p>
        <h:outputLabel value="Amount: $" for="amt"/>
        <h:inputText id="amt" value="#{paymentBean.value}" required="true"
                     requiredMessage="An amount is required."
                     maxlength="15" />
        </p>
        <h:outputLabel value="Options:" for="opt"/>
        <h:selectOneRadio id="opt" value="#{paymentBean.paymentOption}">
            <f:selectItem id="debit" itemLabel="Debit Card" itemValue="1"/>
            <f:selectItem id="credit" itemLabel="Credit Card" itemValue="2" />
        </h:selectOneRadio>
        <p><h:commandButton id="submit" value="Pay"
                            action="#{paymentBean.pay}" /></p>
        <p><h:commandButton value="Reset" action="#{paymentBean.reset}" /></p>
    </h:form>
</h:body>
```

The input text field takes a payment amount, passed to `paymentBean.value`. Two radio buttons ask the user to select a Debit Card or Credit Card payment, passing the integer value to `paymentBean.paymentOption`. Finally, the Pay command button's action is set to the method `paymentBean.pay`, while the Reset button's action is set to the `paymentBean.reset` method.

The `payment.PaymentBean` managed bean uses qualifiers to differentiate between the two kinds of payment event:

```
@Named
@SessionScoped
public class PaymentBean implements Serializable {

   ...
    @Inject
    @Credit
```

```
Event<PaymentEvent> creditEvent;

@Inject
@Debit
Event<PaymentEvent> debitEvent;
```

The qualifiers, `@Credit` and `@Debit`, are defined in the `payment` package along with `PaymentBean`.

Next, the `PaymentBean` defines the properties that it obtains from the Facelets page and will pass on to the event:

```
public static final int DEBIT = 1;
public static final int CREDIT = 2;
private int paymentOption = DEBIT;

@Digits(integer = 10, fraction = 2, message = "Invalid value")
private BigDecimal value;

private Date datetime;
```

The `paymentOption` value is an integer passed in from the radio button component; the default value is `DEBIT`. The `value` is a `BigDecimal` with a Bean Validation constraint that enforces a currency value with a maximum number of digits. The timestamp for the event, `datetime`, is a `Date` object that is initialized when the `pay` method is called.

The `pay` method of the bean first sets the timestamp for this payment event. It then creates and populates the event payload, using the constructor for the `PaymentEvent` and calling the event's setter methods using the bean properties as arguments. It then fires the event.

```
@Logged
public String pay() {
    this.setDatetime(Calendar.getInstance().getTime());
    switch (paymentOption) {
        case DEBIT:
            PaymentEvent debitPayload = new PaymentEvent();
            debitPayload.setPaymentType("Debit");
            debitPayload.setValue(value);
            debitPayload.setDatetime(datetime);
            debitEvent.fire(debitPayload);
            break;
        case CREDIT:
            PaymentEvent creditPayload = new PaymentEvent();
            creditPayload.setPaymentType("Credit");
            creditPayload.setValue(value);
            creditPayload.setDatetime(datetime);
            creditEvent.fire(creditPayload);
            break;
        default:
            logger.severe("Invalid payment option!");
    }
    return "/response.xhtml";
}
```

The `pay` method returns the page to which the action is redirected, `response.xhtml`.

The PaymentBean class also contains a reset method that empties the value field on the index.xhtml page and sets the payment option to the default:

```
@Logged
public void reset() {
    setPaymentOption(DEBIT);
    setValue(BigDecimal.ZERO);
}
```

In this bean, only the pay and reset methods are intercepted.

The response.xhtml page displays the amount paid. It uses a rendered expression to display the payment method:

```
<h:body>
    <h:form>
        <h2>Bill Payment: Result</h2>
        <h3>Amount Paid with
            <h:outputText id="debit" value="Debit Card: "
                          rendered="#{paymentBean.paymentOption eq 1}" />
            <h:outputText id="credit" value="Credit Card: "
                          rendered="#{paymentBean.paymentOption eq 2}" />
            <h:outputText id="result" value="#{paymentBean.value}" >
                <f:convertNumber type="currency"/>
            </h:outputText>
        </h3>
        <p><h:commandButton id="back" value="Back" action="index" /></p>
    </h:form>
</h:body>
```

The LoggedInterceptor Interceptor Class

The interceptor class, LoggedInterceptor, and its interceptor binding, Logged, are both defined in the interceptor package. The Logged interceptor binding is defined as follows:

```
@Inherited
@InterceptorBinding
@Retention(RUNTIME)
@Target({METHOD, TYPE})
public @interface Logged {
}
```

The LoggedInterceptor class looks like this:

```
@Logged
@Interceptor
public class LoggedInterceptor implements Serializable {

    private static final long serialVersionUID = 1L;

    public LoggedInterceptor() {
    }
```

```
    @AroundInvoke
    public Object logMethodEntry(InvocationContext invocationContext)
            throws Exception {
        System.out.println("Entering method: "
                + invocationContext.getMethod().getName() + " in class "
                + invocationContext.getMethod().getDeclaringClass().getName());

        return invocationContext.proceed();
    }
}
```

The class is annotated with both the `@Logged` and the `@Interceptor` annotations. The `@AroundInvoke` method, `logMethodEntry`, takes the required `InvocationContext` argument, and calls the required `proceed` method. When a method is intercepted, `logMethodEntry` displays the name of the method being invoked as well as its class.

To enable the interceptor, the `beans.xml` file defines it as follows:

```
<interceptors>
    <class>billpayment.interceptor.LoggedInterceptor</class>
</interceptors>
```

In this application, the `PaymentEvent` and `PaymentHandler` classes are annotated `@Logged`, so that all their methods are intercepted. In `PaymentBean`, only the `pay` and `reset` methods are annotated `@Logged`, so only those methods are intercepted.

Building, Packaging, Deploying, and Running the `billpayment` Example

You can build, package, deploy, and run the `billpayment` application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the `billpayment` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/cdi/`
3. **Select the `billpayment` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**

6. **In the Projects tab, right-click the `billpayment` project and select Deploy.**

▼ To Build, Package, and Deploy the `billpayment` Example Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/cdi/billpayment/`

2. **Type the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `billpayment.war`, located in the `dist` directory.

3. **Type the following command:**

   ```
   ant deploy
   ```

▼ To Run the `billpayment` Example

1. **In a web browser, type the following URL:**

   ```
   http://localhost:8080/billpayment
   ```

   The Bill Payment Options page opens.

2. **Type a value in the Amount field.**

   The amount can contain up to 10 digits and include up to 2 decimal places. For example:

   ```
   9876.54
   ```

3. **Select Debit Card or Credit Card and click Pay.**

   The Bill Payment: Result page opens, displaying the amount paid and the method of payment:

   ```
   Amount Paid with Credit Card: $9,876.34
   ```

4. **(Optional) Click Back to return to the Bill Payment Options page.**

   You can also click Reset to return to the initial page values.

5. **Examine the server log output.**

   In NetBeans IDE, the output is visible in the GlassFish Server 3.1 output window. Otherwise, view *domain-dir*`/logs/server.log`.

   The output from each interceptor appears in the log, followed by the additional logger output defined by the constructor and methods:

   ```
   INFO: Entering method: pay in class billpayment.payment.PaymentBean
   INFO: PaymentHandler created.
   INFO: PaymentHandler created.
   INFO: PaymentHandler created.
   ```

```
INFO: Entering method: debitPayment in class billpayment.listener.PaymentHandler
INFO: PaymentHandler - Debit Handler: Debit = $1234.56 at Tue Dec 14 14:50:28 EST 2010
```

The decorators Example: Decorating a Bean

The decorators example, which is yet another variation on the encoder example, shows how to use a decorator to implement additional business logic for a bean. Instead of having the user choose between two alternative implementations of an interface at deployment time or runtime, a decorator adds some additional logic to a single implementation of the interface.

The example includes an interface, an implementation of it, a decorator, an interceptor, a managed bean, a Facelets page, and configuration files.

Components of the decorators Example

The decorators example is very similar to the encoder example described in "The encoder Example: Using Alternatives" on page 512. Instead of providing two implementations of the Coder interface, however, this example provides only the CoderImpl class. The decorator class, CoderDecorator, instead of simply returning the coded string, displays the input and output strings' values and length.

The CoderDecorator class, like CoderImpl, implements the business method of the Coder interface, codeString:

```
@Decorator
public abstract class CoderDecorator implements Coder {

    @Inject
    @Delegate
    @Any
    Coder coder;

    public String codeString(String s, int tval) {
        int len = s.length();

        return "\"" + s + "\" becomes " + "\"" + coder.codeString(s, tval)
                + "\", " + len + " characters in length";
    }
}
```

The decorator's codeString method calls the delegate object's codeString method to perform the actual encoding.

The decorators example includes the Logged interceptor binding and LoggedInterceptor class from the billpayment example. For this example, the interceptor is set on the CoderBean.encodeString method and the CoderImpl.codeString method. The interceptor code is unchanged; interceptors are usually reusable for different applications.

Except for the interceptor annotations, the CoderBean and CoderImpl classes are identical to the versions in the encoder example.

The beans.xml file specifies both the decorator and the interceptor:

```
<decorators>
    <class>decorators.CoderDecorator</class>
</decorators>
<interceptors>
    <class>decorators.LoggedInterceptor</class>
</interceptors>
```

Building, Packaging, Deploying, and Running the decorators Example

You can build, package, deploy, and run the decorators application by using either NetBeans IDE or the Ant tool.

▼ To Build, Package, and Deploy the decorators Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install/examples/cdi/
3. **Select the decorators folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the decorators project and select Deploy.**

▼ To Build, Package, and Deploy the decorators Example Using Ant

1. **In a terminal window, go to:**
   tut-install/examples/cdi/decorators/
2. **Type the following command:**
   ant

   This command calls the default target, which builds and packages the application into a WAR file, decorators.war, located in the dist directory.

3. **Type the following command:**

```
ant deploy
```

▼ To Run the decorators Example

1. **In a web browser, type the following URL:**

```
http://localhost:8080/decorators
```

The Bill Payment Options page opens.

2. **Type a string and the number of letters to shift by, then click Encode.**

The output from the decorator method appears in blue on the Result line. For example, if you type Java and 4, you would see the following:

```
"Java" becomes "Neze", 4 characters in length
```

3. **Examine the server log output.**

In NetBeans IDE, the output is visible in the GlassFish Server 3.1 output window. Otherwise, view *domain-dir*/logs/server.log.

The output from the interceptors appears:

```
INFO: Entering method: encodeString in class decorators.CoderBean
INFO: Entering method: codeString in class decorators.CoderImpl
```

PART VI

Persistence

Part VI explores the Java Persistence API. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 32

Introduction to the Java Persistence API

The Java Persistence API provides Java developers with an object/relational mapping facility for managing relational data in Java applications. Java Persistence consists of four areas:

- The Java Persistence API
- The query language
- The Java Persistence Criteria API
- Object/relational mapping metadata

The following topics are addressed here:

Entities

An entity is a lightweight persistence domain object. Typically, an entity represents a table in a relational database, and each entity instance corresponds to a row in that table. The primary programming artifact of an entity is the entity class, although entities can use helper classes.

The persistent state of an entity is represented through either persistent fields or persistent properties. These fields or properties use object/relational mapping annotations to map the entities and entity relationships to the relational data in the underlying data store.

Requirements for Entity Classes

An entity class must follow these requirements.

- The class must be annotated with the `javax.persistence.Entity` annotation.
- The class must have a public or protected, no-argument constructor. The class may have other constructors.
- The class must not be declared `final`. No methods or persistent instance variables must be declared `final`.
- If an entity instance is passed by value as a detached object, such as through a session bean's remote business interface, the class must implement the `Serializable` interface.
- Entities may extend both entity and non-entity classes, and non-entity classes may extend entity classes.
- Persistent instance variables must be declared private, protected, or package-private and can be accessed directly only by the entity class's methods. Clients must access the entity's state through accessor or business methods.

Persistent Fields and Properties in Entity Classes

The persistent state of an entity can be accessed through either the entity's instance variables or properties. The fields or properties must be of the following Java language types:

- Java primitive types
- `java.lang.String`
- Other serializable types, including:
  - Wrappers of Java primitive types
  - `java.math.BigInteger`
  - `java.math.BigDecimal`
  - `java.util.Date`
  - `java.util.Calendar`
  - `java.sql.Date`
  - `java.sql.Time`
  - `java.sql.TimeStamp`
  - User-defined serializable types
  - `byte[]`
  - `Byte[]`
  - `char[]`
  - `Character[]`
- Enumerated types

- Other entities and/or collections of entities
- Embeddable classes

Entities may use persistent fields, persistent properties, or a combination of both. If the mapping annotations are applied to the entity's instance variables, the entity uses persistent fields. If the mapping annotations are applied to the entity's getter methods for JavaBeans-style properties, the entity uses persistent properties.

Persistent Fields

If the entity class uses persistent fields, the Persistence runtime accesses entity-class instance variables directly. All fields not annotated `javax.persistence.Transient` or not marked as Java `transient` will be persisted to the data store. The object/relational mapping annotations must be applied to the instance variables.

Persistent Properties

If the entity uses persistent properties, the entity must follow the method conventions of JavaBeans components. JavaBeans-style properties use getter and setter methods that are typically named after the entity class's instance variable names. For every persistent property *property* of type *Type* of the entity, there is a getter method `get`*Property* and setter method `set`*Property*. If the property is a Boolean, you may use `is`*Property* instead of `get`*Property*. For example, if a `Customer` entity uses persistent properties and has a private instance variable called `firstName`, the class defines a `getFirstName` and `setFirstName` method for retrieving and setting the state of the `firstName` instance variable.

The method signature for single-valued persistent properties are as follows:

```
Type getProperty()
void setProperty(Type type)
```

The object/relational mapping annotations for persistent properties must be applied to the getter methods. Mapping annotations cannot be applied to fields or properties annotated `@Transient` or marked `transient`.

Using Collections in Entity Fields and Properties

Collection-valued persistent fields and properties must use the supported Java collection interfaces regardless of whether the entity uses persistent fields or properties. The following collection interfaces may be used:

- `java.util.Collection`
- `java.util.Set`

- `java.util.List`
- `java.util.Map`

If the entity class uses persistent fields, the type in the preceding method signatures must be one of these collection types. Generic variants of these collection types may also be used. For example, if it has a persistent property that contains a set of phone numbers, the `Customer` entity would have the following methods:

```
Set<PhoneNumber> getPhoneNumbers() { ... }
void setPhoneNumbers(Set<PhoneNumber>) { ... }
```

If a field or property of an entity consists of a collection of basic types or embeddable classes, use the `javax.persistence.ElementCollection` annotation on the field or property.

The two attributes of `@ElementCollection` are `targetClass` and `fetch`. The `targetClass` attribute specifies the class name of the basic or embeddable class and is optional if the field or property is defined using Java programming language generics. The optional `fetch` attribute is used to specify whether the collection should be retrieved lazily or eagerly, using the `javax.persistence.FetchType` constants of either `LAZY` or `EAGER`, respectively. By default, the collection will be fetched lazily.

The following entity, `Person`, has a persistent field, `nicknames`, which is a collection of `String` classes that will be fetched eagerly. The `targetClass` element is not required, because it uses generics to define the field.

```
@Entity
public class Person {
    ...
    @ElementCollection(fetch=EAGER)
    protected Set<String> nickname = new HashSet();
    ...
}
```

Collections of entity elements and relationships may be represented by `java.util.Map` collections. A `Map` consists of a key and a value.

When using `Map` elements or relationships, the following rules apply.

- The `Map` key or value may be a basic Java programming language type, an embeddable class, or an entity.
- When the `Map` value is an embeddable class or basic type, use the `@ElementCollection` annotation.
- When the `Map` value is an entity, use the `@OneToMany` or `@ManyToMany` annotation.
- Use the `Map` type on only one side of a bidirectional relationship.

If the key type of a `Map` is a Java programming language basic type, use the annotation `javax.persistence.MapKeyColumn` to set the column mapping for the key. By default, the `name`

attribute of `@MapKeyColumn` is of the form *RELATIONSHIP-FIELD/PROPERTY-NAME*`_KEY`. For example, if the referencing relationship field name is `image`, the default `name` attribute is `IMAGE_KEY`.

If the key type of a `Map` is an entity, use the `javax.persistence.MapKeyJoinColumn` annotation. If the multiple columns are needed to set the mapping, use the annotation `javax.persistence.MapKeyJoinColumns` to include multiple `@MapKeyJoinColumn` annotations. If no `@MapKeyJoinColumn` is present, the mapping column name is by default set to *RELATIONSHIP-FIELD/PROPERTY-NAME*`_KEY`. For example, if the relationship field name is `employee`, the default `name` attribute is `EMPLOYEE_KEY`.

If Java programming language generic types are not used in the relationship field or property, the key class must be explicitly set using the `javax.persistence.MapKeyClass` annotation.

If the `Map` key is the primary key or a persistent field or property of the entity that is the `Map` value, use the `javax.persistence.MapKey` annotation. The `@MapKeyClass` and `@MapKey` annotations cannot be used on the same field or property.

If the `Map` value is a Java programming language basic type or an embeddable class, it will be mapped as a collection table in the underlying database. If generic types are not used, the `@ElementCollection` annotation's `targetClass` attribute must be set to the type of the `Map` value.

If the `Map` value is an entity and part of a many-to-many or one-to-many unidirectional relationship, it will be mapped as a join table in the underlying database. A unidirectional one-to-many relationship that uses a `Map` may also be mapped using the `@JoinColumn` annotation.

If the entity is part of a one-to-many/many-to-one bidirectional relationship, it will be mapped in the table of the entity that represents the value of the `Map`. If generic types are not used, the `targetEntity` attribute of the `@OneToMany` and `@ManyToMany` annotations must be set to the type of the `Map` value.

Validating Persistent Fields and Properties

The Java API for JavaBeans Validation (Bean Validation) provides a mechanism for validating application data. Bean Validation is integrated into the Java EE containers, allowing the same validation logic to be used in any of the tiers of an enterprise application.

Bean Validation constraints may be applied to persistent entity classes, embeddable classes, and mapped superclasses. By default, the Persistence provider will automatically perform validation on entities with persistent fields or properties annotated with Bean Validation constraints immediately after the `PrePersist`, `PreUpdate`, and `PreRemove` lifecycle events.

Bean Validation constraints are annotations applied to the fields or properties of Java programming language classes. Bean Validation provides a set of constraints as well as an API for defining custom constraints. Custom constraints can be specific combinations of the default

constraints, or new constraints that don't use the default constraints. Each constraint is associated with at least one validator class that validates the value of the constrained field or property. Custom constraint developers must also provide a validator class for the constraint.

Bean Validation constraints are applied to the persistent fields or properties of persistent classes. When adding Bean Validation constraints, use the same access strategy as the persistent class. That is, if the persistent class uses field access, apply the Bean Validation constraint annotations on the class's fields. If the class uses property access, apply the constraints on the getter methods.

Table 9–2 lists Bean Validation's built-in constraints, defined in the `javax.validation.constraints` package.

All the built-in constraints listed in Table 9–2 have a corresponding annotation, *ConstraintName*`.List`, for grouping multiple constraints of the same type on the same field or property. For example, the following persistent field has two `@Pattern` constraints:

```
@Pattern.List({
    @Pattern(regexp="..."),
    @Pattern(regexp="...")
})
```

The following entity class, `Contact`, has Bean Validation constraints applied to its persistent fields.

```
@Entity
public class Contact implements Serializable {
    private static final long serialVersionUID = 1L;
    @Id
    @GeneratedValue(strategy = GenerationType.AUTO)
    private Long id;
    @NotNull
    protected String firstName;
    @NotNull
    protected String lastName;
    @Pattern(regexp="[a-z0-9!#$%&'*+/=?^_`{|}~-]+(?:\\."
        +"[a-z0-9!#$%&'*+/=?^_`{|}~-]+)*@"
        +"(?:[a-z0-9](?:[a-z0-9-]*[a-z0-9])?\\.)+[a-z0-9](?:[a-z0-9-]*[a-z0-9])?",
             message="{invalid.email}")
    protected String email;
    @Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
             message="{invalid.phonenumber}")
    protected String mobilePhone;
    @Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
             message="{invalid.phonenumber}")
    protected String homePhone;
    @Temporal(javax.persistence.TemporalType.DATE)
    @Past
    protected Date birthday;
    ...
}
```

The `@NotNull` annotation on the `firstName` and `lastName` fields specifies that those fields are now required. If a new `Contact` instance is created where `firstName` or `lastName` have not been

initialized, Bean Validation will throw a validation error. Similarly, if a previously created instance of `Contact` has been modified so that `firstName` or `lastName` are null, a validation error will be thrown.

The `email` field has a `@Pattern` constraint applied to it, with a complicated regular expression that matches most valid email addresses. If the value of `email` doesn't match this regular expression, a validation error will be thrown.

The `homePhone` and `mobilePhone` fields have the same `@Pattern` constraints. The regular expression matches 10 digit telephone numbers in the United States and Canada of the form `(`*xxx*`)` *xxx*–*xxxx*.

The `birthday` field is annotated with the `@Past` constraint, which ensures that the value of `birthday` must be in the past.

Primary Keys in Entities

Each entity has a unique object identifier. A customer entity, for example, might be identified by a customer number. The unique identifier, or *primary key*, enables clients to locate a particular entity instance. Every entity must have a primary key. An entity may have either a simple or a composite primary key.

Simple primary keys use the `javax.persistence.Id` annotation to denote the primary key property or field.

Composite primary keys are used when a primary key consists of more than one attribute, which corresponds to a set of single persistent properties or fields. Composite primary keys must be defined in a primary key class. Composite primary keys are denoted using the `javax.persistence.EmbeddedId` and `javax.persistence.IdClass` annotations.

The primary key, or the property or field of a composite primary key, must be one of the following Java language types:

- Java primitive types
- Java primitive wrapper types
- `java.lang.String`
- `java.util.Date` (the temporal type should be `DATE`)
- `java.sql.Date`
- `java.math.BigDecimal`
- `java.math.BigInteger`

Floating-point types should never be used in primary keys. If you use a generated primary key, only integral types will be portable.

A primary key class must meet these requirements.

- The access control modifier of the class must be `public`.
- The properties of the primary key class must be `public` or `protected` if property-based access is used.
- The class must have a public default constructor.
- The class must implement the `hashCode()` and `equals(Object other)` methods.
- The class must be serializable.
- A composite primary key must be represented and mapped to multiple fields or properties of the entity class or must be represented and mapped as an embeddable class.
- If the class is mapped to multiple fields or properties of the entity class, the names and types of the primary key fields or properties in the primary key class must match those of the entity class.

The following primary key class is a composite key, and the `orderId` and `itemId` fields together uniquely identify an entity:

```
public final class LineItemKey implements Serializable {
    public Integer orderId;
    public int itemId;

    public LineItemKey() {}

    public LineItemKey(Integer orderId, int itemId) {
        this.orderId = orderId;
        this.itemId = itemId;
    }

    public boolean equals(Object otherOb) {
        if (this == otherOb) {
            return true;
        }
        if (!(otherOb instanceof LineItemKey)) {
            return false;
        }
        LineItemKey other = (LineItemKey) otherOb;
        return (
                    (orderId==null?other.orderId==null:orderId.equals
                    (other.orderId)
                    )
                    &&
                    (itemId == other.itemId)
                );
    }

    public int hashCode() {
        return (
                    (orderId==null?0:orderId.hashCode())
                    ^
                    ((int) itemId)
                );
```

```
    }

    public String toString() {
        return "" + orderId + "-" + itemId;
    }
}
```

Multiplicity in Entity Relationships

Multiplicities are of the following types: one-to-one, one-to-many, many-to-one, and many-to-many:

- **One-to-one**: Each entity instance is related to a single instance of another entity. For example, to model a physical warehouse in which each storage bin contains a single widget, `StorageBin` and `Widget` would have a one-to-one relationship. One-to-one relationships use the `javax.persistence.OneToOne` annotation on the corresponding persistent property or field.
- **One-to-many**: An entity instance can be related to multiple instances of the other entities. A sales order, for example, can have multiple line items. In the order application, `Order` would have a one-to-many relationship with `LineItem`. One-to-many relationships use the `javax.persistence.OneToMany` annotation on the corresponding persistent property or field.
- **Many-to-one**: Multiple instances of an entity can be related to a single instance of the other entity. This multiplicity is the opposite of a one-to-many relationship. In the example just mentioned, the relationship to `Order` from the perspective of `LineItem` is many-to-one. Many-to-one relationships use the `javax.persistence.ManyToOne` annotation on the corresponding persistent property or field.
- **Many-to-many**: The entity instances can be related to multiple instances of each other. For example, each college course has many students, and every student may take several courses. Therefore, in an enrollment application, `Course` and `Student` would have a many-to-many relationship. Many-to-many relationships use the `javax.persistence.ManyToMany` annotation on the corresponding persistent property or field.

Direction in Entity Relationships

The direction of a relationship can be either bidirectional or unidirectional. A bidirectional relationship has both an owning side and an inverse side. A unidirectional relationship has only an owning side. The owning side of a relationship determines how the Persistence runtime makes updates to the relationship in the database.

Bidirectional Relationships

In a *bidirectional* relationship, each entity has a relationship field or property that refers to the other entity. Through the relationship field or property, an entity class's code can access its

related object. If an entity has a related field, the entity is said to "know" about its related object. For example, if `Order` knows what `LineItem` instances it has and if `LineItem` knows what `Order` it belongs to, they have a bidirectional relationship.

Bidirectional relationships must follow these rules.

- The inverse side of a bidirectional relationship must refer to its owning side by using the `mappedBy` element of the `@OneToOne`, `@OneToMany`, or `@ManyToMany` annotation. The `mappedBy` element designates the property or field in the entity that is the owner of the relationship.
- The many side of many-to-one bidirectional relationships must not define the `mappedBy` element. The many side is always the owning side of the relationship.
- For one-to-one bidirectional relationships, the owning side corresponds to the side that contains the corresponding foreign key.
- For many-to-many bidirectional relationships, either side may be the owning side.

Unidirectional Relationships

In a *unidirectional* relationship, only one entity has a relationship field or property that refers to the other. For example, `LineItem` would have a relationship field that identifies `Product`, but `Product` would not have a relationship field or property for `LineItem`. In other words, `LineItem` knows about `Product`, but `Product` doesn't know which `LineItem` instances refer to it.

Queries and Relationship Direction

Java Persistence query language and Criteria API queries often navigate across relationships. The direction of a relationship determines whether a query can navigate from one entity to another. For example, a query can navigate from `LineItem` to `Product` but cannot navigate in the opposite direction. For `Order` and `LineItem`, a query could navigate in both directions because these two entities have a bidirectional relationship.

Cascade Operations and Relationships

Entities that use relationships often have dependencies on the existence of the other entity in the relationship. For example, a line item is part of an order; if the order is deleted, the line item also should be deleted. This is called a cascade delete relationship.

The `javax.persistence.CascadeType` enumerated type defines the cascade operations that are applied in the `cascade` element of the relationship annotations. Table 32–1 lists the cascade operations for entities.

TABLE 32–1 Cascade Operations for Entities

Cascade Operation	Description
`ALL`	All cascade operations will be applied to the parent entity's related entity. `All` is equivalent to specifying `cascade={DETACH, MERGE, PERSIST, REFRESH, REMOVE}`
`DETACH`	If the parent entity is detached from the persistence context, the related entity will also be detached.
`MERGE`	If the parent entity is merged into the persistence context, the related entity will also be merged.
`PERSIST`	If the parent entity is persisted into the persistence context, the related entity will also be persisted.
`REFRESH`	If the parent entity is refreshed in the current persistence context, the related entity will also be refreshed.
`REMOVE`	If the parent entity is removed from the current persistence context, the related entity will also be removed.

Cascade delete relationships are specified using the `cascade=REMOVE` element specification for `@OneToOne` and `@OneToMany` relationships. For example:

```
@OneToMany(cascade=REMOVE, mappedBy="customer")
public Set<Order> getOrders() { return orders; }
```

Orphan Removal in Relationships

When a target entity in one-to-one or one-to-many relationship is removed from the relationship, it is often desirable to cascade the remove operation to the target entity. Such target entities are considered "orphans," and the `orphanRemoval` attribute can be used to specify that orphaned entities should be removed. For example, if an order has many line items and one of them is removed from the order, the removed line item is considered an orphan. If `orphanRemoval` is set to `true`, the line item entity will be deleted when the line item is removed from the order.

The `orphanRemoval` attribute in `@OneToMany` and `@oneToOne` takes a Boolean value and is by default false.

The following example will cascade the remove operation to the orphaned customer entity when it is removed from the relationship:

```
@OneToMany(mappedBy="customer", orphanRemoval="true")
public List<Order> getOrders() { ... }
```

Embeddable Classes in Entities

Embeddable classes are used to represent the state of an entity but don't have a persistent identity of their own, unlike entity classes. Instances of an embeddable class share the identity of the entity that owns it. Embeddable classes exist only as the state of another entity. An entity may have single-valued or collection-valued embeddable class attributes.

Embeddable classes have the same rules as entity classes but are annotated with the `javax.persistence.Embeddable` annotation instead of `@Entity`.

The following embeddable class, `ZipCode`, has the fields `zip` and `plusFour`:

```
@Embeddable
public class ZipCode {
  String zip;
  String plusFour;
...
}
```

This embeddable class is used by the `Address` entity:

```
@Entity
public class Address {
  @Id
  protected long id
  String street1;
  String street2;
  String city;
  String province;
  @Embedded
  ZipCode zipCode;
  String country;
...
}
```

Entities that own embeddable classes as part of their persistent state may annotate the field or property with the `javax.persistence.Embedded` annotation but are not required to do so.

Embeddable classes may themselves use other embeddable classes to represent their state. They may also contain collections of basic Java programming language types or other embeddable classes. Embeddable classes may also contain relationships to other entities or collections of entities. If the embeddable class has such a relationship, the relationship is from the target entity or collection of entities to the entity that owns the embeddable class.

Entity Inheritance

Entities support class inheritance, polymorphic associations, and polymorphic queries. Entity classes can extend non-entity classes, and non-entity classes can extend entity classes. Entity classes can be both abstract and concrete.

The `roster` example application demonstrates entity inheritance, as described in "Entity Inheritance in the `roster` Application" on page 574.

Abstract Entities

An abstract class may be declared an entity by decorating the class with `@Entity`. Abstract entities are like concrete entities but cannot be instantiated.

Abstract entities can be queried just like concrete entities. If an abstract entity is the target of a query, the query operates on all the concrete subclasses of the abstract entity:

```
@Entity
public abstract class Employee {
    @Id
    protected Integer employeeId;
    ...
}
@Entity
public class FullTimeEmployee extends Employee {
    protected Integer salary;
    ...
}
@Entity
public class PartTimeEmployee extends Employee {
    protected Float hourlyWage;
}
```

Mapped Superclasses

Entities may inherit from superclasses that contain persistent state and mapping information but are not entities. That is, the superclass is not decorated with the `@Entity` annotation and is not mapped as an entity by the Java Persistence provider. These superclasses are most often used when you have state and mapping information common to multiple entity classes.

Mapped superclasses are specified by decorating the class with the annotation `javax.persistence.MappedSuperclass`:

```
@MappedSuperclass
public class Employee {
    @Id
    protected Integer employeeId;
```

```
    ...
}
@Entity
public class FullTimeEmployee extends Employee {
    protected Integer salary;
    ...
}
@Entity
public class PartTimeEmployee extends Employee {
    protected Float hourlyWage;
    ...
}
```

Mapped superclasses cannot be queried and can't be used in `EntityManager` or `Query` operations. You must use entity subclasses of the mapped superclass in `EntityManager` or `Query` operations. Mapped superclasses can't be targets of entity relationships. Mapped superclasses can be abstract or concrete.

Mapped superclasses do not have any corresponding tables in the underlying datastore. Entities that inherit from the mapped superclass define the table mappings. For instance, in the preceding code sample, the underlying tables would be `FULLTIMEEMPLOYEE` and `PARTTIMEEMPLOYEE`, but there is no `EMPLOYEE` table.

Non-Entity Superclasses

Entities may have non-entity superclasses, and these superclasses can be either abstract or concrete. The state of non-entity superclasses is nonpersistent, and any state inherited from the non-entity superclass by an entity class is nonpersistent. Non-entity superclasses may not be used in `EntityManager` or `Query` operations. Any mapping or relationship annotations in non-entity superclasses are ignored.

Entity Inheritance Mapping Strategies

You can configure how the Java Persistence provider maps inherited entities to the underlying datastore by decorating the root class of the hierarchy with the annotation `javax.persistence.Inheritance`. The following mapping strategies are used to map the entity data to the underlying database:

- A single table per class hierarchy
- A table per concrete entity class
- A "join" strategy, whereby fields or properties that are specific to a subclass are mapped to a different table than the fields or properties that are common to the parent class

The strategy is configured by setting the `strategy` element of `@Inheritance` to one of the options defined in the `javax.persistence.InheritanceType` enumerated type:

```
public enum InheritanceType {
    SINGLE_TABLE,
    JOINED,
    TABLE_PER_CLASS
};
```

The default strategy, `InheritanceType.SINGLE_TABLE`, is used if the `@Inheritance` annotation is not specified on the root class of the entity hierarchy.

The Single Table per Class Hierarchy Strategy

With this strategy, which corresponds to the default `InheritanceType.SINGLE_TABLE`, all classes in the hierarchy are mapped to a single table in the database. This table has a *discriminator column* containing a value that identifies the subclass to which the instance represented by the row belongs.

The discriminator column, whose elements are shown in Table 32–2, can be specified by using the `javax.persistence.DiscriminatorColumn` annotation on the root of the entity class hierarchy.

TABLE 32–2 `@DiscriminatorColumn` Elements

Type	Name	Description
`String`	`name`	The name of the column to be used as the discriminator column. The default is `DTYPE`. This element is optional.
`DiscriminatorType`	`discriminatorType`	The type of the column to be used as a discriminator column. The default is `DiscriminatorType.STRING`. This element is optional.
`String`	`columnDefinition`	The SQL fragment to use when creating the discriminator column. The default is generated by the Persistence provider and is implementation-specific. This element is optional.
`String`	`length`	The column length for `String`-based discriminator types. This element is ignored for non-`String` discriminator types. The default is 31. This element is optional.

The `javax.persistence.DiscriminatorType` enumerated type is used to set the type of the discriminator column in the database by setting the `discriminatorType` element of `@DiscriminatorColumn` to one of the defined types. `DiscriminatorType` is defined as:

```
public enum DiscriminatorType {
    STRING,
    CHAR,
    INTEGER
};
```

If `@DiscriminatorColumn` is not specified on the root of the entity hierarchy and a discriminator column is required, the Persistence provider assumes a default column name of `DTYPE` and column type of `DiscriminatorType.STRING`.

The `javax.persistence.DiscriminatorValue` annotation may be used to set the value entered into the discriminator column for each entity in a class hierarchy. You may decorate only concrete entity classes with `@DiscriminatorValue`.

If `@DiscriminatorValue` is not specified on an entity in a class hierarchy that uses a discriminator column, the Persistence provider will provide a default, implementation-specific value. If the `discriminatorType` element of `@DiscriminatorColumn` is `DiscriminatorType.STRING`, the default value is the name of the entity.

This strategy provides good support for polymorphic relationships between entities and queries that cover the entire entity class hierarchy. However, this strategy requires the columns that contain the state of subclasses to be nullable.

The Table per Concrete Class Strategy

In this strategy, which corresponds to `InheritanceType.TABLE_PER_CLASS`, each concrete class is mapped to a separate table in the database. All fields or properties in the class, including inherited fields or properties, are mapped to columns in the class's table in the database.

This strategy provides poor support for polymorphic relationships and usually requires either SQL `UNION` queries or separate SQL queries for each subclass for queries that cover the entire entity class hierarchy.

Support for this strategy is optional and may not be supported by all Java Persistence API providers. The default Java Persistence API provider in the GlassFish Server does not support this strategy.

The Joined Subclass Strategy

In this strategy, which corresponds to `InheritanceType.JOINED`, the root of the class hierarchy is represented by a single table, and each subclass has a separate table that contains only those fields specific to that subclass. That is, the subclass table does not contain columns for inherited fields or properties. The subclass table also has a column or columns that represent its primary key, which is a foreign key to the primary key of the superclass table.

This strategy provides good support for polymorphic relationships but requires one or more join operations to be performed when instantiating entity subclasses. This may result in poor performance for extensive class hierarchies. Similarly, queries that cover the entire class hierarchy require join operations between the subclass tables, resulting in decreased performance.

Some Java Persistence API providers, including the default provider in the GlassFish Server, require a discriminator column that corresponds to the root entity when using the joined subclass strategy. If you are not using automatic table creation in your application, make sure

that the database table is set up correctly for the discriminator column defaults, or use the `@DiscriminatorColumn` annotation to match your database schema. For information on discriminator columns, see "The Single Table per Class Hierarchy Strategy" on page 551.

Managing Entities

Entities are managed by the entity manager, which is represented by `javax.persistence.EntityManager` instances. Each `EntityManager` instance is associated with a persistence context: a set of managed entity instances that exist in a particular data store. A persistence context defines the scope under which particular entity instances are created, persisted, and removed. The `EntityManager` interface defines the methods that are used to interact with the persistence context.

The `EntityManager` Interface

The `EntityManager` API creates and removes persistent entity instances, finds entities by the entity's primary key, and allows queries to be run on entities.

Container-Managed Entity Managers

With a *container-managed entity manager*, an `EntityManager` instance's persistence context is automatically propagated by the container to all application components that use the `EntityManager` instance within a single Java Transaction API (JTA) transaction.

JTA transactions usually involve calls across application components. To complete a JTA transaction, these components usually need access to a single persistence context. This occurs when an `EntityManager` is injected into the application components by means of the `javax.persistence.PersistenceContext` annotation. The persistence context is automatically propagated with the current JTA transaction, and `EntityManager` references that are mapped to the same persistence unit provide access to the persistence context within that transaction. By automatically propagating the persistence context, application components don't need to pass references to `EntityManager` instances to each other in order to make changes within a single transaction. The Java EE container manages the lifecycle of container-managed entity managers.

To obtain an `EntityManager` instance, inject the entity manager into the application component:

```
@PersistenceContext
EntityManager em;
```

Application-Managed Entity Managers

With an *application-managed entity manager*, on the other hand, the persistence context is not propagated to application components, and the lifecycle of `EntityManager` instances is managed by the application.

Application-managed entity managers are used when applications need to access a persistence context that is not propagated with the JTA transaction across `EntityManager` instances in a particular persistence unit. In this case, each `EntityManager` creates a new, isolated persistence context. The `EntityManager` and its associated persistence context are created and destroyed explicitly by the application. They are also used when directly injecting `EntityManager` instances can't be done because `EntityManager` instances are not thread-safe. `EntityManagerFactory` instances are thread-safe.

Applications create `EntityManager` instances in this case by using the `createEntityManager` method of `javax.persistence.EntityManagerFactory`.

To obtain an `EntityManager` instance, you first must obtain an `EntityManagerFactory` instance by injecting it into the application component by means of the `javax.persistence.PersistenceUnit` annotation:

```
@PersistenceUnit
EntityManagerFactory emf;
```

Then obtain an `EntityManager` from the `EntityManagerFactory` instance:

```
EntityManager em = emf.createEntityManager();
```

Application-managed entity managers don't automatically propagate the JTA transaction context. Such applications need to manually gain access to the JTA transaction manager and add transaction demarcation information when performing entity operations. The `javax.transaction.UserTransaction` interface defines methods to begin, commit, and roll back transactions. Inject an instance of `UserTransaction` by creating an instance variable annotated with `@Resource`:

```
@Resource
UserTransaction utx;
```

To begin a transaction, call the `UserTransaction.begin` method. When all the entity operations are complete, call the `UserTransaction.commit` method to commit the transaction. The `UserTransaction.rollback` method is used to roll back the current transaction.

The following example shows how to manage transactions in an application that uses an application-managed entity manager:

```
@PersistenceContext
EntityManagerFactory emf;
EntityManager em;
```

```
@Resource
UserTransaction utx;
...
em = emf.createEntityManager();
try {
  utx.begin();
  em.persist(SomeEntity);
  em.merge(AnotherEntity);
  em.remove(ThirdEntity);
  utx.commit();
} catch (Exception e) {
  utx.rollback();
}
```

Finding Entities Using the `EntityManager`

The `EntityManager.find` method is used to look up entities in the data store by the entity's primary key:

```
@PersistenceContext
EntityManager em;
public void enterOrder(int custID, Order newOrder) {
    Customer cust = em.find(Customer.class, custID);
    cust.getOrders().add(newOrder);
    newOrder.setCustomer(cust);
}
```

Managing an Entity Instance's Lifecycle

You manage entity instances by invoking operations on the entity by means of an `EntityManager` instance. Entity instances are in one of four states: new, managed, detached, or removed.

- New entity instances have no persistent identity and are not yet associated with a persistence context.
- Managed entity instances have a persistent identity and are associated with a persistence context.
- Detached entity instances have a persistent identity and are not currently associated with a persistence context.
- Removed entity instances have a persistent identity, are associated with a persistent context, and are scheduled for removal from the data store.

Persisting Entity Instances

New entity instances become managed and persistent either by invoking the `persist` method or by a cascading `persist` operation invoked from related entities that have the `cascade=PERSIST` or `cascade=ALL` elements set in the relationship annotation. This means that the entity's data is stored to the database when the transaction associated with the `persist` operation is completed. If the entity is already managed, the `persist` operation is ignored,

although the `persist` operation will cascade to related entities that have the `cascade` element set to `PERSIST` or `ALL` in the relationship annotation. If `persist` is called on a removed entity instance, the entity becomes managed. If the entity is detached, either `persist` will throw an `IllegalArgumentException`, or the transaction commit will fail.

```
@PersistenceContext
EntityManager em;
...
public LineItem createLineItem(Order order, Product product,
        int quantity) {
    LineItem li = new LineItem(order, product, quantity);
    order.getLineItems().add(li);
    em.persist(li);
    return li;
}
```

The `persist` operation is propagated to all entities related to the calling entity that have the `cascade` element set to `ALL` or `PERSIST` in the relationship annotation:

```
@OneToMany(cascade=ALL, mappedBy="order")
public Collection<LineItem> getLineItems() {
    return lineItems;
}
```

Removing Entity Instances

Managed entity instances are removed by invoking the `remove` method or by a cascading `remove` operation invoked from related entities that have the `cascade=REMOVE` or `cascade=ALL` elements set in the relationship annotation. If the `remove` method is invoked on a new entity, the `remove` operation is ignored, although `remove` will cascade to related entities that have the `cascade` element set to `REMOVE` or `ALL` in the relationship annotation. If `remove` is invoked on a detached entity, either `remove` will throw an `IllegalArgumentException`, or the transaction commit will fail. If invoked on an already removed entity, `remove` will be ignored. The entity's data will be removed from the data store when the transaction is completed or as a result of the `flush` operation.

```
public void removeOrder(Integer orderId) {
    try {
        Order order = em.find(Order.class, orderId);
        em.remove(order);
    }...
```

In this example, all `LineItem` entities associated with the order are also removed, as `Order.getLineItems` has `cascade=ALL` set in the relationship annotation.

Synchronizing Entity Data to the Database

The state of persistent entities is synchronized to the database when the transaction with which the entity is associated commits. If a managed entity is in a bidirectional relationship with another managed entity, the data will be persisted, based on the owning side of the relationship.

To force synchronization of the managed entity to the data store, invoke the `flush` method of the `EntityManager` instance. If the entity is related to another entity and the relationship annotation has the `cascade` element set to `PERSIST` or `ALL`, the related entity's data will be synchronized with the data store when `flush` is called.

If the entity is removed, calling `flush` will remove the entity data from the data store.

Persistence Units

A persistence unit defines a set of all entity classes that are managed by `EntityManager` instances in an application. This set of entity classes represents the data contained within a single data store.

Persistence units are defined by the `persistence.xml` configuration file. The following is an example `persistence.xml` file:

```
<persistence>
    <persistence-unit name="OrderManagement">
        <description>This unit manages orders and customers.
            It does not rely on any vendor-specific features and can
            therefore be deployed to any persistence provider.
        </description>
        <jta-data-source>jdbc/MyOrderDB</jta-data-source>
        <jar-file>MyOrderApp.jar</jar-file>
        <class>com.widgets.Order</class>
        <class>com.widgets.Customer</class>
    </persistence-unit>
</persistence>
```

This file defines a persistence unit named `OrderManagement`, which uses a JTA-aware data source: `jdbc/MyOrderDB`. The `jar-file` and `class` elements specify managed persistence classes: entity classes, embeddable classes, and mapped superclasses. The `jar-file` element specifies JAR files that are visible to the packaged persistence unit that contain managed persistence classes, whereas the `class` element explicitly names managed persistence classes.

The `jta-data-source` (for JTA-aware data sources) and `non-jta-data-source` (for non-JTA-aware data sources) elements specify the global JNDI name of the data source to be used by the container.

The JAR file or directory whose `META-INF` directory contains `persistence.xml` is called the root of the persistence unit. The scope of the persistence unit is determined by the persistence unit's root. Each persistence unit must be identified with a name that is unique to the persistence unit's scope.

Persistent units can be packaged as part of a WAR or EJB JAR file or can be packaged as a JAR file that can then be included in an WAR or EAR file.

- If you package the persistent unit as a set of classes in an EJB JAR file, `persistence.xml` should be put in the EJB JAR's `META-INF` directory.
- If you package the persistence unit as a set of classes in a WAR file, `persistence.xml` should be located in the WAR file's `WEB-INF/classes/META-INF` directory.
- If you package the persistence unit in a JAR file that will be included in a WAR or EAR file, the JAR file should be located in either
  - The `WEB-INF/lib` directory of a WAR
  - The EAR file's library directory

Note – In the Java Persistence API 1.0, JAR files could be located at the root of an EAR file as the root of the persistence unit. This is no longer supported. Portable applications should use the EAR file's library directory as the root of the persistence unit.

Querying Entities

The Java Persistence API provides the following methods for querying entities.

- The Java Persistence query language (JPQL) is a simple, string-based language similar to SQL used to query entities and their relationships. See Chapter 34, "The Java Persistence Query Language," for more information.
- The Criteria API is used to create typesafe queries using Java programming language APIs to query for entities and their relationships. See Chapter 35, "Using the Criteria API to Create Queries," for more information.

Both JPQL and the Criteria API have advantages and disadvantages.

Just a few lines long, JPQL queries are typically more concise and more readable than Criteria queries. Developers familiar with SQL will find it easy to learn the syntax of JPQL. JPQL named queries can be defined in the entity class using a Java programming language annotation or in the application's deployment descriptor. JPQL queries are not typesafe, however, and require a cast when retrieving the query result from the entity manager. This means that type-casting errors may not be caught at compile time. JPQL queries don't support open-ended parameters.

Criteria queries allow you to define the query in the business tier of the application. Although this is also possible using JPQL dynamic queries, Criteria queries provide better performance because JPQL dynamic queries must be parsed each time they are called. Criteria queries are typesafe and therefore don't require casting, as JPQL queries do. The Criteria API is just another Java programming language API and doesn't require developers to learn the syntax of another

query language. Criteria queries are typically more verbose than JPQL queries and require the developer to create several objects and perform operations on those objects before submitting the query to the entity manager.

Further Information about Persistence

For more information about the Java Persistence API, see

- Java Persistence 2.0 API specification:

  `http://jcp.org/en/jsr/detail?id=317`
- EclipseLink, the Java Persistence API implementation in the GlassFish Server:

  `http://www.eclipse.org/eclipselink/jpa.php`
- EclipseLink team blog:

  `http://eclipselink.blogspot.com/`
- EclipseLink wiki documentation:

  `http://wiki.eclipse.org/EclipseLink`

◆ ◆ ◆ CHAPTER 33

Running the Persistence Examples

This chapter explains how to use the Java Persistence API. The material here focuses on the source code and settings of three examples. The first example, `order`, is an application that uses a stateful session bean to manage entities related to an ordering system. The second example, `roster`, is an application that manages a community sports system. The third example, `address-book`, is a web application that stores contact data. This chapter assumes that you are familiar with the concepts detailed in Chapter 32, "Introduction to the Java Persistence API."

The following topics are addressed here:

The `order` Application

The `order` application is a simple inventory and ordering application for maintaining a catalog of parts and placing an itemized order of those parts. The application has entities that represent parts, vendors, orders, and line items. These entities are accessed using a stateful session bean that holds the business logic of the application. A simple singleton session bean creates the initial entities on application deployment. A Facelets web application manipulates the data and displays data from the catalog.

The information contained in an order can be divided into elements. What is the order number? What parts are included in the order? What parts make up that part? Who makes the part? What are the specifications for the part? Are there any schematics for the part? The `order` application is a simplified version of an ordering system that has all these elements.

The `order` application consists of a single WAR module that includes the enterprise bean classes, the entities, the support classes, and the Facelets XHTML and class files.

Entity Relationships in the order Application

The order application demonstrates several types of entity relationships: self-referential, one-to-one, one-to-many, many-to-one, and unidirectional relationships.

Self-Referential Relationships

A *self-referential* relationship occurs between relationship fields in the same entity. Part has a field, bomPart, which has a one-to-many relationship with the field parts, which is also in Part. That is, a part can be made up of many parts, and each of those parts has exactly one bill-of-material part.

The primary key for Part is a compound primary key, a combination of the partNumber and revision fields. This key is mapped to the PARTNUMBER and REVISION columns in the EJB_ORDER_PART table:

```
...
@ManyToOne
@JoinColumns({
    @JoinColumn(name="BOMPARTNUMBER",
        referencedColumnName="PARTNUMBER"),
    @JoinColumn(name="BOMREVISION",
        referencedColumnName="REVISION")
})
public Part getBomPart() {
    return bomPart;
}
...
@OneToMany(mappedBy="bomPart")
public Collection<Part> getParts() {
    return parts;
}
...
```

One-to-One Relationships

Part has a field, vendorPart, that has a one-to-one relationship with VendorPart's part field. That is, each part has exactly one vendor part, and vice versa.

Here is the relationship mapping in Part:

```
@OneToOne(mappedBy="part")
public VendorPart getVendorPart() {
    return vendorPart;
}
```

Here is the relationship mapping in VendorPart:

```
@OneToOne
@JoinColumns({
    @JoinColumn(name="PARTNUMBER",
```

```
        referencedColumnName="PARTNUMBER"),
    @JoinColumn(name="PARTREVISION",
        referencedColumnName="REVISION")
})
public Part getPart() {
    return part;
}
```

Note that, because `Part` uses a compound primary key, the `@JoinColumns` annotation is used to map the columns in the `PERSISTENCE_ORDER_VENDOR_PART` table to the columns in `PERSISTENCE_ORDER_PART`. The `PERSISTENCE_ORDER_VENDOR_PART` table's `PARTREVISION` column refers to `PERSISTENCE_ORDER_PART`'s `REVISION` column.

One-to-Many Relationship Mapped to Overlapping Primary and Foreign Keys

`Order` has a field, `lineItems`, that has a one-to-many relationship with `LineItem`'s field `order`. That is, each order has one or more line item.

`LineItem` uses a compound primary key that is made up of the `orderId` and `itemId` fields. This compound primary key maps to the `ORDERID` and `ITEMID` columns in the `PERSISTENCE_ORDER_LINEITEM` table. `ORDERID` is a foreign key to the `ORDERID` column in the `PERSISTENCE_ORDER_ORDER` table. This means that the `ORDERID` column is mapped twice: once as a primary key field, `orderId`; and again as a relationship field, `order`.

Here's the relationship mapping in `Order`:

```
@OneToMany(cascade=ALL, mappedBy="order")
    public Collection<LineItem> getLineItems() {
    return lineItems;
}
```

Here is the relationship mapping in `LineItem`:

```
@ManyToOne
    public Order getOrder() {
    return order;
}
```

Unidirectional Relationships

`LineItem` has a field, `vendorPart`, that has a unidirectional many-to-one relationship with `VendorPart`. That is, there is no field in the target entity in this relationship:

```
@ManyToOne
    public VendorPart getVendorPart() {
    return vendorPart;
}
```

Primary Keys in the order Application

The order application uses several types of primary keys: single-valued primary keys, compound primary keys, and generated primary keys.

Generated Primary Keys

VendorPart uses a generated primary key value. That is, the application does not assign primary key values for the entities but instead relies on the persistence provider to generate the primary key values. The @GeneratedValue annotation is used to specify that an entity will use a generated primary key.

In VendorPart, the following code specifies the settings for generating primary key values:

```
@TableGenerator(
    name="vendorPartGen",
    table="PERSISTENCE_ORDER_SEQUENCE_GENERATOR",
    pkColumnName="GEN_KEY",
    valueColumnName="GEN_VALUE",
    pkColumnValue="VENDOR_PART_ID",
    allocationSize=10)
@Id
@GeneratedValue(strategy=GenerationType.TABLE,
    generator="vendorPartGen")
public Long getVendorPartNumber() {
    return vendorPartNumber;
}
```

The @TableGenerator annotation is used in conjunction with @GeneratedValue's strategy=TABLE element. That is, the strategy used to generate the primary keys is to use a table in the database. The @TableGenerator annotation is used to configure the settings for the generator table. The name element sets the name of the generator, which is vendorPartGen in VendorPart.

The EJB_ORDER_SEQUENCE_GENERATOR table, whose two columns are GEN_KEY and GEN_VALUE, will store the generated primary key values. This table could be used to generate other entity's primary keys, so the pkColumnValue element is set to VENDOR_PART_ID to distinguish this entity's generated primary keys from other entity's generated primary keys. The allocationSize element specifies the amount to increment when allocating primary key values. In this case, each VendorPart's primary key will increment by 10.

The primary key field vendorPartNumber is of type Long, as the generated primary key's field must be an integral type.

Compound Primary Keys

A compound primary key is made up of multiple fields and follows the requirements described in "Primary Keys in Entities" on page 543. To use a compound primary key, you must create a wrapper class.

In order, two entities use compound primary keys: Part and LineItem.

- Part uses the PartKey wrapper class. Part's primary key is a combination of the part number and the revision number. PartKey encapsulates this primary key.
- LineItem uses the LineItemKey class. LineItem's primary key is a combination of the order number and the item number. LineItemKey encapsulates this primary key.

This is the LineItemKey compound primary key wrapper class:

```
package order.entity;

public final class LineItemKey implements
             java.io.Serializable {

    private Integer orderId;
    private int itemId;

    public int hashCode() {
        return ((this.getOrderId()==null
                        ?0:this.getOrderId().hashCode())
                 ^ ((int) this.getItemId()));
    }

    public boolean equals(Object otherOb) {
        if (this == otherOb) {
            return true;
        }
        if (!(otherOb instanceof LineItemKey)) {
            return false;
        }
        LineItemKey other = (LineItemKey) otherOb;
        return ((this.getOrderId()==null
                        ?other.orderId==null:this.getOrderId().equals
                (other.orderId)) && (this.getItemId ==
                    other.itemId));
    }

    public String toString() {
        return "" + orderId + "-" + itemId;
    }
}
```

The @IdClass annotation is used to specify the primary key class in the entity class. In LineItem, @IdClass is used as follows:

```
@IdClass(order.entity.LineItemKey.class)
@Entity
...
public class LineItem {
...
}
```

The two fields in LineItem are tagged with the @Id annotation to mark those fields as part of the compound primary key:

```
@Id
public int getItemId() {
    return itemId;
}
...
@Id
@Column(name="ORDERID", nullable=false,
    insertable=false, updatable=false)
public Integer getOrderId() {
    return orderId;
}
```

For `orderId`, you also use the `@Column` annotation to specify the column name in the table and that this column should not be inserted or updated, as it is an overlapping foreign key pointing at the `PERSISTENCE_ORDER_ORDER` table's `ORDERID` column (see "One-to-Many Relationship Mapped to Overlapping Primary and Foreign Keys" on page 563). That is, `orderId` will be set by the `Order` entity.

In `LineItem`'s constructor, the line item number (`LineItem.itemId`) is set using the `Order.getNextId` method:

```
public LineItem(Order order, int quantity, VendorPart
        vendorPart) {
    this.order = order;
    this.itemId = order.getNextId();
    this.orderId = order.getOrderId();
    this.quantity = quantity;
    this.vendorPart = vendorPart;
}
```

`Order.getNextId` counts the number of current line items, adds 1, and returns that number:

```
public int getNextId() {
    return this.lineItems.size() + 1;
}
```

`Part` doesn't require the `@Column` annotation on the two fields that comprise `Part`'s compound primary key, because `Part`'s compound primary key is not an overlapping primary key/foreign key:

```
@IdClass(order.entity.PartKey.class)
@Entity
...
public class Part {
...
    @Id
    public String getPartNumber() {
        return partNumber;
    }
...
    @Id
    public int getRevision() {
        return revision;
    }
```

```
...
}
```

Entity Mapped to More Than One Database Table

Part's fields map to more than one database table: PERSISTENCE_ORDER_PART and PERSISTENCE_ORDER_PART_DETAIL. The PERSISTENCE_ORDER_PART_DETAIL table holds the specification and schematics for the part. The @SecondaryTable annotation is used to specify the secondary table.

```
...
@Entity
@Table(name="PERSISTENCE_ORDER_PART")
@SecondaryTable(name="PERSISTENCE_ORDER_PART_DETAIL", pkJoinColumns={
    @PrimaryKeyJoinColumn(name="PARTNUMBER",
        referencedColumnName="PARTNUMBER"),
    @PrimaryKeyJoinColumn(name="REVISION",
        referencedColumnName="REVISION")
})
public class Part {
...
}
```

PERSISTENCE_ORDER_PART_DETAIL and PERSISTENCE_ORDER_PART share the same primary key values. The pkJoinColumns element of @SecondaryTable is used to specify that PERSISTENCE_ORDER_PART_DETAIL's primary key columns are foreign keys to PERSISTENCE_ORDER_PART. The @PrimaryKeyJoinColumn annotation sets the primary key column names and specifies which column in the primary table the column refers to. In this case, the primary key column names for both PERSISTENCE_ORDER_PART_DETAIL and PERSISTENCE_ORDER_PART are the same: PARTNUMBER and REVISION, respectively.

Cascade Operations in the order Application

Entities that have relationships to other entities often have dependencies on the existence of the other entity in the relationship. For example, a line item is part of an order; if the order is deleted, then the line item also should be deleted. This is called a cascade delete relationship.

In order, there are two cascade delete dependencies in the entity relationships. If the Order to which a LineItem is related is deleted, the LineItem also should be deleted. If the Vendor to which a VendorPart is related is deleted, the VendorPart also should be deleted.

You specify the cascade operations for entity relationships by setting the cascade element in the inverse (nonowning) side of the relationship. The cascade element is set to ALL in the case of Order.lineItems. This means that all persistence operations (deletes, updates, and so on) are cascaded from orders to line items.

Here is the relationship mapping in Order:

```
@OneToMany(cascade=ALL, mappedBy="order")
public Collection<LineItem> getLineItems() {
    return lineItems;
}
```

Here is the relationship mapping in `LineItem`:

```
@ManyToOne
    public Order getOrder() {
    return order;
}
```

BLOB and CLOB Database Types in the `order` Application

The `PARTDETAIL` table in the database has a column, `DRAWING`, of type `BLOB`. `BLOB` stands for binary large objects, which are used for storing binary data, such as an image. The `DRAWING` column is mapped to the field `Part.drawing` of type `java.io.Serializable`. The `@Lob` annotation is used to denote that the field is large object.

```
@Column(table="PERSISTENCE_ORDER_PART_DETAIL")
@Lob
public Serializable getDrawing() {
    return drawing;
}
```

`PERSISTENCE_ORDER_PART_DETAIL` also has a column, `SPECIFICATION`, of type `CLOB`. `CLOB` stands for character large objects, which are used to store string data too large to be stored in a `VARCHAR` column. `SPECIFICATION` is mapped to the field `Part.specification` of type `java.lang.String`. The `@Lob` annotation is also used here to denote that the field is a large object.

```
@Column(table="PERSISTENCE_ORDER_PART_DETAIL")
@Lob
public String getSpecification() {
    return specification;
}
```

Both of these fields use the `@Column` annotation and set the `table` element to the secondary table.

Temporal Types in the order Application

The Order.lastUpdate persistent property, which is of type java.util.Date, is mapped to the PERSISTENCE_ORDER_ORDER.LASTUPDATE database field, which is of the SQL type TIMESTAMP. To ensure the proper mapping between these types, you must use the @Temporal annotation with the proper temporal type specified in @Temporal's element. @Temporal's elements are of type javax.persistence.TemporalType. The possible values are

- DATE, which maps to java.sql.Date
- TIME, which maps to java.sql.Time
- TIMESTAMP, which maps to java.sql.Timestamp

Here is the relevant section of Order:

```
@Temporal(TIMESTAMP)
public Date getLastUpdate() {
    return lastUpdate;
}
```

Managing the order Application's Entities

The RequestBean stateful session bean contains the business logic and manages the entities of order. RequestBean uses the @PersistenceContext annotation to retrieve an entity manager instance, which is used to manage order's entities in RequestBean's business methods:

```
@PersistenceContext
private EntityManager em;
```

This EntityManager instance is a container-managed entity manager, so the container takes care of all the transactions involved in the managing order's entities.

Creating Entities

The RequestBean.createPart business method creates a new Part entity. The EntityManager.persist method is used to persist the newly created entity to the database.

```
Part part = new Part(partNumber,
    revision,
    description,
    revisionDate,
    specification,
    drawing);
em.persist(part);
```

The ConfigBean singleton session bean is used to initialize the data in order. ConfigBean is annotated with @Startup, which indicates that the EJB container should create ConfigBean when order is deployed. The createData method is annotated with @PostConstruct and creates the initial entities used by order by calling RequestsBean's business methods.

Finding Entities

The RequestBean.getOrderPrice business method returns the price of a given order, based on the orderId. The EntityManager.find method is used to retrieve the entity from the database.

```
Order order = em.find(Order.class, orderId);
```

The first argument of EntityManager.find is the entity class, and the second is the primary key.

Setting Entity Relationships

The RequestBean.createVendorPart business method creates a VendorPart associated with a particular Vendor. The EntityManager.persist method is used to persist the newly created VendorPart entity to the database, and the VendorPart.setVendor and Vendor.setVendorPart methods are used to associate the VendorPart with the Vendor.

```
PartKey pkey = new PartKey();
pkey.partNumber = partNumber;
pkey.revision = revision;

Part part = em.find(Part.class, pkey);
VendorPart vendorPart = new VendorPart(description, price,
    part);
em.persist(vendorPart);

Vendor vendor = em.find(Vendor.class, vendorId);
vendor.addVendorPart(vendorPart);
vendorPart.setVendor(vendor);
```

Using Queries

The RequestBean.adjustOrderDiscount business method updates the discount applied to all orders. This method uses the findAllOrders named query, defined in Order:

```
@NamedQuery(
    name="findAllOrders",
    query="SELECT o FROM Order o"
)
```

The EntityManager.createNamedQuery method is used to run the query. Because the query returns a List of all the orders, the Query.getResultList method is used.

```
List orders = em.createNamedQuery(
    "findAllOrders")
    .getResultList();
```

The RequestBean.getTotalPricePerVendor business method returns the total price of all the parts for a particular vendor. This method uses a named parameter, id, defined in the named query findTotalVendorPartPricePerVendor defined in VendorPart.

```
@NamedQuery(
    name="findTotalVendorPartPricePerVendor",
    query="SELECT SUM(vp.price) " +
    "FROM VendorPart vp " +
    "WHERE vp.vendor.vendorId = :id"
)
```

When running the query, the `Query.setParameter` method is used to set the named parameter `id` to the value of `vendorId`, the parameter to `RequestBean.getTotalPricePerVendor`:

```
return (Double) em.createNamedQuery(
    "findTotalVendorPartPricePerVendor")
    .setParameter("id", vendorId)
    .getSingleResult();
```

The `Query.getSingleResult` method is used for this query because the query returns a single value.

Removing Entities

The `RequestBean.removeOrder` business method deletes a given order from the database. This method uses the `EntityManager.remove` method to delete the entity from the database.

```
Order order = em.find(Order.class, orderId);
em.remove(order);
```

Building, Packaging, Deploying, and Running the `order` Application

This section explains how to build, package, deploy, and run the `order` application. To do this, you will create the database tables in the Java DB server, then build, deploy, and run the example.

▼ To Build, Package, Deploy, and Run `order` UsingNetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/persistence/`
3. **Select the `order` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**

6. **In the Projects tab, right-click the `order` project and select Run.**

   NetBeans IDE opens a web browser to `http://localhost:8080/order/`.

▼ To Build, Package, Deploy, and Run `order` Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/persistence/order/`

2. **Type the following command:**

   ```
   ant
   ```

   This runs the `default` task, which compiles the source files and packages the application into a WAR file located at *tut-install*`/examples/persistence/order/dist/order.war`.

3. **To deploy the WAR, make sure that the GlassFish Server is started, then type the following command:**

   ```
   ant deploy
   ```

4. **Open a web browser to `http://localhost:8080/order/` to create and update the order data.**

The `all` Task

As a convenience, the `all` task will build, package, deploy, and run the application. To do this, type the following command:

```
ant all
```

The `roster` Application

The `roster` application maintains the team rosters for players in recreational sports leagues. The application has four components: Java Persistence API entities (`Player`, `Team`, and `League`), a stateful session bean (`RequestBean`), an application client (`RosterClient`), and three helper classes (`PlayerDetails`, `TeamDetails`, and `LeagueDetails`).

Functionally, `roster` is similar to the `order` application, with three new features that `order` does not have: many-to-many relationships, entity inheritance, and automatic table creation at deployment time.

Relationships in the roster Application

A recreational sports system has the following relationships:

- A player can be on many teams.
- A team can have many players.
- A team is in exactly one league.
- A league has many teams.

In roster this system is reflected by the following relationships between the Player, Team, and League entities.

- There is a many-to-many relationship between Player and Team.
- There is a many-to-one relationship between Team and League.

The Many-To-Many Relationship in roster

The many-to-many relationship between Player and Team is specified by using the @ManyToMany annotation. In Team.java, the @ManyToMany annotation decorates the getPlayers method:

```
@ManyToMany
@JoinTable(
    name="EJB_ROSTER_TEAM_PLAYER",
    joinColumns=
        @JoinColumn(name="TEAM_ID", referencedColumnName="ID"),
    inverseJoinColumns=
        @JoinColumn(name="PLAYER_ID", referencedColumnName="ID")
)
public Collection<Player> getPlayers() {
    return players;
}
```

The @JoinTable annotation is used to specify a database table that will associate player IDs with team IDs. The entity that specifies the @JoinTable is the owner of the relationship, so the Team entity is the owner of the relationship with the Player entity. Because roster uses automatic table creation at deployment time, the container will create a join table named EJB_ROSTER_TEAM_PLAYER.

Player is the inverse, or nonowning, side of the relationship with Team. As one-to-one and many-to-one relationships, the nonowning side is marked by the mappedBy element in the relationship annotation. Because the relationship between Player and Team is bidirectional, the choice of which entity is the owner of the relationship is arbitrary.

In Player.java, the @ManyToMany annotation decorates the getTeams method:

```
@ManyToMany(mappedBy="players")
public Collection<Team> getTeams() {
    return teams;
}
```

Entity Inheritance in the roster Application

The roster application shows how to use entity inheritance, as described in "Entity Inheritance" on page 549.

The League entity in roster is an abstract entity with two concrete subclasses: SummerLeague and WinterLeague. Because League is an abstract class, it cannot be instantiated:

```
...
@Entity
@Table(name = "EJB_ROSTER_LEAGUE")
public abstract class League implements java.io.Serializable {
...
}
```

Instead, when creating a league, clients use SummerLeague or WinterLeague. SummerLeague and WinterLeague inherit the persistent properties defined in League and add only a constructor that verifies that the sport parameter matches the type of sport allowed in that seasonal league. For example, here is the SummerLeague entity:

```
...
@Entity
public class SummerLeague extends League
         implements java.io.Serializable {

    /** Creates a new instance of SummerLeague */
    public SummerLeague() {
    }

    public SummerLeague(String id, String name,
             String sport) throws IncorrectSportException {
        this.id = id;
        this.name = name;
        if (sport.equalsIgnoreCase("swimming") ||
                sport.equalsIgnoreCase("soccer") ||
                sport.equalsIgnoreCase("basketball") ||
                sport.equalsIgnoreCase("baseball")) {
            this.sport = sport;
        } else {
            throw new IncorrectSportException(
                "Sport is not a summer sport.");
        }
    }
}
```

The roster application uses the default mapping strategy of InheritanceType.SINGLE_TABLE, so the @Inheritance annotation is not required. If you want to use a different mapping strategy, decorate League with @Inheritance and specify the mapping strategy in the strategy element:

```
@Entity
@Inheritance(strategy=JOINED)
@Table(name="EJB_ROSTER_LEAGUE")
public abstract class League implements java.io.Serializable {
```

```
    ...
}
```

The roster application uses the default discriminator column name, so the @DiscriminatorColumn annotation is not required. Because you are using automatic table generation in roster, the Persistence provider will create a discriminator column called DTYPE in the EJB_ROSTER_LEAGUE table, which will store the name of the inherited entity used to create the league. If you want to use a different name for the discriminator column, decorate League with @DiscriminatorColumn and set the name element:

```
@Entity
@DiscriminatorColumn(name="DISCRIMINATOR")
@Table(name="EJB_ROSTER_LEAGUE")
public abstract class League implements java.io.Serializable {
    ...
}
```

Criteria Queries in the roster Application

The roster application uses Criteria API queries, as opposed to the JPQL queries used in order. Criteria queries are Java programming language, typesafe queries defined in the business tier of roster, in the RequestBean stateless session bean.

Metamodel Classes in the roster Application

Metamodel classes model an entity's attributes and are used by Criteria queries to navigate to an entity's attributes. Each entity class in roster has a corresponding metamodel class, generated at compile time, with the same package name as the entity and appended with an underscore character (_). For example, the roster.entity.Person entity has a corresponding metamodel class, roster.entity.Person_.

Each persistent field or property in the entity class has a corresponding attribute in the entity's metamodel class. For the Person entity, the corresponding metamodel class is:

```
@StaticMetamodel(Person.class)
public class Person_ {
  public static volatile SingularAttribute<Player, String> id;
  public static volatile SingularAttribute<Player, String> name;
  public static volatile SingularAttribute<Player, String> position;
  public static volatile SingularAttribute<Player, Double> salary;
  public static volatile CollectionAttribute<Player, Team> teams;
}
```

Obtaining a CriteriaBuilder Instance in RequestBean

The CrtiteriaBuilder interface defines methods to create criteria query objects and create expressions for modifying those query objects. RequestBean creates an instance of CriteriaBuilder by using a @PostConstruct method, init:

```
@PersistenceContext
private EntityManager em;
private CriteriaBuilder cb;

@PostConstruct
private void init() {
  cb = em.getCriteriaBuilder();
}
```

The EntityManager instance is injected at runtime, and then that EntityManager object is used to create the CriteriaBuilder instance by calling getCriteriaBuilder. The CriteriaBuilder instance is created in a @PostConstruct method to ensure that the EntityManager instance has been injected by the enterprise bean container.

Creating Criteria Queries in RequestBean's Business Methods

Many of the business methods in RequestBean define Criteria queries. One business method, getPlayersByPosition, returns a list of players who play a particular position on a team:

```
public List<PlayerDetails> getPlayersByPosition(String position) {
    logger.info("getPlayersByPosition");
    List<Player> players = null;

    try {
        CriteriaQuery<Player> cq = cb.createQuery(Player.class);
        if (cq != null) {
            Root<Player> player = cq.from(Player.class);

            // set the where clause
            cq.where(cb.equal(player.get(Player_.position), position));
            cq.select(player);
            TypedQuery<Player> q = em.createQuery(cq);
            players = q.getResultList();
        }

        return copyPlayersToDetails(players);
    } catch (Exception ex) {
        throw new EJBException(ex);
    }
}
```

A query object is created by calling the CriteriaBuilder object's createQuery method, with the type set to Player because the query will return a list of players.

The query root, the base entity from which the query will navigate to find the entity's attributes and related entities, is created by calling the from method of the query object. This sets the FROM clause of the query.

The WHERE clause, set by calling the where method on the query object, restricts the results of the query according to the conditions of an expression. The CriteriaBuilder.equal method compares the two expressions. In getPlayersByPosition, the position attribute of the Player_ metamodel class, accessed by calling the get method of the query root, is compared to the position parameter passed to getPlayersByPosition.

The SELECT clause of the query is set by calling the `select` method of the query object. The query will return `Player` entities, so the query root object is passed as a parameter to `select`.

The query object is prepared for execution by calling `EntityManager.createQuery`, which returns a `TypedQuery<T>` object with the type of the query, in this case `Player`. This typed query object is used to execute the query, which occurs when the `getResultList` method is called, and a `List<Player>` collection is returned.

Automatic Table Generation in the `roster` Application

At deployment time, the GlassFish Server will automatically drop and create the database tables used by `roster`. This is done by setting the `eclipselink.ddl-generation` property to `drop-and-create-tables` in `persistence.xml`:

```
<?xml version="1.0" encoding="UTF-8"?>
<persistence version="2.0"
    xmlns="http://java.sun.com/xml/ns/persistence"
    xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
    xsi:schemaLocation="http://java.sun.com/xml/ns/persistence
        http://java.sun.com/xml/ns/persistence/persistence_2_0.xsd">
  <persistence-unit name="em" transaction-type="JTA">
    <jta-data-source>jdbc/__default</jta-data-source>
    <properties>
      <property name="eclipselink.ddl-generation"
                value="drop-and-create-tables"/>
    </properties>
  </persistence-unit>
</persistence>
```

This feature is specific to the Java Persistence API provider used by the GlassFish Server and is nonportable across Java EE servers. Automatic table creation is useful for development purposes, however, and the `eclipselink.ddl-generation` property may be removed from `persistence.xml` when preparing the application for production use or when deploying to other Java EE servers.

Building, Packaging, Deploying, and Running the `roster` Application

This section explains how to build, package, deploy, and run the `roster` application. You can do this using either NetBeans IDE or Ant.

▼ To Build, Package, Deploy, and Run roster Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install/examples/persistence/
3. **Select the roster folder.**
4. **Select the Open as Main Project and Open Required Projects check boxes.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the roster project and select Run.**

   You will see the following partial output from the application client in the Output tab:

```
List all players in team T2:
P6 Ian Carlyle goalkeeper 555.0
P7 Rebecca Struthers midfielder 777.0
P8 Anne Anderson forward 65.0
P9 Jan Wesley defender 100.0
P10 Terry Smithson midfielder 100.0

List all teams in league L1:
T1 Honey Bees Visalia
T2 Gophers Manteca
T5 Crows Orland

List all defenders:
P2 Alice Smith defender 505.0
P5 Barney Bold defender 100.0
P9 Jan Wesley defender 100.0
P22 Janice Walker defender 857.0
P25 Frank Fletcher defender 399.0
...
```

▼ To Build, Package, Deploy, and Run roster Using Ant

1. **In a terminal window, go to:**

   tut-install/examples/persistence/roster/
2. **Type the following command:**

   ant

   This runs the default task, which compiles the source files and packages the application into an EAR file located at *tut-install*/examples/persistence/roster/dist/roster.ear.

3. **To deploy the EAR, make sure that the GlassFish Server is started; then type the following command:**

   ```
   ant deploy
   ```

   The build system will check whether the Java DB database server is running and start it if it is not running, then deploy `roster.ear`. The GlassFish Server will then drop and create the database tables during deployment, as specified in `persistence.xml`.

   After `roster.ear` is deployed, a client JAR, `rosterClient.jar`, is retrieved. This contains the application client.

4. **To run the application client, type the following command:**

   ```
   ant run
   ```

   You will see the output, which begins:

```
[echo] running application client container.
[exec] List all players in team T2:
[exec] P6 Ian Carlyle goalkeeper 555.0
[exec] P7 Rebecca Struthers midfielder 777.0
[exec] P8 Anne Anderson forward 65.0
[exec] P9 Jan Wesley defender 100.0
[exec] P10 Terry Smithson midfielder 100.0

[exec] List all teams in league L1:
[exec] T1 Honey Bees Visalia
[exec] T2 Gophers Manteca
[exec] T5 Crows Orland

[exec] List all defenders:
[exec] P2 Alice Smith defender 505.0
[exec] P5 Barney Bold defender 100.0
[exec] P9 Jan Wesley defender 100.0
[exec] P22 Janice Walker defender 857.0
[exec] P25 Frank Fletcher defender 399.0
...
```

The `all` Task

As a convenience, the `all` task will build, package, deploy, and run the application. To do this, type the following command:

```
ant all
```

The address-book Application

The address-book example application is a simple web application that stores contact data. It uses a single entity class, Contact, that uses the Java API for JavaBeans Validation (Bean Validation) to validate the data stored in the persistent attributes of the entity, as described in "Validating Persistent Fields and Properties" on page 541.

Bean Validation Constraints in address-book

The Contact entity uses the @NotNull, @Pattern, and @Past constraints on the persistent attributes.

The @NotNull constraint marks the attribute as a required field. The attribute must be set to a non-null value before the entity can be persisted or modified. Bean Validation will throw a validation error if the attribute is null when the entity is persisted or modified.

The @Pattern constraint defines a regular expression that the value of the attribute must match before the entity can be persisted or modified. This constraint has two different uses in address-book.

- The regular expression declared in the @Pattern annotation on the email field matches email addresses of the form *name*@*domain name*.*top level domain*, allowing only valid characters for email addresses. For example, username@example.com will pass validation, as will firstname.lastname@mail.example.com. However, firstname,lastname@example.com, which contains an illegal comma character in the local name, will fail validation.
- The mobilePhone and homePhone fields are annotated with a @Pattern constraint that defines a regular expression to match phone numbers of the form (*xxx*) *xxx*–*xxxx*.

The @Past constraint is applied to the birthday field, which must be a java.util.Date in the past.

Here are the relevant parts of the Contact entity class:

```
@Entity
public class Contact implements Serializable {
    private static final long serialVersionUID = 1L;
    @Id
    @GeneratedValue(strategy = GenerationType.AUTO)
    private Long id;
    @NotNull
    protected String firstName;
    @NotNull
    protected String lastName;
    @Pattern(regexp="[a-z0-9!#$%&'*+/=?^_`{|}~-]+(?:\\."
        +"[a-z0-9!#$%&'*+/=?^_`{|}~-]+)*"
        +"@(?:[a-z0-9](?:[a-z0-9-]*[a-z0-9])?\\.)+[a-z0-9](?:[a-z0-9-]*[a-z0-9])?",
```

```
            message="{invalid.email}")
    protected String email;
    @Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
            message="{invalid.phonenumber}")
    protected String mobilePhone;
    @Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
            message="{invalid.phonenumber}")
    protected String homePhone;
    @Temporal(javax.persistence.TemporalType.DATE)
    @Past
    protected Date birthday;
    ...
}
```

Specifying Error Messages for Constraints in `address-book`

Some of the constraints in the `Contact` entity specify an optional message:

```
@Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
            message="{invalid.phonenumber}")
    protected String homePhone;
```

The optional message element in the `@Pattern` constraint overrides the default validation message. The message can be specified directly:

```
@Pattern(regexp="^\\(?(\\d{3})\\)?[- ]?(\\d{3})[- ]?(\\d{4})$",
            message="Invalid phone number!")
    protected String homePhone;
```

The constraints in `Contact`, however, are strings in the resource bundle *tut-install*`/examples/persistence/address-book/src/java/ValidationMessages.properties`. This allows the validation messages to be located in one single properties file and the messages to be easily localized. Overridden Bean Validation messages must be placed in a resource bundle properties file named `ValidationMessages.properties` in the default package, with localized resource bundles taking the form `ValidationMessages_`*locale-prefix*`.properties`. For example, `ValidationMessages_es.properties` is the resource bundle used in Spanish speaking locales.

Validating `Contact` Input from a JavaServer Faces Application

The `address-book` application uses a JavaServer Faces web front end to allow users to enter contacts. While JavaServer Faces has a form input validation mechanism using tags in Facelets XHTML files, `address-book` doesn't use these validation tags. Bean Validation constraints in JavaServer Faces backing beans, in this case in the `Contact` entity, automatically trigger validation when the forms are submitted.

The following code snippet from the `Create.xhtml` Facelets file shows some of the input form for creating new `Contact` instances:

```
<h:form>
    <h:panelGrid columns="3">
        <h:outputLabel value="#{bundle.CreateContactLabel_firstName}"
                       for="firstName" />
        <h:inputText id="firstName"
                     value="#{contactController.selected.firstName}"
                     title="#{bundle.CreateContactTitle_firstName}" />
        <h:message for="firstName"
                   errorStyle="color: red"
                   infoStyle="color: green" />
        <h:outputLabel value="#{bundle.CreateContactLabel_lastName}"
                       for="lastName" />
        <h:inputText id="lastName"
                     value="#{contactController.selected.lastName}"
                     title="#{bundle.CreateContactTitle_lastName}" />
        <h:message for="lastName"
                   errorStyle="color: red"
                   infoStyle="color: green" />
        ...
    </h:panelGrid>
</h:form>
```

The `<h:inputText>` tags `firstName` and `lastName` are bound to the attributes in the `Contact` entity instance `selected` in the `ContactController` stateless session bean. Each `<h:inputText>` tag has an associated `<h:message>` tag that will display validation error messages. The form doesn't require any JavaServer Faces validation tags, however.

Building, Packaging, Deploying, and Running the `address-book` Application

This section describes how to build, package, deploy, and run the `address-book` application. You can do this using either NetBeans IDE or Ant.

▼ Building, Packaging, Deploying, and Running the `address-book` Application in NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/persistence/`
3. **Select the `address-book` folder.**
4. **Select the Open as Main Project and Open Required Projects check boxes.**

5. **Click Open Project.**

6. **In the Projects tab, right-click the `address-book` project and select Run.**

   After the application has been deployed, a web browser window appears at the following URL:

   `http://localhost:8080/address-book/`

7. **Click Show All Contact Items, then Create New Contact. Type values in the form fields; then click Save.**

   If any of the values entered violate the constraints in `Contact`, an error message will appear in red beside the form field with the incorrect values.

▼ Building, Packaging, Deploying, and Running the `address-book` Application Using Ant

1. **In a terminal window, go to:**

   tut-install`/examples/persistence/address-book`

2. **Type the following command:**

   ```
   ant
   ```

   This will compile and assemble the `address-book` application.

3. **Type the following command:**

   ```
   ant deploy
   ```

   This will deploy the application to GlassFish Server.

4. **Open a web browser window and type the following URL:**

   ```
   http://localhost:8080/address-book/
   ```

Tip – As a convenience, the `all` task will build, package, deploy, and run the application. To do this, type the following command:

```
ant all
```

---

5. **Click Show All Contact Items, then Create New Contact. Type values in the form fields; then click Save.**

   If any of the values entered violate the constraints in `Contact`, an error message will appear in red beside the form field with the incorrect values.

◆ ◆ ◆ CHAPTER 34

The Java Persistence Query Language

The Java Persistence query language defines queries for entities and their persistent state. The query language allows you to write portable queries that work regardless of the underlying data store.

The query language uses the abstract persistence schemas of entities, including their relationships, for its data model and defines operators and expressions based on this data model. The scope of a query spans the abstract schemas of related entities that are packaged in the same persistence unit. The query language uses an SQL-like syntax to select objects or values based on entity abstract schema types and relationships among them.

This chapter relies on the material presented in earlier chapters. For conceptual information, see Chapter 32, "Introduction to the Java Persistence API." For code examples, see Chapter 33, "Running the Persistence Examples."

The following topics are addressed here:

Query Language Terminology

The following list defines some of the terms referred to in this chapter:

- **Abstract schema**: The persistent schema abstraction (persistent entities, their state, and their relationships) over which queries operate. The query language translates queries over this persistent schema abstraction into queries that are executed over the database schema to which entities are mapped.
- **Abstract schema type**: The type to which the persistent property of an entity evaluates in the abstract schema. That is, each persistent field or property in an entity has a corresponding state field of the same type in the abstract schema. The abstract schema type of an entity is derived from the entity class and the metadata information provided by Java language annotations.
- **Backus-Naur Form (BNF)**: A notation that describes the syntax of high-level languages. The syntax diagrams in this chapter are in BNF notation.
- **Navigation**: The traversal of relationships in a query language expression. The navigation operator is a period.
- **Path expression**: An expression that navigates to a entity's state or relationship field.
- **State field**: A persistent field of an entity.
- **Relationship field**: A persistent relationship field of an entity whose type is the abstract schema type of the related entity.

Creating Queries Using the Java Persistence Query Language

The `EntityManager.createQuery` and `EntityManager.createNamedQuery` methods are used to query the datastore by using Java Persistence query language queries.

The `createQuery` method is used to create *dynamic queries*, which are queries defined directly within an application's business logic:

```
public List findWithName(String name) {
return em.createQuery(
    "SELECT c FROM Customer c WHERE c.name LIKE :custName")
    .setParameter("custName", name)
    .setMaxResults(10)
    .getResultList();
}
```

The `createNamedQuery` method is used to create *static queries*, or queries that are defined in metadata by using the `javax.persistence.NamedQuery` annotation. The `name` element of `@NamedQuery` specifies the name of the query that will be used with the `createNamedQuery` method. The `query` element of `@NamedQuery` is the query:

```
@NamedQuery(
    name="findAllCustomersWithName",
```

```
    query="SELECT c FROM Customer c WHERE c.name LIKE :custName"
)
```

Here's an example of `createNamedQuery`, which uses the `@NamedQuery`:

```
@PersistenceContext
public EntityManager em;
...
customers = em.createNamedQuery("findAllCustomersWithName")
    .setParameter("custName", "Smith")
    .getResultList();
```

Named Parameters in Queries

Named parameters are query parameters that are prefixed with a colon (`:`). Named parameters in a query are bound to an argument by the following method:

```
javax.persistence.Query.setParameter(String name, Object value)
```

In the following example, the `name` argument to the `findWithName` business method is bound to the `:custName` named parameter in the query by calling `Query.setParameter`:

```
public List findWithName(String name) {
    return em.createQuery(
        "SELECT c FROM Customer c WHERE c.name LIKE :custName")
        .setParameter("custName", name)
        .getResultList();
}
```

Named parameters are case-sensitive and may be used by both dynamic and static queries.

Positional Parameters in Queries

You may use positional parameters instead of named parameters in queries. Positional parameters are prefixed with a question mark (`?`) followed the numeric position of the parameter in the query. The `Query.setParameter(integer position, Object value)` method is used to set the parameter values.

In the following example, the `findWithName` business method is rewritten to use input parameters:

```
public List findWithName(String name) {
    return em.createQuery(
        “SELECT c FROM Customer c WHERE c.name LIKE ?1”)
        .setParameter(1, name)
        .getResultList();
}
```

Input parameters are numbered starting from 1. Input parameters are case-sensitive, and may be used by both dynamic and static queries.

Simplified Query Language Syntax

This section briefly describes the syntax of the query language so that you can quickly move on to "Example Queries" on page 589. When you are ready to learn about the syntax in more detail, see "Full Query Language Syntax" on page 593.

Select Statements

A select query has six clauses: `SELECT`, `FROM`, `WHERE`, `GROUP BY`, `HAVING`, and `ORDER BY`. The `SELECT` and `FROM` clauses are required, but the `WHERE`, `GROUP BY`, `HAVING`, and `ORDER BY` clauses are optional. Here is the high-level BNF syntax of a query language select query:

```
QL_statement ::= select_clause from_clause
  [where_clause][groupby_clause][having_clause][orderby_clause]
```

- The `SELECT` clause defines the types of the objects or values returned by the query.
- The `FROM` clause defines the scope of the query by declaring one or more identification variables, which can be referenced in the `SELECT` and `WHERE` clauses. An identification variable represents one of the following elements:
  - The abstract schema name of an entity
  - An element of a collection relationship
  - An element of a single-valued relationship
  - A member of a collection that is the multiple side of a one-to-many relationship
- The `WHERE` clause is a conditional expression that restricts the objects or values retrieved by the query. Although the clause is optional, most queries have a `WHERE` clause.
- The `GROUP BY` clause groups query results according to a set of properties.
- The `HAVING` clause is used with the `GROUP BY` clause to further restrict the query results according to a conditional expression.
- The `ORDER BY` clause sorts the objects or values returned by the query into a specified order.

Update and Delete Statements

Update and delete statements provide bulk operations over sets of entities. These statements have the following syntax:

```
update_statement :: = update_clause [where_clause]
delete_statement :: = delete_clause [where_clause]
```

The update and delete clauses determine the type of the entities to be updated or deleted. The `WHERE` clause may be used to restrict the scope of the update or delete operation.

Example Queries

The following queries are from the `Player` entity of the `roster` application, which is documented in "The `roster` Application" on page 572.

Simple Queries

If you are unfamiliar with the query language, these simple queries are a good place to start.

A Basic Select Query

```
SELECT p
FROM Player p
```

- **Data retrieved**: All players.
- **Description**: The `FROM` clause declares an identification variable named `p`, omitting the optional keyword `AS`. If the `AS` keyword were included, the clause would be written as follows:

  ```
  FROM Player AS
   p
  ```

  The `Player` element is the abstract schema name of the `Player` entity.
- **See also**: "Identification Variables" on page 599.

Eliminating Duplicate Values

```
SELECT DISTINCT
 p
FROM Player p
WHERE p.position = ?1
```

- **Data retrieved**: The players with the position specified by the query's parameter.
- **Description**: The `DISTINCT` keyword eliminates duplicate values.

  The `WHERE` clause restricts the players retrieved by checking their `position`, a persistent field of the `Player` entity. The `?1` element denotes the input parameter of the query.
- **See also**: "Input Parameters" on page 604 and "The `DISTINCT` Keyword" on page 614.

Using Named Parameters

```
SELECT DISTINCT p
FROM Player p
WHERE p.position = :position AND p.name = :name
```

- **Data retrieved**: The players having the specified positions and names.

- **Description**: The `position` and `name` elements are persistent fields of the `Player` entity. The `WHERE` clause compares the values of these fields with the named parameters of the query, set using the `Query.setNamedParameter` method. The query language denotes a named input parameter using a colon (`:`) followed by an identifier. The first input parameter is `:position`, the second is `:name`.

Queries That Navigate to Related Entities

In the query language, an expression can traverse, or navigate, to related entities. These expressions are the primary difference between the Java Persistence query language and SQL. Queries navigates to related entities, whereas SQL joins tables.

A Simple Query with Relationships

```
SELECT DISTINCT p
FROM Player p, IN(p.teams) t
```

- **Data retrieved**: All players who belong to a team.
- **Description**: The `FROM` clause declares two identification variables: `p` and `t`. The `p` variable represents the `Player` entity, and the `t` variable represents the related `Team` entity. The declaration for `t` references the previously declared `p` variable. The `IN` keyword signifies that `teams` is a collection of related entities. The `p.teams` expression navigates from a `Player` to its related `Team`. The period in the `p.teams` expression is the navigation operator.

  You may also use the `JOIN` statement to write the same query:

  ```
  SELECT DISTINCT p
  FROM Player p JOIN p.teams t
  ```

  This query could also be rewritten as:

  ```
  SELECT DISTINCT p
  FROM Player p
  WHERE p.team IS NOT EMPTY
  ```

Navigating to Single-Valued Relationship Fields

Use the `JOIN` clause statement to navigate to a single-valued relationship field:

```
SELECT t
 FROM Team t JOIN t.league l
 WHERE l.sport = 'soccer' OR l.sport ='football'
```

In this example, the query will return all teams that are in either soccer or football leagues.

Traversing Relationships with an Input Parameter

```
SELECT DISTINCT p
FROM Player p, IN (p.teams) AS t
WHERE t.city = :city
```

- **Data retrieved**: The players whose teams belong to the specified city.
- **Description**: This query is similar to the previous example but adds an input parameter. The `AS` keyword in the `FROM` clause is optional. In the `WHERE` clause, the period preceding the persistent variable `city` is a delimiter, not a navigation operator. Strictly speaking, expressions can navigate to relationship fields (related entities) but not to persistent fields. To access a persistent field, an expression uses the period as a delimiter.

  Expressions cannot navigate beyond (or further qualify) relationship fields that are collections. In the syntax of an expression, a collection-valued field is a terminal symbol. Because the `teams` field is a collection, the `WHERE` clause cannot specify `p.teams.city` (an illegal expression).
- **See also**: "Path Expressions" on page 601.

Traversing Multiple Relationships

```
SELECT DISTINCT p
FROM Player p, IN (p.teams) t
WHERE t.league = :league
```

- **Data retrieved**: The players who belong to the specified league.
- **Description**: The expressions in this query navigate over two relationships. The `p.teams` expression navigates the `Player-Team` relationship, and the `t.league` expression navigates the `Team-League` relationship.

In the other examples, the input parameters are `String` objects; in this example, the parameter is an object whose type is a `League`. This type matches the `league` relationship field in the comparison expression of the `WHERE` clause.

Navigating According to Related Fields

```
SELECT DISTINCT p
FROM Player p, IN (p.teams) t
WHERE t.league.sport = :sport
```

- **Data retrieved**: The players who participate in the specified sport.
- **Description**: The `sport` persistent field belongs to the `League` entity. To reach the `sport` field, the query must first navigate from the `Player` entity to `Team` (`p.teams`) and then from `Team` to the `League` entity (`t.league`). Because it is not a collection, the `league` relationship field can be followed by the `sport` persistent field.

Queries with Other Conditional Expressions

Every `WHERE` clause must specify a conditional expression, of which there are several kinds. In the previous examples, the conditional expressions are comparison expressions that test for equality. The following examples demonstrate some of the other kinds of conditional expressions. For descriptions of all conditional expressions, see "`WHERE` Clause" on page 603.

The LIKE Expression

```
SELECT p
 FROM Player p
 WHERE p.name LIKE 'Mich%'
```

- **Data retrieved**: All players whose names begin with "Mich."
- **Description**: The `LIKE` expression uses wildcard characters to search for strings that match the wildcard pattern. In this case, the query uses the `LIKE` expression and the `%` wildcard to find all players whose names begin with the string "Mich." For example, "Michael" and "Michelle" both match the wildcard pattern.
- **See also**: "`LIKE` Expressions" on page 606.

The IS NULL Expression

```
SELECT t
 FROM Team t
 WHERE t.league IS NULL
```

- **Data retrieved**: All teams not associated with a league.
- **Description**: The `IS NULL` expression can be used to check whether a relationship has been set between two entities. In this case, the query checks whether the teams are associated with any leagues and returns the teams that do not have a league.
- **See also**: "`NULL` Comparison Expressions" on page 606 and "NULL Values" on page 611.

The IS EMPTY Expression

```
SELECT p
FROM Player p
WHERE p.teams IS EMPTY
```

- **Data retrieved**: All players who do not belong to a team.
- **Description**: The `teams` relationship field of the `Player` entity is a collection. If a player does not belong to a team, the `teams` collection is empty, and the conditional expression is `TRUE`.
- **See also**: "Empty Collection Comparison Expressions" on page 607.

The BETWEEN Expression

```
SELECT DISTINCT p
FROM Player p
WHERE p.salary BETWEEN :lowerSalary AND :higherSalary
```

- **Data retrieved**: The players whose salaries fall within the range of the specified salaries.
- **Description**: This `BETWEEN` expression has three arithmetic expressions: a persistent field (`p.salary`) and the two input parameters (`:lowerSalary` and `:higherSalary`). The following expression is equivalent to the `BETWEEN` expression:

  ```
  p.salary >= :lowerSalary AND p.salary <= :higherSalary
  ```

- **See also**: "`BETWEEN` Expressions" on page 605.

Comparison Operators

```
SELECT DISTINCT p1
FROM Player p1, Player p2
WHERE p1.salary > p2.salary AND p2.name = :name
```

- **Data retrieved**: All players whose salaries are higher than the salary of the player with the specified name.
- **Description**: The `FROM` clause declares two identification variables (`p1` and `p2`) of the same type (`Player`). Two identification variables are needed because the `WHERE` clause compares the salary of one player (`p2`) with that of the other players (`p1`).
- **See also**: "Identification Variables" on page 599.

Bulk Updates and Deletes

The following examples show how to use the `UPDATE` and `DELETE` expressions in queries. `UPDATE` and `DELETE` operate on multiple entities according to the condition or conditions set in the `WHERE` clause. The `WHERE` clause in `UPDATE` and `DELETE` queries follows the same rules as `SELECT` queries.

Update Queries

```
UPDATE Player p
SET p.status = 'inactive'
WHERE p.lastPlayed < :inactiveThresholdDate
```

- **Description**: This query sets the status of a set of players to `inactive` if the player's last game was longer than the date specified in `inactiveThresholdDate`.

Delete Queries

```
DELETE
FROM Player p
WHERE p.status = 'inactive'
AND p.teams IS EMPTY
```

- **Description**: This query deletes all inactive players who are not on a team.

Full Query Language Syntax

This section discusses the query language syntax, as defined in the Java Persistence API 2.0 specification available at `http://jcp.org/en/jsr/detail?id=317`. Much of the following material paraphrases or directly quotes the specification.

BNF Symbols

Table 34–1 describes the BNF symbols used in this chapter.

TABLE 34–1 BNF Symbol Summary

Symbol	Description
`::=`	The element to the left of the symbol is defined by the constructs on the right.
*	The preceding construct may occur zero or more times.
`{...}`	The constructs within the braces are grouped together.
`[...]`	The constructs within the brackets are optional.
|	An exclusive `OR`.
`BOLDFACE`	A keyword; although capitalized in the BNF diagram, keywords are not case-sensitive.
White space	A whitespace character can be a space, a horizontal tab, or a line feed.

BNF Grammar of the Java Persistence Query Language

Here is the entire BNF diagram for the query language:

```
QL_statement ::= select_statement | update_statement | delete_statement
select_statement ::= select_clause from_clause [where_clause] [groupby_clause]
    [having_clause] [orderby_clause]
update_statement ::= update_clause [where_clause]
delete_statement ::= delete_clause [where_clause]
from_clause ::=
    FROM identification_variable_declaration
        {, {identification_variable_declaration |
            collection_member_declaration}}*
identification_variable_declaration ::=
        range_variable_declaration { join | fetch_join }*
range_variable_declaration ::= abstract_schema_name [AS]
        identification_variable
join ::= join_spec join_association_path_expression [AS]
        identification_variable
fetch_join ::= join_specFETCH join_association_path_expression
association_path_expression ::=
        collection_valued_path_expression |
        single_valued_association_path_expression
join_spec::= [LEFT [OUTER] |INNER] JOIN
join_association_path_expression ::=
        join_collection_valued_path_expression |
        join_single_valued_association_path_expression
join_collection_valued_path_expression::=
    identification_variable.collection_valued_association_field
join_single_valued_association_path_expression::=
        identification_variable.single_valued_association_field
collection_member_declaration ::=
        IN (collection_valued_path_expression) [AS]
        identification_variable
single_valued_path_expression ::=
```

```
        state_field_path_expression |
        single_valued_association_path_expression
state_field_path_expression ::=
    {identification_variable |
    single_valued_association_path_expression}.state_field
single_valued_association_path_expression ::=
    identification_variable.{single_valued_association_field.}*
    single_valued_association_field
collection_valued_path_expression ::=
    identification_variable.{single_valued_association_field.}*
    collection_valued_association_field
state_field ::=
    {embedded_class_state_field.}*simple_state_field
update_clause ::=UPDATE abstract_schema_name [[AS]
    identification_variable] SET update_item {, update_item}*
update_item ::= [identification_variable.]{state_field |
    single_valued_association_field} = new_value
new_value ::=
     simple_arithmetic_expression |
    string_primary |
    datetime_primary |
    boolean_primary |
    enum_primary simple_entity_expression |
    NULL
delete_clause ::= DELETE FROM abstract_schema_name [[AS]
    identification_variable]
select_clause ::= SELECT [DISTINCT] select_expression {,
    select_expression}*
select_expression ::=
    single_valued_path_expression |
    aggregate_expression |
    identification_variable |
    OBJECT(identification_variable) |
    constructor_expression
constructor_expression ::=
    NEW constructor_name(constructor_item {,
    constructor_item}*)
constructor_item ::= single_valued_path_expression |
    aggregate_expression
aggregate_expression ::=
    {AVG |MAX |MIN |SUM} ([DISTINCT]
        state_field_path_expression) |
    COUNT ([DISTINCT] identification_variable |
        state_field_path_expression |
        single_valued_association_path_expression)
where_clause ::= WHERE conditional_expression
groupby_clause ::= GROUP BY groupby_item {, groupby_item}*
groupby_item ::= single_valued_path_expression
having_clause ::= HAVING conditional_expression
orderby_clause ::= ORDER BY orderby_item {, orderby_item}*
orderby_item ::= state_field_path_expression [ASC |DESC]
subquery ::= simple_select_clause subquery_from_clause
    [where_clause] [groupby_clause] [having_clause]
subquery_from_clause ::=
    FROM subselect_identification_variable_declaration
        {, subselect_identification_variable_declaration}*
subselect_identification_variable_declaration ::=
    identification_variable_declaration |
    association_path_expression [AS] identification_variable |
```

```
    collection_member_declaration
simple_select_clause ::= SELECT [DISTINCT]
    simple_select_expression
simple_select_expression::=
    single_valued_path_expression |
    aggregate_expression |
    identification_variable
conditional_expression ::= conditional_term |
    conditional_expression OR conditional_term
conditional_term ::= conditional_factor | conditional_term AND
    conditional_factor
conditional_factor ::= [NOT] conditional_primary
conditional_primary ::= simple_cond_expression |(
    conditional_expression)
simple_cond_expression ::=
    comparison_expression |
    between_expression |
    like_expression |
    in_expression |
    null_comparison_expression |
    empty_collection_comparison_expression |
    collection_member_expression |
    exists_expression
between_expression ::=
    arithmetic_expression [NOT] BETWEEN
        arithmetic_expressionAND arithmetic_expression |
    string_expression [NOT] BETWEEN string_expression AND
        string_expression |
    datetime_expression [NOT] BETWEEN
        datetime_expression AND datetime_expression
in_expression ::=
    state_field_path_expression [NOT] IN (in_item {, in_item}*
    | subquery)
in_item ::= literal | input_parameter
like_expression ::=
    string_expression [NOT] LIKE pattern_value [ESCAPE
        escape_character]
null_comparison_expression ::=
    {single_valued_path_expression | input_parameter} IS [NOT]
        NULL
empty_collection_comparison_expression ::=
    collection_valued_path_expression IS [NOT] EMPTY
collection_member_expression ::= entity_expression
    [NOT] MEMBER [OF] collection_valued_path_expression
exists_expression::= [NOT] EXISTS (subquery)
all_or_any_expression ::= {ALL |ANY |SOME} (subquery)
comparison_expression ::=
    string_expression comparison_operator {string_expression |
    all_or_any_expression} |
    boolean_expression {= |<> } {boolean_expression |
    all_or_any_expression} |
    enum_expression {= |<> } {enum_expression |
    all_or_any_expression} |
    datetime_expression comparison_operator
        {datetime_expression | all_or_any_expression} |
    entity_expression {= |<> } {entity_expression |
    all_or_any_expression} |
    arithmetic_expression comparison_operator
        {arithmetic_expression | all_or_any_expression}
```

```
comparison_operator ::= = |> |>= |< |<= |<>
arithmetic_expression ::= simple_arithmetic_expression |
    (subquery)
simple_arithmetic_expression ::=
    arithmetic_term | simple_arithmetic_expression {+ |- }
        arithmetic_term
arithmetic_term ::= arithmetic_factor | arithmetic_term {* |/ }
    arithmetic_factor
arithmetic_factor ::= [{+ |- }] arithmetic_primary
arithmetic_primary ::=
    state_field_path_expression |
    numeric_literal |
    (simple_arithmetic_expression) |
    input_parameter |
    functions_returning_numerics |
    aggregate_expression
string_expression ::= string_primary | (subquery)
string_primary ::=
    state_field_path_expression |
    string_literal |
    input_parameter |
    functions_returning_strings |
    aggregate_expression
datetime_expression ::= datetime_primary | (subquery)
datetime_primary ::=
    state_field_path_expression |
    input_parameter |
    functions_returning_datetime |
    aggregate_expression
boolean_expression ::= boolean_primary | (subquery)
boolean_primary ::=
    state_field_path_expression |
    boolean_literal |
    input_parameter
 enum_expression ::= enum_primary | (subquery)
enum_primary ::=
    state_field_path_expression |
    enum_literal |
    input_parameter
entity_expression ::=
    single_valued_association_path_expression |
        simple_entity_expression
simple_entity_expression ::=
    identification_variable |
    input_parameter
functions_returning_numerics::=
    LENGTH(string_primary) |
    LOCATE(string_primary, string_primary[,
        simple_arithmetic_expression]) |
    ABS(simple_arithmetic_expression) |
    SQRT(simple_arithmetic_expression) |
    MOD(simple_arithmetic_expression,
        simple_arithmetic_expression) |
    SIZE(collection_valued_path_expression)
functions_returning_datetime ::=
    CURRENT_DATE |
    CURRENT_TIME |
    CURRENT_TIMESTAMP
functions_returning_strings ::=
```

```
    CONCAT(string_primary, string_primary) |
    SUBSTRING(string_primary,
        simple_arithmetic_expression,
        simple_arithmetic_expression)|
    TRIM([[trim_specification] [trim_character] FROM]
        string_primary) |
    LOWER(string_primary) |
    UPPER(string_primary)
trim_specification ::= LEADING | TRAILING | BOTH
```

FROM Clause

The FROM clause defines the domain of the query by declaring identification variables.

Identifiers

An identifier is a sequence of one or more characters. The first character must be a valid first character (letter, $, _) in an identifier of the Java programming language, hereafter in this chapter called simply "Java". Each subsequent character in the sequence must be a valid nonfirst character (letter, digit, $, _) in a Java identifier. (For details, see the Java SE API documentation of the `isJavaIdentifierStart` and `isJavaIdentifierPart` methods of the `Character` class.) The question mark (?) is a reserved character in the query language and cannot be used in an identifier.

A query language identifier is case-sensitive, with two exceptions:

- Keywords
- Identification variables

An identifier cannot be the same as a query language keyword. Here is a list of query language keywords:

ABS	ALL	AND	ANY	AS
ASC	AVG	BETWEEN	BIT_LENGTH	BOTH
BY	CASE	CHAR_LENGTH	CHARACTER_LENGTH	CLASS
COALESCE	CONCAT	COUNT	CURRENT_DATE	CURRENT_TIMESTAMP
DELETE	DESC	DISTINCT	ELSE	EMPTY
END	ENTRY	ESCAPE	EXISTS	FALSE
FETCH	FROM	GROUP	HAVING	IN
INDEX	INNER	IS	JOIN	KEY
LEADING	LEFT	LENGTH	LIKE	LOCATE
LOWER	MAX	MEMBER	MIN	MOD

NEW	NOT	NULL	NULLIF	OBJECT
OF	OR	ORDER	OUTER	POSITION
SELECT	SET	SIZE	SOME	SQRT
SUBSTRING	SUM	THEN	TRAILING	TRIM
TRUE	TYPE	UNKNOWN	UPDATE	UPPER
VALUE	WHEN	WHERE		

It is not recommended that you use an SQL keyword as an identifier, because the list of keywords may expand to include other reserved SQL words in the future.

Identification Variables

An *identification variable* is an identifier declared in the `FROM` clause. Although they can reference identification variables, the `SELECT` and `WHERE` clauses cannot declare them. All identification variables must be declared in the `FROM` clause.

Because it is an identifier, an identification variable has the same naming conventions and restrictions as an identifier, with the exception that an identification variables is case-insensitive. For example, an identification variable cannot be the same as a query language keyword. (See the preceding section for more naming rules.) Also, within a given persistence unit, an identification variable name must not match the name of any entity or abstract schema.

The `FROM` clause can contain multiple declarations, separated by commas. A declaration can reference another identification variable that has been previously declared (to the left). In the following `FROM` clause, the variable `t` references the previously declared variable `p`:

```
FROM Player p, IN (p.teams) AS t
```

Even if it is not used in the `WHERE` clause, an identification variable's declaration can affect the results of the query. For example, compare the next two queries. The following query returns all players, whether or not they belong to a team:

```
SELECT p
FROM Player p
```

In contrast, because it declares the `t` identification variable, the next query fetches all players who belong to a team:

```
SELECT p
FROM Player p, IN (p.teams) AS t
```

The following query returns the same results as the preceding query, but the `WHERE` clause makes it easier to read:

```
SELECT p
FROM Player p
WHERE p.teams IS NOT EMPTY
```

An identification variable always designates a reference to a single value whose type is that of the expression used in the declaration. There are two kinds of declarations: range variable and collection member.

Range Variable Declarations

To declare an identification variable as an abstract schema type, you specify a range variable declaration. In other words, an identification variable can range over the abstract schema type of an entity. In the following example, an identification variable named `p` represents the abstract schema named `Player`:

```
FROM Player p
```

A range variable declaration can include the optional `AS` operator:

```
FROM Player AS p
```

To obtain objects, a query usually uses path expressions to navigate through the relationships. But for those objects that cannot be obtained by navigation, you can use a range variable declaration to designate a starting point, or *root*.

If the query compares multiple values of the same abstract schema type, the `FROM` clause must declare multiple identification variables for the abstract schema:

```
FROM Player p1, Player p2
```

For an example of such a query, see "Comparison Operators" on page 593.

Collection Member Declarations

In a one-to-many relationship, the multiple side consists of a collection of entities. An identification variable can represent a member of this collection. To access a collection member, the path expression in the variable's declaration navigates through the relationships in the abstract schema. (For more information on path expressions, see "Path Expressions" on page 601.) Because a path expression can be based on another path expression, the navigation can traverse several relationships. See "Traversing Multiple Relationships" on page 591.

A collection member declaration must include the `IN` operator but can omit the optional `AS` operator.

In the following example, the entity represented by the abstract schema named `Player` has a relationship field called `teams`. The identification variable called `t` represents a single member of the `teams` collection.

```
FROM Player p, IN (p.tea
ms) t
```

Joins

The `JOIN` operator is used to traverse over relationships between entities and is functionally similar to the `IN` operator.

In the following example, the query joins over the relationship between customers and orders:

```
SELECT c
 FROM Customer c JOIN c.orders o
 WHERE c.status = 1 AND o.totalPrice > 10000
```

The `INNER` keyword is optional:

```
SELECT c
 FROM Customer c INNER JOIN c.orders o
 WHERE c.status = 1 AND o.totalPrice > 10000
```

These examples are equivalent to the following query, which uses the `IN` operator:

```
SELECT c
 FROM Customer c, IN(c.orders) o
 WHERE c.status = 1 AND o.totalPrice > 10000
```

You can also join a single-valued relationship:

```
SELECT t
 FROM Team t JOIN t.league l
 WHERE l.sport = :sport
```

A `LEFT JOIN` or `LEFT OUTER JOIN` retrieves a set of entities where matching values in the join condition may be absent. The `OUTER` keyword is optional.

```
SELECT c.name, o.totalPrice
FROM Order o LEFT JOIN o.customer c
```

A `FETCH JOIN` is a join operation that returns associated entities as a side effect of running the query. In the following example, the query returns a set of departments and, as a side effect, the associated employees of the departments, even though the employees were not explicitly retrieved by the `SELECT` clause.

```
SELECT d
FROM Department d LEFT JOIN FETCH d.employees
WHERE d.deptno = 1
```

Path Expressions

Path expressions are important constructs in the syntax of the query language, for several reasons. First, path expressions define navigation paths through the relationships in the abstract schema. These path definitions affect both the scope and the results of a query. Second, path expressions can appear in any of the main clauses of a query (`SELECT`, `DELETE`, `HAVING`, `UPDATE`,

WHERE, FROM, GROUP BY, ORDER BY). Finally, although much of the query language is a subset of SQL, path expressions are extensions not found in SQL.

Examples of Path Expressions

Here, the WHERE clause contains a single_valued_path_expression; the p is an identification variable, and salary is a persistent field of Player:

```
SELECT DISTINCT p
FROM Player p
 WHERE p.salary BETWEEN :lowerSalary AND :higherSalary
```

Here, the WHERE clause also contains a single_valued_path_expression; t is an identification variable, league is a single-valued relationship field, and sport is a persistent field of league:

```
SELECT DISTINCT p
FROM Player p, IN (p.teams) t
 WHERE t.league.sport = :sport
```

Here, the WHERE clause contains a collection_valued_path_expression; p is an identification variable, and teams designates a collection-valued relationship field:

```
SELECT DISTINCT p
FROM Player p
 WHERE p.teams IS EMPTY
```

Expression Types

The type of a path expression is the type of the object represented by the ending element, which can be one of the following:

- Persistent field
- Single-valued relationship field
- Collection-valued relationship field

For example, the type of the expression p.salary is double because the terminating persistent field (salary) is a double.

In the expression p.teams, the terminating element is a collection-valued relationship field (teams). This expression's type is a collection of the abstract schema type named Team. Because Team is the abstract schema name for the Team entity, this type maps to the entity. For more information on the type mapping of abstract schemas, see "Return Types" on page 613.

Navigation

A path expression enables the query to navigate to related entities. The terminating elements of an expression determine whether navigation is allowed. If an expression contains a single-valued relationship field, the navigation can continue to an object that is related to the field. However, an expression cannot navigate beyond a persistent field or a collection-valued

relationship field. For example, the expression `p.teams.league.sport` is illegal because `teams` is a collection-valued relationship field. To reach the `sport` field, the `FROM` clause could define an identification variable named `t` for the `teams` field:

```
FROM Player AS p, IN (p.teams) t
 WHERE t.league.sport = 'soccer'
```

`WHERE` Clause

The `WHERE` clause specifies a conditional expression that limits the values returned by the query. The query returns all corresponding values in the data store for which the conditional expression is `TRUE`. Although usually specified, the `WHERE` clause is optional. If the `WHERE` clause is omitted, the query returns all values. The high-level syntax for the `WHERE` clause follows:

```
where_clause ::= WHERE conditional_expression
```

Literals

There are four kinds of literals: string, numeric, Boolean, and enum.

- **String literals**: A string literal is enclosed in single quotes:

  ```
  'Duke'
  ```

  If a string literal contains a single quote, you indicate the quote by using two single quotes:

  ```
  'Duke''s'
  ```

  Like a Java `String`, a string literal in the query language uses the Unicode character encoding.

- **Numeric literals**: There are two types of numeric literals: exact and approximate.

  An exact numeric literal is a numeric value without a decimal point, such as 65, –233, and +12. Using the Java integer syntax, exact numeric literals support numbers in the range of a Java `long`.

  An approximate numeric literal is a numeric value in scientific notation, such as 57., –85.7, and +2.1. Using the syntax of the Java floating-point literal, approximate numeric literals support numbers in the range of a Java `double`.

- **Boolean literals**: A Boolean literal is either `TRUE` or `FALSE`. These keywords are not case-sensitive.

- **Enum literals**: The Java Persistence query language supports the use of enum literals using the Java enum literal syntax. The enum class name must be specified as a fully qualified class name:

  ```
  SELECT e
   FROM Employee e
   WHERE e.status = com.xyz.EmployeeStatus.FULL_TIME
  ```

Input Parameters

An input parameter can be either a named parameter or a positional parameter.

- A named input parameter is designated by a colon (`:`) followed by a string; for example, `:name`.
- A positional input parameter is designated by a question mark (`?`) followed by an integer. For example, the first input parameter is `?1`, the second is `?2`, and so forth.

The following rules apply to input parameters.

- They can be used only in a `WHERE` or `HAVING` clause.
- Positional parameters must be numbered, starting with the integer 1.
- Named parameters and positional parameters may not be mixed in a single query.
- Named parameters are case-sensitive.

Conditional Expressions

A `WHERE` clause consists of a conditional expression, which is evaluated from left to right within a precedence level. You can change the order of evaluation by using parentheses.

Operators and Their Precedence

Table 34–2 lists the query language operators in order of decreasing precedence.

TABLE 34–2 Query Language Order Precedence

Type	Precedence Order
Navigation	`.` (a period)
Arithmetic	`+ –` (unary)
	`* /` (multiplication and division)
	`+ –` (addition and subtraction)

TABLE 34–2 Query Language Order Precedence *(Continued)*

Type	Precedence Order
Comparison	=
	>
	>=
	<
	<=
	<> (not equal)
	[NOT] BETWEEN
	[NOT] LIKE
	[NOT] IN
	IS [NOT] NULL
	IS [NOT] EMPTY
	[NOT] MEMBER OF
Logical	NOT
	AND
	OR

`BETWEEN` Expressions

A `BETWEEN` expression determines whether an arithmetic expression falls within a range of values.

These two expressions are equivalent:

```
p.age BETWEEN 15 AND 19
 p.age >= 15 AND p.age <= 19
```

The following two expressions also are equivalent:

```
p.age NOT BETWEEN 15 AND 19
 p.age < 15 OR p.age > 19
```

If an arithmetic expression has a `NULL` value, the value of the `BETWEEN` expression is unknown.

`IN` Expressions

An `IN` expression determines whether a string belongs to a set of string literals or whether a number belongs to a set of number values.

The path expression must have a string or numeric value. If the path expression has a NULL value, the value of the IN expression is unknown.

In the following example, the expression is TRUE if the country is UK , but FALSE if the country is Peru.

```
o.country IN ('UK', 'US', 'France')
```

You may also use input parameters:

```
o.country IN ('UK', 'US', 'France', :country)
```

LIKE Expressions

A LIKE expression determines whether a wildcard pattern matches a string.

The path expression must have a string or numeric value. If this value is NULL, the value of the LIKE expression is unknown. The pattern value is a string literal that can contain wildcard characters. The underscore (_) wildcard character represents any single character. The percent (%) wildcard character represents zero or more characters. The ESCAPE clause specifies an escape character for the wildcard characters in the pattern value. Table 34–3 shows some sample LIKE expressions.

TABLE 34–3 LIKE Expression Examples

Expression	TRUE	FALSE
address.phone LIKE '12%3'	'123'	'1234'
	'12993'	
asentence.word LIKE 'l_se'	'lose'	'loose'
aword.underscored LIKE '_%' ESCAPE '\'	'_foo'	'bar'
address.phone NOT LIKE '12%3'	'1234'	'123'
		'12993'

NULL Comparison Expressions

A NULL comparison expression tests whether a single-valued path expression or an input parameter has a NULL value. Usually, the NULL comparison expression is used to test whether a single-valued relationship has been set:

```
SELECT t
 FROM Team t
 WHERE t.league IS NULL
```

This query selects all teams where the league relationship is not set. Note that the following query is *not* equivalent:

```
SELECT t
 FROM Team t
 WHERE t.league = NULL
```

The comparison with `NULL` using the equals operator (=) always returns an unknown value, even if the relationship is not set. The second query will always return an empty result.

Empty Collection Comparison Expressions

The `IS [NOT] EMPTY` comparison expression tests whether a collection-valued path expression has no elements. In other words, it tests whether a collection-valued relationship has been set.

If the collection-valued path expression is `NULL`, the empty collection comparison expression has a `NULL` value.

Here is an example that finds all orders that do not have any line items:

```
SELECT o
FROM Order o
WHERE o.lineItems IS EMPTY
```

Collection Member Expressions

The `[NOT] MEMBER [OF]` collection member expression determines whether a value is a member of a collection. The value and the collection members must have the same type.

If either the collection-valued or single-valued path expression is unknown, the collection member expression is unknown. If the collection-valued path expression designates an empty collection, the collection member expression is `FALSE`.

The `OF` keyword is optional.

The following example tests whether a line item is part of an order:

```
SELECT o
 FROM Order o
 WHERE :lineItem MEMBER OF o.lineItems
```

Subqueries

Subqueries may be used in the `WHERE` or `HAVING` clause of a query. Subqueries must be surrounded by parentheses.

The following example finds all customers who have placed more than ten orders:

```
SELECT c
FROM Customer c
WHERE (SELECT COUNT(o) FROM c.orders o) > 10
```

Subqueries may contain `EXISTS`, `ALL`, and `ANY` expressions.

- **`EXISTS` expressions**: The `[NOT] EXISTS` expression is used with a subquery and is true only if the result of the subquery consists of one or more values and is false otherwise.

  The following example finds all employees whose spouses are also employees:

  ```
  SELECT DISTINCT emp
  FROM Employee emp
  WHERE EXISTS (
      SELECT spouseEmp
      FROM Employee spouseEmp
      WHERE spouseEmp = emp.spouse)
  ```

- **`ALL` and `ANY` expressions**: The `ALL` expression is used with a subquery and is true if all the values returned by the subquery are true or if the subquery is empty.

  The `ANY` expression is used with a subquery and is true if some of the values returned by the subquery are true. An `ANY` expression is false if the subquery result is empty or if all the values returned are false. The `SOME` keyword is synonymous with `ANY`.

  The `ALL` and `ANY` expressions are used with the =, <, <=, >, >=, and <> comparison operators.

  The following example finds all employees whose salaries are higher than the salaries of the managers in the employee's department:

  ```
  SELECT emp
  FROM Employee emp
  WHERE emp.salary > ALL (
      SELECT m.salary
      FROM Manager m
      WHERE m.department = emp.department)
  ```

Functional Expressions

The query language includes several string, arithmetic, and date/time functions that may be used in the `SELECT`, `WHERE`, or `HAVING` clause of a query. The functions are listed in Table 34–4, Table 34–5, and Table 34–6.

In Table 34–4, the `start` and `length` arguments are of type `int` and designate positions in the `String` argument. The first position in a string is designated by 1.

TABLE 34–4 String Expressions

Function Syntax	Return Type
`CONCAT(String, String)`	`String`
`LENGTH(String)`	`int`
`LOCATE(String, String [, start])`	`int`
`SUBSTRING(String, start, length)`	`String`
`TRIM([[LEADING|TRAILING|BOTH] char) FROM] (String)`	`String`
`LOWER(String)`	`String`
`UPPER(String)`	`String`

The `CONCAT` function concatenates two strings into one string.

The `LENGTH` function returns the length of a string in characters as an integer.

The `LOCATE` function returns the position of a given string within a string. This function returns the first position at which the string was found as an integer. The first argument is the string to be located. The second argument is the string to be searched. The optional third argument is an integer that represents the starting string position. By default, `LOCATE` starts at the beginning of the string. The starting position of a string is `1`. If the string cannot be located, `LOCATE` returns `0`.

The `SUBSTRING` function returns a string that is a substring of the first argument based on the starting position and length.

The `TRIM` function trims the specified character from the beginning and/or end of a string. If no character is specified, `TRIM` removes spaces or blanks from the string. If the optional `LEADING` specification is used, `TRIM` removes only the leading characters from the string. If the optional `TRAILING` specification is used, `TRIM` removes only the trailing characters from the string. The default is `BOTH`, which removes the leading and trailing characters from the string.

The `LOWER` and `UPPER` functions convert a string to lowercase or uppercase, respectively.

In Table 34–5, the `number` argument can be an `int`, a `float`, or a `double`.

TABLE 34–5 Arithmetic Expressions

Function Syntax	Return Type
`ABS(number)`	`int`, `float`, or `double`
`MOD(int, int)`	`int`
`SQRT(double)`	`double`
`SIZE(Collection)`	`int`

The `ABS` function takes a numeric expression and returns a number of the same type as the argument.

The `MOD` function returns the remainder of the first argument divided by the second.

The `SQRT` function returns the square root of a number.

The `SIZE` function returns an integer of the number of elements in the given collection.

In Table 34–6, the date/time functions return the date, time, or timestamp on the database server.

TABLE 34–6 Date/Time Expressions

Function Syntax	Return Type
`CURRENT_DATE`	`java.sql.Date`
`CURRENT_TIME`	`java.sql.Time`
`CURRENT_TIMESTAMP`	`java.sql.Timestamp`

Case Expressions

Case expressions change based on a condition, similar to the `case` keyword of the Java programming language. The `CASE` keyword indicates the start of a case expression, and the expression is terminated by the `END` keyword. The `WHEN` and `THEN` keywords define individual conditions, and the `ELSE` keyword defines the default condition should none of the other conditions be satisfied.

The following query selects the name of a person and a conditional string, depending on the subtype of the `Person` entity. If the subtype is `Student`, the string `kid` is returned . If the subtype is `Guardian` or `Staff`, the string `adult` is returned. If the entity is some other subtype of `Person`, the string `unknown` is returned.

```
SELECT p.name
CASE TYPE(p)
  WHEN Student THEN 'kid'
```

```
  WHEN Guardian THEN 'adult'
  WHEN Staff THEN 'adult'
  ELSE 'unknown'
END
FROM Person p
```

The following query sets a discount for various types of customers. Gold-level customers get a 20% discount, silver-level customers get a 15% discount, bronze-level customers get a 10% discount, and everyone else gets a 5% discount.

```
UPDATE Customer c
SET c.discount =
  CASE c.level
    WHEN 'Gold' THEN 20
    WHEN 'SILVER' THEN 15
    WHEN 'Bronze' THEN 10
    ELSE 5
  END
```

NULL Values

If the target of a reference is not in the persistent store, the target is `NULL`. For conditional expressions containing `NULL`, the query language uses the semantics defined by SQL92. Briefly, these semantics are as follows.

- If a comparison or arithmetic operation has an unknown value, it yields a `NULL` value.
- Two `NULL` values are not equal. Comparing two `NULL` values yields an unknown value.
- The `IS NULL` test converts a `NULL` persistent field or a single-valued relationship field to `TRUE`. The `IS NOT NULL` test converts them to `FALSE`.
- Boolean operators and conditional tests use the three-valued logic defined by Table 34–7 and Table 34–8. (In these tables, T stands for `TRUE`, F for `FALSE`, and U for unknown.)

TABLE 34–7 `AND` Operator Logic

AND	T	F	U
T	T	F	U
F	F	F	F
U	U	F	U

TABLE 34–8 OR Operator Logic

OR	T	F	U
T	T	T	T
F	T	F	U
U	T	U	U

Equality Semantics

In the query language, only values of the same type can be compared. However, this rule has one exception: Exact and approximate numeric values can be compared. In such a comparison, the required type conversion adheres to the rules of Java numeric promotion.

The query language treats compared values as if they were Java types and not as if they represented types in the underlying data store. For example, a persistent field that could be either an integer or a `NULL` must be designated as an `Integer` object and not as an `int` primitive. This designation is required because a Java object can be `NULL`, but a primitive cannot.

Two strings are equal only if they contain the same sequence of characters. Trailing blanks are significant; for example, the strings `'abc'` and `'abc '` are not equal.

Two entities of the same abstract schema type are equal only if their primary keys have the same value. Table 34–9 shows the operator logic of a negation, and Table 34–10 shows the truth values of conditional tests.

TABLE 34–9 NOT Operator Logic

NOT Value	Value
T	F
F	T
U	U

TABLE 34–10 Conditional Test

Conditional Test	T	F	U
Expression `IS TRUE`	T	F	F
Expression `IS FALSE`	F	T	F
Expression is unknown	F	F	T

SELECT Clause

The SELECT clause defines the types of the objects or values returned by the query.

Return Types

The return type of the SELECT clause is defined by the result types of the select expressions contained within it. If multiple expressions are used, the result of the query is an Object[], and the elements in the array correspond to the order of the expressions in the SELECT clause and in type to the result types of each expression.

A SELECT clause cannot specify a collection-valued expression. For example, the SELECT clause p.teams is invalid because teams is a collection. However, the clause in the following query is valid because the t is a single element of the teams collection:

```
SELECT t
FROM Player p, IN (p.teams) t
```

The following query is an example of a query with multiple expressions in the SELECT clause:

```
SELECT c.name, c.country.name
 FROM customer c
 WHERE c.lastname = 'Coss' AND c.firstname = 'Roxane'
```

This query returns a list of Object[] elements; the first array element is a string denoting the customer name, and the second array element is a string denoting the name of the customer's country.

The result of a query may be the result of an aggregate function, listed in Table 34–11.

TABLE 34–11 Aggregate Functions in Select Statements

Name	Return Type	Description
AVG	Double	Returns the mean average of the fields
COUNT	Long	Returns the total number of results
MAX	The type of the field	Returns the highest value in the result set
MIN	The type of the field	Returns the lowest value in the result set
SUM	Long (for integral fields) Double (for floating-point fields) BigInteger (for BigInteger fields) BigDecimal (for BigDecimal fields)	Returns the sum of all the values in the result set

For select method queries with an aggregate function (AVG, COUNT, MAX, MIN, or SUM) in the SELECT clause, the following rules apply:

- The AVG, MAX, MIN, and SUM functions return null if there are no values to which the function can be applied.
- The COUNT function returns 0 if there are no values to which the function can be applied.

The following example returns the average order quantity:

```
SELECT AVG(o.quantity)
 FROM Order o
```

The following example returns the total cost of the items ordered by Roxane Coss:

```
SELECT SUM(l.price)
FROM Order o JOIN o.lineItems l JOIN o.customer c
WHERE c.lastname = 'Coss' AND c.firstname = 'Roxane'
```

The following example returns the total number of orders:

```
SELECT COUNT(o)
FROM Order o
```

The following example returns the total number of items that have prices in Hal Incandenza's order:

```
SELECT COUNT(l.price)
FROM Order o JOIN o.lineItems l JOIN o.customer c
WHERE c.lastname = 'Incandenza' AND c.firstname = 'Hal'
```

The DISTINCT Keyword

The DISTINCT keyword eliminates duplicate return values. If a query returns a java.util.Collection, which allows duplicates, you must specify the DISTINCT keyword to eliminate duplicates.

Constructor Expressions

Constructor expressions allow you to return Java instances that store a query result element instead of an Object[].

The following query creates a CustomerDetail instance per Customer matching the WHERE clause. A CustomerDetail stores the customer name and customer's country name. So the query returns a List of CustomerDetail instances:

```
SELECT NEW com.xyz.CustomerDetail(c.name, c.country.name)
 FROM customer c
WHERE c.lastname = 'Coss' AND c.firstname = 'Roxane'
```

ORDER BY Clause

As its name suggests, the ORDER BY clause orders the values or objects returned by the query.

If the ORDER BY clause contains multiple elements, the left-to-right sequence of the elements determines the high-to-low precedence.

The ASC keyword specifies ascending order, the default, and the DESC keyword indicates descending order.

When using the ORDER BY clause, the SELECT clause must return an orderable set of objects or values. You cannot order the values or objects for values or objects not returned by the SELECT clause. For example, the following query is valid because the ORDER BY clause uses the objects returned by the SELECT clause:

```
SELECT o
FROM Customer c JOIN c.orders o JOIN c.address a
WHERE a.state = 'CA'
ORDER BY o.quantity, o.totalcost
```

The following example is *not* valid, because the ORDER BY clause uses a value not returned by the SELECT clause:

```
SELECT p.product_name
FROM Order o, IN(o.lineItems) l JOIN o.customer c
WHERE c.lastname = 'Faehmel' AND c.firstname = 'Robert'
ORDER BY o.quantity
```

GROUP BY and HAVING Clauses

The GROUP BY clause allows you to group values according to a set of properties.

The following query groups the customers by their country and returns the number of customers per country:

```
SELECT c.country, COUNT(c)
 FROM Customer c GROUP BY c.country
```

The HAVING clause is used with the GROUP BY clause to further restrict the returned result of a query.

The following query groups orders by the status of their customer and returns the customer status plus the average totalPrice for all orders where the corresponding customers has the same status. In addition, it considers only customers with status 1, 2, or 3, so orders of other customers are not taken into account:

```
SELECT c.status, AVG(o.totalPrice)
 FROM Order o JOIN o.customer c
GROUP BY c.status HAVING c.status IN (1, 2, 3)
```

◆ ◆ ◆ CHAPTER 35

Using the Criteria API to Create Queries

The Criteria API is used to define queries for entities and their persistent state by creating query-defining objects. Criteria queries are written using Java programming language APIs, are typesafe, and are portable. Such queries work regardless of the underlying data store.

The following topics are addressed here:

Overview of the Criteria and Metamodel APIs

Similar to JPQL, the Criteria API is based on the abstract schema of persistent entities, their relationships, and embedded objects. The Criteria API operates on this abstract schema to allow developers to find, modify, and delete persistent entities by invoking Java Persistence API entity operations. The Metamodel API works in concert with the Criteria API to model persistent entity classes for Criteria queries.

The Criteria API and JPQL are closely related and are designed to allow similar operations in their queries. Developers familiar with JPQL syntax will find equivalent object-level operations in the Criteria API.

The following simple Criteria query returns all instances of the `Pet` entity in the data source:

```
EntityManager em = ...;
CriteriaBuilder cb = em.getCriteriaBuilder();
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.select(pet);
TypedQuery<Pet> q = em.createQuery(cq);
List<Pet> allPets = q.getResultList();
```

The equivalent JPQL query is:

```
SELECT p
FROM Pet p
```

This query demonstrates the basic steps to create a Criteria query:

1. Use an `EntityManager` instance to create a `CriteriaBuilder` object.
2. Create a query object by creating an instance of the `CriteriaQuery` interface. This query object's attributes will be modified with the details of the query.
3. Set the query root by calling the `from` method on the `CriteriaQuery` object.
4. Specify what the type of the query result will be by calling the `select` method of the `CriteriaQuery` object.
5. Prepare the query for execution by creating a `TypedQuery<T>` instance, specifying the type of the query result.
6. Execute the query by calling the `getResultList` method on the `TypedQuery<T>` object. Because this query returns a collection of entities, the result is stored in a `List`.

The tasks associated with each step are discussed in detail in this chapter.

To create a `CriteriaBuilder` instance, call the `getCriteriaBuilder` method on the `EntityManager` instance:

```
CriteriaBuilder cb = em.getCriteriaBuilder();
```

The query object is created by using the `CriteriaBuilder` instance:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
```

The query will return instances of the `Pet` entity, so the type of the query is specified when the `CriteriaQuery` object is created to create a typesafe query.

The `FROM` clause of the query is set, and the root of the query specified, by calling the `from` method of the query object:

```
Root<Pet> pet = cq.from(Pet.class);
```

The `SELECT` clause of the query is set by calling the `select` method of the query object and passing in the query root:

```
cq.select(pet);
```

The query object is now used to create a `TypedQuery<T>` object that can be executed against the data source. The modifications to the query object are captured to create a ready-to-execute query:

```
TypedQuery<Pet> q = em.createQuery(cq);
```

This typed query object is executed by calling its `getResultList` method, because this query will return multiple entity instances. The results are stored in a `List<Pet>` collection-valued object.

```
List<Pet> allPets = q.getResultList();
```

Using the Metamodel API to Model Entity Classes

The Metamodel API is used to create a metamodel of the managed entities in a particular persistence unit. For each entity class in a particular package, a metamodel class is created with a trailing underscore and with attributes that correspond to the persistent fields or properties of the entity class.

The following entity class, `com.example.Pet`, has four persistent fields: `id`, `name`, `color`, and `owners`:

```
package com.example;

...

@Entity
public class Pet {
  @Id
  protected Long id;
  protected String name;
  protected String color;
  @ManyToOne
  protected Set<Person> owners;
  ...
}
```

The corresponding Metamodel class is:

```
package com.example;

...

@Static Metamodel(Pet.class)
public class Pet_ {

  public static volatile SingularAttribute<Pet, Long> id;
  public static volatile SingularAttribute<Pet, String> name;
  public static volatile SingularAttribute<Pet, String> color;
  public static volatile SetAttribute<Pet, Person> owners;
}
```

The metamodel class and its attributes are used in Criteria queries to refer to the managed entity classes and their persistent state and relationships.

Using Metamodel Classes

Metamodel classes that correspond to entity classes are of the following type:

```
javax.persistence.metamodel.EntityType<T>
```

Metamodel classes are typically generated by annotation processors either at development time or at runtime. Developers of applications that use Criteria queries may generate static metamodel classes by using the persistence provider's annotation processor or may obtain the metamodel class by either calling the `getModel` method on the query root object or first obtaining an instance of the `Metamodel` interface and then passing the entity type to the instance's `entity` method.

The following code snippet shows how to obtain the `Pet` entity's metamodel class by calling `Root<T>.getModel`:

```
EntityManager em = ...;
CriteriaBuilder cb = em.getCriteriaBuilder();
CriteriaQuery cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
EntityType<Pet> Pet_ = pet.getModel();
```

The following code snippet shows how to obtain the `Pet` entity's metamodel class by first obtaining a metamodel instance by using `EntityManager.getMetamodel` and then calling `entity` on the metamodel instance:

```
EntityManager em = ...;
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
```

Using the Criteria API and Metamodel API to Create Basic Typesafe Queries

The basic semantics of a Criteria query consists of a `SELECT` clause, a `FROM` clause, and an optional `WHERE` clause, similar to a JPQL query. Criteria queries set these clauses by using Java programming language objects, so the query can be created in a typesafe manner.

Creating a Criteria Query

The `javax.persistence.criteria.CriteriaBuilder` interface is used to construct

- Criteria queries
- Selections
- Expressions
- Predicates

- Ordering

To obtain an instance of the `CriteriaBuilder` interface, call the `getCriteriaBuilder` method on either an `EntityManager` or an `EntityManagerFactory` instance.

The following code shows how to obtain a `CriteriaBuilder` instance by using the `EntityManager.getCriteriaBuilder` method.

```
EntityManager em = ...;
CriteriaBuilder cb = em.getCriteriaBuilder();
```

Criteria queries are constructed by obtaining an instance of the following interface:

```
javax.persistence.criteria.CriteriaQuery
```

`CriteriaQuery` objects define a particular query that will navigate over one or more entities. Obtain `CriteriaQuery` instances by calling one of the `CriteriaBuilder.createQuery` methods. For creating typesafe queries, call the `CriteriaBuilder.createQuery` method as follows:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
```

The `CriteriaQuery` object's type should be set to the expected result type of the query. In the preceding code, the object's type is set to `CriteriaQuery<Pet>` for a query that will find instances of the `Pet` entity.

In the following code snippet, a `CriteriaQuery` object is created for a query that returns a `String`:

```
CriteriaQuery<String> cq = cb.createQuery(String.class);
```

Query Roots

For a particular `CriteriaQuery`object, the root entity of the query, from which all navigation originates, is called the *query root*. It is similar to the `FROM` clause in a JPQL query.

Create the query root by calling the `from` method on the `CriteriaQuery` instance. The argument to the `from` method is either the entity class or an `EntityType<T>` instance for the entity.

The following code sets the query root to the `Pet` entity:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
```

The following code sets the query root to the `Pet` class by using an `EntityType<T>` instance:

```
EntityManager em = ...;
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet_);
```

Criteria queries may have more than one query root. This usually occurs when the query navigates from several entities.

The following code has two `Root` instances:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet1 = cq.from(Pet.class);
Root<Pet> pet2 = cq.from(Pet.class);
```

Querying Relationships Using Joins

For queries that navigate to related entity classes, the query must define a join to the related entity by calling one of the `From.join` methods on the query root object or another join object. The `join` methods are similar to the `JOIN` keyword in JPQL.

The target of the join uses the Metamodel class of type `EntityType<T>` to specify the persistent field or property of the joined entity.

The `join` methods return an object of type `Join<X, Y>`, where `X` is the source entity and `Y` is the target of the join. In the following code snippet, `Pet` is the source entity, and `Owner` is the target:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);

Root<Pet> pet = cq.from(Pet.class);
Join<Pet, Owner> owner = pet.join(Pet_.owners);
```

Joins can be chained together to navigate to related entities of the target entity without having to create a `Join<X, Y>` instance for each join:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
EntityType<Owner> Owner_ = m.entity(Owner.class);

Root<Pet> pet = cq.from(Pet.class);
Join<Owner, Address> address = cq.join(Pet_.owners).join(Owner_.addresses);
```

Path Navigation in Criteria Queries

`Path` objects are used in the `SELECT` and `WHERE` clauses of a Criteria query and can be query root entities, join entities, or other `Path` objects. The `Path.get` method is used to navigate to attributes of the entities of a query.

The argument to the `get` method is the corresponding attribute of the entity's Metamodel class. The attribute can either be a single-valued attribute, specified by `@SingularAttribute` in the Metamodel class, or a collection-valued attribute, specified by one of `@CollectionAttribute`, `@SetAttribute`, `@ListAttribute`, or `@MapAttribute`.

The following query returns the names of all the pets in the data store. The `get` method is called on the query root, `pet`, with the `name` attribute of the `Pet` entity's Metamodel class, `Pet_` as the argument:

```
CriteriaQuery<String> cq = cb.createQuery(String.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);

Root<Pet> pet = cq.from(Pet.class);
cq.select(pet.get(Pet_.name));
```

Restricting Criteria Query Results

The results of a query can be restricted on the `CriteriaQuery` object according to conditions set by calling the `CriteriaQuery.where` method. Calling the `where` method is analogous to setting the `WHERE` clause in a JPQL query.

The `where` method evaluates instances of the `Expression` interface to restrict the results according to the conditions of the expressions. `Expression` instances are created by using methods defined in the `Expression` and `CriteriaBuilder` interfaces.

The `Expression` Interface Methods

An `Expression` object is used in a query's `SELECT`, `WHERE`, or `HAVING` clause. Table 35–1 shows conditional methods you can use with `Expression` objects.

TABLE 35–1 Conditional Methods in the `Expression` Interface

Method	Description
`isNull`	Tests whether an expression is null
`isNotNull`	Tests whether an expression is not null
`in`	Tests whether an expression is within a list of values

The following query uses the `Expression.isNull` method to find all pets where the `color` attribute is null:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(pet.get(Pet_.color).isNull());
```

The following query uses the `Expression.in` method to find all brown and black pets:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(pet.get(Pet_.color).in("brown", "black");
```

The `in` method also can check whether an attribute is a member of a collection.

Expression Methods in the `CriteriaBuilder` Interface

The `CriteriaBuilder` interface defines additional methods for creating expressions. These methods correspond to the arithmetic, string, date, time, and case operators and functions of JPQL. Table 35–2 shows conditional methods you can use with `CriteriaBuilder` objects.

TABLE 35–2 Conditional Methods in the `CriteriaBuilder` Interface

Conditional Method	Description
`equal`	Tests whether two expressions are equal
`notEqual`	Tests whether two expressions are not equal
`gt`	Tests whether the first numeric expression is greater than the second numeric expression
`ge`	Tests whether the first numeric expression is greater than or equal to the second numeric expression
`lt`	Tests whether the first numeric expression is less than the second numeric expression
`le`	Tests whether the first numeric expression is less than or equal to the second numeric expression
`between`	Tests whether the first expression is between the second and third expression in value
`like`	Tests whether the expression matches a given pattern

The following code uses the `CriteriaBuilder.equal` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
```

```
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.equal(pet.get(Pet_.name)), "Fido");
...
```

The following code uses the `CriteriaBuilder.gt` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
Date someDate = new Date(...);
cq.where(cb.gt(pet.get(Pet_.birthday)), date);
```

The following code uses the `CriteriaBuilder.between` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
Date firstDate = new Date(...);
Date secondDate = new Date(...);
cq.where(cb.between(pet.get(Pet_.birthday)), firstDate, secondDate);
```

The following code uses the `CriteriaBuilder.like` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.like(pet.get(Pet_.name)), "*do");
```

Multiple conditional predicates can be specified by using the compound predicate methods of the `CriteriaBuilder` interface, as shown in Table 35–3.

TABLE 35–3 Compound Predicate Methods in the `CriteriaBuilder` Interface

Method	Description
`and`	A logical conjunction of two Boolean expressions
`or`	A logical disjunction of two Boolean expressions
`not`	A logical negation of the given Boolean expression

The following code shows the use of compound predicates in queries:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.equal(pet.get(Pet_.name), "Fido")
    .and(cb.equal(pet.get(Pet_.color), "brown");
```

Managing Criteria Query Results

For queries that return more than one result, it's often helpful to organize those results. The `CriteriaQuery` interface defines the `orderBy` method to order query results according to attributes of an entity. The `CriteriaQuery` interface also defines the `groupBy` method to group the results of a query together according to attributes of an entity, and the `having` method to restrict those groups according to a condition.

Ordering Results

The order of the results of a query can be set by calling the `CriteriaQuery.orderBy` method and passing in an `Order` object. `Order` objects are created by calling either the `CriteriaBuilder.asc` or the `CriteriaBuilder.desc` method. The `asc` method is used to order the results by ascending value of the passed expression parameter. The `desc` method is used to order the results by descending value of the passed expression parameter. The following query shows the use of the `desc` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.select(pet);
cq.orderBy(cb.desc(pet.get(Pet_.birthday));
```

In this query, the results will be ordered by the pet's birthday from highest to lowest. That is, pets born in December will appear before pets born in May.

The following query shows the use of the `asc` method:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
Join<Owner, Address> address = cq.join(Pet_.owners).join(Owner_.address);
cq.select(pet);
cq.orderBy(cb.asc(address.get(Address_.postalCode));
```

In this query, the results will be ordered by the pet owner's postal code from lowest to highest. That is, pets whose owner lives in the 10001 zip code will appear before pets whose owner lives in the 91000 zip code.

If more than one `Order` object is passed to `orderBy`, the precedence is determined by the order in which they appear in the argument list of `orderBy`. The first `Order` object has precedence.

The following code orders results by multiple criteria:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
Join<Pet, Owner> owner = cq.join(Pet_.owners);
cq.select(pet);
cq.orderBy(cb.asc(owner.get(Owner_.lastName), owner.get(Owner_.firstName));
```

The results of this query will be ordered alphabetically by the pet owner's last name, then first name.

Grouping Results

The `CriteriaQuery.groupBy` method partitions the query results into groups. These groups are set by passing an expression to `groupBy`:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.groupBy(pet.get(Pet_.color));
```

This query returns all `Pet` entities and groups the results by the pet's color.

The `CriteriaQuery.having` method is used in conjunction with `groupBy` to filter over the groups. The `having` method takes a conditional expression as a parameter. By calling the `having` method, the query result is restricted according to the conditional expression:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.groupBy(pet.get(Pet_.color));
cq.having(cb.in(pet.get(Pet_.color)).value("brown").value("blonde");
```

In this example, the query groups the returned `Pet` entities by color, as in the preceding example. However, the only returned groups will be `Pet` entities where the `color` attribute is set to `brown` or `blonde`. That is, no gray-colored pets will be returned in this query.

Executing Queries

To prepare a query for execution, create a `TypedQuery<T>` object with the type of the query result by passing the `CriteriaQuery` object to `EntityManager.createQuery`.

Queries are executed by calling either `getSingleResult` or `getResultList` on the `TypedQuery<T>` object.

Single-Valued Query Results

The `TypedQuery<T>.getSingleResult` method is used for executing queries that return a single result:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
...
TypedQuery<Pet> q = em.createQuery(cq);
Pet result = q.getSingleResult();
```

Collection-Valued Query Results

The `TypedQuery<T>.getResultList` method is used for executing queries that return a collection of objects:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
...
TypedQuery<Pet> q = em.createQuery(cq);
List<Pet> results = q.getResultList();
```

◆ ◆ ◆ CHAPTER 36

Creating and Using String-Based Criteria Queries

This chapter describes how to create weakly-typed string-based Criteria API queries.

Overview of String-Based Criteria API Queries

String-based Criteria API queries ("string-based queries") are Java programming language queries that use strings rather than strongly-typed metamodel objects to specify entity attributes when traversing a data hierarchy. String-based queries are constructed similarly to metamodel queries, can be static or dynamic, and can express the same kind of queries and operations as strongly-typed metamodel queries.

Strongly-typed metamodel queries are the preferred method of constructing Criteria API queries. The main advantage of string-based queries over metamodel queries is the ability to construct Criteria queries at development time without the need to generate static metamodel classes or otherwise access dynamically generated metamodel classes. The main disadvantage to string-based queries is their lack of type safety, which may lead to runtime errors due to type mismatches that would be caught at development time when using strongly-typed metamodel queries.

For information on constructing criteria queries, see Chapter 35, "Using the Criteria API to Create Queries"

Creating String-Based Queries

To create a string-based query, specify the attribute names of entity classes directly as strings, rather than the attributes of the metamodel class. For example, this query finds all `Pet` entities where the value of the `name` attribute is `Fido`:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.equal(pet.get("name"), "Fido"));
...
```

The name of the attribute is specified as a string. This query is the equivalent of the following metamodel query:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Metamodel m = em.getMetamodel();
EntityType<Pet> Pet_ = m.entity(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.equal(pet.get(Pet_.name), "Fido"));
```

Note – Type mismatch errors in string-based queries won't appear until the code is executed at runtime, unlike the above metamodel query, where type mismatches will be caught at compile time.

Joins are specified in the same way:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
Join<Owner, Address> address = pet.join("owners").join("addresses");
...
```

All the conditional expressions, method expressions, path navigation methods, and result restriction methods used in metamodel queries can be used in string-based queries. In each case, the attributes are specified using strings. For example, here is a string-based query that uses the `in` expression:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(pet.get("color").in("brown", "black"));
```

Here is a string-based query that orders the results in descending order by date:

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.select(pet);
cq.orderBy(cb.desc(pet.get("birthday")));
```

Executing String-Based Queries

String-based queries are executed similarly to strongly-typed Criteria queries. First create a `javax.persistence.TypedQuery` object by passing the criteria query object to the `EntityManager.createQuery` method and then call either `getSingleResult` or `getResultList` on the query object to execute the query.

```
CriteriaQuery<Pet> cq = cb.createQuery(Pet.class);
Root<Pet> pet = cq.from(Pet.class);
cq.where(cb.equal(pet.get("name"), "Fido"));
TypedQuery<Pet> q = em.createQuery(cq);
List<Pet> results = q.getResultList();
```

◆ ◆ ◆ CHAPTER 37

Controlling Concurrent Access to Entity Data with Locking

This chapter details how to handle concurrent access to entity data, and the locking strategies available to Java Persistence API application developers.

The following topics are addressed here:

Overview of Entity Locking and Concurrency

Entity data is *concurrently accessed* if the data in a data source is accessed at the same time by multiple applications. Special care must be taken to ensure that the underlying data's integrity is preserved when accessed concurrently.

When data is updated in the database tables in a transaction, the persistence provider assumes that the database management system will hold short-term read locks and long-term write locks to maintain data integrity. Most persistence providers will delay database writes until the end of the transaction, except when the application explicitly calls for a flush (that is, the application calls the `EntityManager.flush` method or executes queries with the flush mode set to `AUTO`).

By default, persistence providers use *optimistic locking*, where, before committing changes to the data, the persistence provider checks that no other transaction has modified or deleted the data since the data was read. This is accomplished by a version column in the database table, with a corresponding version attribute in the entity class. When a row is modified, the version value is incremented. The original transaction checks the version attribute, and if the data has been modified by another transaction, a `javax.persistence.OptimisticLockException` will be thrown, and the original transaction will be rolled back. When the application specifies optimistic lock modes, the persistence provider verifies that a particular entity has not changed since it was read from the database even if the entity data was not modified.

Pessimistic locking goes further than optimistic locking. With pessimistic locking, the persistence provider creates a transaction that obtains a long-term lock on the data until the

transaction is completed, which prevents other transactions from modifying or deleting the data until the lock has ended. Pessimistic locking is a better strategy than optimistic locking when the underlying data is frequently accessed and modified by many transactions.

Caution – Using pessimistic locks on entities that are not subject to frequent modification may result in decreased application performance.

Using Optimistic Locking

The `javax.persistence.Version` annotation is used to mark a persistent field or property as a version attribute of an entity. By adding a version attribute, the entity is enabled for optimistic concurrency control. The version attribute is read and updated by the persistence provider when an entity instance is modified during a transaction. The application may read the version attribute, but *must not* modify the value.

Note – Although some persistence providers may support optimistic locking for entities that do not have a version attribute, portable applications should always use entities with a version attribute when using optimistic locking. If the application attempts to lock an entity without a version attribute, and the persistence provider doesn't support optimistic locking for non-versioned entities, a `PersistenceException` will be thrown.

The `@Version` annotation has the following requirements:

- Only a single `@Version` attribute may be defined per entity.
- The `@Version` attribute must be in the primary table for an entity mapped to multiple tables.
- The type of the `@Version` attribute must be one of the following: `int`, `Integer`, `long`, `Long`, `short`, `Short`, and `java.sql.Timestamp`.

The following code snippet shows how to define a version attribute in an entity with persistent fields:

```
@Version
protected int version;
```

The following code snippet shows how to define a version attribute in an entity with persistent properties:

```
@Version
protected Short getVersion() { ... }
```

Lock Modes

The application may increase the level of locking for an entity by specifying the use of lock modes. Lock modes may be specified to increase the level of optimistic locking or to request the use of pessimistic locks.

The use of optimistic lock modes causes the persistence provider to check the version attributes for entities that were read (but not modified) during a transaction as well as for those entities that were updated.

The use of pessimistic lock modes specifies that the persistence provider is to immediately acquire long-term read or write locks for the database data corresponding to entity state.

The lock mode for an entity operation may be set by specifying one of the lock modes defined in the `javax.persistence.LockModeType` enumerated type, listed in Table 37–1.

TABLE 37–1 Lock Modes for Concurrent Entity Access

Lock Mode	Description
`OPTIMISTIC`	Obtain an optimistic read lock for all entities with a version attribute.
`OPTIMISTIC_FORCE_INCREMENT`	Obtain an optimistic read lock for all entities with a version attribute, and increment the version attribute value.
`PESSIMISTIC_READ`	Immediately obtain a long-term read lock on the data to prevent the data from being modified or deleted. Other transactions may read the data while the lock is maintained, but may not modify or delete the data. The persistence provider is permitted to obtain a database write lock when a read lock was requested, but not vice versa.
`PESSIMISTIC_WRITE`	Immediately obtain a long-term write lock on the data to prevent the data from being read, modified, or deleted.
`PESSIMISTIC_FORCE_INCREMENT`	Immediately obtain a long-term lock on the data to prevent the data from being modified or deleted, and increment the version attribute of versioned entities.
`READ`	A synonym for `OPTIMISTIC`. Use of `LockModeType.OPTIMISTIC` is to be preferred for new applications.
`WRITE`	A synonym for `OPTIMISTIC_FORCE_INCREMENT`. Use of `LockModeType.OPTIMISTIC_FORCE_INCREMENT` is to be preferred for new applications.

TABLE 37–1 Lock Modes for Concurrent Entity Access *(Continued)*

Lock Mode	Description
NONE	No additional locking will occur on the data in the database.

Setting the Lock Mode

The lock mode may be specified by one of the following techniques:

- Calling the `EntityManager.lock` and passing in one of the lock modes:

```
EntityManager em = ...;
Person person = ...;
em.lock(person, LockModeType.OPTIMISTIC);
```

- Calling one of the `EntityManager.find` methods that takes the lock mode as a parameter:

```
EntityManager em = ...;
String personPK = ...;
Person person = em.find(Person.class, personPK, LockModeType.PESSIMISTIC_WRITE);
```

- Calling one of the `EntityManager.refresh` methods that takes the lock mode as a parameter:

```
EntityManager em = ...;
String personPK = ...;
Person person = em.find(Person.class, personPK);
...
em.refresh(person, LockModeType.OPTIMISTIC_FORCE_INCREMENT);
```

- Calling the `Query.setLockMode` or `TypedQuery.setLockMode` method, passing the lock mode as the parameter:

```
Query q = em.createQuery(...);
q.setLockMode(LockModeType.PESSIMISTIC_FORCE_INCREMENT);
```

- Adding a `lockMode` element to the `@NamedQuery` annotation:

```
@NamedQuery(name="lockPersonQuery",
  query="SELECT p FROM Person p WHERE p.name LIKE :name",
  lockMode=PESSIMISTIC_READ)
```

Using Pessimistic Locking

Versioned entities as well as entities that do not have a version attribute can be locked pessimistically.

To lock entities pessimistically, set the lock mode to `PESSIMISTIC_READ`, `PESSIMISTIC_WRITE`, or `PESSIMISTIC_FORCE_INCREMENT`.

If a pessimistic lock cannot be obtained on the database rows, and the failure to lock the data results in a transaction rollback, a `PessimisticLockException` is thrown. If a pessimistic lock cannot be obtained, but the locking failure doesn't result in a transaction rollback, a `LockTimeoutException` is thrown.

Pessimistically locking a version entity with `PESSIMISTIC_FORCE_INCREMENT` results in the version attribute being incremented, even if the entity data is unmodified. When pessimistically locking a versioned entity, the persistence provider will perform the version checks that occur during optimistic locking, and if the version check fails, an `OptimisticLockException` will be thrown. Attempting to lock a non-versioned entity with `PESSIMISTIC_FORCE_INCREMENT` is not portable and may result in a `PersistenceException` if the persistence provider doesn't support optimistic locks for non-versioned entities. Locking a versioned entity with `PESSIMISTIC_WRITE` results in the version attribute being incremented if the transaction was successfully committed.

Pessimistic Locking Timeouts

The length of time in milliseconds the persistence provider should wait to obtain a lock on the database tables may be specified using the `javax.persistence.lock.timeout` property. If the time it takes to obtain a lock exceeds the value of this property, a `LockTimeoutException` will be thrown, but the current transaction will not be marked for rollback. If this property is set to `0`, the persistence provider should throw a `LockTimeoutException` if it cannot immediately obtain a lock.

Note – Portable applications should not rely on the setting of `javax.persistence.lock.timeout`, as the locking strategy and underlying database may mean that the timeout value cannot be used. The value of `javax.persistence.lock.timeout` is a hint, not a contract.

This property may be set programmatically by passing it to the `EntityManager` methods that allow lock modes to be specified, the `Query.setLockMode` and `TypedQuery.setLockMode` methods, the `@NamedQuery` annotation, and as a property to the `Persistence.createEntityManagerFactory` method. It may also be set as a property in the `persistence.xml` deployment descriptor.

If `javax.persistence.lock.timeout` is set in multiple places, the value will be determined in the following order:

1. The argument to one of the `EntityManager` or `Query` methods.
2. The setting in the `@NamedQuery` annotation.
3. The argument to the `Persistence.createEntityManagerFactory` method.
4. The value in the `persistence.xml` deployment descriptor.

◆ ◆ ◆ CHAPTER 38

Improving the Performance of Java Persistence API Applications By Setting a Second-Level Cache

This chapter explains how to modify the second-level cache mode settings to improve the performance of applications that use the Java Persistence API.

The following topics are addressed here:

Overview of the Second-Level Cache

A *second-level cache* is a local store of entity data managed by the persistence provider to improve application performance. A second-level cache helps improve performance by avoiding expensive database calls, keeping the entity data local to the application. A second-level cache is typically transparent to the application, as it is managed by the persistence provider and underlies the persistence context of an application. That is, the application reads and commits data through the normal entity manager operations without knowing about the cache.

Note – Persistence providers are not required to support a second-level cache. Portable applications should not rely on support by persistence providers for a second-level cache.

The second-level cache for a persistence unit may be configured to one of several second-level cache modes. The following cache mode settings are defined by the Java Persistence API:

TABLE 38–1 Cache Mode Settings for the Second-Level Cache

Cache Mode Setting	Description
ALL	All entity data is stored in the second-level cache for this persistence unit.

TABLE 38–1 Cache Mode Settings for the Second-Level Cache *(Continued)*

Cache Mode Setting	Description
`NONE`	No data is cached in the persistence unit. The persistence provider must not cache any data.
`ENABLE_SELECTIVE`	Enable caching for entities that have been explicitly set with the `@Cacheable` annotation.
`DISABLE_SELECTIVE`	Enable caching for all entities except those that have been explicitly set with the `@Cacheable(false)` annotation.
`UNSPECIFIED`	The caching behavior for the persistence unit is undefined. The persistence provider's default caching behavior will be used.

One consequence of using a second-level cache in an application is that the underlying data may have changed in the database tables, but the value in the cache has not, a circumstance called a *stale read*. Stale reads may be avoided by changing the second-level cache to one of the cache mode settings, controlling which entities may be cached (described in "Controlling Whether Entities May Be Cached" on page 638), or changing the cache's retrieval or store modes (described in "Setting the Cache Retrieval and Store Modes" on page 639). Which strategies best avoid stale reads are application dependent.

Controlling Whether Entities May Be Cached

The `javax.persistence.Cacheable` annotation is used to specify that an entity class, and any subclasses, may be cached when using the `ENABLE_SELECTIVE` or `DISABLE_SELECTIVE` cache modes. Subclasses may override the `@Cacheable` setting by adding a `@Cacheable` annotation and changing the value.

To specify that an entity may be cached, add a `Cacheable` annotation at the class level:

```
@Cacheable
@Entity
public class Person { ... }
```

By default, the `@Cacheable` annotation is `true`. The following example is equivalent:

```
@Cacheable(true)
@Entity
public class Person{ ... }
```

To specify that an entity must not be cached, add a `@Cacheable` annotation and set it to `false`:

```
@Cacheable(false)
@Entity
public class OrderStatus { ... }
```

When the ENABLE_SELECTIVE cache mode is set, the persistence provider will cache any entities that have a @Cacheable(true) annotation and any subclasses of that entity that have not been overridden. The persistence provider will not cache entities that have @Cacheable(false) or have no @Cacheable annotation. That is, the ENABLE_SELECTIVE mode will only cache entities that have been explicitly marked for the cache using the @Cacheable annotation.

When the DISABLE_SELECTIVE cache mode is set, the persistence provider will cache any entities that *do not* have a @Cacheable(false) annotation. Entities that do not have a @Cacheable annotation, and entities with a @Cacheable(true) annotation will be cached. That is, the DISABLE_SELECTIVE mode will cache all entities that have not been explicitly prevented from being cached.

If the cache mode is set to UNDEFINED, or is left unset, the behavior of entities annotated with @Cacheable is undefined. If the cache mode is set to ALL or NONE, the value of the @Cacheable annotation is ignored by the persistence provider.

Specifying the Cache Mode Settings to Improve Performance

To adjust the cache mode settings for a persistence unit, specify one of the cache modes as the value of the shared-cache-mode element in the persistence.xml deployment descriptor:

```
<persistence-unit name="examplePU" transaction-type="JTA">
  <provider>org.eclipse.persistence.jpa.PersistenceProvider</provider>
  <jta-data-source>jdbc/__default</jta-data-source>
  <shared-cache-mode>DISABLE_SELECTIVE</shared-cache-mode>
</persistence-unit>
```

Note – Because support for a second-level cache is not required by the Java Persistence API specification, setting the second-level cache mode in persistence.xml will have no affect when using a persistence provider that does not implement a second-level cache.

Alternately, the shared cache mode may be specified by setting the javax.persistence.sharedCache.mode property to one of the shared cache mode settings:

```
EntityManagerFactor emf = Persistence.createEntityManagerFactory("myExamplePU",
            new Properties().add("javax.persistence.sharedCache.mode", "ENABLE_SELECTIVE"));
```

Setting the Cache Retrieval and Store Modes

If the second-level cache has been enabled for a persistence unit by setting the shared cache mode, the behavior of the second-level cache can be further modified by setting the javax.persistence.cache.retrieveMode and javax.persistence.cache.storeMode properties. These properties may be set at the persistence context level by passing the property

name and value to the `EntityManager.setProperty` method, or may be set on a per-`EntityManager` operation (`EntityManager.find` or `EntityManager.refresh`) or per-query level.

Cache Retrieval Mode

The cache retrieval mode, set by the `javax.persistence.retrieveMode` property, controls how data is read from the cache for calls to the `EntityManager.find` method and from queries.

The `retrieveMode` property can be set to one of the constants defined by the `javax.persistence.CacheRetrieveMode` enumerated type, either `USE` (the default) or `BYPASS`. When set to `USE`, data is retrieved from the second-level cache, if available. If the data is not in the cache, the persistence provider will read it from the database. When set to `BYPASS`, the second-level cache is bypassed and a call to the database is made to retrieve the data.

Cache Store Mode

The cache store mode, set by the `javax.persistence.storeMode` property, controls how data is stored in the cache.

The `storeMode` property can be set to one of the constants defined by the `javax.persistence.CacheStoreMode` enumerated type, either `USE` (the default), `BYPASS`, or `REFRESH`. When set to `USE` the cache data is created or updated when data is read from or committed to the database. If data is already in the cache, setting the store mode to `USE` will not force a refresh when data is read from the database.

When the store mode is set to `BYPASS`, data read from or committed to the database is *not* inserted or updated in the cache. That is, the cache is unchanged.

When the store mode is set to `REFRESH` the cache data is created or updated when data is read from or committed to the database, and a refresh is forced on data in the cache upon database reads.

Setting the Cache Retrieval or Store Mode

To set the cache retrieval or store mode for the persistence context, call the `EntityManager.setProperty` method with the property name and value pair:

```
EntityManager em = ...;
em.setProperty("javax.persistence.cache.storeMode", "BYPASS");
```

To set the cache retrieval or store mode when calling the `EntityManger.find` or `EntityManager.refresh` methods, first create a `Map<String, Object>` instance and add a name/value pair as follows:

```
EntityManager em = ...;
Map<String, Object> props = new HashMap<String, Object>();
props.put("javax.persistence.cache.retrieveMode", "BYPASS");
```

```
String personPK = ...;
Person person = em.find(Person.class, personPK, props);
```

Note – The cache retrieve mode is ignored when calling the `EntityManager.refresh` method, as calls to `refresh` always result in data being read from the database, not the cache.

To set the retrieval or store mode when using queries, call the `Query.setHint` or `TypedQuery.setHint` methods, depending on the type of query:

```
EntityManager em = ...;
CriteriaQuery<Person> cq = ...;
TypedQuery<Person> q = em.createQuery(cq);
q.setHint("javax.persistence.cache.storeMode", "REFRESH");
...
```

Setting the store or retrieve mode in a query or when calling the `EntityManager.find` or `EntityManager.refresh` methods overrides the setting of the entity manager.

Controlling the Second-Level Cache Programmatically

The `javax.persistence.Cache` interface defines methods for interacting with the second-level cache programmatically. The `Cache` interface defines methods to check whether a particular entity has cached data, to remove a particular entity from the cache, to remove all instances (and instances of subclasses) of an entity class from the cache, and to clear the cache of all entity data.

Note – If the second-level cache has been disabled, calls to the `Cache` interface's methods have no effect, except for `contains`, which will always return `false`.

Checking Whether An Entity's Data is Cached

Call the `Cache.contains` method to find out whether a given entity is currently in the second-level cache. The `contains` method returns `true` if the entity's data is cached, and `false` if the data is not in the cache.

```
EntityManager em = ...;
Cache cache = em.getEntityManagerFactory().getCache();
String personPK = ...;
if (cache.contains(Person.class, personPK)) {
  // the data is cached
} else {
  // the data is NOT cached
}
```

Removing an Entity from the Cache

Call one of the `Cache.evict` methods to remove a particular entity or all entities of a given type from the second-level cache. To remove a particular entity from the cache, call the `evict` method and pass in the entity class and the primary key of the entity:

```
EntityManager em = ...;
Cache cache = em.getEntityManagerFactory().getCache();
String personPK = ...;
cache.evict(Person.class, personPK);
```

To remove all instances of a particular entity class, including subclasses, call the `evict` method and specify the entity class:

```
EntityManager em = ...;
Cache cache = em.getEntityManagerFactory().getCache();
cache.evict(Person.class);
```

All instances of the `Person` entity class will be removed from the cache. If the `Person` entity has a subclass, `Student`, calls to the above method will remove all instances of `Student` from the cache as well.

Removing All Data from the Cache

Call the `Cache.evictAll` method to completely clear the second-level cache:

```
EntityManager em = ...;
Cache cache = em.getEntityManagerFactory().getCache();
cache.evictAll();
```

PART VII

Security

Part VII explores security concepts and examples. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 39

Introduction to Security in the Java EE Platform

The chapters in Part VII discuss security requirements in web tier and enterprise tier applications. Every enterprise that has either sensitive resources that can be accessed by many users or resources that traverse unprotected, open, networks, such as the Internet, needs to be protected.

This chapter introduces basic security concepts and security mechanisms. More information on these concepts and mechanisms can be found in the chapter on security in the Java EE 6 specification. This document is available for download online at `http://www.jcp.org/en/jsr/detail?id=316`.

In this tutorial, security requirements are also addressed in the following chapters.

- Chapter 40, "Getting Started Securing Web Applications," explains how to add security to web components, such as servlets.
- Chapter 41, "Getting Started Securing Enterprise Applications," explains how to add security to Java EE components, such as enterprise beans and application clients.

Some of the material in this chapter assumes that you understand basic security concepts. To learn more about these concepts before you begin this chapter, you should explore the Java SE security web site at `http://download.oracle.com/javase/6/docs/technotes/guides/security/`.

The following topics are addressed here:

Overview of Java EE Security

Enterprise tier and web tier applications are made up of components that are deployed into various containers. These components are combined to build a multitier enterprise application. Security for components is provided by their containers. A container provides two kinds of security: declarative and programmatic.

- *Declarative security* expresses an application component's security requirements by using either deployment descriptors or annotations.

  A deployment descriptor is an XML file that is external to the application and that expresses an application's security structure, including security roles, access control, and authentication requirements. For more information about deployment descriptors, read "Using Deployment Descriptors for Declarative Security" on page 655.

  Annotations, also called metadata, are used to specify information about security within a class file. When the application is deployed, this information can be either used by or overridden by the application deployment descriptor. Annotations save you from having to write declarative information inside XML descriptors. Instead, you simply put annotations on the code, and the required information gets generated. For this tutorial, annotations are used for securing applications wherever possible. For more information about annotations, see "Using Annotations to Specify Security Information" on page 654.
- *Programmatic security* is embedded in an application and is used to make security decisions. Programmatic security is useful when declarative security alone is not sufficient to express the security model of an application. For more information about programmatic security, read "Using Programmatic Security" on page 655.

A Simple Security Example

The security behavior of a Java EE environment may be better understood by examining what happens in a simple application with a web client, a user interface, and enterprise bean business logic.

In the following example, which is taken from the Java EE 6 Specification, the web client relies on the web server to act as its authentication proxy by collecting user authentication data from the client and using it to establish an authenticated session.

Step 1: Initial Request

In the first step of this example, the web client requests the main application URL. This action is shown in Figure 39–1.

FIGURE 39–1 Initial Request



Since the client has not yet authenticated itself to the application environment, the server responsible for delivering the web portion of the application, hereafter referred to as the *web server*, detects this and invokes the appropriate authentication mechanism for this resource. For more information on these mechanisms, see "Security Mechanisms" on page 651.

Step 2: Initial Authentication

The web server returns a form that the web client uses to collect authentication data, such as user name and password, from the user. The web client forwards the authentication data to the web server, where it is validated by the web server, as shown in Figure 39–2. The validation mechanism may be local to a server or may leverage the underlying security services. On the basis of the validation, the web server sets a credential for the user.

FIGURE 39–2 Initial Authentication



Step 3: URL Authorization

The credential is used for future determinations of whether the user is authorized to access restricted resources it may request. The web server consults the security policy associated with the web resource to determine the security roles that are permitted access to the resource. The security policy is derived from annotations or from the deployment descriptor. The web container then tests the user's credential against each role to determine whether it can map the user to the role. Figure 39–3 shows this process.

FIGURE 39–3 URL Authorization



The web server's evaluation stops with an "is authorized" outcome when the web server is able to map the user to a role. A "not authorized" outcome is reached if the web server is unable to map the user to any of the permitted roles.

Step 4: Fulfilling the Original Request

If the user is authorized, the web server returns the result of the original URL request, as shown in Figure 39–4.

FIGURE 39–4 Fulfilling the Original Request



In our example, the response URL of a web page is returned, enabling the user to post form data that needs to be handled by the business-logic component of the application. See Chapter 40, "Getting Started Securing Web Applications," for more information on protecting web applications.

Step 5: Invoking Enterprise Bean Business Methods

The web page performs the remote method call to the enterprise bean, using the user's credential to establish a secure association between the web page and the enterprise bean, as shown in Figure 39–5. The association is implemented as two related security contexts: one in the web server and one in the EJB container.

FIGURE 39–5 Invoking an Enterprise Bean Business Method



The EJB container is responsible for enforcing access control on the enterprise bean method. The container consults the security policy associated with the enterprise bean to determine the security roles that are permitted access to the method. The security policy is derived from annotations or from the deployment descriptor. For each role, the EJB container determines whether it can map the caller to the role by using the security context associated with the call.

The container's evaluation stops with an "is authorized" outcome when the container is able to map the caller's credential to a role. A "not authorized" outcome is reached if the container is unable to map the caller to any of the permitted roles. A "not authorized" result causes an exception to be thrown by the container and propagated back to the calling web page.

If the call is authorized, the container dispatches control to the enterprise bean method. The result of the bean's execution of the call is returned to the web page and ultimately to the user by the web server and the web client.

Features of a Security Mechanism

A properly implemented security mechanism will provide the following functionality:

- Prevent unauthorized access to application functions and business or personal data (authentication)
- Hold system users accountable for operations they perform (non-repudiation)
- Protect a system from service interruptions and other breaches that affect quality of service

Ideally, properly implemented security mechanisms will also be

- Easy to administer
- Transparent to system users
- Interoperable across application and enterprise boundaries

Characteristics of Application Security

Java EE applications consist of components that can contain both protected and unprotected resources. Often, you need to protect resources to ensure that only authorized users have access. *Authorization* provides controlled access to protected resources. Authorization is based on identification and authentication. *Identification* is a process that enables recognition of an entity by a system, and *authentication* is a process that verifies the identity of a user, device, or other entity in a computer system, usually as a prerequisite to allowing access to resources in a system.

Authorization and authentication are not required for an entity to access unprotected resources. Accessing a resource without authentication is referred to as unauthenticated, or anonymous, access.

The characteristics of application security that, when properly addressed, help to minimize the security threats faced by an enterprise include the following:

- **Authentication**: The means by which communicating entities, such as client and server, prove to each other that they are acting on behalf of specific identities that are authorized for access. This ensures that users are who they say they are.
- **Authorization**, or **access control**: The means by which interactions with resources are limited to collections of users or programs for the purpose of enforcing integrity, confidentiality, or availability constraints. This ensures that users have permission to perform operations or access data.
- **Data integrity**: The means used to prove that information has not been modified by a third party, an entity other than the source of the information. For example, a recipient of data sent over an open network must be able to detect and discard messages that were modified after they were sent. This ensures that only authorized users can modify data.
- **Confidentiality**, or **data privacy**: The means used to ensure that information is made available only to users who are authorized to access it. This ensures that only authorized users can view sensitive data.
- **Non-repudiation**: The means used to prove that a user who performed some action cannot reasonably deny having done so. This ensures that transactions can be proved to have happened.

- **Quality of Service**: The means used to provide better service to selected network traffic over various technologies.
- **Auditing**: The means used to capture a tamper-resistant record of security-related events for the purpose of being able to evaluate the effectiveness of security policies and mechanisms. To enable this, the system maintains a record of transactions and security information.

Security Mechanisms

The characteristics of an application should be considered when deciding the layer and type of security to be provided for applications. The following sections discuss the characteristics of the common mechanisms that can be used to secure Java EE applications. Each of these mechanisms can be used individually or with others to provide protection layers based on the specific needs of your implementation.

Java SE Security Mechanisms

Java SE provides support for a variety of security features and mechanisms:

- **Java Authentication and Authorization Service (JAAS)**: JAAS is a set of APIs that enable services to authenticate and enforce access controls upon users. JAAS provides a pluggable and extensible framework for programmatic user authentication and authorization. JAAS is a core Java SE API and is an underlying technology for Java EE security mechanisms.
- **Java Generic Security Services (Java GSS-API)**: Java GSS-API is a token-based API used to securely exchange messages between communicating applications. The GSS-API offers application programmers uniform access to security services atop a variety of underlying security mechanisms, including Kerberos.
- **Java Cryptography Extension (JCE)**: JCE provides a framework and implementations for encryption, key generation and key agreement, and Message Authentication Code (MAC) algorithms. Support for encryption includes symmetric, asymmetric, block, and stream ciphers. Block ciphers operate on groups of bytes; stream ciphers operate on one byte at a time. The software also supports secure streams and sealed objects.
- **Java Secure Sockets Extension (JSSE)**: JSSE provides a framework and an implementation for a Java version of the Secure Sockets Layer (SSL) and Transport Layer Security (TLS) protocols and includes functionality for data encryption, server authentication, message integrity, and optional client authentication to enable secure Internet communications.
- **Simple Authentication and Security Layer (SASL)**: SASL is an Internet standard (RFC 2222) that specifies a protocol for authentication and optional establishment of a security layer between client and server applications. SASL defines how authentication data is to be exchanged but does not itself specify the contents of that data. SASL is a framework into which specific authentication mechanisms that specify the contents and semantics of the authentication data can fit.

Java SE also provides a set of tools for managing keystores, certificates, and policy files; generating and verifying JAR signatures; and obtaining, listing, and managing Kerberos tickets.

For more information on Java SE security, visit `http://download.oracle.com/javase/6/docs/technotes/guides/security/`.

Java EE Security Mechanisms

Java EE security services are provided by the component container and can be implemented by using declarative or programmatic techniques (see "Securing Containers" on page 654). Java EE security services provide a robust and easily configured security mechanism for authenticating users and authorizing access to application functions and associated data at many different layers. Java EE security services are separate from the security mechanisms of the operating system.

Application-Layer Security

In Java EE, component containers are responsible for providing application-layer security, security services for a specific application type tailored to the needs of the application. At the application layer, application firewalls can be used to enhance application protection by protecting the communication stream and all associated application resources from attacks.

Java EE security is easy to implement and configure and can offer fine-grained access control to application functions and data. However, as is inherent to security applied at the application layer, security properties are not transferable to applications running in other environments and protect data only while it is residing in the application environment. In the context of a traditional enterprise application, this is not necessarily a problem, but when applied to a web services application, in which data often travels across several intermediaries, you would need to use the Java EE security mechanisms along with transport-layer security and message-layer security for a complete security solution.

The advantages of using application-layer security include the following.

- Security is uniquely suited to the needs of the application.
- Security is fine grained, with application-specific settings.

The disadvantages of using application-layer security include the following.

- The application is dependent on security attributes that are not transferable between application types.
- Support for multiple protocols makes this type of security vulnerable.
- Data is close to or contained within the point of vulnerability.

For more information on providing security at the application layer, see "Securing Containers" on page 654.

Transport-Layer Security

Transport-layer security is provided by the transport mechanisms used to transmit information over the wire between clients and providers; thus, transport-layer security relies on secure HTTP transport (HTTPS) using Secure Sockets Layer (SSL). Transport security is a point-to-point security mechanism that can be used for authentication, message integrity, and confidentiality. When running over an SSL-protected session, the server and client can authenticate each other and negotiate an encryption algorithm and cryptographic keys before the application protocol transmits or receives its first byte of data. Security is active from the time the data leaves the client until it arrives at its destination, or vice versa, even across intermediaries. The problem is that the data is not protected once it gets to the destination. One solution is to encrypt the message before sending.

Transport-layer security is performed in a series of phases, as follows.

- The client and server agree on an appropriate algorithm.
- A key is exchanged using public-key encryption and certificate-based authentication.
- A symmetric cipher is used during the information exchange.

Digital certificates are necessary when running HTTPS using SSL. The HTTPS service of most web servers will not run unless a digital certificate has been installed. Digital certificates have already been created for the GlassFish Server.

The advantages of using transport-layer security include the following.

- It is relatively simple, well-understood, standard technology.
- It applies to both a message body and its attachments.

The disadvantages of using transport-layer security include the following.

- It is tightly coupled with the transport-layer protocol.
- It represents an all-or-nothing approach to security. This implies that the security mechanism is unaware of message contents, so that you cannot selectively apply security to portions of the message as you can with message-layer security.
- Protection is transient. The message is protected only while in transit. Protection is removed automatically by the endpoint when it receives the message.
- It is not an end-to-end solution, simply point-to-point.

For more information on transport-layer security, see "Establishing a Secure Connection Using SSL" on page 664.

Message-Layer Security

In message-layer security, security information is contained within the SOAP message and/or SOAP message attachment, which allows security information to travel along with the message or attachment. For example, a portion of the message may be signed by a sender and encrypted

for a particular receiver. When sent from the initial sender, the message may pass through intermediate nodes before reaching its intended receiver. In this scenario, the encrypted portions continue to be opaque to any intermediate nodes and can be decrypted only by the intended receiver. For this reason, message-layer security is also sometimes referred to as end-to-end security.

The advantages of message-layer security include the following.

- Security stays with the message over all hops and after the message arrives at its destination.
- Security can be selectively applied to different portions of a message and, if using XML Web Services Security, to attachments.
- Message security can be used with intermediaries over multiple hops.
- Message security is independent of the application environment or transport protocol.

The disadvantage of using message-layer security is that it is relatively complex and adds some overhead to processing.

The GlassFish Server supports message security using Metro, a web services stack that uses Web Services Security (WSS) to secure messages. Because this message security is specific to Metro and is not a part of the Java EE platform, this tutorial does not discuss using WSS to secure messages. See the *Metro User's Guide* at `http://metro.java.net/guide/`.

Securing Containers

In Java EE, the component containers are responsible for providing application security. A container provides two types of security: declarative and programmatic.

Using Annotations to Specify Security Information

Annotations enable a declarative style of programming and so encompass both the declarative and programmatic security concepts. Users can specify information about security within a class file by using annotations. The GlassFish Server uses this information when the application is deployed. Not all security information can be specified by using annotations, however. Some information must be specified in the application deployment descriptors.

Specific annotations that can be used to specify security information within an enterprise bean class file are described in "Securing an Enterprise Bean Using Declarative Security" on page 704. Chapter 40, "Getting Started Securing Web Applications," describes how to use annotations to secure web applications where possible. Deployment descriptors are described only where necessary.

For more information on annotations, see "Further Information about Security" on page 669.

Using Deployment Descriptors for Declarative Security

Declarative security can express an application component's security requirements by using deployment descriptors. Because deployment descriptor information is declarative, it can be changed without the need to modify the source code. At runtime, the Java EE server reads the deployment descriptor and acts upon the corresponding application, module, or component accordingly. Deployment descriptors must provide certain structural information for each component if this information has not been provided in annotations or is not to be defaulted.

This part of the tutorial does not document how to create deployment descriptors; it describes only the elements of the deployment descriptor relevant to security. NetBeans IDE provides tools for creating and modifying deployment descriptors.

Different types of components use different formats, or schemas, for their deployment descriptors. The security elements of deployment descriptors discussed in this tutorial include the following.

- Web components may use a web application deployment descriptor named `web.xml`.

  The schema for web component deployment descriptors is provided in Chapter 14 of the Java Servlet 3.0 specification (JSR 315), which can be downloaded from `http://jcp.org/en/jsr/detail?id=315`.

- Enterprise JavaBeans components may use an EJB deployment descriptor named `META-INF/ejb-jar.xml`, contained in the EJB JAR file.

  The schema for enterprise bean deployment descriptors is provided in Chapter 19 of the EJB 3.1 specification (JSR 318), which can be downloaded from `http://jcp.org/en/jsr/detail?id=318`.

Using Programmatic Security

Programmatic security is embedded in an application and is used to make security decisions. Programmatic security is useful when declarative security alone is not sufficient to express the security model of an application. The API for programmatic security consists of methods of the `EJBContext` interface and the `HttpServletRequest` interface. These methods allow components to make business-logic decisions based on the security role of the caller or remote user.

Programmatic security is discussed in more detail in the following sections:

- "Using Programmatic Security with Web Applications" on page 684
- "Securing an Enterprise Bean Programmatically" on page 708

Securing the GlassFish Server

This tutorial describes deployment to the GlassFish Server, which provides highly secure, interoperable, and distributed component computing based on the Java EE security model. GlassFish Server supports the Java EE 6 security model. You can configure GlassFish Server for the following purposes:

- Adding, deleting, or modifying authorized users. For more information on this topic, see "Working with Realms, Users, Groups, and Roles" on page 656.
- Configuring secure HTTP and Internet Inter-Orb Protocol (IIOP) listeners.
- Configuring secure Java Management Extensions (JMX) connectors.
- Adding, deleting, or modifying existing or custom realms.
- Defining an interface for pluggable authorization providers using Java Authorization Contract for Containers (JACC). JACC defines security contracts between the GlassFish Server and authorization policy modules. These contracts specify how the authorization providers are installed, configured, and used in access decisions.
- Using pluggable audit modules.
- Customizing authentication mechanisms. All implementations of Java EE 6 compatible Servlet containers are required to support the Servlet Profile of JSR 196, which offers an avenue for customizing the authentication mechanism applied by the web container on behalf of one or more applications.
- Setting and changing policy permissions for an application.

Working with Realms, Users, Groups, and Roles

You often need to protect resources to ensure that only authorized users have access. See "Characteristics of Application Security" on page 650 for an introduction to the concepts of authentication, identification, and authorization.

This section discusses setting up users so that they can be correctly identified and either given access to protected resources or denied access if they are not authorized to access the protected resources. To authenticate a user, you need to follow these basic steps.

1. The application developer writes code to prompt for a user name and password. The various methods of authentication are discussed in "Specifying an Authentication Mechanism in the Deployment Descriptor" on page 682.
2. The application developer communicates how to set up security for the deployed application by use of a metadata annotation or deployment descriptor. This step is discussed in "Setting Up Security Roles" on page 662.
3. The server administrator sets up authorized users and groups on the GlassFish Server. This is discussed in "Managing Users and Groups on the GlassFish Server" on page 660.

4. The application deployer maps the application's security roles to users, groups, and principals defined on the GlassFish Server. This topic is discussed in "Mapping Roles to Users and Groups" on page 663.

What Are Realms, Users, Groups, and Roles?

A *realm* is a security policy domain defined for a web or application server. A realm contains a collection of users, who may or may not be assigned to a group. Managing users on the GlassFish Server is discussed in "Managing Users and Groups on the GlassFish Server" on page 660.

An application will often prompt for a user name and password before allowing access to a protected resource. After the user name and password have been entered, that information is passed to the server, which either authenticates the user and sends the protected resource or does not authenticate the user, in which case access to the protected resource is denied. This type of user authentication is discussed in "Specifying an Authentication Mechanism in the Deployment Descriptor" on page 682.

In some applications, authorized users are assigned to roles. In this situation, the role assigned to the user in the application must be mapped to a principal or group defined on the application server. Figure 39–6 shows this. More information on mapping roles to users and groups can be found in "Setting Up Security Roles" on page 662.

The following sections provide more information on realms, users, groups, and roles.

FIGURE 39–6 Mapping Roles to Users and Groups



What Is a Realm?

A realm is a security policy domain defined for a web or application server. The protected resources on a server can be partitioned into a set of protection spaces, each with its own authentication scheme and/or authorization database containing a collection of users and groups. For a web application, a realm is a complete database of users and groups identified as valid users of a web application or a set of web applications and controlled by the same authentication policy.

The Java EE server authentication service can govern users in multiple realms. The `file`, `admin-realm`, and `certificate` realms come preconfigured for the GlassFish Server.

In the `file` realm, the server stores user credentials locally in a file named `keyfile`. You can use the Administration Console to manage users in the `file` realm. When using the `file` realm, the server authentication service verifies user identity by checking the `file` realm. This realm is used for the authentication of all clients except for web browser clients that use HTTPS and certificates.

In the `certificate` realm, the server stores user credentials in a certificate database. When using the `certificate` realm, the server uses certificates with HTTPS to authenticate web clients. To verify the identity of a user in the `certificate` realm, the authentication service

verifies an X.509 certificate. For step-by-step instructions for creating this type of certificate, see "Working with Digital Certificates" on page 666. The common name field of the X.509 certificate is used as the principal name.

The `admin-realm` is also a `file` realm and stores administrator user credentials locally in a file named `admin-keyfile`. You can use the Administration Console to manage users in this realm in the same way you manage users in the `file` realm. For more information, see "Managing Users and Groups on the GlassFish Server" on page 660.

What Is a User?

A *user* is an individual or application program identity that has been defined in the GlassFish Server. In a web application, a user can have associated with that identify a set of roles that entitle the user to access all resources protected by those roles. Users can be associated with a group.

A Java EE user is similar to an operating system user. Typically, both types of users represent people. However, these two types of users are not the same. The Java EE server authentication service has no knowledge of the user name and password you provide when you log in to the operating system. The Java EE server authentication service is not connected to the security mechanism of the operating system. The two security services manage users that belong to different realms.

What Is a Group?

A *group* is a set of authenticated users, classified by common traits, defined in the GlassFish Server. A Java EE user of the `file` realm can belong to a group on the GlassFish Server. (A user in the `certificate` realm cannot.) A group on the GlassFish Server is a category of users classified by common traits, such as job title or customer profile. For example, most customers of an e-commerce application might belong to the `CUSTOMER` group, but the big spenders would belong to the `PREFERRED` group. Categorizing users into groups makes it easier to control the access of large numbers of users.

A group on the GlassFish Server has a different scope from a role. A group is designated for the entire GlassFish Server, whereas a role is associated only with a specific application in the GlassFish Server.

What Is a Role?

A *role* is an abstract name for the permission to access a particular set of resources in an application. A role can be compared to a key that can open a lock. Many people might have a copy of the key. The lock doesn't care who you are, only that you have the right key.

Some Other Terminology

The following terminology is also used to describe the security requirements of the Java EE platform:

- **Principal**: An entity that can be authenticated by an authentication protocol in a security service that is deployed in an enterprise. A principal is identified by using a principal name and authenticated by using authentication data.
- **Security policy domain**, also known as **security domain** or **realm**: A scope over which a common security policy is defined and enforced by the security administrator of the security service.
- **Security attributes**: A set of attributes associated with every principal. The security attributes have many uses: for example, access to protected resources and auditing of users. Security attributes can be associated with a principal by an authentication protocol.
- **Credential**: An object that contains or references security attributes used to authenticate a principal for Java EE services. A principal acquires a credential upon authentication or from another principal that allows its credential to be used.

Managing Users and Groups on the GlassFish Server

Follow these steps for managing users before you run the tutorial examples.

▼ To Add Users to the GlassFish Server

1. **Start the GlassFish Server, if you haven't already done so.**

   Information on starting the GlassFish Server is available in "Starting and Stopping the GlassFish Server" on page 71.

2. **Start the Administration Console, if you haven't already done so.**

   To start the Administration Console, open a web browser and specify the URL `http://localhost:4848/`. If you changed the default Admin port during installation, type the correct port number in place of `4848`.

3. **In the navigation tree, expand the Configurations node, then expand the server-config node.**

4. **Expand the Security node.**

5. **Expand the Realms node.**

6 **Select the realm to which you are adding users.**

- **Select the `file` realm to add users you want to access applications running in this realm.**

  For the example security applications, select the `file` realm.

  The Edit Realm page opens.

- **Select the `admin-realm` to add users you want to enable as system administrators of the GlassFish Server.**

  The Edit Realm page opens.

You cannot add users to the `certificate` realm by using the Administration Console. In the `certificate` realm, you can add only certificates. For information on adding (importing) certificates to the `certificate` realm, see "Adding Users to the Certificate Realm" on page 661.

7 **On the Edit Realm page, click the Manage Users button.**

The File Users or Admin Users page opens.

8 **On the File Users or Admin Users page, click New to add a new user to the realm.**

The New File Realm User page opens.

9 **Type values in the User ID, Group List, New Password, and Confirm New Password fields.**

For the Admin Realm, the Group List field is read-only, and the group name is `asadmin`. Restart the GlassFish Server and Administration Console after you add a user to the Admin Realm.

For more information on these properties, see "Working with Realms, Users, Groups, and Roles" on page 656.

For the example security applications, specify a user with any name and password you like, but make sure that the user is assigned to the group `TutorialUser`. The user name and password are case-sensitive. Keep a record of the user name and password for working with the examples later in this tutorial.

10 **Click OK to add this user to the realm, or click Cancel to quit without saving.**

Adding Users to the Certificate Realm

In the `certificate` realm, user identity is set up in the GlassFish Server security context and populated with user data obtained from cryptographically verified client certificates. For step-by-step instructions for creating this type of certificate, see "Working with Digital Certificates" on page 666.

Setting Up Security Roles

When you design an enterprise bean or web component, you should always think about the kinds of users who will access the component. For example, a web application for a human resources department might have a different request URL for someone who has been assigned the role of `DEPT_ADMIN` than for someone who has been assigned the role of `DIRECTOR`. The `DEPT_ADMIN` role may let you view employee data, but the `DIRECTOR` role enables you to modify employee data, including salary data. Each of these security roles is an abstract logical grouping of users that is defined by the person who assembles the application. When an application is deployed, the deployer will map the roles to security identities in the operational environment, as shown in Figure 39–6.

For Java EE components, you define security roles using the `@DeclareRoles` and `@RolesAllowed` metadata annotations.

The following is an example of an application in which the role of `DEPT-ADMIN` is authorized for methods that review employee payroll data, and the role of `DIRECTOR` is authorized for methods that change employee payroll data.

The enterprise bean would be annotated as shown in the following code:

```
import javax.annotation.security.DeclareRoles;
import javax.annotation.security.RolesAllowed;
...
@DeclareRoles({"DEPT-ADMIN", "DIRECTOR"})
@Stateless public class PayrollBean implements Payroll {
    @Resource SessionContext ctx;


    @RolesAllowed("DEPT-ADMIN")
    public void reviewEmployeeInfo(EmplInfo info) {

        oldInfo = ... read from database;

        // ...
    }

    @RolesAllowed("DIRECTOR")
    public void updateEmployeeInfo(EmplInfo info) {

        newInfo = ... update database;

        // ...
    }
    ...
 }
```

For a servlet, you can use the `@HttpConstraint` annotation within the `@ServletSecurity` annotation to specify the roles that are allowed to access the servlet. For example, a servlet might be annotated as follows:

```
@WebServlet(name = "PayrollServlet", urlPatterns = {"/payroll"})
@ServletSecurity(
@HttpConstraint(transportGuarantee = TransportGuarantee.CONFIDENTIAL,
    rolesAllowed = {"DEPT-ADMIN", "DIRECTOR"}))
public class GreetingServlet extends HttpServlet {
```

These annotations are discussed in more detail in "Specifying Security for Basic Authentication Using Annotations" on page 691 and "Securing an Enterprise Bean Using Declarative Security" on page 704.

After users have provided their login information and the application has declared what roles are authorized to access protected parts of an application, the next step is to map the security role to the name of a user, or principal.

Mapping Roles to Users and Groups

When you are developing a Java EE application, you don't need to know what categories of users have been defined for the realm in which the application will be run. In the Java EE platform, the security architecture provides a mechanism for mapping the roles defined in the application to the users or groups defined in the runtime realm.

The role names used in the application are often the same as the group names defined on the GlassFish Server. Under these circumstances, you can enable a default principal-to-role mapping on the GlassFish Server by using the Administration Console. The task "To Set Up Your System for Running the Security Examples" on page 689 explains how to do this. All the tutorial security examples use default principal-to-role mapping.

If the role names used in an application are not the same as the group names defined on the server, use the runtime deployment descriptor to specify the mapping. The following example demonstrates how to do this mapping in the `glassfish-web.xml` file, which is the file used for web applications:

```
<glassfish-web-app>
    ...
    <security-role-mapping>
        <role-name>Mascot</role-name>
        <principal-name>Duke</principal-name>
    </security-role-mapping>

    <security-role-mapping>
        <role-name>Admin</role-name>
        <group-name>Director</group-name>
    </security-role-mapping>
    ...
</glassfish-web-app>
```

A role can be mapped to specific principals, specific groups, or both. The principal or group names must be valid principals or groups in the current default realm or in the realm specified in the `login-config` element. In this example, the role of `Mascot` used in the application is

mapped to a principal, named `Duke`, that exists on the application server. Mapping a role to a specific principal is useful when the person occupying that role may change. For this application, you would need to modify only the runtime deployment descriptor rather than search and replace throughout the application for references to this principal.

Also in this example, the role of `Admin` is mapped to a group of users assigned the group name of `Director`. This is useful because the group of people authorized to access director-level administrative data has to be maintained only on the GlassFish Server. The application developer does not need to know who these people are, but only needs to define the group of people who will be given access to the information.

The `role-name` must match the `role-name` in the `security-role` element of the corresponding deployment descriptor or the role name defined in a `@DeclareRoles` annotation.

Establishing a Secure Connection Using SSL

Secure Socket Layer (SSL) technology is security that is implemented at the transport layer (see "Transport-Layer Security" on page 653 for more information about transport-layer security). SSL allows web browsers and web servers to communicate over a secure connection. In this secure connection, the data is encrypted before being sent and then is decrypted upon receipt and before processing. Both the browser and the server encrypt all traffic before sending any data.

SSL addresses the following important security considerations:

- **Authentication**: During your initial attempt to communicate with a web server over a secure connection, that server will present your web browser with a set of credentials in the form of a server certificate. The purpose of the certificate is to verify that the site is who and what it claims to be. In some cases, the server may request a certificate proving that the client is who and what it claims to be; this mechanism is known as client authentication.
- **Confidentiality**: When data is being passed between the client and the server on a network, third parties can view and intercept this data. SSL responses are encrypted so that the data cannot be deciphered by the third party and the data remains confidential.
- **Integrity**: When data is being passed between the client and the server on a network, third parties can view and intercept this data. SSL helps guarantee that the data will not be modified in transit by that third party.

The SSL protocol is designed to be as efficient as securely possible. However, encryption and decryption are computationally expensive processes from a performance standpoint. It is not strictly necessary to run an entire web application over SSL, and it is customary for a developer to decide which pages require a secure connection and which do not. Pages that might require a secure connection include those for login, personal information, shopping cart checkouts, or credit card information transmittal. Any page within an application can be requested over a secure socket by simply prefixing the address with `https:` instead of `http:`. Any pages that

absolutely require a secure connection should check the protocol type associated with the page request and take the appropriate action if `https:` is not specified.

Using name-based virtual hosts on a secured connection can be problematic. This is a design limitation of the SSL protocol itself. The *SSL handshake*, whereby the client browser accepts the server certificate, must occur before the HTTP request is accessed. As a result, the request information containing the virtual host name cannot be determined before authentication, and it is therefore not possible to assign multiple certificates to a single IP address. If all virtual hosts on a single IP address need to authenticate against the same certificate, the addition of multiple virtual hosts should not interfere with normal SSL operations on the server. Be aware, however, that most client browsers will compare the server's domain name against the domain name listed in the certificate, if any; this is applicable primarily to official certificates signed by a certificate authority (CA). If the domain names do not match, these browsers will display a warning to the client. In general, only address-based virtual hosts are commonly used with SSL in a production environment.

Verifying and Configuring SSL Support

As a general rule, you must address the following issues to enable SSL for a server:

- There must be a `Connector` element for an SSL connector in the server deployment descriptor.
- There must be valid keystore and certificate files.
- The location of the keystore file and its password must be specified in the server deployment descriptor.

An SSL HTTPS connector is already enabled in the GlassFish Server.

For testing purposes and to verify that SSL support has been correctly installed, load the default introduction page with a URL that connects to the port defined in the server deployment descriptor:

```
https://localhost:8181/
```

The `https` in this URL indicates that the browser should be using the SSL protocol. The `localhost` in this example assumes that you are running the example on your local machine as part of the development process. The `8181` in this example is the secure port that was specified where the SSL connector was created. If you are using a different server or port, modify this value accordingly.

The first time that you load this application, the New Site Certificate or Security Alert dialog box appears. Select Next to move through the series of dialog boxes, and select Finish when you reach the last dialog box. The certificates will display only the first time. When you accept the certificates, subsequent hits to this site assume that you still trust the content.

Working with Digital Certificates

Digital certificates for the GlassFish Server have already been generated and can be found in the directory *as-install*`/`*domain-dir*`/config/`. These digital certificates are self-signed and are intended for use in a development environment; they are not intended for production purposes. For production purposes, generate your own certificates and have them signed by a CA.

To use SSL, an application or web server must have an associated certificate for each external interface, or IP address, that accepts secure connections. The theory behind this design is that a server should provide some kind of reasonable assurance that its owner is who you think it is, particularly before receiving any sensitive information. It may be useful to think of a certificate as a "digital driver's license" for an Internet address. The certificate states with which company the site is associated, along with some basic contact information about the site owner or administrator.

The digital certificate is cryptographically signed by its owner and is difficult for anyone else to forge. For sites involved in e-commerce or in any other business transaction in which authentication of identity is important, a certificate can be purchased from a well-known CA such as VeriSign or Thawte. If your server certificate is self-signed, you must install it in the GlassFish Server keystore file (`keystore.jks`). If your client certificate is self-signed, you should install it in the GlassFish Server truststore file (`cacerts.jks`).

Sometimes, authentication is not really a concern. For example, an administrator might simply want to ensure that data being transmitted and received by the server is private and cannot be snooped by anyone eavesdropping on the connection. In such cases, you can save the time and expense involved in obtaining a CA certificate and simply use a self-signed certificate.

SSL uses *public-key cryptography*, which is based on *key pairs*. Key pairs contain one public key and one private key. Data encrypted with one key can be decrypted only with the other key of the pair. This property is fundamental to establishing trust and privacy in transactions. For example, using SSL, the server computes a value and encrypts it by using its private key. The encrypted value is called a *digital signature*. The client decrypts the encrypted value by using the server's public key and compares the value to its own computed value. If the two values match, the client can trust that the signature is authentic, because only the private key could have been used to produce such a signature.

Digital certificates are used with HTTPS to authenticate web clients. The HTTPS service of most web servers will not run unless a digital certificate has been installed. Use the procedure outlined in the next section, "Creating a Server Certificate" on page 667, to set up a digital certificate that can be used by your application or web server to enable SSL.

One tool that can be used to set up a digital certificate is `keytool`, a key and certificate management utility that ships with the JDK. This tool enables users to administer their own public/private key pairs and associated certificates for use in self-authentication, whereby the user authenticates himself or herself to other users or services, or data integrity and authentication services, using digital signatures. The tool also allows users to cache the public

keys, in the form of certificates, of their communicating peers. For a better understanding of `keytool` and public-key cryptography, see the `keytool` documentation at `http://download.oracle.com/javase/6/docs/technotes/tools/solaris/keytool.html`.

Creating a Server Certificate

A server certificate has already been created for the GlassFish Server and can be found in the *domain-dir*`/config/` directory. The server certificate is in `keystore.jks`. The `cacerts.jks` file contains all the trusted certificates, including client certificates.

If necessary, you can use `keytool` to generate certificates. The `keytool` utility stores the keys and certificates in a file termed a *keystore*, a repository of certificates used for identifying a client or a server. Typically, a keystore is a file that contains one client's or one server's identity. The keystore protects private keys by using a password.

If you don't specify a directory when specifying the keystore file name, the keystores are created in the directory from which the `keytool` command is run. This can be the directory where the application resides, or it can be a directory common to many applications.

The general steps for creating a server certificate are as follows.

1. Create the keystore.
2. Export the certificate from the keystore.
3. Sign the certificate.
4. Import the certificate into a *truststore:* a repository of certificates used for verifying the certificates. A truststore typically contains more than one certificate.

"To Use `keytool` to Create a Server Certificate" on page 667 provides specific information on using the `keytool` utility to perform these steps.

▼ To Use `keytool` to Create a Server Certificate

Run `keytool` to generate a new key pair in the default development keystore file, `keystore.jks`. This example uses the alias `server-alias` to generate a new public/private key pair and wrap the public key into a self-signed certificate inside `keystore.jks`. The key pair is generated by using an algorithm of type RSA, with a default password of `changeit`. For more information and other examples of creating and managing keystore files, read the `keytool` online help at `http://download.oracle.com/javase/6/docs/technotes/tools/solaris/keytool.html`.

Note – RSA is public-key encryption technology developed by RSA Data Security, Inc.

From the directory in which you want to create the key pair, run `keytool` as shown in the following steps.

1. **Generate the server certificate.**

   Type the `keytool` command all on one line:

   java-home`/bin/keytool -genkey -alias server-alias -keyalg RSA -keypass changeit -storepass changeit -keystore keystore.jks`

   When you press Enter, `keytool` prompts you to enter the server name, organizational unit, organization, locality, state, and country code.

   You must type the server name in response to `keytool`'s first prompt, in which it asks for first and last names. For testing purposes, this can be `localhost`.

   When you run the example applications, the host (server name) specified in the keystore must match the host identified in the `javaee.server.name` property specified in the file *tut-install*`/examples/bp-project/build.properties` (by default, this is `localhost`).

2. **Export the generated server certificate in `keystore.jks` into the file `server.cer`.**

   Type the `keytool` command all on one line:

   java-home`/bin/keytool -export -alias server-alias -storepass changeit -file server.cer -keystore keystore.jks`

3. **If you want to have the certificate signed by a CA, read the example at `http://download.oracle.com/javase/6/docs/technotes/tools/solaris/keytool.html`.**

4. **To add the server certificate to the truststore file, `cacerts.jks`, run `keytool` from the directory where you created the keystore and server certificate.**

   Use the following parameters:

   java-home`/bin/keytool -import -v -trustcacerts -alias server-alias -file server.cer -keystore cacerts.jks -keypass changeit -storepass changeit`

   Information on the certificate, such as that shown next, will appear:

   ```
   Owner: CN=localhost, OU=Sun Micro, O=Docs, L=Santa Clara, ST=CA,
   C=USIssuer: CN=localhost, OU=Sun Micro, O=Docs, L=Santa Clara, ST=CA,
   C=USSerial number: 3e932169Valid from: Tue Apr 08Certificate
   fingerprints:MD5: 52:9F:49:68:ED:78:6F:39:87:F3:98:B3:6A:6B:0F:90 SHA1:
   EE:2E:2A:A6:9E:03:9A:3A:1C:17:4A:28:5E:97:20:78:3F:
   Trust this certificate? [no]:
   ```

5. **Type `yes`, then press the `Enter` or `Return` key.**

   The following information appears:

   ```
   Certificate was added to keystore[Saving cacerts.jks]
   ```

Further Information about Security

For more information about security in Java EE applications, see

- Java EE 6 specification:

  `http://jcp.org/en/jsr/detail?id=316`
- Enterprise JavaBeans 3.1 specification:

  `http://jcp.org/en/jsr/detail?id=318`
- Implementing Enterprise Web Services 1.3 specification:

  `http://jcp.org/en/jsr/detail?id=109`
- Java SE security information:

  `http://download.oracle.com/javase/6/docs/technotes/guides/security/`
- Java Servlet 3.0 specification:

  `http://jcp.org/en/jsr/detail?id=315`
- Java Authorization Contract for Containers 1.3 specification:

  `http://jcp.org/en/jsr/detail?id=115`
- *Java Authentication and Authorization Service (JAAS) Reference Guide:*

  `http://download.oracle.com/javase/6/docs/technotes/guides/security/jaas/JAASRefGuide.html`
- *Java Authentication and Authorization Service (JAAS): LoginModule Developer's Guide:*

  `http://download.oracle.com/javase/6/docs/technotes/guides/security/jaas/JAASLMDevGuide.html`

◆ ◆ ◆ CHAPTER 40

Getting Started Securing Web Applications

A web application is accessed using a web browser over a network, such as the Internet or a company's intranet. As discussed in "Distributed Multitiered Applications" on page 37, the Java EE platform uses a distributed multitiered application model, and web applications run in the web tier.

Web applications contain resources that can be accessed by many users. These resources often traverse unprotected, open networks, such as the Internet. In such an environment, a substantial number of web applications will require some type of security. The ways to implement security for Java EE web applications are discussed in a general way in "Securing Containers" on page 654. This chapter provides more detail and a few examples that explore these security services as they relate to web components.

Securing applications and their clients in the business tier and the EIS tier is discussed in Chapter 41, "Getting Started Securing Enterprise Applications."

The following topics are addressed here:

Overview of Web Application Security

In the Java EE platform, web components provide the dynamic extension capabilities for a web server. Web components can be Java servlets or JavaServer Faces pages. The interaction between a web client and a web application is illustrated in Figure 40–1.

FIGURE 40–1 Java Web Application Request Handling



Certain aspects of web application security can be configured when the application is installed, or deployed, to the web container. Annotations and/or deployment descriptors are used to relay information to the deployer about security and other aspects of the application. Specifying this information in annotations or in the deployment descriptor helps the deployer set up the appropriate security policy for the web application. Any values explicitly specified in the deployment descriptor override any values specified in annotations.

Security for Java EE web applications can be implemented in the following ways.

- **Declarative security**: Can be implemented using either metadata annotations or an application's deployment descriptor. See "Overview of Java EE Security" on page 646 for more information.

  Declarative security for web applications is described in "Securing Web Applications" on page 673.

- **Programmatic security**: Is embedded in an application and can be used to make security decisions when declarative security alone is not sufficient to express the security model of an application. Declarative security alone may not be sufficient when conditional login in a particular work flow, instead of for all cases, is required in the middle of an application. See "Overview of Java EE Security" on page 646 for more information.

  Servlet 3.0 provides the `authenticate`, `login`, and `logout` methods of the `HttpServletRequest` interface. With the addition of the `authenticate`, `login`, and `logout` methods to the Servlet specification, an application deployment descriptor is no longer required for web applications but may still be used to further specify security requirements beyond the basic default values.

Programmatic security is discussed in "Using Programmatic Security with Web Applications" on page 684

- **Message Security**: Works with web services and incorporates security features, such as digital signatures and encryption, into the header of a SOAP message, working in the application layer, ensuring end-to-end security. Message security is not a component of Java EE 6 and is mentioned here for informational purposes only.

Some of the material in this chapter builds on material presented earlier in this tutorial. In particular, this chapter assumes that you are familiar with the information in the following chapters:

- Chapter 3, "Getting Started with Web Applications"
- Chapter 4, "JavaServer Faces Technology"
- Chapter 15, "Java Servlet Technology"
- Chapter 39, "Introduction to Security in the Java EE Platform"

Securing Web Applications

Web applications are created by application developers who give, sell, or otherwise transfer the application to an application deployer for installation into a runtime environment. Application developers communicate how to set up security for the deployed application by using annotations or deployment descriptors. This information is passed on to the deployer, who uses it to define method permissions for security roles, set up user authentication, and set up the appropriate transport mechanism. If the application developer doesn't define security requirements, the deployer will have to determine the security requirements independently.

Some elements necessary for security in a web application cannot be specified as annotations for all types of web applications. This chapter explains how to secure web applications using annotations wherever possible. It explains how to use deployment descriptors where annotations cannot be used.

Specifying Security Constraints

A *security constraint* is used to define the access privileges to a collection of resources using their URL mapping.

If your web application uses a servlet, you can express the security constraint information by using annotations. Specifically, you use the `@HttpConstraint` and, optionally, the `@HttpMethodConstraint` annotations within the `@ServletSecurity` annotation to specify a security constraint.

If your web application does not use a servlet, however, you must specify a `security-constraint` element in the deployment descriptor file. The authentication mechanism cannot be expressed using annotations, so if you use any authentication method other than `BASIC` (the default), a deployment descriptor is required.

The following subelements can be part of a `security-constraint`:

- **Web resource collection** (`web-resource-collection`): A list of URL patterns (the part of a URL *after* the host name and port you want to constrain) and HTTP operations (the methods within the files that match the URL pattern you want to constrain) that describe a set of resources to be protected. Web resource collections are discussed in "Specifying a Web Resource Collection" on page 674.
- **Authorization constraint** (`auth-constraint`): Specifies whether authentication is to be used and names the roles authorized to perform the constrained requests. For more information about authorization constraints, see "Specifying an Authorization Constraint" on page 675.
- **User data constraint** (`user-data-constraint`): Specifies how data is protected when transported between a client and a server. User data constraints are discussed in "Specifying a Secure Connection" on page 675.

Specifying a Web Resource Collection

A web resource collection consists of the following subelements:

- `web-resource-name` is the name you use for this resource. Its use is optional.
- `url-pattern` is used to list the request URI to be protected. Many applications have both unprotected and protected resources. To provide unrestricted access to a resource, do not configure a security constraint for that particular request URI.

  The request URI is the part of a URL *after* the host name and port. For example, let's say that you have an e-commerce site with a catalog that you would want anyone to be able to access and browse, and a shopping cart area for customers only. You could set up the paths for your web application so that the pattern `/cart/*` is protected but nothing else is protected. Assuming that the application is installed at context path `/myapp`, the following are true:

  - `http://localhost:8080/myapp/index.xhtml` is *not* protected.
  - `http://localhost:8080/myapp/cart/index.xhtml` *is* protected.

  A user will be prompted to log in the first time he or she accesses a resource in the `cart/` subdirectory.
- `http-method` or `http-method-omission` is used to specify which methods should be protected or which methods should be omitted from protection. An HTTP method is protected by a `web-resource-collection` under any of the following circumstances:
  - If no HTTP methods are named in the collection (which means that all are protected)
  - If the collection specifically names the HTTP method in an `http-method` subelement
  - If the collection contains one or more `http-method-omission` elements, none of which names the HTTP method

Specifying an Authorization Constraint

An authorization constraint (`auth-constraint`) contains the `role-name` element. You can use as many `role-name` elements as needed here.

An authorization constraint establishes a requirement for authentication and names the roles authorized to access the URL patterns and HTTP methods declared by this security constraint. If there is no authorization constraint, the container must accept the request without requiring user authentication. If there is an authorization constraint but no roles are specified within it, the container will not allow access to constrained requests under any circumstances. Each role name specified here must either correspond to the role name of one of the `security-role` elements defined for this web application or be the specially reserved role name *, which indicates all roles in the web application. Role names are case sensitive. The roles defined for the application must be mapped to users and groups defined on the server, except when default principal-to-role mapping is used.

For more information about security roles, see "Declaring Security Roles" on page 683. For information on mapping security roles, see "Mapping Roles to Users and Groups" on page 663.

For a servlet, the `@HttpConstraint` and `@HttpMethodConstraint` annotations accept a `rolesAllowed` element that specifies the authorized roles.

Specifying a Secure Connection

A user data constraint (`user-data-constraint` in the deployment descriptor) contains the `transport-guarantee` subelement. A user data constraint can be used to require that a protected transport-layer connection, such as HTTPS, be used for all constrained URL patterns and HTTP methods specified in the security constraint. The choices for transport guarantee are `CONFIDENTIAL`, `INTEGRAL`, or `NONE`. If you specify `CONFIDENTIAL` or `INTEGRAL` as a security constraint, it generally means that the use of SSL is required and applies to all requests that match the URL patterns in the web resource collection, not just to the login dialog box.

The strength of the required protection is defined by the value of the transport guarantee.

- Specify `CONFIDENTIAL` when the application requires that data be transmitted so as to prevent other entities from observing the contents of the transmission.
- Specify `INTEGRAL` when the application requires that the data be sent between client and server in such a way that it cannot be changed in transit.
- Specify `NONE` to indicate that the container must accept the constrained requests on any connection, including an unprotected one.

Note – In practice, Java EE servers treat the `CONFIDENTIAL` and `INTEGRAL` transport guarantee values identically.

The user data constraint is handy to use in conjunction with basic and form-based user authentication. When the login authentication method is set to `BASIC` or `FORM`, passwords are not protected, meaning that passwords sent between a client and a server on an unprotected session can be viewed and intercepted by third parties. Using a user data constraint with the user authentication mechanism can alleviate this concern. Configuring a user authentication mechanism is described in "Specifying an Authentication Mechanism in the Deployment Descriptor" on page 682.

To guarantee that data is transported over a secure connection, ensure that SSL support is configured for your server. SSL support is already configured for the GlassFish Server.

Note – After you switch to SSL for a session, you should never accept any non-SSL requests for the rest of that session. For example, a shopping site might not use SSL until the checkout page, and then it might switch to using SSL to accept your card number. After switching to SSL, you should stop listening to non-SSL requests for this session. The reason for this practice is that the session ID itself was not encrypted on the earlier communications. This is not so bad when you're only doing your shopping, but after the credit card information is stored in the session, you don't want anyone to use that information to fake the purchase transaction against your credit card. This practice could be easily implemented by using a filter.

Specifying Separate Security Constraints for Various Resources

You can create a separate security constraint for various resources within your application. For example, you could allow users with the role of `PARTNER` access to the `GET` and `POST` methods of all resources with the URL pattern `/acme/wholesale/*` and allow users with the role of `CLIENT` access to the `GET` and `POST` methods of all resources with the URL pattern `/acme/retail/*`. An example of a deployment descriptor that would demonstrate this functionality is the following:

```
<!-- SECURITY CONSTRAINT #1 -->
<security-constraint>
    <web-resource-collection>
        <web-resource-name>wholesale</web-resource-name>
        <url-pattern>/acme/wholesale/*</url-pattern>
        <http-method>GET</http-method>
        <http-method>POST</http-method>
    </web-resource-collection>
    <auth-constraint>
        <role-name>PARTNER</role-name>
    </auth-constraint>
    <user-data-constraint>
        <transport-guarantee>CONFIDENTIAL</transport-guarantee>
    </user-data-constraint>
</security-constraint>

<!-- SECURITY CONSTRAINT #2 -->
<security-constraint>
    <web-resource-collection>
        <web-resource-name>retail</web-resource-name>
        <url-pattern>/acme/retail/*</url-pattern>
```

```
        <http-method>GET</http-method>
        <http-method>POST</http-method>
    </web-resource-collection>
    <auth-constraint>
        <role-name>CLIENT</role-name>
    </auth-constraint>
    <user-data-constraint>
        <transport-guarantee>CONFIDENTIAL</transport-guarantee>
    </user-data-constraint>
</security-constraint>
```

When the same `url-pattern` and `http-method` occur in multiple security constraints, the constraints on the pattern and method are defined by combining the individual constraints, which could result in unintentional denial of access.

Specifying Authentication Mechanisms

A user authentication mechanism specifies

- The way a user gains access to web content
- With basic authentication, the realm in which the user will be authenticated
- With form-based authentication, additional attributes

When an authentication mechanism is specified, the user must be authenticated before access is granted to any resource that is constrained by a security constraint. There can be multiple security constraints applying to multiple resources, but the same authentication method will apply to all constrained resources in an application.

Before you can authenticate a user, you must have a database of user names, passwords, and roles configured on your web or application server. For information on setting up the user database, see "Managing Users and Groups on the GlassFish Server" on page 660.

HTTP basic authentication and form-based authentication are not very secure authentication mechanisms. Basic authentication sends user names and passwords over the Internet as Base64-encoded text; form-based authentication sends this data as plain text. In both cases, the target server is not authenticated. Therefore, these forms of authentication leave user data exposed and vulnerable. If someone can intercept the transmission, the user name and password information can easily be decoded. However, when a secure transport mechanism, such as SSL, or security at the network level, such as the Internet Protocol Security (IPsec) protocol or virtual private network (VPN) strategies, is used in conjunction with basic or form-based authentication, some of these concerns can be alleviated. To specify a secure transport mechanism, use the elements described in "Specifying a Secure Connection" on page 675.

HTTP Basic Authentication

Specifying *HTTP basic authentication* requires that the server request a user name and password from the web client and verify that the user name and password are valid by comparing them against a database of authorized users in the specified or default realm.

Basic authentication is the default when you do not specify an authentication mechanism.

When basic authentication is used, the following actions occur:

1. A client requests access to a protected resource.
2. The web server returns a dialog box that requests the user name and password.
3. The client submits the user name and password to the server.
4. The server authenticates the user in the specified realm and, if successful, returns the requested resource.

Figure 40–2 shows what happens when you specify HTTP basic authentication.

FIGURE 40–2 HTTP Basic Authentication



Form-Based Authentication

Form-based authentication allows the developer to control the look and feel of the login authentication screens by customizing the login screen and error pages that an HTTP browser presents to the end user. When form-based authentication is declared, the following actions occur.

1. A client requests access to a protected resource.
2. If the client is unauthenticated, the server redirects the client to a login page.
3. The client submits the login form to the server.
4. The server attempts to authenticate the user.
   a. If authentication succeeds, the authenticated user's principal is checked to ensure that it is in a role that is authorized to access the resource. If the user is authorized, the server redirects the client to the resource by using the stored URL path.

b. If authentication fails, the client is forwarded or redirected to an error page.

Figure 40–3 shows what happens when you specify form-based authentication.

FIGURE 40–3 Form-Based Authentication



The section "Example: Form-Based Authentication with a JavaServer Faces Application" on page 694 is an example application that uses form-based authentication.

When you create a form-based login, be sure to maintain sessions using cookies or SSL session information.

For authentication to proceed appropriately, the action of the login form must always be `j_security_check`. This restriction is made so that the login form will work no matter which resource it is for and to avoid requiring the server to specify the action field of the outbound form. The following code snippet shows how the form should be coded into the HTML page:

```
<form method="POST" action="j_security_check">
<input type="text" name="j_username">
<input type="password" name="j_password">
</form>
```

Digest Authentication

Like basic authentication, *digest authentication* authenticates a user based on a user name and a password. However, unlike basic authentication, digest authentication does not send user passwords over the network. Instead, the client sends a one-way cryptographic hash of the password and additional data. Although passwords are not sent on the wire, digest authentication requires that clear-text password equivalents be available to the authenticating container so that it can validate received authenticators by calculating the expected digest.

Client Authentication

With *client authentication*, the web server authenticates the client by using the client's public key certificate. Client authentication is a more secure method of authentication than either basic or form-based authentication. It uses HTTP over SSL (HTTPS), in which the server authenticates the client using the client's public key certificate. SSL technology provides data encryption, server authentication, message integrity, and optional client authentication for a TCP/IP connection. You can think of a public key certificate as the digital equivalent of a passport. The certificate is issued by a trusted organization, a certificate authority (CA), and provides identification for the bearer.

Before using client authentication, make sure the client has a valid public key certificate. For more information on creating and using public key certificates, read "Working with Digital Certificates" on page 666.

Mutual Authentication

With *mutual authentication*, the server and the client authenticate each other. Mutual authentication is of two types:

- Certificate-based (see Figure 40–4)
- User name/password-based (see Figure 40–5)

When using certificate-based mutual authentication, the following actions occur.

1. A client requests access to a protected resource.
2. The web server presents its certificate to the client.
3. The client verifies the server's certificate.
4. If successful, the client sends its certificate to the server.
5. The server verifies the client's credentials.
6. If successful, the server grants access to the protected resource requested by the client.

Figure 40–4 shows what occurs during certificate-based mutual authentication.

FIGURE 40–4 Certificate-Based Mutual Authentication



In user name/password-based mutual authentication, the following actions occur.

1. A client requests access to a protected resource.
2. The web server presents its certificate to the client.
3. The client verifies the server's certificate.
4. If successful, the client sends its user name and password to the server, which verifies the client's credentials.
5. If the verification is successful, the server grants access to the protected resource requested by the client.

Figure 40–5 shows what occurs during user name/password-based mutual authentication.

FIGURE 40–5 User Name/Password-Based Mutual Authentication



Specifying an Authentication Mechanism in the Deployment Descriptor

To specify an authentication mechanism, use the `login-config` element. It can contain the following subelements.

- The `auth-method` subelement configures the authentication mechanism for the web application. The element content must be either `NONE`, `BASIC`, `DIGEST`, `FORM`, or `CLIENT-CERT`.
- The `realm-name` subelement indicates the realm name to use when the basic authentication scheme is chosen for the web application.
- The `form-login-config` subelement specifies the login and error pages that should be used when form-based login is specified.

Note – Another way to specify form-based authentication is to use the `authenticate`, `login`, and `logout` methods of `HttpServletRequest`, as discussed in "Authenticating Users Programmatically" on page 684.

When you try to access a web resource that is constrained by a `security-constraint` element, the web container activates the authentication mechanism that has been configured for that resource. The authentication mechanism specifies how the user will be prompted to log in. If the `login-config` element is present and the `auth-method` element contains a value other than

NONE, the user must be authenticated to access the resource. If you do not specify an authentication mechanism, authentication of the user is not required.

The following example shows how to declare form-based authentication in your deployment descriptor:

```
<login-config>
    <auth-method>FORM</auth-method>
    <realm-name>file</realm-name>
    <form-login-config>
        <form-login-page>/login.xhtml</form-login-page>
        <form-error-page>/error.xhtml</form-error-page>
    </form-login-config>
</login-config>
```

The login and error page locations are specified relative to the location of the deployment descriptor. Examples of login and error pages are shown in "Creating the Login Form and the Error Page" on page 694.

The following example shows how to declare digest authentication in your deployment descriptor:

```
<login-config>
    <auth-method>DIGEST</auth-method>
</login-config>
```

The following example shows how to declare client authentication in your deployment descriptor:

```
<login-config>
    <auth-method>CLIENT-CERT</auth-method>
</login-config>
```

Declaring Security Roles

You can declare security role names used in web applications by using the `security-role` element of the deployment descriptor. Use this element to list all the security roles that you have referenced in your application.

The following snippet of a deployment descriptor declares the roles that will be used in an application using the `security-role` element and specifies which of these roles is authorized to access protected resources using the `auth-constraint` element:

```
<security-constraint>
    <web-resource-collection>
        <web-resource-name>Protected Area</web-resource-name>
        <url-pattern>/security/protected/*</url-pattern>
        <http-method>PUT</http-method>
        <http-method>DELETE</http-method>
```

```
        <http-method>GET</http-method>
        <http-method>POST</http-method>
    </web-resource-collection>
    <auth-constraint>
        <role-name>manager</role-name>
    </auth-constraint>
</security-constraint>

 <!-- Security roles used by this web application -->
<security-role>
    <role-name>manager</role-name>
</security-role>
<security-role>
    <role-name>employee</role-name>
</security-role>
```

In this example, the `security-role` element lists all the security roles used in the application: `manager` and `employee`. This enables the deployer to map all the roles defined in the application to users and groups defined on the GlassFish Server.

The `auth-constraint` element specifies the role, `manager`, that can access the HTTP methods `PUT`, `DELETE`, `GET`, `POST` located in the directory specified by the `url-pattern` element (`/jsp/security/protected/*`).

The `@ServletSecurity` annotation cannot be used in this situation because its constraints apply to all URL patterns specified by the `@WebServlet` annotation.

Using Programmatic Security with Web Applications

Programmatic security is used by security-aware applications when declarative security alone is not sufficient to express the security model of the application.

Authenticating Users Programmatically

Servlet 3.0 specifies the following methods of the `HttpServletRequest` interface that enable you to authenticate users for a web application programmatically:

- `authenticate`, which allows an application to instigate authentication of the request caller by the container from within an unconstrained request context. A login dialog box displays and collects the user name and password for authentication purposes.
- `login`, which allows an application to collect username and password information as an alternative to specifying form-based authentication in an application deployment descriptor.
- `logout`, which allows an application to reset the caller identity of a request.

The following example code shows how to use the `login` and `logout` methods:

```
package test;

import java.io.IOException;
import java.io.PrintWriter;
import java.math.BigDecimal;
import javax.ejb.EJB;
import javax.servlet.ServletException;
import javax.servlet.annotation.WebServlet;
import javax.servlet.http.HttpServlet;
import javax.servlet.http.HttpServletRequest;
import javax.servlet.http.HttpServletResponse;

@WebServlet(name="TutorialServlet", urlPatterns={"/TutorialServlet"})
public class TutorialServlet extends HttpServlet {
    @EJB
    private ConverterBean converterBean;

    /**
     * Processes requests for both HTTP <code>GET</code>
     *    and <code>POST</code> methods.
     * @param request servlet request
     * @param response servlet response
     * @throws ServletException if a servlet-specific error occurs
     * @throws IOException if an I/O error occurs
     */
    protected void processRequest(HttpServletRequest request,
            HttpServletResponse response)
    throws ServletException, IOException {
        response.setContentType("text/html;charset=UTF-8");
        PrintWriter out = response.getWriter();
        try {

            out.println("<html>");
            out.println("<head>");
            out.println("<title>Servlet TutorialServlet</title>");
            out.println("</head>");
            out.println("<body>");
            request.login("TutorialUser", "TutorialUser");
            BigDecimal result =
                converterBean.dollarToYen(new BigDecimal("1.0"));
            out.println("<h1>Servlet TutorialServlet result of dollarToYen= "
                + result + "</h1>");
            out.println("</body>");
            out.println("</html>");
        } catch (Exception e) {
            throw new ServletException(e);
        } finally {
            request.logout();
            out.close();
        }
    }
}
```

The following example code shows how to use the `authenticate` method:

```
package com.sam.test;

import java.io.*;
import javax.servlet.*;
import javax.servlet.http.*;

public class TestServlet extends HttpServlet {

    protected void processRequest(HttpServletRequest request,
            HttpServletResponse response)
            throws ServletException, IOException {
        response.setContentType("text/html;charset=UTF-8");
        PrintWriter out = response.getWriter();
        try {
            request.authenticate(response);
            out.println("Authenticate Successful");
        } finally {
            out.close();
        }
    }
```

Checking Caller Identity Programmatically

In general, security management should be enforced by the container in a manner that is transparent to the web component. The security API described in this section should be used only in the less frequent situations in which the web component methods need to access the security context information.

Servlet 3.0 specifies the following methods that enable you to access security information about the component's caller:

- `getRemoteUser`, which determines the user name with which the client authenticated. The `getRemoteUser` method returns the name of the remote user (the caller) associated by the container with the request. If no user has been authenticated, this method returns `null`.
- `isUserInRole`, which determines whether a remote user is in a specific security role. If no user has been authenticated, this method returns `false`. This method expects a `String` user `role-name` parameter.

  The `security-role-ref` element should be declared in the deployment descriptor with a `role-name` subelement containing the role name to be passed to the method. Using security role references is discussed in "Declaring and Linking Role References" on page 688.
- `getUserPrincipal`, which determines the principal name of the current user and returns a `java.security.Principal` object. If no user has been authenticated, this method returns `null`. Calling the `getName` method on the `Principal` returned by `getUserPrincipal` returns the name of the remote user.

Your application can make business-logic decisions based on the information obtained using these APIs.

Example Code for Programmatic Security

The following code demonstrates the use of programmatic security for the purposes of programmatic login. This servlet does the following:

1. It displays information about the current user.
2. It prompts the user to log in.
3. It prints out the information again to demonstrate the effect of the `login` method.
4. It logs the user out.
5. It prints out the information again to demonstrate the effect of the `logout` method.

```
package enterprise.programmatic_login;

import java.io.*;
import java.net.*;
import javax.annotation.security.DeclareRoles;
import javax.servlet.*;
import javax.servlet.http.*;

@DeclareRoles("javaee6user")
public class LoginServlet extends HttpServlet {

    /**
     * Processes requests for both HTTP GET and POST methods.
     * @param request servlet request
     * @param response servlet response
     */
    protected void processRequest(HttpServletRequest request,
                HttpServletResponse response)
            throws ServletException, IOException {
        response.setContentType("text/html;charset=UTF-8");
        PrintWriter out = response.getWriter();
        try {
            String userName = request.getParameter("txtUserName");
            String password = request.getParameter("txtPassword");

            out.println("Before Login" + "<br><br>");
            out.println("IsUserInRole?.."
                        + request.isUserInRole("javaee6user")+"<br>");
            out.println("getRemoteUser?.." + request.getRemoteUser()+"<br>");
            out.println("getUserPrincipal?.."
                        + request.getUserPrincipal()+"<br>");
            out.println("getAuthType?.." + request.getAuthType()+"<br><br>");

            try {
                request.login(userName, password);
            } catch(ServletException ex) {
                out.println("Login Failed with a ServletException.."
                    + ex.getMessage());
                return;
            }
            out.println("After Login..."+"<br><br>");
            out.println("IsUserInRole?.."
                        + request.isUserInRole("javaee6user")+"<br>");
```

```
            out.println("getRemoteUser?.." + request.getRemoteUser()+"<br>");
            out.println("getUserPrincipal?.."
                        + request.getUserPrincipal()+"<br>");
            out.println("getAuthType?.." + request.getAuthType()+"<br><br>");

            request.logout();
            out.println("After Logout..."+"<br><br>");
            out.println("IsUserInRole?.."
                        + request.isUserInRole("javaee6user")+"<br>");
            out.println("getRemoteUser?.." + request.getRemoteUser()+"<br>");
            out.println("getUserPrincipal?.."
                        + request.getUserPrincipal()+"<br>");
            out.println("getAuthType?.." + request.getAuthType()+"<br>");
        } finally {
            out.close();
        }
    }
    ...
}
```

Declaring and Linking Role References

A *security role reference* defines a mapping between the name of a role that is called from a web component using `isUserInRole(String role)` and the name of a security role that has been defined for the application. If no `security-role-ref` element is declared in a deployment descriptor and the `isUserInRole` method is called, the container defaults to checking the provided role name against the list of all security roles defined for the web application. Using the default method instead of using the `security-role-ref` element limits your flexibility to change role names in an application without also recompiling the servlet making the call.

The `security-role-ref` element is used when an application uses the `HttpServletRequest.isUserInRole(String role)`. The value passed to the `isUserInRole` method is a `String` representing the role name of the user. The value of the `role-name` element must be the `String` used as the parameter to the `HttpServletRequest.isUserInRole(String role)`. The `role-link` must contain the name of one of the security roles defined in the `security-role` elements. The container uses the mapping of `security-role-ref` to `security-role` when determining the return value of the call.

For example, to map the security role reference `cust` to the security role with role name `bankCustomer`, the syntax would be:

```
<servlet>
...
    <security-role-ref>
        <role-name>cust</role-name>
        <role-link>bankCustomer</role-link>
    </security-role-ref>
...
</servlet>
```

If the servlet method is called by a user in the `bankCustomer` security role, `isUserInRole("cust")` returns `true`.

The `role-link` element in the `security-role-ref` element must match a `role-name` defined in the `security-role` element of the same `web.xml` deployment descriptor, as shown here:

```
<security-role>
    <role-name>bankCustomer</role-name>
</security-role>
```

A security role reference, including the name defined by the reference, is scoped to the component whose deployment descriptor contains the `security-role-ref` deployment descriptor element.

Examples: Securing Web Applications

Some basic setup is required before any of the example applications will run correctly. The examples use annotations, programmatic security, and/or declarative security to demonstrate adding security to existing web applications.

Here are some other locations where you will find examples of securing various types of applications:

- "Example: Securing an Enterprise Bean with Declarative Security" on page 712
- "Example: Securing an Enterprise Bean with Programmatic Security" on page 716
- GlassFish samples: `http://glassfish-samples.java.net/`

▼ To Set Up Your System for Running the Security Examples

To set up your system for running the security examples, you need to configure a user database that the application can use for authenticating users. Before continuing, follow these steps.

1 **Add an authorized user to the GlassFish Server. For the examples in this chapter and in Chapter 41, "Getting Started Securing Enterprise Applications," add a user to the `file` realm of the GlassFish Server, and assign the user to the group `TutorialUser`:**

   a. **From the Administration Console, expand the Configurations node, then expand the server-config node.**

   b. **Expand the Security node.**

   c. **Expand the Realms node.**

   d. **Select the File node.**

   e. **On the Edit Realm page, click Manage Users.**

f. **On the File Users page, click New.**

g. **In the User ID field, type a User ID.**

h. **In the Group List field, type `TutorialUser`.**

i. **In the New Password and Confirm New Password fields, type a password.**

j. **Click OK.**

Be sure to write down the user name and password for the user you create so that you can use it for testing the example applications. Authentication is case sensitive for both the user name and password, so write down the user name and password exactly. This topic is discussed more in "Managing Users and Groups on the GlassFish Server" on page 660.

2 **Set up Default Principal to Role Mapping on the GlassFish Server:**

a. **From the Administration Console, expand the Configurations node, then expand the server-config node.**

b. **Select the Security node.**

c. **Select the Default Principal to Role Mapping Enabled check box.**

d. **Click Save.**

Example: Basic Authentication with a Servlet

This example explains how to use basic authentication with a servlet. With basic authentication of a servlet, the web browser presents a standard login dialog that is not customizable. When a user submits his or her name and password, the server determines whether the user name and password are those of an authorized user and sends the requested web resource if the user is authorized to view it.

In general, the following steps are necessary for adding basic authentication to an unsecured servlet, such as the ones described in Chapter 3, "Getting Started with Web Applications." In the example application included with this tutorial, many of these steps have been completed for you and are listed here simply to show what needs to be done should you wish to create a similar application. The completed version of this example application can be found in the directory *tut-install*`/examples/security/hello2_basicauth/`.

1. Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.
2. Create a web module as described in Chapter 3, "Getting Started with Web Applications," for the servlet example, `hello2`.
3. Add the appropriate security annotations to the servlet. The security annotations are described in "Specifying Security for Basic Authentication Using Annotations" on page 691.
4. Build, package, and deploy the web application by following the steps in "To Build, Package, and Deploy the Servlet Basic Authentication Example Using NetBeans IDE" on page 692 or "To Build, Package, and Deploy the Servlet Basic Authentication Example Using Ant" on page 692.
5. Run the web application by following the steps described in "To Run the Basic Authentication Servlet" on page 693.

Specifying Security for Basic Authentication Using Annotations

The default authentication mechanism used by the GlassFish Server is basic authentication. With basic authentication, the GlassFish Server spawns a standard login dialog to collect user name and password data for a protected resource. Once the user is authenticated, access to the protected resource is permitted.

To specify security for a servlet, use the `@ServletSecurity` annotation. This annotation allows you to specify both specific constraints on HTTP methods and more general constraints that apply to all HTTP methods for which no specific constraint is specified. Within the `@ServletSecurity` annotation, you can specify the following annotations:

- The `@HttpMethodConstraint` annotation, which applies to a specific HTTP method
- The more general `@HttpConstraint` annotation, which applies to all HTTP methods for which there is no corresponding `@HttpMethodConstraint` annotation

Both the `@HttpMethodConstraint` and `@HttpConstraint` annotations within the `@ServletSecurity` annotation can specify the following:

- A `transportGuarantee` element that specifies the data protection requirements (that is, whether or not SSL/TLS is required) that must be satisfied by the connections on which requests arrive. Valid values for this element are `NONE` and `CONFIDENTIAL`.
- A `rolesAllowed` element that specifies the names of the authorized roles.

For the `hello2_basicauth` application, the `GreetingServlet` has the following annotations:

```
@WebServlet(name = "GreetingServlet", urlPatterns = {"/greeting"})
@ServletSecurity(
@HttpConstraint(transportGuarantee = TransportGuarantee.CONFIDENTIAL,
    rolesAllowed = {"TutorialUser"}))
```

These annotations specify that the request URI `/greeting` can be accessed only by users who have been authorized to access this URL because they have been verified to be in the role `TutorialUser`. The data will be sent over a protected transport in order to keep the user name and password data from being read in transit.

If you use the `@ServletSecurity` annotation, you do not need to specify security settings in the deployment descriptor. Use the deployment descriptor to specify settings for nondefault authentication mechanisms, for which you cannot use the `@ServletSecurity` annotation.

▼ To Build, Package, and Deploy the Servlet Basic Authentication Example Using NetBeans IDE

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In NetBeans IDE, from the File menu, choose Open Project.**
3. **In the Open Project dialog, navigate to:**
   tut-install`/examples/security`
4. **Select the `hello2_basicauth` folder.**
5. **Select the Open as Main Project check box.**
6. **Click Open Project.**
7. **Right-click `hello2_basicauth` in the Projects pane and select Deploy.**
   This option builds and deploys the example application to your GlassFish Server instance.

▼ To Build, Package, and Deploy the Servlet Basic Authentication Example Using Ant

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In a terminal window, go to:**
   tut-install`/examples/security/hello2_basicauth/`
3. **Type the following command:**
   `ant`

This command calls the `default` target, which builds and packages the application into a WAR file, `hello2_basicauth.war`, that is located in the `dist` directory.

4 **Make sure that the GlassFish Server is started.**

5 **To deploy the application, type the following command:**

```
ant deploy
```

▼ To Run the Basic Authentication Servlet

1 **In a web browser, navigate to the following URL:**

```
https://localhost:8181/hello2_basicauth/greeting
```

You may be prompted to accept the security certificate for the server. If so, accept the security certificate. If the browser warns that the certificate is invalid because it is self-signed, add a security exception for the application.

An Authentication Required dialog box appears. Its appearance varies, depending on the browser you use. Figure 40–6 shows an example.

FIGURE 40–6 Sample Basic Authentication Dialog Box

2 **Type a user name and password combination that corresponds to a user who has already been created in the `file` realm of the GlassFish Server and has been assigned to the group of `TutorialUser`; then click OK.**

Basic authentication is case sensitive for both the user name and password, so type the user name and password exactly as defined for the GlassFish Server.

The server returns the requested resource if all the following conditions are met.

- A user with the user name you entered is defined for the GlassFish Server.
- The user with the user name you entered has the password you entered.
- The user name and password combination you entered is assigned to the group `TutorialUser` on the GlassFish Server.
- The role of `TutorialUser`, as defined for the application, is mapped to the group `TutorialUser`, as defined for the GlassFish Server.

When these conditions are met and the server has authenticated the user, the application will appear as shown in Figure 3–2 but with a different URL.

3 **Type a name in the text field and click the Submit button.**

Because you have already been authorized, the name you enter in this step does not have any limitations. You have unlimited access to the application now.

The application responds by saying "Hello" to you, as shown in Figure 3–3 but with a different URL.

Next Steps For repetitive testing of this example, you may need to close and reopen your browser. You should also run the `ant undeploy` and `ant clean` targets or the NetBeans IDE Clean and Build option to get a fresh start.

Example: Form-Based Authentication with a JavaServer Faces Application

This example explains how to use form-based authentication with a JavaServer Faces application. With form-based authentication, you can customize the login screen and error pages that are presented to the web client for authentication of the user name and password. When a user submits his or her name and password, the server determines whether the user name and password are those of an authorized user and, if authorized, sends the requested web resource.

This example, `hello1_formauth`, adds security to the basic JavaServer Faces application shown in "Web Modules: The `hello1` Example" on page 83.

In general, the steps necessary for adding form-based authentication to an unsecured JavaServer Faces application are similar to those described in "Example: Basic Authentication with a Servlet" on page 690. The major difference is that you must use a deployment descriptor to specify the use of form-based authentication, as described in "Specifying Security for the Form-Based Authentication Example" on page 696. In addition, you must create a login form page and a login error page, as described in "Creating the Login Form and the Error Page" on page 694.

The completed version of this example application can be found in the directory *tut-install*`/examples/security/hello1_formauth/`.

Creating the Login Form and the Error Page

When using form-based login mechanisms, you must specify a page that contains the form you want to use to obtain the user name and password, as well as a page to display if login authentication fails. This section discusses the login form and the error page used in this example. "Specifying Security for the Form-Based Authentication Example" on page 696 shows how you specify these pages in the deployment descriptor.

The login page can be an HTML page or a servlet, and it must return an HTML page containing a form that conforms to specific naming conventions (see the Java Servlet 3.0 specification for more information on these requirements). To do this, include the elements that accept user name and password information between `<form></form>` tags in your login page. The content of an HTML page or servlet for a login page should be coded as follows:

```
<form method="post" action="j_security_check">
    <input type="text" name="j_username">
    <input type="password" name= "j_password">
</form>
```

The full code for the login page used in this example can be found at *tut-install*`/examples/security/hello1_formauth/web/login.xhtml`. An example of the running login form page is shown later, in Figure 40–7. Here is the code for this page:

```
<html xmlns="http://www.w3.org/1999/xhtml">
    <head>
        <title>Login Form</title>
    </head>
    <body>
        <h2>Hello, please log in:</h2>
        <form name="loginForm" method="POST" action="j_security_check">
            <p><strong>Please type your user name: </strong>
                <input type="text" name="j_username" size="25"></p>
            <p><strong>Please type your password: </strong>
                <input type="password" size="15" name="j_password"></p>
            <p>
                <input type="submit" value="Submit"/>
                <input type="reset" value="Reset"/></p>
        </form>
    </body>
</html>
```

The login error page is displayed if the user enters a user name and password combination that is not authorized to access the protected URI. For this example, the login error page can be found at *tut-install*`/examples/security/hello1_formauth/web/error.xhtml`. For this example, the login error page explains the reason for receiving the error page and provides a link that will allow the user to try again. Here is the code for this page:

```
<html xmlns="http://www.w3.org/1999/xhtml">
    <head>
        <title>Login Error</title>
    </head>
    <body>
    <h2>Invalid user name or password.</h2>

    <p>Please enter a user name or password that is authorized to access this
        application. For this application, this means a user that has been
        created in the <code>file</code> realm and has been assigned to the
        <em>group</em> of <code>TutorialUser</code>.</p>
    <p><a href="login.xhtml">Return to login page</a></p>

    </body>
</html>
```

Specifying Security for the Form-Based Authentication Example

This example takes a very simple servlet-based web application and adds form-based security. To specify form-based instead of basic authentication for a JavaServer Faces example, you must use the deployment descriptor.

The following sample code shows the security elements added to the deployment descriptor for this example, which can be found in *tut-install*`/examples/security/hello1_formauth/web/WEB-INF/web.xml`.

```
<security-constraint>
    <display-name>Constraint1</display-name>
    <web-resource-collection>
        <web-resource-name>wrcoll</web-resource-name>
        <description/>
        <url-pattern>/*</url-pattern>
    </web-resource-collection>
    <auth-constraint>
        <description/>
        <role-name>TutorialUser</role-name>
    </auth-constraint>
</security-constraint>

<login-config>
    <auth-method>FORM</auth-method>
    <realm-name>file</realm-name>
    <form-login-config>
        <form-login-page>/login.xhtml</form-login-page>
        <form-error-page>/error.xhtml</form-error-page>
    </form-login-config>
</login-config>

<security-role>
    <description/>
    <role-name>TutorialUser</role-name>
</security-role>
```

▼ To Build, Package, and Deploy the Form-Based Authentication Example Using NetBeans IDE

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In NetBeans IDE, from the File menu, choose Open Project.**
3. **In the Open Project dialog, navigate to:**

   tut-install`/examples/security`
4. **Select the `hello1_formauth` folder.**
5. **Select the Open as Main Project check box.**

6. **Click Open Project.**

7. **Right-click `hello1_formauth` in the Projects pane and select Deploy.**

▼ To Build, Package, and Deploy the Form-Based Authentication Example Using Ant

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**

2. **In a terminal window, go to:**

   tut-install`/examples/security/hello2_formauth/`

3. **Type the following command at the terminal window or command prompt:**

   ```
   ant
   ```

   This target will spawn any necessary compilations, copy files to the *tut-install*`/examples/security/hello2_formauth/build/` directory, create the WAR file, and copy it to the *tut-install*`/examples/security/hello2_formauth/dist/` directory.

4. **To deploy `hello2_formauth.war` to the GlassFish Server, type the following command:**

   ```
   ant deploy
   ```

▼ To Run the Form-Based Authentication Example

To run the web client for `hello1_formauth`, follow these steps.

1. **Open a web browser to the following URL:**

   ```
   https://localhost:8181/hello1_formauth/
   ```

   The login form displays in the browser, as shown in Figure 40–7.

FIGURE 40–7 Form-Based Login Page

2 Type a user name and password combination that corresponds to a user who has already been created in the `file` realm of the GlassFish Server and has been assigned to the group of `TutorialUser`.

Form-based authentication is case sensitive for both the user name and password, so type the user name and password exactly as defined for the GlassFish Server.

3 Click the Submit button.

If you entered `My_Name` as the name and `My_Pwd` for the password, the server returns the requested resource if all the following conditions are met.

- A user with the user name `My_Name` is defined for the GlassFish Server.
- The user with the user name `My_Name` has a password `My_Pwd` defined for the GlassFish Server.
- The user `My_Name` with the password `My_Pwd` is assigned to the group `TutorialUser` on the GlassFish Server.
- The role `TutorialUser`, as defined for the application, is mapped to the group `TutorialUser`, as defined for the GlassFish Server.

  When these conditions are met and the server has authenticated the user, the application appears.

4 Type your name and click the Submit button.

Because you have already been authorized, the name you enter in this step does not have any limitations. You have unlimited access to the application now.

The application responds by saying "Hello" to you.

Next Steps For additional testing and to see the login error page generated, close and reopen your browser, type the application URL, and type a user name and password that are not authorized.

Note – For repetitive testing of this example, you may need to close and reopen your browser. You should also run the `ant clean` and `ant undeploy` commands to ensure a fresh build if using the Ant tool, or select Clean and Build then Deploy if using NetBeans IDE.

◆ ◆ ◆ CHAPTER 41

Getting Started Securing Enterprise Applications

The following parties are responsible for administering security for enterprise applications:

- **System administrator**: Responsible for setting up a database of users and assigning them to the proper group. The system administrator is also responsible for setting GlassFish Serverproperties that enable the applications to run properly. Some security-related examples set up a default principal-to-role mapping, anonymous users, default users, and propagated identities. When needed for this tutorial, the steps for performing specific tasks are provided.
- **Application developer/bean provider**: Responsible for annotating the classes and methods of the enterprise application in order to provide information to the deployer about which methods need to have restricted access. This tutorial describes the steps necessary to complete this task.
- **Deployer**: Responsible for taking the security view provided by the application developer and implementing that security upon deployment. This document provides the information needed to accomplish this task for the tutorial example applications.

The following topics are addressed here:

Securing Enterprise Beans

Enterprise beans are Java EE components that implement EJB technology. Enterprise beans run in the EJB container, a runtime environment within the GlassFish Server. Although transparent to the application developer, the EJB container provides system-level services, such as transactions and security to its enterprise beans, which form the core of transactional Java EE applications.

Enterprise bean methods can be secured in either of the following ways:

- **Declarative security** (preferred): Expresses an application component's security requirements using either deployment descriptors or annotations. The presence of an annotation in the business method of an enterprise bean class that specifies method permissions is all that is needed for method protection and authentication in some situations. This section discusses this simple and efficient method of securing enterprise beans.

  Because of some limitations to the simplified method of securing enterprise beans, you would want to continue to use the deployment descriptor to specify security information in some instances. An authentication mechanism must be configured on the server for the simple solution to work. Basic authentication is the GlassFish Server's default authentication method.

  This tutorial explains how to invoke user name/password authentication of authorized users by decorating the enterprise application's business methods with annotations that specify method permissions.

  To make the deployer's task easier, the application developer can define security roles. A security role is a grouping of permissions that a given type of application users must have in order to successfully use the application. For example, in a payroll application, some users will want to view their own payroll information (*employee*), some will need to view others' payroll information (*manager*), and some will need to be able to change others' payroll information (*payrollDept*). The application developer would determine the potential users of the application and which methods would be accessible to which users. The application developer would then decorate classes or methods of the enterprise bean with annotations that specify the types of users authorized to access those methods. Using annotations to specify authorized users is described in "Specifying Authorized Users by Declaring Security Roles" on page 705.

  When one of the annotations is used to define method permissions, the deployment system will automatically require user name/password authentication. In this type of authentication, a user is prompted to enter a user name and password, which will be compared against a database of known users. If the user is found and the password matches, the roles that the user is assigned will be compared against the roles that are authorized to access the method. If the user is authenticated and found to have a role that is authorized to access that method, the data will be returned to the user.

  Using declarative security is discussed in "Securing an Enterprise Bean Using Declarative Security" on page 704.

- **Programmatic security**: For an enterprise bean, code embedded in a business method that is used to access a caller's identity programmatically and that uses this information to make security decisions. Programmatic security is useful when declarative security alone is not sufficient to express the security model of an application.

  In general, security management should be enforced by the container in a manner that is transparent to the enterprise beans' business methods. The programmatic security APIs described in this chapter should be used only in the less frequent situations in which the

enterprise bean business methods need to access the security-context information, such as when you want to grant access based on the time of day or other nontrivial condition checks for a particular role.

Programmatic security is discussed in "Securing an Enterprise Bean Programmatically" on page 708.

Some of the material in this chapter assumes that you have already read Chapter 22, "Enterprise Beans," Chapter 23, "Getting Started with Enterprise Beans," and Chapter 39, "Introduction to Security in the Java EE Platform."

As mentioned earlier, enterprise beans run in the EJB container, a runtime environment within the GlassFish Server, as shown in Figure 41–1.

FIGURE 41–1 Java EE Server and Containers



This section discusses securing a Java EE application where one or more modules, such as EJB JAR files, are packaged into an EAR file, the archive file that holds the application. Security annotations will be used in the Java programming class files to specify authorized users and basic, or user name/password, authentication.

Enterprise beans often provide the business logic of a web application. In these cases, packaging the enterprise bean within the web application's WAR module simplifies deployment and application organization. Enterprise beans may be packaged within a WAR module as Java class files or within a JAR file that is bundled within the WAR module. When a servlet or JavaServer Faces page handles the web front end and the application is packaged into a WAR module as a Java class file, security for the application can be handled in the application's `web.xml` file. The EJB in the WAR file can have its own deployment descriptor, `ejb-jar.xml`, if required. Securing web applications using `web.xml` is discussed in Chapter 40, "Getting Started Securing Web Applications."

The following sections describe declarative and programmatic security mechanisms that can be used to protect enterprise bean resources. The protected resources include enterprise bean methods that are called from application clients, web components, or other enterprise beans.

For more information on this topic, read the Enterprise JavaBeans 3.1 specification. This document can be downloaded from `http://jcp.org/en/jsr/detail?id=318`. Chapter 17 of this specification, "Security Management," discusses security management for enterprise beans.

Securing an Enterprise Bean Using Declarative Security

Declarative security enables the application developer to specify which users are authorized to access which methods of the enterprise beans and to authenticate these users with basic, or username-password, authentication. Frequently, the person who is developing an enterprise application is not the same person who is responsible for deploying the application. An application developer who uses declarative security to define method permissions and authentications mechanisms is passing along to the deployer a *security view* of the enterprise beans contained in the EJB JAR. When a security view is passed on to the deployer, he or she uses this information to define method permissions for security roles. If you don't define a security view, the deployer will have to determine what each business method does to determine which users are authorized to call each method.

A security view consists of a set of security roles, a semantic grouping of permissions that a given type of users of an application must have to successfully access the application. Security roles are meant to be logical roles, representing a type of user. You can define method permissions for each security role. A method permission is a permission to invoke a specified group of methods of an enterprise bean's business interface, home interface, component interface, and/or web service endpoints. After method permissions are defined, user name/password authentication will be used to verify the identity of the user.

It is important to keep in mind that security roles are used to define the logical security view of an application. They should not be confused with the user groups, users, principals, and other concepts that exist in the GlassFish Server. An additional step is required to map the roles defined in the application to users, groups, and principals that are the components of the user database in the file realm of the GlassFish Server. These steps are outlined in "Mapping Roles to Users and Groups" on page 663.

The following sections show how an application developer uses declarative security to either secure an application or to create a security view to pass along to the deployer.

Specifying Authorized Users by Declaring Security Roles

This section discusses how to use annotations to specify the method permissions for the methods of a bean class. For more information on these annotations, refer to the Common Annotations for the Java Platform specification at `http://jcp.org/en/jsr/detail?id=250`.

Method permissions can be specified on the class, the business methods of the class, or both. Method permissions can be specified on a method of the bean class to override the method permissions value specified on the entire bean class. The following annotations are used to specify method permissions:

- `@DeclareRoles`: Specifies all the roles that the application will use, including roles not specifically named in a `@RolesAllowed` annotation. The set of security roles the application uses is the total of the security roles defined in the `@DeclareRoles` and `@RolesAllowed` annotations.

  The `@DeclareRoles` annotation is specified on a bean class, where it serves to declare roles that can be tested (for example, by calling `isCallerInRole`) from within the methods of the annotated class. When declaring the name of a role used as a parameter to the `isCallerInRole(String roleName)` method, the declared name must be the same as the parameter value.

  The following example code demonstrates the use of the `@DeclareRoles` annotation:

  ```
  @DeclareRoles("BusinessAdmin")
  public class Calculator {
      ...
  }
  ```

  The syntax for declaring more than one role is as shown in the following example:

  ```
  @DeclareRoles({"Administrator", "Manager", "Employee"})
  ```

- `@RolesAllowed("`*list-of-roles*`")`: Specifies the security roles permitted to access methods in an application. This annotation can be specified on a class or on one or more methods. When specified at the class level, the annotation applies to all methods in the class. When specified on a method, the annotation applies to that method only and overrides any values specified at the class level.

To specify that no roles are authorized to access methods in an application, use the `@DenyAll` annotation. To specify that a user in any role is authorized to access the application, use the `@PermitAll` annotation.

When used in conjunction with the `@DeclareRoles` annotation, the combined set of security roles is used by the application.

The following example code demonstrates the use of the `@RolesAllowed` annotation:

```
@DeclareRoles({"Administrator", "Manager", "Employee"})
public class Calculator {

    @RolesAllowed("Administrator")
    public void setNewRate(int rate) {
        ...
    }
}
```

- `@PermitAll`: Specifies that *all* security roles are permitted to execute the specified method or methods. The user is not checked against a database to ensure that he or she is authorized to access this application.

  This annotation can be specified on a class or on one or more methods. Specifying this annotation on the class means that it applies to all methods of the class. Specifying it at the method level means that it applies to only that method.

  The following example code demonstrates the use of the `@PermitAll` annotation:

```
import javax.annotation.security.*;
@RolesAllowed("RestrictedUsers")
public class Calculator {

    @RolesAllowed("Administrator")
    public void setNewRate(int rate) {
        //...
    }
    @PermitAll
    public long convertCurrency(long amount) {
        //...
    }
}
```

- `@DenyAll`: Specifies that *no* security roles are permitted to execute the specified method or methods. This means that these methods are excluded from execution in the Java EE container.

  The following example code demonstrates the use of the `@DenyAll` annotation:

```
import javax.annotation.security.*;
@RolesAllowed("Users")
public class Calculator {
    @RolesAllowed("Administrator")
    public void setNewRate(int rate) {
        //...
    }
    @DenyAll
    public long convertCurrency(long amount) {
        //...
```

```
        }
    }
```

The following code snippet demonstrates the use of the `@DeclareRoles` annotation with the `isCallerInRole` method. In this example, the `@DeclareRoles` annotation declares a role that the enterprise bean `PayrollBean` uses to make the security check by using `isCallerInRole("payroll")` to verify that the caller is authorized to change salary data:

```
@DeclareRoles("payroll")
@Stateless public class PayrollBean implements Payroll {
    @Resource SessionContext ctx;

    public void updateEmployeeInfo(EmplInfo info) {

        oldInfo = ... read from database;

        // The salary field can be changed only by callers
        // who have the security role "payroll"
        Principal callerPrincipal = ctx.getCallerPrincipal();
        if (info.salary != oldInfo.salary && !ctx.isCallerInRole("payroll")) {
            throw new SecurityException(...);
        }
        ...
    }
    ...
}
```

The following example code illustrates the use of the `@RolesAllowed` annotation:

```
@RolesAllowed("admin")
public class SomeClass {
    public void aMethod () {...}
    public void bMethod () {...}
    ...
}

@Stateless public class MyBean extends SomeClass implements A  {

    @RolesAllowed("HR")
    public void aMethod () {...}

    public void cMethod () {...}
    ...
}
```

In this example, assuming that `aMethod`, `bMethod`, and `cMethod` are methods of business interface `A`, the method permissions values of methods `aMethod` and `bMethod` are `@RolesAllowed("HR")` and `@RolesAllowed("admin")`, respectively. The method permissions for method `cMethod` have not been specified.

To clarify, the annotations are not inherited by the subclass itself. Instead, the annotations apply to methods of the superclass that are inherited by the subclass.

Specifying an Authentication Mechanism and Secure Connection

When method permissions are specified, basic user name/password authentication will be invoked by the GlassFish Server.

To use a different type of authentication or to require a secure connection using SSL, specify this information in an application deployment descriptor.

Securing an Enterprise Bean Programmatically

Programmatic security, code that is embedded in a business method, is used to access a caller's identity programmatically and uses this information to make security decisions within the method itself.

Accessing an Enterprise Bean Caller's Security Context

In general, security management should be enforced by the container in a manner that is transparent to the enterprise bean's business methods. The security API described in this section should be used only in the less frequent situations in which the enterprise bean business methods need to access the security context information, such as when you want to restrict access to a particular time of day.

The `javax.ejb.EJBContext` interface provides two methods that allow the bean provider to access security information about the enterprise bean's caller:

- `getCallerPrincipal`, which allows the enterprise bean methods to obtain the current caller principal's name. The methods might, for example, use the name as a key to information in a database.

  The following code sample illustrates the use of the `getCallerPrincipal` method:

```
@Stateless public class EmployeeServiceBean implements EmployeeService {
    @Resource SessionContext ctx;
    @PersistenceContext EntityManager em;

    public void changePhoneNumber(...) {
        ...
        // obtain the caller principal.
        callerPrincipal = ctx.getCallerPrincipal();

        // obtain the caller principal's name.
        callerKey = callerPrincipal.getName();

        // use callerKey as primary key to find EmployeeRecord
        EmployeeRecord myEmployeeRecord =
            em.find(EmployeeRecord.class, callerKey);

        // update phone number
        myEmployeeRecord.setPhoneNumber(...);

        ...
    }
}
```

In this example, the enterprise bean obtains the principal name of the current caller and uses it as the primary key to locate an `EmployeeRecord` entity. This example assumes that application has been deployed such that the current caller principal contains the primary key used for the identification of employees (for example, employee number).

- `isCallerInRole`, which the enterprise bean code can use to allow the bean provider/application developer to code the security checks that cannot be easily defined using method permissions. Such a check might impose a role-based limit on a request, or it might depend on information stored in the database.

  The enterprise bean code can use the `isCallerInRole` method to test whether the current caller has been assigned to a given security role. Security roles are defined by the bean provider or the application assembler and are assigned by the deployer to principals or principal groups that exist in the operational environment.

  The following code sample illustrates the use of the `isCallerInRole` method:

```
@Stateless public class PayrollBean implements Payroll {
     @Resource SessionContext ctx;

     public void updateEmployeeInfo(EmplInfo info) {

         oldInfo = ... read from database;

         // The salary field can be changed only by callers
         // who have the security role "payroll"
         if (info.salary != oldInfo.salary &&
             !ctx.isCallerInRole("payroll")) {
                 throw new SecurityException(...);
         }
         ...
     }
     ...
 }
```

You would use programmatic security in this way to dynamically control access to a method, for example, when you want to deny access except during a particular time of day. An example application that uses the `getCallerPrincipal` and `isCallerInRole` methods is described in "Example: Securing an Enterprise Bean with Programmatic Security" on page 716.

Propagating a Security Identity (Run-As)

You can specify whether a caller's security identity should be used for the execution of specified methods of an enterprise bean or whether a specific run-as identity should be used. Figure 41–2 illustrates this concept.

FIGURE 41–2 Security Identity Propagation



In this illustration, an application client is making a call to an enterprise bean method in one EJB container. This enterprise bean method, in turn, makes a call to an enterprise bean method in another container. The security identity during the first call is the identity of the caller. The security identity during the second call can be any of the following options.

- By default, the identity of the caller of the intermediate component is propagated to the target enterprise bean. This technique is used when the target container trusts the intermediate container.
- A *specific* identity is propagated to the target enterprise bean. This technique is used when the target container expects access using a specific identity.

  To propagate an identity to the target enterprise bean, configure a run-as identity for the bean, as described in "Configuring a Component's Propagated Security Identity" on page 710. Establishing a run-as identity for an enterprise bean does not affect the identities of its callers, which are the identities tested for permission to access the methods of the enterprise bean. The run-as identity establishes the identity that the enterprise bean will use when it makes calls.

  The run-as identity applies to the enterprise bean as a whole, including all the methods of the enterprise bean's business interface, local and remote interfaces, component interface, and web service endpoint interfaces, the message listener methods of a message-driven bean, the timeout method of an enterprise bean, and all internal methods of the bean that might be called in turn.

Configuring a Component's Propagated Security Identity

You can configure an enterprise bean's run-as, or propagated, security identity by using the `@RunAs` annotation, which defines the role of the application during execution in a Java EE container. The annotation can be specified on a class, allowing developers to execute an application under a particular role. The role must map to the user/group information in the container's security realm. The `@RunAs` annotation specifies the name of a security role as its parameter.

Here is some example code that demonstrates the use of the `@RunAs` annotation.

```
@RunAs("Admin")
public class Calculator {
```

```
    //....
}
```

You will have to map the run-as role name to a given principal defined on the GlassFish Server if the given roles are associated with more than one user principal.

Trust between Containers

When an enterprise bean is designed so that either the original caller identity or a designated identity is used to call a target bean, the target bean will receive the propagated identity only. The target bean will not receive any authentication data.

There is no way for the target container to authenticate the propagated security identity. However, because the security identity is used in authorization checks (for example, method permissions or with the `isCallerInRole` method), it is vitally important that the security identity be authentic. Because no authentication data is available to authenticate the propagated identity, the target must trust that the calling container has propagated an authenticated security identity.

By default, the GlassFish Server is configured to trust identities that are propagated from different containers. Therefore, you do not need to take any special steps to set up a trust relationship.

Deploying Secure Enterprise Beans

The deployer is responsible for ensuring that an assembled application is secure after it has been deployed in the target operational environment. If a security view has been provided to the deployer through the use of security annotations and/or a deployment descriptor, the security view is mapped to the mechanisms and policies used by the security domain in the target operational environment, which in this case is the GlassFish Server. If no security view is provided, the deployer must set up the appropriate security policy for the enterprise bean application.

Deployment information is specific to a web or application server.

Examples: Securing Enterprise Beans

The following examples show how to secure enterprise beans using declarative and programmatic security.

Example: Securing an Enterprise Bean with Declarative Security

This section discusses how to configure an enterprise bean for basic user name/password authentication. When a bean that is constrained in this way is requested, the server requests a user name and password from the client and verifies that the user name and password are valid by comparing them against a database of authorized users on the GlassFish Server.

If the topic of authentication is new to you, see "Specifying an Authentication Mechanism in the Deployment Descriptor" on page 682.

This example demonstrates security by starting with the unsecured enterprise bean application, `cart`, which is found in the directory *tut-install*`/examples/ejb/cart/` and is discussed in "The `cart` Example" on page 421.

In general, the following steps are necessary to add user name/password authentication to an existing application that contains an enterprise bean. In the example application included with this tutorial, these steps have been completed for you and are listed here simply to show what needs to be done should you wish to create a similar application.

1. Create an application like the one in "The `cart` Example" on page 421. The example in this tutorial starts with this example and demonstrates adding basic authentication of the client to this application. The example application discussed in this section can be found at *tut-install*`/examples/security/cart-secure/`.
2. If you have not already done so, complete the steps in "To Set Up Your System for Running the Security Examples" on page 689 to configure your system for running the tutorial applications.
3. Modify the source code for the enterprise bean, `CartBean.java`, to specify which roles are authorized to access which protected methods. This step is discussed in "Annotating the Bean" on page 712.
4. Build, package, and deploy the enterprise bean; then build and run the client application by following the steps in "To Build, Package, Deploy, and Run the Secure Cart Example Using NetBeans IDE" on page 714 or "To Build, Package, Deploy, and Run the Secure Cart Example Using Ant" on page 715.

Annotating the Bean

The source code for the original `cart` application was modified as shown in the following code snippet (modifications in **bold**). The resulting file can be found in the following location:

tut-install`/examples/security/cart-secure/cart-secure-ejb/src/java/cart/ejb/CartBean.java`

The code snippet is as follows:

```
package cart.ejb;

import cart.util.BookException;
import cart.util.IdVerifier;
import java.util.ArrayList;
import java.util.List;
import javax.ejb.Remove;
import javax.ejb.Stateful;
import javax.annotation.security.DeclareRoles;
import javax.annotation.security.RolesAllowed;

@Stateful
@DeclareRoles("TutorialUser")
public class CartBean implements Cart {
    List<String> contents;
    String customerId;
    String customerName;

    public void initialize(String person) throws BookException {
        if (person == null) {
            throw new BookException("Null person not allowed.");
        } else {
            customerName = person;
        }

        customerId = "0";
        contents = new ArrayList<String>();
    }

    public void initialize(
        String person,
        String id) throws BookException {
        if (person == null) {
            throw new BookException("Null person not allowed.");
        } else {
            customerName = person;
        }

        IdVerifier idChecker = new IdVerifier();

        if (idChecker.validate(id)) {
            customerId = id;
        } else {
            throw new BookException("Invalid id: " + id);
        }

        contents = new ArrayList<String>();
    }

    @RolesAllowed("TutorialUser")
    public void addBook(String title) {
        contents.add(title);
    }

    @RolesAllowed("TutorialUser")
    public void removeBook(String title) throws BookException {
        boolean result = contents.remove(title);

        if (result == false) {
```

```
            throw new BookException("\"" + title + "\" not in cart.");
        }
    }

    @RolesAllowed("TutorialUser")
    public List<String> getContents() {
        return contents;
    }

    @Remove()
    @RolesAllowed("TutorialUser")
    public void remove() {
        contents = null;
    }
}
```

The `@RolesAllowed` annotation is specified on methods for which you want to restrict access. In this example, only users in the role of `TutorialUser` will be allowed to add and remove books from the cart and to list the contents of the cart. A `@RolesAllowed` annotation implicitly declares a role that will be referenced in the application; therefore, no `@DeclareRoles` annotation is required. The presence of the `@RolesAllowed` annotation also implicitly declares that authentication will be required for a user to access these methods. If no authentication method is specified in the deployment descriptor, the type of authentication will be user name/password authentication.

▼ To Build, Package, Deploy, and Run the Secure Cart Example Using NetBeans IDE

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In NetBeans IDE, from the File menu, choose Open Project.**
3. **In the Open Project dialog, navigate to:**

   tut-install`/examples/security/`
4. **Select the `cart-secure` folder.**
5. **Select the Open as Main Project and Open Required Projects check boxes.**
6. **Click Open Project.**
7. **In the Projects tab, right-click the `cart-secure` project and select Build.**
8. **In the Projects tab, right-click the `cart-secure` project and select Deploy.**

   This step builds and packages the application into `cart-secure.ear`, located in the directory *tut-install*`/examples/security/cart-secure/dist/`, and deploys this EAR file to your GlassFish Server instance.

9. **To run the application client, right-click the `cart-secure` project and select Run.**

   A `Login for user:` dialog box appears.

10. **In the dialog box, type the user name and password of a file realm user created on the GlassFish Server and assigned to the group `TutorialUser`; then click OK.**

    If the user name and password you enter are authenticated, the output of the application client appears in the Output pane:

```
...
Retrieving book title from cart: Infinite Jest
Retrieving book title from cart: Bel Canto
Retrieving book title from cart: Kafka on the Shore
Removing "Gravity's Rainbow" from cart.
Caught a BookException: "Gravity's Rainbow" not in cart.
Java Result: 1
...
```

    If the user name and password are not authenticated, the dialog box reappears until you type correct values.

▼ To Build, Package, Deploy, and Run the Secure Cart Example Using Ant

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**

2. **In a terminal window, go to:**

   tut-install`/examples/security/cart-secure/`

3. **To build the application and package it into an EAR file, type the following command at the terminal window or command prompt:**

```
ant
```

4. **To deploy the application to the GlassFish Server, type the following command:**

```
ant deploy
```

5. **To run the application client, type the following command:**

```
ant run
```

   This task retrieves the application client JAR and runs the application client.

   A `Login for user:` dialog box appears.

6. **In the dialog box, type the user name and password of a file realm user created on the GlassFish Server and assigned to the group `TutorialUser`; then click OK.**

   If the user name and password are authenticated, the client displays the following output:

```
[echo] running application client container.
[exec] Retrieving book title from cart: Infinite Jest
[exec] Retrieving book title from cart: Bel Canto
[exec] Retrieving book title from cart: Kafka on the Shore
```

```
[exec] Removing "Gravity's Rainbow" from cart.
[exec] Caught a BookException: "Gravity's Rainbow" not in cart.
[exec] Result: 1
```

If the username and password are not authenticated, the dialog box reappears until you type correct values.

Example: Securing an Enterprise Bean with Programmatic Security

This example demonstrates how to use the `getCallerPrincipal` and `isCallerInRole` methods with an enterprise bean. This example starts with a very simple EJB application, `converter`, and modifies the methods of the `ConverterBean` so that currency conversion will occur only when the requester is in the role of `TutorialUser`.

The completed version of this example can be found in the directory *tut-install*`/examples/security/converter-secure`. This example is based on the unsecured enterprise bean application, `converter`, which is discussed in Chapter 23, "Getting Started with Enterprise Beans," and is found in the directory *tut-install*`/examples/ejb/converter/`. This section builds on the example by adding the necessary elements to secure the application by using the `getCallerPrincipal` and `isCallerInRole` methods, which are discussed in more detail in "Accessing an Enterprise Bean Caller's Security Context" on page 708.

In general, the following steps are necessary when using the `getCallerPrincipal` and `isCallerInRole` methods with an enterprise bean. In the example application included with this tutorial, many of these steps have been completed for you and are listed here simply to show what needs to be done should you wish to create a similar application.

1. Create a simple enterprise bean application.
2. Set up a user on the GlassFish Server in the `file` realm, in the group `TutorialUser`, and set up default principal to role mapping. To do this, follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.
3. Modify the bean to add the `getCallerPrincipal` and `isCallerInRole` methods.
4. If the application contains a web client that is a servlet, specify security for the servlet, as described in "Specifying Security for Basic Authentication Using Annotations" on page 691.
5. Build, package, deploy, and run the application.

Modifying `ConverterBean`

The source code for the original `ConverterBean` class was modified to add the `if..else` clause that tests whether the caller is in the role of `TutorialUser`. . If the user is in the correct role, the currency conversion is computed and displayed. If the user is not in the correct role, the computation is not performed, and the application displays the result as `0`. The code example can be found in the following file:

tut-install/examples/ejb/converter-secure/converter-secure-ejb/src/java/converter/ejb/ConverterBean.java

The code snippet (with modifications shown in **bold**) is as follows:

```
package converter.ejb;

import java.math.BigDecimal;
import javax.ejb.Stateless;
import java.security.Principal;
import javax.annotation.Resource;
import javax.ejb.SessionContext;
import javax.annotation.security.DeclareRoles;
import javax.annotation.security.RolesAllowed;

@Stateless()
@DeclareRoles("TutorialUser")
public class ConverterBean{

    @Resource SessionContext ctx;
    private BigDecimal yenRate = new BigDecimal("89.5094");
    private BigDecimal euroRate = new BigDecimal("0.0081");

    @RolesAllowed("TutorialUser")
     public BigDecimal dollarToYen(BigDecimal dollars) {
        BigDecimal result = new BigDecimal("0.0");
        Principal callerPrincipal = ctx.getCallerPrincipal();
        if (ctx.isCallerInRole("TutorialUser")) {
            result = dollars.multiply(yenRate);
            return result.setScale(2, BigDecimal.ROUND_UP);
        } else {
            return result.setScale(2, BigDecimal.ROUND_UP);
        }
    }

    @RolesAllowed("TutorialUser")
    public BigDecimal yenToEuro(BigDecimal yen) {
        BigDecimal result = new BigDecimal("0.0");
        Principal callerPrincipal = ctx.getCallerPrincipal();
        if (ctx.isCallerInRole("TutorialUser")) {
             result = yen.multiply(euroRate);
             return result.setScale(2, BigDecimal.ROUND_UP);
        } else {
             return result.setScale(2, BigDecimal.ROUND_UP);
        }
    }
}
```

Modifying `ConverterServlet`

The following annotations specify security for the `converter` web client, `ConverterServlet`:

```
@WebServlet(name = "ConverterServlet", urlPatterns = {"/"})
@ServletSecurity(
@HttpConstraint(transportGuarantee = TransportGuarantee.CONFIDENTIAL,
    rolesAllowed = {"TutorialUser"}))
```

▼ To Build, Package, and Deploy the Secure Converter Example Using NetBeans IDE

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In NetBeans IDE, from the File menu, choose Open Project.**
3. **In the Open Project dialog, navigate to:**
   tut-install`/examples/security/`
4. **Select the `converter-secure` folder.**
5. **Select the Open as Main Project check box.**
6. **Click Open Project.**
7. **Right-click the `converter-secure` project and select Build.**
8. **Right-click the `converter-secure` project and select Deploy.**

▼ To Build, Package, and Deploy the Secure Converter Example Using Ant

1. **Follow the steps in "To Set Up Your System for Running the Security Examples" on page 689.**
2. **In a terminal window, go to:**
   tut-install`/examples/security/converter-secure/`
3. **Type the following command:**
   ```
   ant all
   ```
   This command both builds and deploys the example.

▼ To Run the Secure Converter Example

1. **Open a web browser to the following URL:**
   ```
   http://localhost:8080/converter-secure
   ```
   An Authentication Required dialog box appears.
2. **Type a user name and password combination that corresponds to a user who has already been created in the `file` realm of the GlassFish Server and has been assigned to the group of `TutorialUser`; then click OK.**
   The screen shown in Figure 23–1 appears.

3 **Type `100` in the input field and click Submit.**

A second page appears, showing the converted values.

Securing Application Clients

The Java EE authentication requirements for application clients are the same as for other Java EE components, and the same authentication techniques can be used as for other Java EE application components. No authentication is necessary when accessing unprotected web resources.

When accessing protected web resources, the usual varieties of authentication can be used: HTTP basic authentication, SSL client authentication, or HTTP login-form authentication. These authentication methods are discussed in "Specifying an Authentication Mechanism in the Deployment Descriptor" on page 682.

Authentication is required when accessing protected enterprise beans. The authentication mechanisms for enterprise beans are discussed in "Securing Enterprise Beans" on page 701.

An application client makes use of an authentication service provided by the application client container for authenticating its users. The container's service can be integrated with the native platform's authentication system, so that a single sign-on capability is used. The container can authenticate the user either when the application is started or when a protected resource is accessed.

An application client can provide a class, called a login module, to gather authentication data. If so, the `javax.security.auth.callback.CallbackHandler` interface must be implemented, and the class name must be specified in its deployment descriptor. The application's callback handler must fully support `Callback` objects specified in the `javax.security.auth.callback` package.

Using Login Modules

An application client can use the Java Authentication and Authorization Service (JAAS) to create *login modules* for authentication. A JAAS-based application implements the `javax.security.auth.callback.CallbackHandler` interface so that it can interact with users to enter specific authentication data, such as user names or passwords, or to display error and warning messages.

Applications implement the `CallbackHandler` interface and pass it to the login context, which forwards it directly to the underlying login modules. A login module uses the callback handler both to gather input, such as a password or smart card PIN, from users and to supply information, such as status information, to users. Because the application specifies the callback handler, an underlying login module can remain independent of the various ways that applications interact with users.

For example, the implementation of a callback handler for a GUI application might display a window to solicit user input. Or the implementation of a callback handler for a command-line tool might simply prompt the user for input directly from the command line.

The login module passes an array of appropriate callbacks to the callback handler's `handle` method, such as a `NameCallback` for the user name and a `PasswordCallback` for the password; the callback handler performs the requested user interaction and sets appropriate values in the callbacks. For example, to process a `NameCallback`, the `CallbackHandler` might prompt for a name, retrieve the value from the user, and call the `setName` method of the `NameCallback` to store the name.

For more information on using JAAS for login modules for authentication, refer to the following sources (see "Further Information about Security" on page 669 for the URLs):

- *Java Authentication and Authorization Service (JAAS) Reference Guide*
- *Java Authentication and Authorization Service (JAAS): LoginModule Developer's Guide*

Using Programmatic Login

Programmatic login enables the client code to supply user credentials. If you are using an EJB client, you can use the `com.sun.appserv.security.ProgrammaticLogin` class with its convenient `login` and `logout` methods. Programmatic login is specific to a server.

Securing Enterprise Information Systems Applications

In EIS applications, components request a connection to an EIS resource. As part of this connection, the EIS can require a sign-on for the requester to access the resource. The application component provider has two choices for the design of the EIS sign-on:

- **Container-managed sign-on**: The application component lets the container take the responsibility of configuring and managing the EIS sign-on. The container determines the user name and password for establishing a connection to an EIS instance. For more information, see "Container-Managed Sign-On" on page 721.
- **Component-managed sign-on**: The application component code manages EIS sign-on by including code that performs the sign-on process to an EIS. For more information, see "Component-Managed Sign-On" on page 721.

You can also configure security for resource adapters. See "Configuring Resource Adapter Security" on page 721 for more information.

Container-Managed Sign-On

In container-managed sign-on, an application component does not have to pass any sign-on security information to the `getConnection()` method. The security information is supplied by the container, as shown in the following example:

```
// Business method in an application component
Context initctx = new InitialContext();
// Perform JNDI lookup to obtain a connection factory
javax.resource.cci.ConnectionFactory cxf =
    (javax.resource.cci.ConnectionFactory)initctx.lookup(
    "java:comp/env/eis/MainframeCxFactory");
// Invoke factory to obtain a connection. The security
// information is not passed in the getConnection method
javax.resource.cci.Connection cx = cxf.getConnection();
...
```

Component-Managed Sign-On

In component-managed sign-on, an application component is responsible for passing the needed sign-on security information to the resource to the `getConnection` method. For example, security information might be a user name and password, as shown here:

```
// Method in an application component
Context initctx = new InitialContext();

// Perform JNDI lookup to obtain a connection factory
javax.resource.cci.ConnectionFactory cxf =
    (javax.resource.cci.ConnectionFactory)initctx.lookup(
    "java:comp/env/eis/MainframeCxFactory");

// Get a new ConnectionSpec
com.myeis.ConnectionSpecImpl properties = //..

// Invoke factory to obtain a connection
properties.setUserName("...");
properties.setPassword("...");
javax.resource.cci.Connection cx =
    cxf.getConnection(properties);
...
```

Configuring Resource Adapter Security

A resource adapter is a system-level software component that typically implements network connectivity to an external resource manager. A resource adapter can extend the functionality of the Java EE platform either by implementing one of the Java EE standard service APIs, such as a JDBC driver, or by defining and implementing a resource adapter for a connector to an external application system. Resource adapters can also provide services that are entirely local, perhaps interacting with native resources. Resource adapters interface with the Java EE

platform through the Java EE service provider interfaces (Java EE SPI). A resource adapter that uses the Java EE SPIs to attach to the Java EE platform will be able to work with all Java EE products.

To configure the security settings for a resource adapter, you need to edit the resource adapter descriptor file, `ra.xml`. Here is an example of the part of an `ra.xml` file that configures the following security properties for a resource adapter:

```
<authentication-mechanism>
    <authentication-mechanism-type>
        BasicPassword
    </authentication-mechanism-type>
    <credential-interface>
        javax.resource.spi.security.PasswordCredential
    </credential-interface>
</authentication-mechanism>
<reauthentication-support>false</reauthentication-support>
```

You can find out more about the options for configuring resource adapter security by reviewing *as-install*`/lib/dtds/connector_1_0.dtd`. You can configure the following elements in the resource adapter deployment descriptor file:

- **Authentication mechanisms**: Use the `authentication-mechanism` element to specify an authentication mechanism supported by the resource adapter. This support is for the resource adapter, not for the underlying EIS instance.

  There are two supported mechanism types:

  - `BasicPassword`, which supports the following interface:

    ```
    javax.resource.spi.security.PasswordCredential
    ```

  - `Kerbv5`, which supports the following interface:

    ```
    javax.resource.spi.security.GenericCredential
    ```

    The GlassFish Server does not currently support this mechanism type.

- **Reauthentication support**: Use the `reauthentication-support` element to specify whether the resource adapter implementation supports reauthentication of existing `Managed-Connection` instances. Options are `true` or `false`.
- **Security permissions**: Use the `security-permission` element to specify a security permission that is required by the resource adapter code. Support for security permissions is optional and is not supported in the current release of the GlassFish Server. You can, however, manually update the `server.policy` file to add the relevant permissions for the resource adapter.

  The security permissions listed in the deployment descriptor are different from those required by the default permission set as specified in the connector specification.

  For more information on the implementation of the security permission specification, visit `http://download.oracle.com/javase/6/docs/technotes/guides/security/PolicyFiles.html#FileSyntax`.

In addition to specifying resource adapter security in the `ra.xml` file, you can create a security map for a connector connection pool to map an application principal or a user group to a back-end EIS principal. The security map is usually used if one or more EIS back-end principals are used to execute operations (on the EIS) initiated by various principals or user groups in the application.

▼ To Map an Application Principal to EIS Principals

When using the GlassFish Server, you can use security maps to map the caller identity of the application (principal or user group) to a suitable EIS principal in container-managed transaction-based scenarios. When an application principal initiates a request to an EIS, the GlassFish Server first checks for an exact principal by using the security map defined for the connector connection pool to determine the mapped back-end EIS principal. If there is no exact match, the GlassFish Server uses the wildcard character specification, if any, to determine the mapped back-end EIS principal. Security maps are used when an application user needs to execute EIS operations that require to be executed as a specific identity in the EIS.

To work with security maps, use the Administration Console. From the Administration Console, follow these steps to get to the security maps page.

1. **In the navigation tree, expand the Resources node.**
2. **Expand the Connectors node.**
3. **Select the Connector Connection Pools node.**
4. **On the Connector Connection Pools page, click the name of the connection pool for which you want to create a security map.**
5. **Click the Security Maps tab.**
6. **Click New to create a new security map for the connection pool.**
7. **Type a name by which you will refer to the security map, as well as the other required information.**

   Click the Help button for more information on the individual options.

PART VIII

Java EE Supporting Technologies

Part VIII explores several technologies that support the Java EE platform. This part contains the following chapters:

◆ ◆ ◆ CHAPTER 42

Introduction to Java EE Supporting Technologies

The Java EE platform includes several technologies and APIs that extend its functionality. These technologies allow applications to access a wide range of services in a uniform manner. These technologies are explained in greater detail in Chapter 43, "Transactions," and Chapter 44, "Resource Connections," as well as Chapter 45, "Java Message Service Concepts," Chapter 46, "Java Message Service Examples," and Chapter 47, "Advanced Bean Validation Concepts and Examples."

The following topics are addressed here:

Transactions

In a Java EE application, a transaction is a series of actions that must all complete successfully, or else all the changes in each action are backed out. Transactions end in either a commit or a rollback.

The Java Transaction API (JTA) allows applications to access transactions in a manner that is independent of specific implementations. JTA specifies standard Java interfaces between a transaction manager and the parties involved in a distributed transaction system: the transactional application, the Java EE server, and the manager that controls access to the shared resources affected by the transactions.

The JTA defines the `UserTransaction` interface that applications use to start, commit, or abort transactions. Application components get a `UserTransaction` object through a JNDI lookup by using the name `java:comp/UserTransaction` or by requesting injection of a `UserTransaction` object. An application server uses a number of JTA-defined interfaces to communicate with a transaction manager; a transaction manager uses JTA-defined interfaces to interact with a resource manager.

See Chapter 43, "Transactions," for a more detailed explanation. The JTA 1.1 specification is available at `http://www.oracle.com/technetwork/java/javaee/tech/jta-138684.html`.

Resources

A resource is a program object that provides connections to such systems as database servers and messaging systems.

The Java EE Connector Architecture and Resource Adapters

The Java EE Connector Architecture enables Java EE components to interact with enterprise information systems (EISs) and EISs to interact with Java EE components. EIS software includes such kinds of systems as enterprise resource planning (ERP), mainframe transaction processing, and nonrelational databases. Connector architecture simplifies the integration of diverse EISs. Each EIS requires only one implementation of the Connector architecture. Because it adheres to the Connector specification, an implementation is portable across all compliant Java EE servers.

The specification defines the contracts for an application server as well as for resource adapters, which are system-level software drivers for specific EIS resources. These standard contracts provide pluggability between application servers and EISs. The Java EE Connector Architecture 1.6 specification defines new system contracts such as Generic Work Context and Security Inflow. The Java EE Connector Architecture 1.6 specification is available at `http://jcp.org/en/jsr/detail?id=322`.

A resource adapter is a Java EE component that implements the Connector architecture for a specific EIS. A resource adapter can choose to support the following levels of transactions:

- `NoTransaction`: No transaction support is provided.
- `LocalTransaction`: Resource manager local transactions are supported.
- `XATransaction`: The resource adapter supports the XA distributed transaction processing model and the JTA `XATransaction` interface.

See Chapter 44, "Resource Connections," for a more detailed explanation of resource adapters.

Java Database Connectivity Software

To store, organize, and retrieve data, most applications use relational databases. Java EE applications access relational databases through the JDBC API.

A JDBC resource, or data source, provides applications with a means of connecting to a database. Typically, a JDBC resource is created for each database accessed by the applications deployed in a domain. Transactional access to JDBC resources is available from servlets, JavaServer Faces pages, and enterprise beans. The connection pooling and distributed transaction features are intended for use by JDBC drivers to coordinate with an application server. For more information, see "`DataSource` Objects and Connection Pools" on page 744.

Java Message Service

Messaging is a method of communication between software components or applications. A messaging system is a peer-to-peer facility: A messaging client can send messages to, and receive messages from, any other client. Each client connects to a messaging agent that provides facilities for creating, sending, receiving, and reading messages.

The Java Message Service (JMS) API allows applications to create, send, receive, and read messages. It defines a common set of interfaces and associated semantics that allow programs written in the Java programming language to communicate with other messaging implementations.

The JMS API minimizes the set of concepts a programmer must learn in order to use messaging products but provides enough features to support sophisticated messaging applications. It also strives to maximize the portability of JMS applications across JMS providers in the same messaging domain.

◆ ◆ ◆ CHAPTER 43

Transactions

A typical enterprise application accesses and stores information in one or more databases. Because this information is critical for business operations, it must be accurate, current, and reliable. Data integrity would be lost if multiple programs were allowed to update the same information simultaneously or if a system that failed while processing a business transaction were to leave the affected data only partially updated. By preventing both of these scenarios, software transactions ensure data integrity. Transactions control the concurrent access of data by multiple programs. In the event of a system failure, transactions make sure that after recovery, the data will be in a consistent state.

The following topics are addressed here:

What Is a Transaction?

To emulate a business transaction, a program may need to perform several steps. A financial program, for example, might transfer funds from a checking account to a savings account by using the steps listed in the following pseudocode:

```
begin transaction
    debit checking account
    credit savings account
    update history log
commit transaction
```

Either all or none of the three steps must complete. Otherwise, data integrity is lost. Because the steps within a transaction are a unified whole, a *transaction* is often defined as an indivisible unit of work.

A transaction can end in two ways: with a commit or with a rollback. When a transaction commits, the data modifications made by its statements are saved. If a statement within a transaction fails, the transaction rolls back, undoing the effects of all statements in the transaction. In the pseudocode, for example, if a disk drive were to crash during the `credit` step, the transaction would roll back and undo the data modifications made by the `debit` statement. Although the transaction fails, data integrity would be intact because the accounts still balance.

In the preceding pseudocode, the `begin` and `commit` statements mark the boundaries of the transaction. When designing an enterprise bean, you determine how the boundaries are set by specifying either container-managed or bean-managed transactions.

Container-Managed Transactions

In an enterprise bean with *container-managed transaction demarcation*, the EJB container sets the boundaries of the transactions. You can use container-managed transactions with any type of enterprise bean: session or message-driven. Container-managed transactions simplify development because the enterprise bean code does not explicitly mark the transaction's boundaries. The code does not include statements that begin and end the transaction. By default, if no transaction demarcation is specified, enterprise beans use container-managed transaction demarcation.

Typically, the container begins a transaction immediately before an enterprise bean method starts and commits the transaction just before the method exits. Each method can be associated with a single transaction. Nested or multiple transactions are not allowed within a method.

Container-managed transactions do not require all methods to be associated with transactions. When developing a bean, you can set the transaction attributes to specify which of the bean's methods are associated with transactions.

Enterprise beans that use container-managed transaction demarcation must not use any transaction-management methods that interfere with the container's transaction demarcation boundaries. Examples of such methods are the `commit`, `setAutoCommit`, and `rollback` methods of `java.sql.Connection` or the `commit` and `rollback` methods of `javax.jms.Session`. If you require control over the transaction demarcation, you must use application-managed transaction demarcation.

Enterprise beans that use container-managed transaction demarcation also must not use the `javax.transaction.UserTransaction` interface.

Transaction Attributes

A *transaction attribute* controls the scope of a transaction. Figure 43–1 illustrates why controlling the scope is important. In the diagram, `method-A` begins a transaction and then invokes `method-B` of `Bean-2`. When `method-B` executes, does it run within the scope of the transaction started by `method-A`, or does it execute with a new transaction? The answer depends on the transaction attribute of `method-B`.

FIGURE 43–1 Transaction Scope



A transaction attribute can have one of the following values:

- `Required`
- `RequiresNew`
- `Mandatory`
- `NotSupported`
- `Supports`
- `Never`

`Required` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the method executes within the client's transaction. If the client is not associated with a transaction, the container starts a new transaction before running the method.

The `Required` attribute is the implicit transaction attribute for all enterprise bean methods running with container-managed transaction demarcation. You typically do not set the `Required` attribute unless you need to override another transaction attribute. Because transaction attributes are declarative, you can easily change them later.

`RequiresNew` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the container takes the following steps:

1. Suspends the client's transaction
2. Starts a new transaction
3. Delegates the call to the method
4. Resumes the client's transaction after the method completes

If the client is not associated with a transaction, the container starts a new transaction before running the method.

You should use the `RequiresNew` attribute when you want to ensure that the method always runs within a new transaction.

`Mandatory` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the method executes within the client's transaction. If the client is not associated with a transaction, the container throws a `TransactionRequiredException`.

Use the `Mandatory` attribute if the enterprise bean's method must use the transaction of the client.

`NotSupported` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the container suspends the client's transaction before invoking the method. After the method has completed, the container resumes the client's transaction.

If the client is not associated with a transaction, the container does not start a new transaction before running the method.

Use the `NotSupported` attribute for methods that don't need transactions. Because transactions involve overhead, this attribute may improve performance.

`Supports` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the method executes within the client's transaction. If the client is not associated with a transaction, the container does not start a new transaction before running the method.

Because the transactional behavior of the method may vary, you should use the `Supports` attribute with caution.

`Never` Attribute

If the client is running within a transaction and invokes the enterprise bean's method, the container throws a `RemoteException`. If the client is not associated with a transaction, the container does not start a new transaction before running the method.

Summary of Transaction Attributes

Table 43–1 summarizes the effects of the transaction attributes. Both the `T1` and the `T2` transactions are controlled by the container. A `T1` transaction is associated with the client that calls a method in the enterprise bean. In most cases, the client is another enterprise bean. A `T2` transaction is started by the container just before the method executes.

In the last column of Table 43–1, the word "None" means that the business method does not execute within a transaction controlled by the container. However, the database calls in such a business method might be controlled by the transaction manager of the database management system.

TABLE 43–1 Transaction Attributes and Scope

Transaction Attribute	Client's Transaction	Business Method's Transaction
`Required`	None	T2
	T1	T1
`RequiresNew`	None	T2
	T1	T2
`Mandatory`	None	Error
	T1	T1
`NotSupported`	None	None
	T1	None
`Supports`	None	None
	T1	T1
`Never`	None	None
	T1	Error

Setting Transaction Attributes

Transaction attributes are specified by decorating the enterprise bean class or method with a `javax.ejb.TransactionAttribute` annotation and setting it to one of the `javax.ejb.TransactionAttributeType` constants.

If you decorate the enterprise bean class with `@TransactionAttribute`, the specified `TransactionAttributeType` is applied to all the business methods in the class. Decorating a business method with `@TransactionAttribute` applies the `TransactionAttributeType` only to that method. If a `@TransactionAttribute` annotation decorates both the class and the method, the method `TransactionAttributeType` overrides the class `TransactionAttributeType`.

The `TransactionAttributeType` constants shown in Table 43–2 encapsulate the transaction attributes described earlier in this section.

TABLE 43–2 `TransactionAttributeType` Constants

Transaction Attribute	`TransactionAttributeType` Constant
`Required`	`TransactionAttributeType.REQUIRED`
`RequiresNew`	`TransactionAttributeType.REQUIRES_NEW`
`Mandatory`	`TransactionAttributeType.MANDATORY`
`NotSupported`	`TransactionAttributeType.NOT_SUPPORTED`
`Supports`	`TransactionAttributeType.SUPPORTS`
`Never`	`TransactionAttributeType.NEVER`

The following code snippet demonstrates how to use the `@TransactionAttribute` annotation:

```
@TransactionAttribute(NOT_SUPPORTED)
@Stateful
public class TransactionBean implements Transaction {
...
    @TransactionAttribute(REQUIRES_NEW)
    public void firstMethod() {...}

    @TransactionAttribute(REQUIRED)
    public void secondMethod() {...}

    public void thirdMethod() {...}

    public void fourthMethod() {...}
}
```

In this example, the `TransactionBean` class's transaction attribute has been set to `NotSupported`, `firstMethod` has been set to `RequiresNew`, and `secondMethod` has been set to `Required`. Because a `@TransactionAttribute` set on a method overrides the class `@TransactionAttribute`, calls to `firstMethod` will create a new transaction, and calls to `secondMethod` will either run in the current transaction or start a new transaction. Calls to `thirdMethod` or `fourthMethod` do not take place within a transaction.

Rolling Back a Container-Managed Transaction

There are two ways to roll back a container-managed transaction. First, if a system exception is thrown, the container will automatically roll back the transaction. Second, by invoking the `setRollbackOnly` method of the `EJBContext` interface, the bean method instructs the container to roll back the transaction. If the bean throws an application exception, the rollback is not automatic but can be initiated by a call to `setRollbackOnly`.

Synchronizing a Session Bean's Instance Variables

The `SessionSynchronization` interface, which is optional, allows stateful session bean instances to receive transaction synchronization notifications. For example, you could synchronize the instance variables of an enterprise bean with their corresponding values in the database. The container invokes the `SessionSynchronization` methods (`afterBegin`, `beforeCompletion`, and `afterCompletion`) at each of the main stages of a transaction.

The `afterBegin` method informs the instance that a new transaction has begun. The container invokes `afterBegin` immediately before it invokes the business method.

The container invokes the `beforeCompletion` method after the business method has finished but just before the transaction commits. The `beforeCompletion` method is the last opportunity for the session bean to roll back the transaction (by calling `setRollbackOnly`).

The `afterCompletion` method indicates that the transaction has completed. This method has a single `boolean` parameter whose value is `true` if the transaction was committed and `false` if it was rolled back.

Methods Not Allowed in Container-Managed Transactions

You should not invoke any method that might interfere with the transaction boundaries set by the container. The list of prohibited methods follows:

- The `commit`, `setAutoCommit`, and `rollback` methods of `java.sql.Connection`
- The `getUserTransaction` method of `javax.ejb.EJBContext`
- Any method of `javax.transaction.UserTransaction`

You can, however, use these methods to set boundaries in application-managed transactions.

Bean-Managed Transactions

In *bean-managed transaction demarcation*, the code in the session or message-driven bean explicitly marks the boundaries of the transaction. Although beans with container-managed transactions require less coding, they have one limitation: When a method is executing, it can be associated with either a single transaction or no transaction at all. If this limitation will make coding your bean difficult, you should consider using bean-managed transactions.

The following pseudocode illustrates the kind of fine-grained control you can obtain with application-managed transactions. By checking various conditions, the pseudocode decides whether to start or stop certain transactions within the business method:

```
begin transaction
...
    update table-a
...
    if (condition-x)
   commit transaction
    else if (condition-y)
   update table-b
   commit transaction
    else
   rollback transaction
   begin transaction
   update table-c
   commit transaction
```

When coding an application-managed transaction for session or message-driven beans, you must decide whether to use Java Database Connectivity or JTA transactions. The sections that follow discuss both types of transactions.

JTA Transactions

JTA, or the Java Transaction API, allows you to demarcate transactions in a manner that is independent of the transaction manager implementation. GlassFish Server implements the transaction manager with the Java Transaction Service (JTS). However, your code doesn't call the JTS methods directly but instead invokes the JTA methods, which then call the lower-level JTS routines.

A *JTA transaction* is controlled by the Java EE transaction manager. You may want to use a JTA transaction because it can span updates to multiple databases from different vendors. A particular DBMS's transaction manager may not work with heterogeneous databases. However, the Java EE transaction manager does have one limitation: It does not support nested transactions. In other words, it cannot start a transaction for an instance until the preceding transaction has ended.

To demarcate a JTA transaction, you invoke the `begin`, `commit`, and `rollback` methods of the `javax.transaction.UserTransaction` interface.

Returning without Committing

In a stateless session bean with bean-managed transactions, a business method must commit or roll back a transaction before returning. However, a stateful session bean does not have this restriction.

In a stateful session bean with a JTA transaction, the association between the bean instance and the transaction is retained across multiple client calls. Even if each business method called by the client opens and closes the database connection, the association is retained until the instance completes the transaction.

In a stateful session bean with a JDBC transaction, the JDBC connection retains the association between the bean instance and the transaction across multiple calls. If the connection is closed, the association is not retained.

Methods Not Allowed in Bean-Managed Transactions

Do not invoke the `getRollbackOnly` and `setRollbackOnly` methods of the `EJBContext` interface in bean-managed transactions. These methods should be used only in container-managed transactions. For bean-managed transactions, invoke the `getStatus` and `rollback` methods of the `UserTransaction` interface.

Transaction Timeouts

For container-managed transactions, you can use the Administration Console to configure the transaction timeout interval. See "Starting the Administration Console" on page 72.

For enterprise beans with bean-managed JTA transactions, you invoke the `setTransactionTimeout` method of the `UserTransaction` interface.

▼ To Set a Transaction Timeout

1. **In the Administration Console, expand the Configurations node, then expand the server-config node and select Transaction Service.**

2. **On the Transaction Service page, set the value of the Transaction Timeout field to the value of your choice (for example, 5).**

   With this setting, if the transaction has not completed within 5 seconds, the EJB container rolls it back.

   The default value is 0, meaning that the transaction will not time out.

3 **Click Save.**

Updating Multiple Databases

The Java EE transaction manager controls all enterprise bean transactions except for bean-managed JDBC transactions. The Java EE transaction manager allows an enterprise bean to update multiple databases within a transaction. Figure 43–2 and Figure 43–3 show two scenarios for updating multiple databases in a single transaction.

In Figure 43–2, the client invokes a business method in `Bean-A`. The business method begins a transaction, updates Database X, updates Database Y, and invokes a business method in `Bean-B`. The second business method updates Database Z and returns control to the business method in `Bean-A`, which commits the transaction. All three database updates occur in the same transaction.

In Figure 43–3, the client calls a business method in `Bean-A`, which begins a transaction and updates Database X. Then `Bean-A` invokes a method in `Bean-B`, which resides in a remote Java EE server. The method in `Bean-B` updates Database Y. The transaction managers of the Java EE servers ensure that both databases are updated in the same transaction.

FIGURE 43–2 Updating Multiple Databases



FIGURE 43–3 Updating Multiple Databases across Java EE Servers



Transactions in Web Components

You can demarcate a transaction in a web component by using either the `java.sql.Connection` or the `javax.transaction.UserTransaction` interface. These are the same interfaces that a session bean with bean-managed transactions can use. Transactions demarcated with the `UserTransaction` interface are discussed in "JTA Transactions" on page 738.

Further Information about Transactions

For more information about transactions, see

- Java Transaction API 1.1 specification:

  `http://www.oracle.com/technetwork/java/javaee/tech/jta-138684.html`

◆ ◆ ◆ CHAPTER 44

Resource Connections

Java EE components can access a wide variety of resources, including databases, mail sessions, Java Message Service objects, and URLs. The Java EE 6 platform provides mechanisms that allow you to access all these resources in a similar manner. This chapter explains how to get connections to several types of resources.

The following topics are addressed here:

Resources and JNDI Naming

In a distributed application, components need to access other components and resources, such as databases. For example, a servlet might invoke remote methods on an enterprise bean that retrieves information from a database. In the Java EE platform, the Java Naming and Directory Interface (JNDI) naming service enables components to locate other components and resources.

A *resource* is a program object that provides connections to systems, such as database servers and messaging systems. (A Java Database Connectivity resource is sometimes referred to as a data source.) Each resource object is identified by a unique, people-friendly name, called the JNDI name. For example, the JNDI name of the JDBC resource for the Java DB database that is shipped with the GlassFish Server is `jdbc/__default`.

An administrator creates resources in a JNDI namespace. In the GlassFish Server, you can use either the Administration Console or the `asadmin` command to create resources. Applications

then use annotations to inject the resources. If an application uses resource injection, the GlassFish Server invokes the JNDI API, and the application is not required to do so. However, it is also possible for an application to locate resources by making direct calls to the JNDI API.

A resource object and its JNDI name are bound together by the naming and directory service. To create a new resource, a new name/object binding is entered into the JNDI namespace. You inject resources by using the `@Resource` annotation in an application.

You can use a deployment descriptor to override the resource mapping that you specify in an annotation. Using a deployment descriptor allows you to change an application by repackaging it rather than by both recompiling the source files and repackaging. However, for most applications, a deployment descriptor is not necessary.

`DataSource` Objects and Connection Pools

To store, organize, and retrieve data, most applications use a relational database. Java EE 6 components may access relational databases through the JDBC API. For information on this API, see `http://www.oracle.com/technetwork/java/javase/tech/index-jsp-136101.html`.

In the JDBC API, databases are accessed by using `DataSource` objects. A `DataSource` has a set of properties that identify and describe the real-world data source that it represents. These properties include such information as the location of the database server, the name of the database, the network protocol to use to communicate with the server, and so on. In the GlassFish Server, a data source is called a JDBC resource.

Applications access a data source by using a connection, and a `DataSource` object can be thought of as a factory for connections to the particular data source that the `DataSource` instance represents. In a basic `DataSource` implementation, a call to the `getConnection` method returns a connection object that is a physical connection to the data source.

A `DataSource` object may be registered with a JNDI naming service. If so, an application can use the JNDI API to access that `DataSource` object, which can then be used to connect to the data source it represents.

`DataSource` objects that implement connection pooling also produce a connection to the particular data source that the `DataSource` class represents. The connection object that the `getConnection` method returns is a handle to a `PooledConnection` object rather than being a physical connection. An application uses the connection object in the same way that it uses a connection. Connection pooling has no effect on application code except that a pooled connection, like all connections, should always be explicitly closed. When an application closes a connection that is pooled, the connection is returned to a pool of reusable connections. The next time `getConnection` is called, a handle to one of these pooled connections will be returned if one is available. Because connection pooling avoids creating a new physical connection every time one is requested, applications can run significantly faster.

A JDBC connection pool is a group of reusable connections for a particular database. Because creating each new physical connection is time consuming, the server maintains a pool of available connections to increase performance. When it requests a connection, an application obtains one from the pool. When an application closes a connection, the connection is returned to the pool.

Applications that use the Persistence API specify the `DataSource` object they are using in the `jta-data-source` element of the `persistence.xml` file:

```
<jta-data-source>jdbc/MyOrderDB</jta-data-source>
```

This is typically the only reference to a JDBC object for a persistence unit. The application code does not refer to any JDBC objects.

Resource Injection

The `javax.annotation.Resource` annotation is used to declare a reference to a resource; `@Resource` can decorate a class, a field, or a method. The container will inject the resource referred to by `@Resource` into the component either at runtime or when the component is initialized, depending on whether field/method injection or class injection is used. With field-based and method-based injection, the container will inject the resource when the application is initialized. For class-based injection, the resource is looked up by the application at runtime.

The `@Resource` annotation has the following elements:

- `name`: The JNDI name of the resource
- `type`: The Java language type of the resource
- `authenticationType`: The authentication type to use for the resource
- `shareable`: Indicates whether the resource can be shared
- `mappedName`: A nonportable, implementation-specific name to which the resource should be mapped
- `description`: The description of the resource

The `name` element is the JNDI name of the resource and is optional for field-based and method-based injection. For field-based injection, the default `name` is the field name qualified by the class name. For method-based injection, the default `name` is the JavaBeans property name, based on the method qualified by the class name. The `name` element must be specified for class-based injection.

The type of resource is determined by one of the following:

- The type of the field the `@Resource` annotation is decorating for field-based injection
- The type of the JavaBeans property the `@Resource` annotation is decorating for method-based injection
- The `type` element of `@Resource`

For class-based injection, the `type` element is required.

The `authenticationType` element is used only for connection factory resources, such as the resources of a connector, also called the resource adapter, or data source. This element can be set to one of the `javax.annotation.Resource.AuthenticationType` enumerated type values: `CONTAINER`, the default, and `APPLICATION`.

The `shareable` element is used only for Object Resource Broker (ORB) instance resources or connection factory resource. This element indicates whether the resource can be shared between this component and other components and may be set to `true`, the default, or `false`.

The `mappedName` element is a nonportable, implementation-specific name to which the resource should be mapped. Because the `name` element, when specified or defaulted, is local only to the application, many Java EE servers provide a way of referring to resources across the application server. This is done by setting the `mappedName` element. Use of the `mappedName` element is nonportable across Java EE server implementations.

The `description` element is the description of the resource, typically in the default language of the system on which the application is deployed. This element is used to help identify resources and to help application developers choose the correct resource.

Field-Based Injection

To use field-based resource injection, declare a field and decorate it with the `@Resource` annotation. The container will infer the name and type of the resource if the `name` and `type` elements are not specified. If you do specify the `type` element, it must match the field's `type` declaration.

In the following code, the container infers the `name` of the resource, based on the class name and the field name: `com.example.SomeClass/myDB`. The inferred `type` is `javax.sql.DataSource.class`:

```
package com.example;

public class SomeClass {
    @Resource
    private javax.sql.DataSource myDB;
...
}
```

In the following code, the JNDI name is `customerDB`, and the inferred `type` is `javax.sql.DataSource.class`:

```
package com.example;

public class SomeClass {
    @Resource(name="customerDB")
    private javax.sql.DataSource myDB;
...
}
```

Method-Based Injection

To use method-based injection, declare a setter method and decorate it with the `@Resource` annotation. The container will infer the name and type of the resource if the `name` and `type` elements are not specified. The setter method must follow the JavaBeans conventions for property names: The method name must begin with `set`, have a `void` return type, and only one parameter. If you do specify the `type` element, it must match the field's type declaration.

In the following code, the container infers the `name` of the resource based on the class name and the field name: `com.example.SomeClass/myDB`. The inferred `type` is `javax.sql.DataSource.class`:

```
package com.example;

public class SomeClass {

    private javax.sql.DataSource myDB;
...
    @Resource
    private void setMyDB(javax.sql.DataSource ds) {
        myDB = ds;
    }
...
}
```

In the following code, the JNDI name is `customerDB`, and the inferred `type` is `javax.sql.DataSource.class`:

```
package com.example;

public class SomeClass {

    private javax.sql.DataSource myDB;
...
    @Resource(name="customerDB")
    private void setMyDB(javax.sql.DataSource ds) {
        myDB = ds;
    }
...
}
```

Class-Based Injection

To use class-based injection, decorate the class with a `@Resource` annotation, and set the required `name` and `type` elements:

```
@Resource(name="myMessageQueue",
                type="javax.jms.ConnectionFactory")
public class SomeMessageBean {
...
}
```

The `@Resources` annotation is used to group together multiple `@Resource` declarations for class-based injection. The following code shows the `@Resources` annotation containing two `@Resource` declarations. One is a Java Message Service message queue, and the other is a JavaMail session:

```
@Resources({
    @Resource(name="myMessageQueue",
                    type="javax.jms.ConnectionFactory"),
    @Resource(name="myMailSession",
                    type="javax.mail.Session")
})
public class SomeMessageBean {
...
}
```

Resource Adapters and Contracts

A resource adapter is a Java EE component that implements the Java EE Connector Architecture for a specific EIS. Examples of EISs include enterprise resource planning, mainframe transaction processing, and database systems. As illustrated in Figure 44–1, the resource adapter facilitates communication between a Java EE application and an EIS.

FIGURE 44–1 Resource Adapters



Stored in a Resource Adapter Archive (RAR) file, a resource adapter can be deployed on any Java EE server, much like a Java EE application. A RAR file may be contained in an Enterprise Archive (EAR) file, or it may exist as a separate file.

A resource adapter is analogous to a JDBC driver. Both provide a standard API through which an application can access a resource that is outside the Java EE server. For a resource adapter, the target system is an EIS; for a JDBC driver, it is a DBMS. Resource adapters and JDBC drivers are rarely created by application developers. In most cases, both types of software are built by vendors that sell tools, servers, or integration software.

The resource adapter mediates communication between the Java EE server and the EIS by means of contracts. The application contract defines the API through which a Java EE component, such as an enterprise bean, accesses the EIS. This API is the only view that the component has of the EIS. The system contracts link the resource adapter to important services that are managed by the Java EE server. The resource adapter itself and its system contracts are transparent to the Java EE component.

Management Contracts

The Java EE Connector Architecture defines system contracts that enable resource adapter lifecycle and thread management.

Lifecycle Management

The Connector Architecture specifies a lifecycle management contract that allows an application server to manage the lifecycle of a resource adapter. This contract provides a mechanism for the application server to bootstrap a resource adapter instance during the deployment or application server startup. This contract also provides a means for the application server to notify the resource adapter instance when it is undeployed or when an orderly shutdown of the application server takes place.

Work Management Contract

The Connector Architecture work management contract ensures that resource adapters use threads in the proper, recommended manner. This contract also enables an application server to manage threads for resource adapters.

Resource adapters that improperly use threads can jeopardize the entire application server environment. For example, a resource adapter might create too many threads or might not properly release threads it has created. Poor thread handling inhibits application server shutdown and impacts the application server's performance because creating and destroying threads are expensive operations.

The work management contract establishes a means for the application server to pool and reuse threads, similar to pooling and reusing connections. By adhering to this contract, the resource adapter does not have to manage threads itself. Instead, the resource adapter has the application server create and provide needed threads. When it is finished with a given thread, the resource adapter returns the thread to the application server. The application server manages the thread, either returning it to a pool for later reuse or destroying it. Handling threads in this manner results in increased application server performance and more efficient use of resources.

In addition to moving thread management to the application server, the Connector Architecture provides a flexible model for a resource adapter that uses threads.

- The requesting thread can choose to block (stop its own execution) until the work thread completes.
- The requesting thread can block while it waits to get the work thread. When the application server provides a work thread, the requesting thread and the work thread execute in parallel.
- The resource adapter can opt to submit the work for the thread to a queue. The thread executes the work from the queue at some later point. The resource adapter continues its own execution from the point it submitted the work to the queue, no matter when the thread executes it.

With the latter two approaches, the submitting thread and the work thread may execute simultaneously or independently. For these approaches, the contract specifies a listener mechanism to notify the resource adapter that the thread has completed its operation. The resource adapter can also specify the execution context for the thread, and the work management contract controls the context in which the thread executes.

Generic Work Context Contract

The work management contract between the application server and a resource adapter enables a resource adapter to do a task, such as communicating with the EIS or delivering messages, by delivering `Work` instances for execution.

A generic work context contract enables a resource adapter to control the contexts in which the `Work` instances that it submits are executed by the application server's `WorkManager`. A generic work context mechanism also enables an application server to support new message inflow and delivery schemes. It also provides a richer contextual `Work` execution environment to the resource adapter while still maintaining control over concurrent behavior in a managed environment.

The generic work context contract standardizes the transaction context and the security context.

Outbound and Inbound Contracts

The Connector Architecture defines the following outbound contracts, system-level contracts between an application server and an EIS that enable outbound connectivity to an EIS.

- The connection management contract supports connection pooling, a technique that enhances application performance and scalability. Connection pooling is transparent to the application, which simply obtains a connection to the EIS.
- The transaction management contract extends the connection management contract and provides support for management of both local and XA transactions.

  A local transaction is limited in scope to a single EIS system, and the EIS resource manager itself manages such transaction. An XA transaction or global transaction can span multiple resource managers. This form of transaction requires transaction coordination by an external transaction manager, typically bundled with an application server. A transaction manager uses a two-phase commit protocol to manage a transaction that spans multiple resource managers or EISs, and uses one-phase commit optimization if only one resource manager is participating in an XA transaction.
- The security management contract provides mechanisms for authentication, authorization, and secure communication between a Java EE server and an EIS to protect the information in the EIS.

  A work security map matches EIS identities to the application server domain's identities.

Inbound contracts are system contracts between a Java EE server and an EIS that enable inbound connectivity from the EIS: pluggability contracts for message providers and contracts for importing transactions.

Metadata Annotations

Java EE Connector Architecture 1.6 introduces a set of annotations to minimize the need for deployment descriptors.

- The `@Connector` annotation can be used by the resource adapter developer to specify that the JavaBeans component is a resource adapter JavaBeans component. This annotation is used for providing metadata about the capabilities of the resource adapter. Optionally, you can provide a JavaBeans component implementing the `ResourceAdapter` interface, as in the following example:

```
@Connector(
   description = "Sample adapter using the JavaMail API",
   displayName = "InboundResourceAdapter",
   vendorName = "My Company, Inc.",
   eisType = "MAIL",
   version = "1.0"
)
public class ResourceAdapterImpl
        implements ResourceAdapter, java.io.Serializable {
    ...
    ...
}
```

- The `@ConnectionDefinition` annotation defines a set of connection interfaces and classes pertaining to a particular connection type, as in the following example:

```
@ConnectionDefinition(
    connectionFactory =
        samples.mailra..api.JavaMailConnectionFactory.class,
    connectionFactoryImpl =
        samples.mailra.ra.outbound.JavaMailConnectionFactoryImpl.class,
    connection =
        samples.connectors.mailconnector.api.JavaMailConnection.class,
    connectionImpl =
        samples.mailra..ra.outbound.JavaMailConnectionImpl.class
)
public class ManagedConnectionFactoryImpl implements
        ManagedConnectionFactory, Serializable {
    ...
    ...
    @ConfigProperty(defaultValue = "UnknownHostName")
    public void setServerName(String serverName) {
       ...
    }
}
```

- The `@AdministeredObject` annotation designates a JavaBeans component as an administered object.
- The `@Activation` annotation contains configuration information pertaining to inbound connectivity from an EIS instance, as in the following example:

```
@Activation(
        messageListeners = {
            samples.mailra.api.JavaMailMessageListener.class
        }
```

```
)
public class ActivationSpecImpl
        implements javax.resource.spi.ActivationSpec,
                   java.io.Serializable {
    ...
    @ConfigProperty()
    // serverName property value
    private String serverName = new String("");

    @ConfigProperty()
    // userName property value
    private String userName = new String("");

    @ConfigProperty()
    // password property value
    private String password = new String("");

    @ConfigProperty()
    // folderName property value
    private String folderName = new String("Inbox");

    // protocol property value
    // Normally imap or pop3
    @ConfigProperty(
            description = "Normally imap or pop3"
    )
    private String protocol = new String("imap");
    ...
    ...
}
```

- The `@ConfigProperty` annotation can be used on JavaBeans components to provide additional configuration information that may be used by the deployer and resource adapter provider. The preceding example code shows several `@ConfigProperty` annotations.

The specification allows a resource adapter to be developed in mixed-mode form, that is the ability for a resource adapter developer to use both metadata annotations and deployment descriptors in applications. An application assembler or deployer may use the deployment descriptor to override the metadata annotations specified by the resource adapter developer.

The deployment descriptor for a resource adapter is named `ra.xml`. The `metadata-complete` attribute defines whether the deployment descriptor for the resource adapter module is complete or whether the class files available to the module and packaged with the resource adapter need to be examined for annotations that specify deployment information.

For the complete list of annotations and JavaBeans components introduced in the Java EE 6 platform, see the Java EE Connector Architecture 1.6 specification.

Common Client Interface

This section explains how components use the Connector Architecture Common Client Interface (CCI) API and a resource adapter to access data from an EIS. The CCI API defines a set of interfaces and classes whose methods allow a client to perform typical data access operations. The CCI interfaces and classes are as follows:

- `ConnectionFactory`: Provides an application component with a `Connection` instance to an EIS.
- `Connection`: Represents the connection to the underlying EIS.
- `ConnectionSpec`: Provides a means for an application component to pass connection-request-specific properties to the `ConnectionFactory` when making a connection request.
- `Interaction`: Provides a means for an application component to execute EIS functions, such as database stored procedures.
- `InteractionSpec`: Holds properties pertaining to an application component's interaction with an EIS.
- `Record`: The superinterface for the various kinds of record instances. Record instances can be `MappedRecord`, `IndexedRecord`, or `ResultSet` instances, all of which inherit from the `Record` interface.
- `RecordFactory`: Provides an application component with a `Record` instance.
- `IndexedRecord`: Represents an ordered collection of `Record` instances based on the `java.util.List` interface.

A client or application component that uses the CCI to interact with an underlying EIS does so in a prescribed manner. The component must establish a connection to the EIS's resource manager, and it does so using the `ConnectionFactory`. The `Connection` object represents the connection to the EIS and is used for subsequent interactions with the EIS.

The component performs its interactions with the EIS, such as accessing data from a specific table, using an `Interaction` object. The application component defines the Interaction object by using an `InteractionSpec` object. When it reads data from the EIS, such as from database tables, or writes to those tables, the application component does so by using a particular type of `Record` instance: a `MappedRecord`, an `IndexedRecord`, or a `ResultSet` instance.

Note, too, that a client application that relies on a CCI resource adapter is very much like any other Java EE client that uses enterprise bean methods.

Further Information about Resources

For more information about resources and annotations, see

- Java EE 6 Platform Specification (JSR 316):
  `http://jcp.org/en/jsr/detail?id=316`
- Java EE Connector Architecture 1.6 specification:
  `http://jcp.org/en/jsr/detail?id=322`
- EJB 3.1 specification:
  `http://jcp.org/en/jsr/detail?id=318`
- Common Annotations for the Java Platform:
  `http://www.jcp.org/en/jsr/detail?id=250`

◆ ◆ ◆ CHAPTER 45

Java Message Service Concepts

This chapter provides an introduction to the Java Message Service (JMS) API, a Java API that allows applications to create, send, receive, and read messages using reliable, asynchronous, loosely coupled communication. It covers the following topics:

Overview of the JMS API

This overview of the JMS API answers the following questions.

What Is Messaging?

Messaging is a method of communication between software components or applications. A messaging system is a peer-to-peer facility: A messaging client can send messages to, and receive messages from, any other client. Each client connects to a messaging agent that provides facilities for creating, sending, receiving, and reading messages.

Messaging enables distributed communication that is *loosely coupled*. A component sends a message to a destination, and the recipient can retrieve the message from the destination. However, the sender and the receiver do not have to be available at the same time in order to

communicate. In fact, the sender does not need to know anything about the receiver; nor does the receiver need to know anything about the sender. The sender and the receiver need to know only which message format and which destination to use. In this respect, messaging differs from tightly coupled technologies, such as Remote Method Invocation (RMI), which require an application to know a remote application's methods.

Messaging also differs from electronic mail (email), which is a method of communication between people or between software applications and people. Messaging is used for communication between software applications or software components.

What Is the JMS API?

The Java Message Service is a Java API that allows applications to create, send, receive, and read messages. Designed by Sun and several partner companies, the JMS API defines a common set of interfaces and associated semantics that allow programs written in the Java programming language to communicate with other messaging implementations.

The JMS API minimizes the set of concepts a programmer must learn in order to use messaging products but provides enough features to support sophisticated messaging applications. It also strives to maximize the portability of JMS applications across JMS providers in the same messaging domain.

The JMS API enables communication that is not only loosely coupled but also

- **Asynchronous**: A JMS provider can deliver messages to a client as they arrive; a client does not have to request messages in order to receive them.
- **Reliable**: The JMS API can ensure that a message is delivered once and only once. Lower levels of reliability are available for applications that can afford to miss messages or to receive duplicate messages.

The JMS specification was first published in August 1998. The latest version is Version 1.1, which was released in April 2002. You can download a copy of the specification from the JMS web site: `http://www.oracle.com/technetwork/java/index-jsp-142945.html`.

When Can You Use the JMS API?

An enterprise application provider is likely to choose a messaging API over a tightly coupled API, such as remote procedure call (RPC), under the following circumstances.

- The provider wants the components not to depend on information about other components' interfaces, so that components can be easily replaced.
- The provider wants the application to run whether or not all components are up and running simultaneously.
- The application business model allows a component to send information to another and to continue to operate without receiving an immediate response.

For example, components of an enterprise application for an automobile manufacturer can use the JMS API in situations like these:

- The inventory component can send a message to the factory component when the inventory level for a product goes below a certain level so that the factory can make more cars.
- The factory component can send a message to the parts components so that the factory can assemble the parts it needs.
- The parts components in turn can send messages to their own inventory and order components to update their inventories and to order new parts from suppliers.
- Both the factory and the parts components can send messages to the accounting component to update their budget numbers.
- The business can publish updated catalog items to its sales force.

Using messaging for these tasks allows the various components to interact with one another efficiently, without tying up network or other resources. Figure 45–1 illustrates how this simple example might work.

FIGURE 45–1 Messaging in an Enterprise Application



Manufacturing is only one example of how an enterprise can use the JMS API. Retail applications, financial services applications, health services applications, and many others can make use of messaging.

How Does the JMS API Work with the Java EE Platform?

When the JMS API was introduced in 1998, its most important purpose was to allow Java applications to access existing messaging-oriented middleware (MOM) systems, such as MQSeries from IBM. Since that time, many vendors have adopted and implemented the JMS API, so a JMS product can now provide a complete messaging capability for an enterprise.

Beginning with the 1.3 release of the Java EE platform, the JMS API has been an integral part of the platform, and application developers can use messaging with Java EE components.

The JMS API in the Java EE platform has the following features.

- Application clients, Enterprise JavaBeans (EJB) components, and web components can send or synchronously receive a JMS message. Application clients can in addition receive JMS messages asynchronously. (Applets, however, are not required to support the JMS API.)
- Message-driven beans, which are a kind of enterprise bean, enable the asynchronous consumption of messages. A JMS provider can optionally implement concurrent processing of messages by message-driven beans.
- Message send and receive operations can participate in distributed transactions, which allow JMS operations and database accesses to take place within a single transaction.

The JMS API enhances the Java EE platform by simplifying enterprise development, allowing loosely coupled, reliable, asynchronous interactions among Java EE components and legacy systems capable of messaging. A developer can easily add new behavior to a Java EE application that has existing business events by adding a new message-driven bean to operate on specific business events. The Java EE platform, moreover, enhances the JMS API by providing support for distributed transactions and allowing for the concurrent consumption of messages. For more information, see the Enterprise JavaBeans specification, v3.1.

The JMS provider can be integrated with the application server using the Java EE Connector architecture. You access the JMS provider through a resource adapter. This capability allows vendors to create JMS providers that can be plugged in to multiple application servers, and it allows application servers to support multiple JMS providers. For more information, see the Java EE Connector architecture specification, v1.6.

Basic JMS API Concepts

This section introduces the most basic JMS API concepts, the ones you must know to get started writing simple application clients that use the JMS API.

The next section introduces the JMS API programming model. Later sections cover more advanced concepts, including the ones you need to write applications that use message-driven beans.

JMS API Architecture

A JMS application is composed of the following parts.

- A *JMS provider* is a messaging system that implements the JMS interfaces and provides administrative and control features. An implementation of the Java EE platform includes a JMS provider.
- *JMS clients* are the programs or components, written in the Java programming language, that produce and consume messages. Any Java EE application component can act as a JMS client.
- *Messages* are the objects that communicate information between JMS clients.
- *Administered objects* are preconfigured JMS objects created by an administrator for the use of clients. The two kinds of JMS administered objects are destinations and connection factories, which are described in "JMS Administered Objects" on page 765.

Figure 45–2 illustrates the way these parts interact. Administrative tools allow you to bind destinations and connection factories into a JNDI namespace. A JMS client can then use resource injection to access the administered objects in the namespace and then establish a logical connection to the same objects through the JMS provider.

FIGURE 45–2 JMS API Architecture



Messaging Domains

Before the JMS API existed, most messaging products supported either the *point-to-point* or the *publish/subscribe* approach to messaging. The JMS specification provides a separate domain for each approach and defines compliance for each domain. A stand-alone JMS provider can implement one or both domains. A Java EE provider must implement both domains.

In fact, most implementations of the JMS API support both the point-to-point and the publish/subscribe domains, and some JMS clients combine the use of both domains in a single application. In this way, the JMS API has extended the power and flexibility of messaging products.

The JMS specification goes one step further: It provides common interfaces that enable you to use the JMS API in a way that is not specific to either domain. The following subsections describe the two messaging domains and then describe the use of the common interfaces.

Point-to-Point Messaging Domain

A point-to-point (PTP) product or application is built on the concept of message *queues*, senders, and receivers. Each message is addressed to a specific queue, and receiving clients extract messages from the queues established to hold their messages. Queues retain all messages sent to them until the messages are consumed or until the messages expire.

PTP messaging has the following characteristics and is illustrated in Figure 45–3.

FIGURE 45–3 Point-to-Point Messaging



- Each message has only one consumer.
- A sender and a receiver of a message have no timing dependencies. The receiver can fetch the message whether or not it was running when the client sent the message.
- The receiver acknowledges the successful processing of a message.

Use PTP messaging when every message you send must be processed successfully by one consumer.

Publish/Subscribe Messaging Domain

In a publish/subscribe (pub/sub) product or application, clients address messages to a *topic*, which functions somewhat like a bulletin board. Publishers and subscribers are generally anonymous and can dynamically publish or subscribe to the content hierarchy. The system takes care of distributing the messages arriving from a topic's multiple publishers to its multiple subscribers. Topics retain messages only as long as it takes to distribute them to current subscribers.

Pub/sub messaging has the following characteristics.

- Each message can have multiple consumers.
- Publishers and subscribers have a timing dependency. A client that subscribes to a topic can consume only messages published after the client has created a subscription, and the subscriber must continue to be active in order for it to consume messages.

The JMS API relaxes this timing dependency to some extent by allowing subscribers to create *durable subscriptions*, which receive messages sent while the subscribers are not active. Durable subscriptions provide the flexibility and reliability of queues but still allow clients to send messages to many recipients. For more information about durable subscriptions, see "Creating Durable Subscriptions" on page 779.

Use pub/sub messaging when each message can be processed by zero, one, or many consumers. Figure 45–4 illustrates pub/sub messaging.

FIGURE 45–4 Publish/Subscribe Messaging



Programming with the Common Interfaces

Version 1.1 of the JMS API allows you to use the same code to send and receive messages under either the PTP or the pub/sub domain. The destinations that you use remain domain-specific, and the behavior of the application will depend in part on whether you are using a queue or a topic. However, the code itself can be common to both domains, making your applications flexible and reusable. This tutorial describes and illustrates these common interfaces.

Message Consumption

Messaging products are inherently asynchronous: There is no fundamental timing dependency between the production and the consumption of a message. However, the JMS specification uses this term in a more precise sense. Messages can be consumed in either of two ways:

- **Synchronously**: A subscriber or a receiver explicitly fetches the message from the destination by calling the `receive` method. The `receive` method can block until a message arrives or can time out if a message does not arrive within a specified time limit.
- **Asynchronously**: A client can register a *message listener* with a consumer. A message listener is similar to an event listener. Whenever a message arrives at the destination, the JMS provider delivers the message by calling the listener's `onMessage` method, which acts on the contents of the message.

The JMS API Programming Model

The basic building blocks of a JMS application consist of

- Administered objects: connection factories and destinations
- Connections
- Sessions
- Message producers
- Message consumers
- Messages

Figure 45–5 shows how all these objects fit together in a JMS client application.

FIGURE 45–5 The JMS API Programming Model



This section describes all these objects briefly and provides sample commands and code snippets that show how to create and use the objects. The last subsection briefly describes JMS API exception handling.

Examples that show how to combine all these objects in applications appear in later sections. For more details, see the JMS API documentation, which is part of the Java EE API documentation.

JMS Administered Objects

Two parts of a JMS application, destinations and connection factories, are best maintained administratively rather than programmatically. The technology underlying these objects is likely to be very different from one implementation of the JMS API to another. Therefore, the management of these objects belongs with other administrative tasks that vary from provider to provider.

JMS clients access these objects through interfaces that are portable, so a client application can run with little or no change on more than one implementation of the JMS API. Ordinarily, an administrator configures administered objects in a JNDI namespace, and JMS clients then access them by using resource injection.

With GlassFish Server, you can use the `asadmin create-jms-resource` command or the Administration Console to create JMS administered objects in the form of connector resources. You can also specify the resources in a file named `glassfish-resources.xml` that you can bundle with an application.

NetBeans IDE provides a wizard that allows you to create JMS resources for GlassFish Server. See "To Create JMS Resources Using NetBeans IDE" on page 795 for details.

JMS Connection Factories

A *connection factory* is the object a client uses to create a connection to a provider. A connection factory encapsulates a set of connection configuration parameters that has been defined by an administrator. Each connection factory is an instance of the `ConnectionFactory`, `QueueConnectionFactory`, or `TopicConnectionFactory` interface. To learn how to create connection factories, see "To Create JMS Resources Using NetBeans IDE" on page 795.

At the beginning of a JMS client program, you usually inject a connection factory resource into a `ConnectionFactory` object. For example, the following code fragment specifies a resource whose JNDI name is `jms/ConnectionFactory` and assigns it to a `ConnectionFactory` object:

```
@Resource(lookup = "jms/ConnectionFactory")
private static ConnectionFactory connectionFactory;
```

In a Java EE application, JMS administered objects are normally placed in the `jms` naming subcontext.

JMS Destinations

A *destination* is the object a client uses to specify the target of messages it produces and the source of messages it consumes. In the PTP messaging domain, destinations are called queues. In the pub/sub messaging domain, destinations are called topics. A JMS application can use multiple queues or topics (or both). To learn how to create destination resources, see "To Create JMS Resources Using NetBeans IDE" on page 795.

To create a destination using the GlassFish Server, you create a JMS destination resource that specifies a JNDI name for the destination.

In the GlassFish Server implementation of JMS, each destination resource refers to a physical destination. You can create a physical destination explicitly, but if you do not, the Application Server creates it when it is needed and deletes it when you delete the destination resource.

In addition to injecting a connection factory resource into a client program, you usually inject a destination resource. Unlike connection factories, destinations are specific to one domain or the other. To create an application that allows you to use the same code for both topics and queues, you assign the destination to a `Destination` object.

The following code specifies two resources, a queue and a topic. The resource names are mapped to destination resources created in the JNDI namespace.

```
@Resource(lookup = "jms/Queue")
private static Queue queue;

@Resource(lookup = "jms/Topic")
private static Topic topic;
```

With the common interfaces, you can mix or match connection factories and destinations. That is, in addition to using the `ConnectionFactory` interface, you can inject a `QueueConnectionFactory` resource and use it with a `Topic`, and you can inject a `TopicConnectionFactory` resource and use it with a `Queue`. The behavior of the application will depend on the kind of destination you use and not on the kind of connection factory you use.

JMS Connections

A *connection* encapsulates a virtual connection with a JMS provider. A connection could represent an open TCP/IP socket between a client and a provider service daemon. You use a connection to create one or more sessions.

Connections implement the `Connection` interface. When you have a `ConnectionFactory` object, you can use it to create a `Connection`:

```
Connection connection = connectionFactory.createConnection();
```

Before an application completes, you must close any connections that you have created. Failure to close a connection can cause resources not to be released by the JMS provider. Closing a connection also closes its sessions and their message producers and message consumers.

```
connection.close();
```

Before your application can consume messages, you must call the connection's `start` method; for details, see "JMS Message Consumers" on page 769. If you want to stop message delivery temporarily without closing the connection, you call the `stop` method.

JMS Sessions

A *session* is a single-threaded context for producing and consuming messages. You use sessions to create the following:

- Message producers
- Message consumers
- Messages
- Queue browsers
- Temporary queues and topics (see "Creating Temporary Destinations" on page 778)

Sessions serialize the execution of message listeners; for details, see "JMS Message Listeners" on page 769.

A session provides a transactional context with which to group a set of sends and receives into an atomic unit of work. For details, see "Using JMS API Local Transactions" on page 781.

Sessions implement the `Session` interface. After you create a `Connection` object, you use it to create a `Session`:

```
Session session = connection.createSession(false,
     Session.AUTO_ACKNOWLEDGE);
```

The first argument means that the session is not transacted; the second means that the session automatically acknowledges messages when they have been received successfully. (For more information, see "Controlling Message Acknowledgment" on page 775.)

To create a transacted session, use the following code:

```
Session session = connection.createSession(true, 0);
```

Here, the first argument means that the session is transacted; the second indicates that message acknowledgment is not specified for transacted sessions. For more information on transactions, see "Using JMS API Local Transactions" on page 781. For information about the way JMS transactions work in Java EE applications, see "Using the JMS API in Java EE Applications" on page 783.

JMS Message Producers

A *message producer* is an object that is created by a session and used for sending messages to a destination. It implements the `MessageProducer` interface.

You use a `Session` to create a `MessageProducer` for a destination. The following examples show that you can create a producer for a `Destination` object, a `Queue` object, or a `Topic` object:

```
MessageProducer producer = session.createProducer(dest);
MessageProducer producer = session.createProducer(queue);
MessageProducer producer = session.createProducer(topic);
```

You can create an unidentified producer by specifying `null` as the argument to `createProducer`. With an unidentified producer, you do not specify a destination until you send a message.

After you have created a message producer, you can use it to send messages by using the `send` method:

```
producer.send(message);
```

You must first create the messages; see "JMS Messages" on page 771.

If you created an unidentified producer, use an overloaded `send` method that specifies the destination as the first parameter. For example:

```
MessageProducer anon_prod = session.createProducer(null);
anon_prod.send(dest, message);
```

JMS Message Consumers

A *message consumer* is an object that is created by a session and used for receiving messages sent to a destination. It implements the `MessageConsumer` interface.

A message consumer allows a JMS client to register interest in a destination with a JMS provider. The JMS provider manages the delivery of messages from a destination to the registered consumers of the destination.

For example, you could use a `Session` to create a `MessageConsumer` for a `Destination` object, a `Queue` object, or a `Topic` object:

```
MessageConsumer consumer = session.createConsumer(dest);
MessageConsumer consumer = session.createConsumer(queue);
MessageConsumer consumer = session.createConsumer(topic);
```

You use the `Session.createDurableSubscriber` method to create a durable topic subscriber. This method is valid only if you are using a topic. For details, see "Creating Durable Subscriptions" on page 779.

After you have created a message consumer, it becomes active, and you can use it to receive messages. You can use the `close` method for a `MessageConsumer` to make the message consumer inactive. Message delivery does not begin until you start the connection you created by calling its `start` method. (Remember always to call the `start` method; forgetting to start the connection is one of the most common JMS programming errors.)

You use the `receive` method to consume a message synchronously. You can use this method at any time after you call the `start` method:

```
connection.start();
Message m = consumer.receive();
connection.start();
Message m = consumer.receive(1000); // time out after a second
```

To consume a message asynchronously, you use a message listener, described in the next section.

JMS Message Listeners

A message listener is an object that acts as an asynchronous event handler for messages. This object implements the `MessageListener` interface, which contains one method, `onMessage`. In the `onMessage` method, you define the actions to be taken when a message arrives.

You register the message listener with a specific MessageConsumer by using the `setMessageListener` method. For example, if you define a class named `Listener` that implements the `MessageListener` interface, you can register the message listener as follows:

```
Listener myListener = new Listener();
consumer.setMessageListener(myListener);
```

After you register the message listener, you call the `start` method on the `Connection` to begin message delivery. (If you call `start` before you register the message listener, you are likely to miss messages.)

When message delivery begins, the JMS provider automatically calls the message listener's `onMessage` method whenever a message is delivered. The `onMessage` method takes one argument of type `Message`, which your implementation of the method can cast to any of the other message types (see "Message Bodies" on page 772).

A message listener is not specific to a particular destination type. The same listener can obtain messages from either a queue or a topic, depending on the type of destination for which the message consumer was created. A message listener does, however, usually expect a specific message type and format.

Your `onMessage` method should handle all exceptions. It must not throw checked exceptions, and throwing a `RuntimeException` is considered a programming error.

The session used to create the message consumer serializes the execution of all message listeners registered with the session. At any time, only one of the session's message listeners is running.

In the Java EE platform, a message-driven bean is a special kind of message listener. For details, see "Using Message-Driven Beans to Receive Messages Asynchronously" on page 785.

JMS Message Selectors

If your messaging application needs to filter the messages it receives, you can use a JMS API message selector, which allows a message consumer to specify the messages it is interested in. Message selectors assign the work of filtering messages to the JMS provider rather than to the application. For an example of an application that uses a message selector, see "An Application That Uses the JMS API with a Session Bean" on page 829.

A message selector is a `String` that contains an expression. The syntax of the expression is based on a subset of the SQL92 conditional expression syntax. The message selector in the example selects any message that has a `NewsType` property that is set to the value `'Sports'` or `'Opinion'`:

```
NewsType = 'Sports' OR NewsType = 'Opinion'
```

The `createConsumer` and `createDurableSubscriber` methods allow you to specify a message selector as an argument when you create a message consumer.

The message consumer then receives only messages whose headers and properties match the selector. (See "Message Headers" on page 771, and "Message Properties" on page 772.) A message selector cannot select messages on the basis of the content of the message body.

JMS Messages

The ultimate purpose of a JMS application is to produce and to consume messages that can then be used by other software applications. JMS messages have a basic format that is simple but highly flexible, allowing you to create messages that match formats used by non-JMS applications on heterogeneous platforms.

A JMS message has three parts: a header, properties, and a body. Only the header is required. The following sections describe these parts.

For complete documentation of message headers, properties, and bodies, see the documentation of the `Message` interface in the API documentation.

Message Headers

A JMS message header contains a number of predefined fields that contain values that both clients and providers use to identify and to route messages. Table 45–1 lists the JMS message header fields and indicates how their values are set. For example, every message has a unique identifier, which is represented in the header field `JMSMessageID`. The value of another header field, `JMSDestination`, represents the queue or the topic to which the message is sent. Other fields include a timestamp and a priority level.

Each header field has associated setter and getter methods, which are documented in the description of the `Message` interface. Some header fields are intended to be set by a client, but many are set automatically by the `send` or the `publish` method, which overrides any client-set values.

TABLE 45–1 How JMS Message Header Field Values Are Set

Header Field	Set By
`JMSDestination`	`send` or `publish` method
`JMSDeliveryMode`	`send` or `publish` method
`JMSExpiration`	`send` or `publish` method
`JMSPriority`	`send` or `publish` method
`JMSMessageID`	`send` or `publish` method
`JMSTimestamp`	`send` or `publish` method
`JMSCorrelationID`	Client
`JMSReplyTo`	Client
`JMSType`	Client
`JMSRedelivered`	JMS provider

Message Properties

You can create and set properties for messages if you need values in addition to those provided by the header fields. You can use properties to provide compatibility with other messaging systems, or you can use them to create message selectors (see "JMS Message Selectors" on page 770). For an example of setting a property to be used as a message selector, see "An Application That Uses the JMS API with a Session Bean" on page 829.

The JMS API provides some predefined property names that a provider can support. The use either of these predefined properties or of user-defined properties is optional.

Message Bodies

The JMS API defines five message body formats, also called message types, which allow you to send and to receive data in many different forms and provide compatibility with existing messaging formats. Table 45–2 describes these message types.

TABLE 45–2 JMS Message Types

Message Type	Body Contains
`TextMessage`	A `java.lang.String` object (for example, the contents of an XML file).
`MapMessage`	A set of name-value pairs, with names as `String` objects and values as primitive types in the Java programming language. The entries can be accessed sequentially by enumerator or randomly by name. The order of the entries is undefined.
`BytesMessage`	A stream of uninterpreted bytes. This message type is for literally encoding a body to match an existing message format.
`StreamMessage`	A stream of primitive values in the Java programming language, filled and read sequentially.
`ObjectMessage`	A `Serializable` object in the Java programming language.
`Message`	Nothing. Composed of header fields and properties only. This message type is useful when a message body is not required.

The JMS API provides methods for creating messages of each type and for filling in their contents. For example, to create and send a `TextMessage`, you might use the following statements:

```
TextMessage message = session.createTextMessage();
message.setText(msg_text);     // msg_text is a String
producer.send(message);
```

At the consuming end, a message arrives as a generic `Message` object and must be cast to the appropriate message type. You can use one or more getter methods to extract the message contents. The following code fragment uses the `getText` method:

```
Message m = consumer.receive();
if (m instanceof TextMessage) {
    TextMessage message = (TextMessage) m;
    System.out.println("Reading message: " + message.getText());
} else {
    // Handle error
}
```

JMS Queue Browsers

You can create a `QueueBrowser` object to inspect the messages in a queue. Messages sent to a queue remain in the queue until the message consumer for that queue consumes them. Therefore, the JMS API provides an object that allows you to browse the messages in the queue and display the header values for each message. To create a `QueueBrowser` object, use the `Session.createBrowser` method. For example:

```
QueueBrowser browser = session.createBrowser(queue);
```

See "A Simple Example of Browsing Messages in a Queue" on page 807 for an example of the use of a `QueueBrowser` object.

The `createBrowser` method allows you to specify a message selector as a second argument when you create a `QueueBrowser`. For information on message selectors, see "JMS Message Selectors" on page 770.

The JMS API provides no mechanism for browsing a topic. Messages usually disappear from a topic as soon as they appear: if there are no message consumers to consume them, the JMS provider removes them. Although durable subscriptions allow messages to remain on a topic while the message consumer is not active, no facility exists for examining them.

JMS Exception Handling

The root class for exceptions thrown by JMS API methods is `JMSException`. Catching `JMSException` provides a generic way of handling all exceptions related to the JMS API.

The `JMSException` class includes the following subclasses, which are described in the API documentation:

- `IllegalStateException`
- `InvalidClientIDException`
- `InvalidDestinationException`
- `InvalidSelectorException`
- `JMSSecurityException`
- `MessageEOFException`
- `MessageFormatException`
- `MessageNotReadableException`

- `MessageNotWriteableException`
- `ResourceAllocationException`
- `TransactionInProgressException`
- `TransactionRolledBackException`

All the examples in the tutorial catch and handle `JMSException` when it is appropriate to do so.

Creating Robust JMS Applications

This section explains how to use features of the JMS API to achieve the level of reliability and performance your application requires. Many people choose to implement JMS applications because they cannot tolerate dropped or duplicate messages and require that every message be received once and only once. The JMS API provides this functionality.

The most reliable way to produce a message is to send a `PERSISTENT` message within a transaction. JMS messages are `PERSISTENT` by default. A *transaction* is a unit of work into which you can group a series of operations, such as message sends and receives, so that the operations either all succeed or all fail. For details, see "Specifying Message Persistence" on page 776 and "Using JMS API Local Transactions" on page 781.

The most reliable way to consume a message is to do so within a transaction, either from a queue or from a durable subscription to a topic. For details, see "Creating Temporary Destinations" on page 778, "Creating Durable Subscriptions" on page 779, and "Using JMS API Local Transactions" on page 781.

For other applications, a lower level of reliability can reduce overhead and improve performance. You can send messages with varying priority levels (see "Setting Message Priority Levels" on page 777) and you can set them to expire after a certain length of time (see "Allowing Messages to Expire" on page 777).

The JMS API provides several ways to achieve various kinds and degrees of reliability. This section divides them into two categories, basic and advanced.

The following sections describe these features as they apply to JMS clients. Some of the features work differently in Java EE applications; in these cases, the differences are noted here and are explained in detail in "Using the JMS API in Java EE Applications" on page 783.

Using Basic Reliability Mechanisms

The basic mechanisms for achieving or affecting reliable message delivery are as follows:

- **Controlling message acknowledgment**: You can specify various levels of control over message acknowledgment.
- **Specifying message persistence**: You can specify that messages are persistent, meaning that they must not be lost in the event of a provider failure.
- **Setting message priority levels**: You can set various priority levels for messages, which can affect the order in which the messages are delivered.
- **Allowing messages to expire**: You can specify an expiration time for messages so that they will not be delivered if they are obsolete.
- **Creating temporary destinations**: You can create temporary destinations that last only for the duration of the connection in which they are created.

Controlling Message Acknowledgment

Until a JMS message has been acknowledged, it is not considered to be successfully consumed. The successful consumption of a message ordinarily takes place in three stages.

1. The client receives the message.
2. The client processes the message.
3. The message is acknowledged. Acknowledgment is initiated either by the JMS provider or by the client, depending on the session acknowledgment mode.

In transacted sessions (see "Using JMS API Local Transactions" on page 781), acknowledgment happens automatically when a transaction is committed. If a transaction is rolled back, all consumed messages are redelivered.

In nontransacted sessions, when and how a message is acknowledged depend on the value specified as the second argument of the `createSession` method. The three possible argument values are as follows:

- `Session.AUTO_ACKNOWLEDGE`: The session automatically acknowledges a client's receipt of a message either when the client has successfully returned from a call to `receive` or when the `MessageListener` it has called to process the message returns successfully. A synchronous receive in an `AUTO_ACKNOWLEDGE` session is the one exception to the rule that message consumption is a three-stage process as described earlier.

  In this case, the receipt and acknowledgment take place in one step, followed by the processing of the message.
- `Session.CLIENT_ACKNOWLEDGE`: A client acknowledges a message by calling the message's `acknowledge` method. In this mode, acknowledgment takes place on the session level: Acknowledging a consumed message automatically acknowledges the receipt of *all*

messages that have been consumed by its session. For example, if a message consumer consumes ten messages and then acknowledges the fifth message delivered, all ten messages are acknowledged.

- `Session.DUPS_OK_ACKNOWLEDGE`: This option instructs the session to lazily acknowledge the delivery of messages. This is likely to result in the delivery of some duplicate messages if the JMS provider fails, so it should be used only by consumers that can tolerate duplicate messages. (If the JMS provider redelivers a message, it must set the value of the `JMSRedelivered` message header to `true`.) This option can reduce session overhead by minimizing the work the session does to prevent duplicates.

If messages have been received from a queue but not acknowledged when a session terminates, the JMS provider retains them and redelivers them when a consumer next accesses the queue. The provider also retains unacknowledged messages for a terminated session that has a durable `TopicSubscriber`. (See "Creating Durable Subscriptions" on page 779.) Unacknowledged messages for a nondurable `TopicSubscriber` are dropped when the session is closed.

If you use a queue or a durable subscription, you can use the `Session.recover` method to stop a nontransacted session and restart it with its first unacknowledged message. In effect, the session's series of delivered messages is reset to the point after its last acknowledged message. The messages it now delivers may be different from those that were originally delivered, if messages have expired or if higher-priority messages have arrived. For a nondurable `TopicSubscriber`, the provider may drop unacknowledged messages when its session is recovered.

The sample program in XREF the next section demonstrates two ways to ensure that a message will not be acknowledged until processing of the message is complete.

Specifying Message Persistence

The JMS API supports two delivery modes for messages to specify whether messages are lost if the JMS provider fails. These delivery modes are fields of the `DeliveryMode` interface.

- The `PERSISTENT` delivery mode, which is the default, instructs the JMS provider to take extra care to ensure that a message is not lost in transit in case of a JMS provider failure. A message sent with this delivery mode is logged to stable storage when it is sent.
- The `NON_PERSISTENT` delivery mode does not require the JMS provider to store the message or otherwise guarantee that it is not lost if the provider fails.

You can specify the delivery mode in either of two ways.

- You can use the `setDeliveryMode` method of the `MessageProducer` interface to set the delivery mode for all messages sent by that producer. For example, the following call sets the delivery mode to `NON_PERSISTENT` for a producer:

```
producer.setDeliveryMode(DeliveryMode.NON_PERSISTENT);
```

- You can use the long form of the `send` or the `publish` method to set the delivery mode for a specific message. The second argument sets the delivery mode. For example, the following `send` call sets the delivery mode for `message` to `NON_PERSISTENT`:

  ```
  producer.send(message, DeliveryMode.NON_PERSISTENT, 3, 10000);
  ```

  The third and fourth arguments set the priority level and expiration time, which are described in the next two subsections.

If you do not specify a delivery mode, the default is `PERSISTENT`. Using the `NON_PERSISTENT` delivery mode may improve performance and reduce storage overhead, but you should use it only if your application can afford to miss messages.

Setting Message Priority Levels

You can use message priority levels to instruct the JMS provider to deliver urgent messages first. You can set the priority level in either of two ways.

- You can use the `setPriority` method of the `MessageProducer` interface to set the priority level for all messages sent by that producer. For example, the following call sets a priority level of 7 for a producer:

  ```
  producer.setPriority(7);
  ```

- You can use the long form of the `send` or the `publish` method to set the priority level for a specific message. The third argument sets the priority level. For example, the following `send` call sets the priority level for `message` to 3:

  ```
  producer.send(message, DeliveryMode.NON_PERSISTENT, 3, 10000);
  ```

The ten levels of priority range from 0 (lowest) to 9 (highest). If you do not specify a priority level, the default level is 4. A JMS provider tries to deliver higher-priority messages before lower-priority ones but does not have to deliver messages in exact order of priority.

Allowing Messages to Expire

By default, a message never expires. If a message will become obsolete after a certain period, however, you may want to set an expiration time. You can do this in either of two ways.

- You can use the `setTimeToLive` method of the `MessageProducer` interface to set a default expiration time for all messages sent by that producer. For example, the following call sets a time to live of one minute for a producer:

  ```
  producer.setTimeToLive(60000);
  ```

- You can use the long form of the `send` or the `publish` method to set an expiration time for a specific message. The fourth argument sets the expiration time in milliseconds. For example, the following `send` call sets a time to live of 10 seconds:

  ```
  producer.send(message, DeliveryMode.NON_PERSISTENT, 3, 10000);
  ```

If the specified `timeToLive` value is `0`, the message never expires.

When the message is sent, the specified `timeToLive` is added to the current time to give the expiration time. Any message not delivered before the specified expiration time is destroyed. The destruction of obsolete messages conserves storage and computing resources.

Creating Temporary Destinations

Normally, you create JMS destinations (queues and topics) administratively rather than programmatically. Your JMS provider includes a tool that you use to create and remove destinations, and it is common for destinations to be long-lasting.

The JMS API also enables you to create destinations (`TemporaryQueue` and `TemporaryTopic` objects) that last only for the duration of the connection in which they are created. You create these destinations dynamically using the `Session.createTemporaryQueue` and the `Session.createTemporaryTopic` methods.

The only message consumers that can consume from a temporary destination are those created by the same connection that created the destination. Any message producer can send to the temporary destination. If you close the connection that a temporary destination belongs to, the destination is closed and its contents are lost.

You can use temporary destinations to implement a simple request/reply mechanism. If you create a temporary destination and specify it as the value of the `JMSReplyTo` message header field when you send a message, then the consumer of the message can use the value of the `JMSReplyTo` field as the destination to which it sends a reply. The consumer can also reference the original request by setting the `JMSCorrelationID` header field of the reply message to the value of the `JMSMessageID` header field of the request. For example, an `onMessage` method can create a session so that it can send a reply to the message it receives. It can use code such as the following:

```
producer = session.createProducer(msg.getJMSReplyTo());
replyMsg = session.createTextMessage("Consumer " +
    "processed message: " + msg.getText());
replyMsg.setJMSCorrelationID(msg.getJMSMessageID());
producer.send(replyMsg);
```

For more examples, see Chapter 46, “Java Message Service Examples.”

Using Advanced Reliability Mechanisms

The more advanced mechanisms for achieving reliable message delivery are the following:

- **Creating durable subscriptions**: You can create durable topic subscriptions, which receive messages published while the subscriber is not active. Durable subscriptions offer the reliability of queues to the publish/subscribe message domain.
- **Using local transactions**: You can use local transactions, which allow you to group a series of sends and receives into an atomic unit of work. Transactions are rolled back if they fail at any time.

Creating Durable Subscriptions

To ensure that a pub/sub application receives all published messages, use `PERSISTENT` delivery mode for the publishers. In addition, use durable subscriptions for the subscribers.

The `Session.createConsumer` method creates a nondurable subscriber if a topic is specified as the destination. A nondurable subscriber can receive only messages that are published while it is active.

At the cost of higher overhead, you can use the `Session.createDurableSubscriber` method to create a durable subscriber. A durable subscription can have only one active subscriber at a time.

A durable subscriber registers a durable subscription by specifying a unique identity that is retained by the JMS provider. Subsequent subscriber objects that have the same identity resume the subscription in the state in which it was left by the preceding subscriber. If a durable subscription has no active subscriber, the JMS provider retains the subscription's messages until they are received by the subscription or until they expire.

You establish the unique identity of a durable subscriber by setting the following:

- A client ID for the connection
- A topic and a subscription name for the subscriber

You set the client ID administratively for a client-specific connection factory using either the command line or the Administration Console.

After using this connection factory to create the connection and the session, you call the `createDurableSubscriber` method with two arguments: the topic and a string that specifies the name of the subscription:

```
String subName = "MySub";
MessageConsumer topicSubscriber =
     session.createDurableSubscriber(myTopic, subName);
```

The subscriber becomes active after you start the `Connection` or `TopicConnection`. Later, you might close the subscriber:

```
topicSubscriber.close();
```

The JMS provider stores the messages sent or published to the topic, as it would store messages sent to a queue. If the program or another application calls `createDurableSubscriber` using the same connection factory and its client ID, the same topic, and the same subscription name, the subscription is reactivated, and the JMS provider delivers the messages that were published while the subscriber was inactive.

To delete a durable subscription, first close the subscriber, and then use the `unsubscribe` method, with the subscription name as the argument:

```
topicSubscriber.close();
session.unsubscribe("MySub");
```

The `unsubscribe` method deletes the state that the provider maintains for the subscriber.

Figure 45–6 and Figure 45–7 show the difference between a nondurable and a durable subscriber. With an ordinary, nondurable subscriber, the subscriber and the subscription begin and end at the same point and are, in effect, identical. When a subscriber is closed, the subscription also ends. Here, `create` stands for a call to `Session.createConsumer` with a `Topic` argument, and `close` stands for a call to `MessageConsumer.close`. Any messages published to the topic between the time of the first `close` and the time of the second `create` are not consumed by the subscriber. In Figure 45–6, the subscriber consumes messages M1, M2, M5, and M6, but messages M3 and M4 are lost.

FIGURE 45–6 Nondurable Subscribers and Subscriptions



With a durable subscriber, the subscriber can be closed and re-created, but the subscription continues to exist and to hold messages until the application calls the `unsubscribe` method. In Figure 45–7, `create` stands for a call to `Session.createDurableSubscriber`, `close` stands for a call to `MessageConsumer.close`, and `unsubscribe` stands for a call to `Session.unsubscribe`. Messages published while the subscriber is closed are received when the subscriber is created again. So even though messages M2, M4, and M5 arrive while the subscriber is closed, they are not lost.

FIGURE 45–7 A Durable Subscriber and Subscription



See "A Message Acknowledgment Example" on page 819, "A Durable Subscription Example" on page 821, and "An Application That Uses the JMS API with a Session Bean" on page 829 for examples of Java EE applications that use durable subscriptions.

Using JMS API Local Transactions

You can group a series of operations into an atomic unit of work called a transaction. If any one of the operations fails, the transaction can be rolled back, and the operations can be attempted again from the beginning. If all the operations succeed, the transaction can be committed.

In a JMS client, you can use local transactions to group message sends and receives. The JMS API `Session` interface provides `commit` and `rollback` methods that you can use in a JMS client. A transaction commit means that all produced messages are sent and all consumed messages are acknowledged. A transaction rollback means that all produced messages are destroyed and all consumed messages are recovered and redelivered unless they have expired (see "Allowing Messages to Expire" on page 777).

A transacted session is always involved in a transaction. As soon as the `commit` or the `rollback` method is called, one transaction ends and another transaction begins. Closing a transacted session rolls back its transaction in progress, including any pending sends and receives.

In an Enterprise JavaBeans component, you cannot use the `Session.commit` and `Session.rollback` methods. Instead, you use distributed transactions, which are described in "Using the JMS API in Java EE Applications" on page 783.

You can combine several sends and receives in a single JMS API local transaction. If you do so, you need to be careful about the order of the operations. You will have no problems if the transaction consists of all sends or all receives or if the receives come before the sends. But if you try to use a request/reply mechanism, whereby you send a message and then try to receive a

reply to the sent message in the same transaction, the program will hang, because the send cannot take place until the transaction is committed. The following code fragment illustrates the problem:

```
// Don't do this!
outMsg.setJMSReplyTo(replyQueue);
producer.send(outQueue, outMsg);
consumer = session.createConsumer(replyQueue);
inMsg = consumer.receive();
session.commit();
```

Because a message sent during a transaction is not actually sent until the transaction is committed, the transaction cannot contain any receives that depend on that message's having been sent.

In addition, the production and the consumption of a message cannot both be part of the same transaction. The reason is that the transactions take place between the clients and the JMS provider, which intervenes between the production and the consumption of the message. Figure 45–8 illustrates this interaction.

FIGURE 45–8 Using JMS API Local Transactions



The sending of one or more messages to one or more destinations by client 1 can form a single transaction, because it forms a single set of interactions with the JMS provider using a single session. Similarly, the receiving of one or more messages from one or more destinations by client 2 also forms a single transaction using a single session. But because the two clients have no direct interaction and are using two different sessions, no transactions can take place between them.

Another way of putting this is that the act of producing and/or consuming messages in a session can be transactional, but the act of producing and consuming a specific message across different sessions cannot be transactional.

This is the fundamental difference between messaging and synchronized processing. Instead of tightly coupling the sending and receiving of data, message producers and consumers use an alternative approach to reliability, one that is built on a JMS provider's ability to supply a once-and-only-once message delivery guarantee.

When you create a session, you specify whether it is transacted. The first argument to the `createSession` method is a `boolean` value. A value of `true` means that the session is transacted; a value of `false` means that it is not transacted. The second argument to this method is the acknowledgment mode, which is relevant only to nontransacted sessions (see "Controlling Message Acknowledgment" on page 775). If the session is transacted, the second argument is ignored, so it is a good idea to specify `0` to make the meaning of your code clear. For example:

```
session = connection.createSession(true, 0);
```

The `commit` and the `rollback` methods for local transactions are associated with the session. You can combine queue and topic operations in a single transaction if you use the same session to perform the operations. For example, you can use the same session to receive a message from a queue and send a message to a topic in the same transaction.

You can pass a client program's session to a message listener's constructor function and use it to create a message producer. In this way, you can use the same session for receives and sends in asynchronous message consumers.

"A Local Transaction Example" on page 823 provides an example of the use of JMS API local transactions.

Using the JMS API in Java EE Applications

This section describes the ways in which using the JMS API in enterprise bean applications or web applications differs from using it in application clients.

A general rule in the Java EE platform specification applies to all Java EE components that use the JMS API within EJB or web containers:

Application components in the web and EJB containers must not attempt to create more than one active (not closed) `Session` object per connection.

This rule does not apply to application clients. The application client container supports the creation of multiple sessions for each connection.

Using `@Resource` Annotations in Enterprise Bean or Web Components

When you use the `@Resource` annotation in an application client component, you normally declare the JMS resource static:

```
@Resource(lookup = "jms/ConnectionFactory")
private static ConnectionFactory connectionFactory;

@Resource(lookup = "jms/Queue")
private static Queue queue;
```

However, when you use this annotation in a session bean, a message-driven bean, or a web component, do *not* declare the resource static:

```
@Resource(lookup = "jms/ConnectionFactory")
private ConnectionFactory connectionFactory;

@Resource(lookup = "jms/Topic")
private Topic topic;
```

If you declare the resource static, runtime errors will result.

Using Session Beans to Produce and to Synchronously Receive Messages

An application that produces messages or synchronously receives them can use a session bean to perform these operations. The example in "An Application That Uses the JMS API with a Session Bean" on page 829 uses a stateless session bean to publish messages to a topic.

Because a blocking synchronous receive ties up server resources, it is not a good programming practice to use such a `receive` call in an enterprise bean. Instead, use a timed synchronous receive, or use a message-driven bean to receive messages asynchronously. For details about blocking and timed synchronous receives, see "Writing the Clients for the Synchronous Receive Example" on page 792.

Using the JMS API in an enterprise bean or web application is in many ways similar to using it in an application client. The main differences are the areas of resource management and transactions.

Resource Management

The JMS API resources are a JMS API connection and a JMS API session. In general, it is important to release JMS resources when they are no longer being used. Here are some useful practices to follow.

- If you wish to maintain a JMS API resource only for the life span of a business method, it is a good idea to close the resource in a `finally` block within the method.
- If you would like to maintain a JMS API resource for the life span of an enterprise bean instance, it is a good idea to use a `@PostConstruct` callback method to create the resource and to use a `@PreDestroy` callback method to close the resource. If you use a stateful session bean and you wish to maintain the JMS API resource in a cached state, you must close the resource in a `@PrePassivate` callback method and set its value to `null`, and you must create it again in a `@PostActivate` callback method.

Transactions

Instead of using local transactions, you use container-managed transactions for bean methods that perform sends or receives, allowing the EJB container to handle transaction demarcation. Because container-managed transactions are the default, you do not have to use an annotation to specify them.

You can use bean-managed transactions and the `javax.transaction.UserTransaction` interface's transaction demarcation methods, but you should do so only if your application has special requirements and you are an expert in using transactions. Usually, container-managed transactions produce the most efficient and correct behavior. This tutorial does not provide any examples of bean-managed transactions.

Using Message-Driven Beans to Receive Messages Asynchronously

The sections "What Is a Message-Driven Bean?" on page 399 and "How Does the JMS API Work with the Java EE Platform?" on page 759 describe how the Java EE platform supports a special kind of enterprise bean, the message-driven bean, which allows Java EE applications to process JMS messages asynchronously. Session beans allow you to send messages and to receive them synchronously but not asynchronously.

A message-driven bean is a message listener that can reliably consume messages from a queue or a durable subscription. The messages can be sent by any Java EE component (from an application client, another enterprise bean, or a web component) or from an application or a system that does not use Java EE technology.

Like a message listener in an application client, a message-driven bean contains an `onMessage` method that is called automatically when a message arrives. Like a message listener, a message-driven bean class can implement helper methods invoked by the `onMessage` method to aid in message processing.

A message-driven bean, however, differs from an application client's message listener in the following ways:

- Certain setup tasks are performed by the EJB container.
- The bean class uses the `@MessageDriven` annotation to specify properties for the bean or the connection factory, such as a destination type, a durable subscription, a message selector, or an acknowledgment mode. The examples in Chapter 46, "Java Message Service Examples," show how the JMS resource adapter works in the GlassFish Server.

The EJB container automatically performs several setup tasks that a stand-alone client has to do:

- Creating a message consumer to receive the messages. Instead of creating a message consumer in your source code, you associate the message-driven bean with a destination and a connection factory at deployment time. If you want to specify a durable subscription or use a message selector, you do this at deployment time also.
- Registering the message listener. You must not call `setMessageListener`.
- Specifying a message acknowledgment mode. The default mode, `AUTO_ACKNOWLEDGE`, is used unless it is overriden by a property setting.

If JMS is integrated with the application server using a resource adapter, the JMS resource adapter handles these tasks for the EJB container.

Your message-driven bean class must implement the `javax.jms.MessageListener` interface and the `onMessage` method.

It may implement a `@PostConstruct` callback method to create a connection, and a `@PreDestroy` callback method to close the connection. Typically, it implements these methods if it produces messages or does synchronous receives from another destination.

The bean class commonly injects a `MessageDrivenContext` resource, which provides some additional methods that you can use for transaction management.

The main difference between a message-driven bean and a session bean is that a message-driven bean has no local or remote interface. Instead, it has only a bean class.

A message-driven bean is similar in some ways to a stateless session bean: Its instances are relatively short-lived and retain no state for a specific client. The instance variables of the message-driven bean instance can contain some state across the handling of client messages: for example, a JMS API connection, an open database connection, or an object reference to an enterprise bean object.

Like a stateless session bean, a message-driven bean can have many interchangeable instances running at the same time. The container can pool these instances to allow streams of messages to be processed concurrently. The container attempts to deliver messages in chronological order when it does not impair the concurrency of message processing, but no guarantees are made as to the exact order in which messages are delivered to the instances of the message-driven bean class. Because concurrency can affect the order in which messages are delivered, you should write your applications to handle messages that arrive out of sequence.

For example, your application could manage conversations by using application-level sequence numbers. An application-level conversation control mechanism with a persistent conversation state could cache later messages until earlier messages have been processed.

Another way to ensure order is to have each message or message group in a conversation require a confirmation message that the sender blocks on receipt of. This forces the responsibility for order back on the sender and more tightly couples senders to the progress of message-driven beans.

To create a new instance of a message-driven bean, the container does the following:

- Instantiates the bean
- Performs any required resource injection
- Calls the `@PostConstruct` callback method, if it exists

To remove an instance of a message-driven bean, the container calls the `@PreDestroy` callback method.

Figure 45–9 shows the lifecycle of a message-driven bean.

FIGURE 45–9 Lifecycle of a Message-Driven Bean



Managing Distributed Transactions

JMS client applications use JMS API local transactions (described in "Using JMS API Local Transactions" on page 781), which allow the grouping of sends and receives within a specific JMS session. Java EE applications commonly use distributed transactions to ensure the integrity of accesses to external resources. For example, distributed transactions allow multiple applications to perform atomic updates on the same database, and they allow a single application to perform atomic updates on multiple databases.

In a Java EE application that uses the JMS API, you can use transactions to combine message sends or receives with database updates and other resource manager operations. You can access resources from multiple application components within a single transaction. For example, a servlet can start a transaction, access multiple databases, invoke an enterprise bean that sends a JMS message, invoke another enterprise bean that modifies an EIS system using the Connector architecture, and finally commit the transaction. Your application cannot, however, both send a

JMS message and receive a reply to it within the same transaction; the restriction described in "Using JMS API Local Transactions" on page 781 still applies.

Distributed transactions within the EJB container can be either of two kinds:

- **Container-managed transactions**: The EJB container controls the integrity of your transactions without your having to call `commit` or `rollback`. Container-managed transactions are recommended for Java EE applications that use the JMS API. You can specify appropriate transaction attributes for your enterprise bean methods.

  Use the `Required` transaction attribute (the default) to ensure that a method is always part of a transaction. If a transaction is in progress when the method is called, the method will be part of that transaction; if not, a new transaction will be started before the method is called and will be committed when the method returns.
- **Bean-managed transactions**: You can use these in conjunction with the `javax.transaction.UserTransaction` interface, which provides its own `commit` and `rollback` methods that you can use to delimit transaction boundaries. Bean-managed transactions are recommended only for those who are experienced in programming transactions.

You can use either container-managed transactions or bean-managed transactions with message-driven beans. To ensure that all messages are received and handled within the context of a transaction, use container-managed transactions and use the `Required` transaction attribute (the default) for the `onMessage` method. This means that if there is no transaction in progress, a new transaction will be started before the method is called and will be committed when the method returns.

When you use container-managed transactions, you can call the following `MessageDrivenContext` methods:

- `setRollbackOnly`: Use this method for error handling. If an exception occurs, `setRollbackOnly` marks the current transaction so that the only possible outcome of the transaction is a rollback.
- `getRollbackOnly`: Use this method to test whether the current transaction has been marked for rollback.

If you use bean-managed transactions, the delivery of a message to the `onMessage` method takes place outside the distributed transaction context. The transaction begins when you call the `UserTransaction.begin` method within the `onMessage` method, and it ends when you call `UserTransaction.commit` or `UserTransaction.rollback`. Any call to the `Connection.createSession` method must take place within the transaction. If you call `UserTransaction.rollback`, the message is not redelivered, whereas calling `setRollbackOnly` for container-managed transactions does cause a message to be redelivered.

Neither the JMS API specification nor the Enterprise JavaBeans specification (available from `http://jcp.org/en/jsr/detail?id=318`) specifies how to handle calls to JMS API methods outside transaction boundaries. The Enterprise JavaBeans specification does state that the EJB

container is responsible for acknowledging a message that is successfully processed by the `onMessage` method of a message-driven bean that uses bean-managed transactions. Using bean-managed transactions allows you to process the message by using more than one transaction or to have some parts of the message processing take place outside a transaction context. In most cases, however, container-managed transactions provide greater reliability and are therefore preferable.

When you create a session in an enterprise bean, the container ignores the arguments you specify, because it manages all transactional properties for enterprise beans. It is still a good idea to specify arguments of `true` and `0` to the `createSession` method to make this situation clear:

```
session = connection.createSession(true, 0);
```

When you use container-managed transactions, you normally use the `Required` transaction attribute (the default) for your enterprise bean's business methods.

You do not specify a message acknowledgment mode when you create a message-driven bean that uses container-managed transactions. The container acknowledges the message automatically when it commits the transaction.

If a message-driven bean uses bean-managed transactions, the message receipt cannot be part of the bean-managed transaction, so the container acknowledges the message outside the transaction.

If the `onMessage` method throws a `RuntimeException`, the container does not acknowledge processing the message. In that case, the JMS provider will redeliver the unacknowledged message in the future.

Using the JMS API with Application Clients and Web Components

An application client in a Java EE application can use the JMS API in much the same way that a stand-alone client program does. It can produce messages, and it can consume messages by using either synchronous receives or message listeners. See Chapter 25, "A Message-Driven Bean Example," for an example of an application client that produces messages. For an example of using an application client to produce and to consume messages, see "An Application Example That Deploys a Message-Driven Bean on Two Servers" on page 847.

The Java EE platform specification does not impose strict constraints on how web components should use the JMS API. In the GlassFish Server, a web component can send messages and consume them synchronously but cannot consume them asynchronously.

Because a blocking synchronous receive ties up server resources, it is not a good programming practice to use such a `receive` call in a web component. Instead, use a timed synchronous receive. For details about blocking and timed synchronous receives, see "Writing the Clients for the Synchronous Receive Example" on page 792.

Further Information about JMS

For more information about JMS, see:

- Java Message Service web site:
  `http://www.oracle.com/technetwork/java/index-jsp-142945.html`
- Java Message Service specification, version 1.1, available from
  `http://www.oracle.com/technetwork/java/docs-136352.html`

◆ ◆ ◆ CHAPTER 46

Java Message Service Examples

This chapter provides examples that show how to use the JMS API in various kinds of Java EE applications. It covers the following topics:

The examples are in the following directory:

tut-install`/examples/jms/`

To build and run the examples, you will do the following:

1. Use NetBeans IDE or the Ant tool to compile and package the example.
2. Use NetBeans IDE or the Ant tool to deploy the example and create resources for it.
3. Use NetBeans IDE, the `appclient` command, or the Ant tool to run the client.

Each example has a `build.xml` file that refers to files in the following directory:

tut-install`/examples/bp-project/`

Each example has a `setup/glassfish-resources.xml` file that is used to create resources for the example.

See Chapter 25, "A Message-Driven Bean Example," for a simpler example of a Java EE application that uses the JMS API.

Writing Simple JMS Applications

This section shows how to create, package, and run simple JMS clients that are packaged as application clients and deployed to a Java EE server. The clients demonstrate the basic tasks that a JMS application must perform:

- Creating a connection and a session
- Creating message producers and consumers
- Sending and receiving messages

In a Java EE application, some of these tasks are performed, in whole or in part, by the container. If you learn about these tasks, you will have a good basis for understanding how a JMS application works on the Java EE platform.

Each example uses two clients: one that sends messages and one that receives them. You can run the clients in NetBeans IDE or in two terminal windows.

When you write a JMS client to run in a enterprise bean application, you use many of the same methods in much the same sequence as you do for an application client. However, there are some significant differences. "Using the JMS API in Java EE Applications" on page 783 describes these differences, and this chapter provides examples that illustrate them.

The examples for this section are in the following directory:

tut-install`/examples/jms/simple/`

The examples are in the following four subdirectories:

```
producer
synchconsumer
asynchconsumer
messagebrowser
```

A Simple Example of Synchronous Message Receives

This section describes the sending and receiving clients in an example that uses the `receive` method to consume messages synchronously. This section then explains how to compile, package, and run the clients using the GlassFish Server.

The following sections describe the steps in creating and running the example.

Writing the Clients for the Synchronous Receive Example

The sending client, `producer/src/java/Producer.java`, performs the following steps:

1. Injects resources for a connection factory, queue, and topic:

```
@Resource(lookup = "jms/ConnectionFactory")
private static ConnectionFactory connectionFactory;
@Resource(lookup = "jms/Queue")private static Queue queue;
@Resource(lookup = "jms/Topic")private static Topic topic;
```

2. Retrieves and verifies command-line arguments that specify the destination type and the number of arguments:

```
final int NUM_MSGS;
String destType = args[0];
System.out.println("Destination type is " + destType);
if ( ! ( destType.equals("queue") || destType.equals("topic") ) ) {
    System.err.println("Argument must be \"queue\" or " + "\"topic\"");
    System.exit(1);
}
if (args.length == 2){
    NUM_MSGS = (new Integer(args[1])).intValue();
}
else {
    NUM_MSGS = 1;
}
```

3. Assigns either the queue or topic to a destination object, based on the specified destination type:

```
Destination dest = null;
try {
    if (destType.equals("queue")) {
        dest = (Destination) queue;
    } else {
        dest = (Destination) topic;
    }
}
catch (Exception e) {
    System.err.println("Error setting destination: " + e.toString());
    e.printStackTrace();
    System.exit(1);
}
```

4. Creates a `Connection` and a `Session`:

```
Connection connection = connectionFactory.createConnection();
Session session = connection.createSession(false, Session.AUTO_ACKNOWLEDGE);
```

5. Creates a `MessageProducer` and a `TextMessage`:

```
MessageProducer producer = session.createProducer(dest);
TextMessage message = session.createTextMessage();
```

6. Sends one or more messages to the destination:

```
for (int i = 0; i < NUM_MSGS; i++) {
    message.setText("This is message " + (i + 1) + " from producer");
    System.out.println("Sending message: " + message.getText());
    producer.send(message);
}
```

7. Sends an empty control message to indicate the end of the message stream:

```
producer.send(session.createMessage());
```

Sending an empty message of no specified type is a convenient way to indicate to the consumer that the final message has arrived.

8. Closes the connection in a `finally` block, automatically closing the session and `MessageProducer`:

```
} finally {
    if (connection != null) {
        try { connection.close(); }
        catch (JMSException e) { }
    }
}
```

The receiving client, `synchconsumer/src/java/SynchConsumer.java`, performs the following steps:

1. Injects resources for a connection factory, queue, and topic.
2. Assigns either the queue or topic to a destination object, based on the specified destination type.
3. Creates a `Connection` and a `Session`.
4. Creates a `MessageConsumer`:

```
consumer = session.createConsumer(dest);
```

5. Starts the connection, causing message delivery to begin:

```
connection.start();
```

6. Receives the messages sent to the destination until the end-of-message-stream control message is received:

```
while (true) {
    Message m = consumer.receive(1);
    if (m != null) {
        if (m instanceof TextMessage) {
            message = (TextMessage) m;
            System.out.println("Reading message: " + message.getText());
        } else {
            break;
        }
    }
}
```

Because the control message is not a `TextMessage`, the receiving client terminates the `while` loop and stops receiving messages after the control message arrives.

7. Closes the connection in a `finally` block, automatically closing the session and `MessageConsumer`.

The `receive` method can be used in several ways to perform a synchronous receive. If you specify no arguments or an argument of `0`, the method blocks indefinitely until a message arrives:

```
Message m = consumer.receive();
Message m = consumer.receive(0);
```

For a simple client, this may not matter. But if you do not want your application to consume system resources unnecessarily, use a timed synchronous receive. Do one of the following:

- Call the `receive` method with a timeout argument greater than `0`:

```
Message m = consumer.receive(1); // 1 millisecond
```

- Call the `receiveNoWait` method, which receives a message only if one is available:

```
Message m = consumer.receiveNoWait();
```

The `SynchConsumer` client uses an indefinite `while` loop to receive messages, calling `receive` with a timeout argument. Calling `receiveNoWait` would have the same effect.

Starting the JMS Provider

When you use the GlassFish Server, your JMS provider is the GlassFish Server. Start the server as described in "Starting and Stopping the GlassFish Server" on page 71.

JMS Administered Objects for the Synchronous Receive Example

This example uses the following JMS administered objects:

- A connection factory
- Two destination resources, a topic and a queue

NetBeans IDE and the Ant tasks for the JMS examples create needed JMS resources when you deploy the applications, using a file named `setup/glassfish-resources.xml`. This file is most easily created using NetBeans IDE, although you can create it by hand.

You can also use the `asadmin create-jms-resource` command to create resources, and the `asadmin delete-jms-resource` command to remove them.

▼ To Create JMS Resources Using NetBeans IDE

Follow these steps to create a JMS resource in GlassFish Server using NetBeans IDE. Repeat these steps for each resource you need.

The example applications in Chapter 46, "Java Message Service Examples," already have the resources, so you will need to follow these steps only when you create your own applications.

1. **Right-click the project for which you want to create resources and choose New, then choose Other.**

   The New File wizard opens.

2. **Under Categories, select GlassFish.**

3. **Under File Types, select JMS Resource.**

   The General Attributes - JMS Resource page opens.

4. **In the JNDI Name field, type the name of the resource.**

   By convention, JMS resource names begin with `jms/`.

5. **Select the radio button for the resource type.**

   Normally, this is either `javax.jms.Queue`, `javax.jms.Topic`, or `javax.jms.ConnectionFactory`.

6. **Click Next.**

   The JMS Properties page opens.

7. **For a queue or topic, type a name for a physical queue in the Value field for the Name property.**

   You can type any value for this required field.

   Connection factories have no required properties. In a few situations, discussed in later sections, you may need to specify a property.

8. **Click Finish.**

   A file named `glassfish-resources.xml` is created in your project, in a directory named `setup`. In the project pane, you can find it under the Server Resources node. If this file exists, resources are created automatically by NetBeans IDE when you deploy the project.

▼ To Delete JMS Resources Using NetBeans IDE

1. **In the Services pane, expand the Servers node, then expand the GlassFish Server 3.1 node.**
2. **Expand the Resources node, then expand the Connector Resources node.**
3. **Expand the Admin Object Resources node.**
4. **Right-click any destination you want to remove and select Unregister.**
5. **Expand the Connector Connection Pools node.**
6. **Right-click any connection factory you want to remove and select Unregister.**

   Every connection factory has both a connector connection pool and an associated connector resource. When you remove the connector connection pool, the resource is removed automatically. You can verify the removal by expanding the Connector Resources node.

Building, Packaging, Deploying, and Running the Clients for the Synchronous Receive Example

To run these examples using the GlassFish Server, package each one in an application client JAR file. The application client JAR file requires a manifest file, located in the `src/conf` directory for each example, along with the `.class` file.

The `build.xml` file for each example contains Ant targets that compile, package, and deploy the example. The targets place the `.class` file for the example in the `build/jar` directory. Then the targets use the `jar` command to package the class file and the manifest file in an application client JAR file.

Because the examples use the common interfaces, you can run them using either a queue or a topic.

▼ To Build and Package the Clients for the Synchronous Receive Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/jms/simple/`
3. **Select the `producer` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the project and select Build.**
7. **Select the `synchconsumer` folder.**
8. **Select the Open as Main Project check box.**
9. **Click Open Project.**
10. **In the Projects tab, right-click the project and select Build.**

▼ To Deploy and Run the Clients for the Synchronous Receive Example Using NetBeans IDE

1 **Deploy and run the `Producer` example:**

   a. **Right-click the `producer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      queue 3
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The output of the program looks like this (along with some additional output):

      ```
      Destination type is queue
      Sending message: This is message 1 from producer
      Sending message: This is message 2 from producer
      Sending message: This is message 3 from producer
      ```

      The messages are now in the queue, waiting to be received.

Note – When you run an application client, the command often takes a long time to complete.

---

2 **Now deploy and run the `SynchConsumer` example:**

   a. **Right-click the `synchconsumer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      queue
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The output of the program looks like this (along with some additional output):

      ```
      Destination type is queue
      Reading message: This is message 1 from producer
      Reading message: This is message 2 from producer
      Reading message: This is message 3 from producer
      ```

3. **Now try running the programs in the opposite order. Right-click the `synchconsumer` project and select Run.**

   The Output pane displays the destination type and then appears to hang, waiting for messages.

4. **Right-click the `producer` project and select Run.**

   The Output pane shows the output of both programs, in two different tabs.

5. **Now run the `Producer` example using a topic instead of a queue.**

   a. **Right-click the `producer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      topic 3
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The output looks like this (along with some additional output):

      ```
      Destination type is topic
      Sending message: This is message 1 from producer
      Sending message: This is message 2 from producer
      Sending message: This is message 3 from producer
      ```

6. **Now run the `SynchConsumer` example using the topic.**

   a. **Right-click the `synchconsumer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      topic
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The result, however, is different. Because you are using a topic, messages that were sent before you started the consumer cannot be received. (See "Publish/Subscribe Messaging Domain" on page 762 for details.) Instead of receiving the messages, the program appears to hang.

7. **Run the `Producer` example again. Right-click the `producer` project and select Run.**

   Now the `SynchConsumer` example receives the messages:

```
Destination type is topic
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
Reading message: This is message 3 from producer
```

▼ To Build and Package the Clients for the Synchronous Receive Example Using Ant

1. **In a terminal window, go to the `producer` directory:**

```
cd producer
```

2. **Type the following command:**

```
ant
```

3. **In a terminal window, go to the `synchconsumer` directory:**

```
cd ../synchconsumer
```

4. **Type the following command:**

```
ant
```

   The targets place the application client JAR file in the `dist` directory for each example.

▼ To Deploy and Run the Clients for the Synchronous Receive Example Using Ant and the `appclient` Command

You can run the clients using the `appclient` command. The `build.xml` file for each project includes a target that creates resources, deploys the client, and then retrieves the client stubs that the `appclient` command uses. Each of the clients takes one or more command-line arguments: a destination type and, for `Producer`, a number of messages.

To build, deploy, and run the `Producer` and `SynchConsumer` examples using Ant and the `appclient` command, follow these steps.

To run the clients, you need two terminal windows.

1. **In a terminal window, go to the `producer` directory:**

```
cd ../producer
```

2. **Create any needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

```
ant getclient
```

   Ignore the message that states that the application is deployed at a URL.

3. **Run the `Producer` program, sending three messages to the queue:**

   ```
   appclient -client client-jar/producerClient.jar queue 3
   ```

   The output of the program looks like this (along with some additional output):

   ```
   Destination type is queue
   Sending message: This is message 1 from producer
   Sending message: This is message 2 from producer
   Sending message: This is message 3 from producer
   ```

   The messages are now in the queue, waiting to be received.

   Note – When you run an application client, the command often takes a long time to complete.

4. **In the same window, go to the `synchconsumer` directory:**

   ```
   cd ../synchconsumer
   ```

5. **Deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

   ```
   ant getclient
   ```

   Ignore the message that states that the application is deployed at a URL.

6. **Run the `SynchConsumer` client, specifying the queue:**

   ```
   appclient -client client-jar/synchconsumerClient.jar queue
   ```

   The output of the client looks like this (along with some additional output):

   ```
   Destination type is queue
   Reading message: This is message 1 from producer
   Reading message: This is message 2 from producer
   Reading message: This is message 3 from producer
   ```

7. **Now try running the clients in the opposite order. Run the `SynchConsumer` client:**

   ```
   appclient -client client-jar/synchconsumerClient.jar queue
   ```

   The client displays the destination type and then appears to hang, waiting for messages.

8. **In a different terminal window, run the `Producer` client.**

   ```
   cd tut-install/examples/jms/simple/producer
   appclient -client client-jar/producerClient.jar queue 3
   ```

   When the messages have been sent, the `SynchConsumer` client receives them and exits.

9. **Now run the `Producer` client using a topic instead of a queue:**

   ```
   appclient -client client-jar/producerClient.jar topic 3
   ```

   The output of the client looks like this (along with some additional output):

   ```
   Destination type is topic
   Sending message: This is message 1 from producer
   ```

```
Sending message: This is message 2 from producer
Sending message: This is message 3 from producer
```

10 **Now run the `SynchConsumer` client using the topic:**

```
appclient -client client-jar/synchconsumerClient.jar topic
```

The result, however, is different. Because you are using a topic, messages that were sent before you started the consumer cannot be received. (See "Publish/Subscribe Messaging Domain" on page 762, for details.) Instead of receiving the messages, the client appears to hang.

11 **Run the `Producer` client again.**

Now the `SynchConsumer` client receives the messages (along with some additional output):

```
Destination type is topic
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
Reading message: This is message 3 from producer
```

A Simple Example of Asynchronous Message Consumption

This section describes the receiving clients in an example that uses a message listener to consume messages asynchronously. This section then explains how to compile and run the clients using the GlassFish Server.

Writing the Clients for the Asynchronous Receive Example

The sending client is `producer/src/java/Producer.java`, the same client used in the example in "A Simple Example of Synchronous Message Receives" on page 792.

An asynchronous consumer normally runs indefinitely. This one runs until the user types the letter `q` or `Q` to stop the client.

The receiving client, `asynchconsumer/src/java/AsynchConsumer.java`, performs the following steps:

1. Injects resources for a connection factory, queue, and topic.
2. Assigns either the queue or topic to a destination object, based on the specified destination type.
3. Creates a `Connection` and a `Session`.
4. Creates a `MessageConsumer`.
5. Creates an instance of the `TextListener` class and registers it as the message listener for the `MessageConsumer`:

   ```
   listener = new TextListener();consumer.setMessageListener(listener);
   ```
6. Starts the connection, causing message delivery to begin.

7. Listens for the messages published to the destination, stopping when the user types the character `q` or `Q`:

```
System.out.println("To end program, type Q or q, " + "then <return>");
inputStreamReader = new InputStreamReader(System.in);
while (!((answer == 'q') || (answer == 'Q'))) {
    try {
        answer = (char) inputStreamReader.read();
    } catch (IOException e) {
        System.out.println("I/O exception: " + e.toString());
    }
}
```

8. Closes the connection, which automatically closes the session and `MessageConsumer`.

The message listener, `asynchconsumer/src/java/TextListener.java`, follows these steps:

1. When a message arrives, the `onMessage` method is called automatically.
2. The `onMessage` method converts the incoming message to a `TextMessage` and displays its content. If the message is not a text message, it reports this fact:

```
public void onMessage(Message message) {
    TextMessage msg = null;
    try {
        if (message instanceof TextMessage) {
            msg = (TextMessage) message;
             System.out.println("Reading message: " + msg.getText());
        } else {
             System.out.println("Message is not a " + "TextMessage");
        }
    } catch (JMSException e) {
        System.out.println("JMSException in onMessage(): " + e.toString());
    } catch (Throwable t) {
        System.out.println("Exception in onMessage():" + t.getMessage());
    }
}
```

You will use the connection factory and destinations you created for "A Simple Example of Synchronous Message Receives" on page 792.

▼ To Build and Package the `AsynchConsumer` Client Using NetBeans IDE

1 From the File menu, choose Open Project.

2 In the Open Project dialog, navigate to:

tut-install`/examples/jms/simple/`

3 Select the `asynchconsumer` folder.

4 Select the Open as Main Project check box.

5 Click Open Project.

6. **In the Projects tab, right-click the project and select Build.**

▼ To Deploy and Run the Clients for the Asynchronous Receive Example Using NetBeans IDE

1. **Run the `AsynchConsumer` example:**

   a. **Right-click the `asynchconsumer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      topic
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The client displays the following lines and appears to hang:

      ```
      Destination type is topic
      To end program, type Q or q, then <return>
      ```

2. **Now run the `Producer` example:**

   a. **Right-click the `producer` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type the following:**

      ```
      topic 3
      ```

   d. **Click OK.**

   e. **Right-click the project and select Run.**

      The output of the client looks like this:

      ```
      Destination type is topic
      Sending message: This is message 1 from producer
      Sending message: This is message 2 from producer
      Sending message: This is message 3 from producer
      ```

      In the other window, the `AsynchConsumer` client displays the following:

      ```
      Destination type is topic
      To end program, type Q or q, then <return>
      Reading message: This is message 1 from producer
      Reading message: This is message 2 from producer
      ```

```
Reading message: This is message 3 from producer
Message is not a TextMessage
```

The last line appears because the client has received the non-text control message sent by the `Producer` client.

3 Type `Q` or `q` in the Output window and press Return to stop the client.

4 Now run the `Producer` client using a queue.

In this case, as with the synchronous example, you can run the `Producer` client first, because there is no timing dependency between the sender and receiver.

a. Right-click the `producer` project and select Properties.

b. Select Run from the Categories tree.

c. In the Arguments field, type the following:

```
queue 3
```

d. Click OK.

e. Right-click the project and select Run.

The output of the client looks like this:

```
Destination type is queue
Sending message: This is message 1 from producer
Sending message: This is message 2 from producer
Sending message: This is message 3 from producer
```

5 Run the `AsynchConsumer` client.

a. Right-click the `asynchconsumer` project and select Properties.

b. Select Run from the Categories tree.

c. In the Arguments field, type the following:

```
queue
```

d. Click OK.

e. Right-click the project and select Run.

The output of the client looks like this:

```
Destination type is queue
To end program, type Q or q, then <return>
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
```

```
Reading message: This is message 3 from producer
Message is not a TextMessage
```

6. **Type `Q` or `q` in the Output window and press Return to stop the client.**

▼ To Build and Package the `AsynchConsumer` Client Using Ant

1. **In a terminal window, go to the `asynchconsumer` directory:**

   ```
   cd ../asynchconsumer
   ```

2. **Type the following command:**

   ```
   ant
   ```

   The targets package both the main class and the message listener class in the JAR file and place the file in the `dist` directory for the example.

▼ To Deploy and Run the Clients for the Asynchronous Receive Example Using Ant and the `appclient` Command

1. **Deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

   ```
   ant getclient
   ```

   Ignore the message that states that the application is deployed at a URL.

2. **Run the `AsynchConsumer` client, specifying the `topic` destination type.**

   ```
   appclient -client client-jar/asynchconsumerClient.jar topic
   ```

   The client displays the following lines (along with some additional output) and appears to hang:

   ```
   Destination type is topic
   To end program, type Q or q, then <return>
   ```

3. **In the terminal window where you ran the `Producer` client previously, run the client again, sending three messages.**

   ```
   appclient -client client-jar/producerClient.jar topic 3
   ```

   The output of the client looks like this (along with some additional output):

   ```
   Destination type is topic
   Sending message: This is message 1 from producer
   Sending message: This is message 2 from producer
   Sending message: This is message 3 from producer
   ```

   In the other window, the `AsynchConsumer` client displays the following (along with some additional output):

   ```
   Destination type is topic
   To end program, type Q or q, then <return>
   ```

```
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
Reading message: This is message 3 from producer
Message is not a TextMessage
```

The last line appears because the client has received the non-text control message sent by the `Producer` client.

4. **Type `Q` or `q` and press Return to stop the client.**

5. **Now run the clients using a queue.**

   In this case, as with the synchronous example, you can run the `Producer` client first, because there is no timing dependency between the sender and receiver:

   ```
   appclient -client client-jar/producerClient.jar queue 3
   ```

   The output of the client looks like this:

   ```
   Destination type is queue
   Sending message: This is message 1 from producer
   Sending message: This is message 2 from producer
   Sending message: This is message 3 from producer
   ```

6. **Run the `AsynchConsumer` client:**

   ```
   appclient -client client-jar/asynchconsumerClient.jar queue
   ```

   The output of the client looks like this (along with some additional output):

   ```
   Destination type is queue
   To end program, type Q or q, then <return>
   Reading message: This is message 1 from producer
   Reading message: This is message 2 from producer
   Reading message: This is message 3 from producer
   Message is not a TextMessage
   ```

7. **Type `Q` or `q` to stop the client.**

A Simple Example of Browsing Messages in a Queue

This section describes an example that creates a `QueueBrowser` object to examine messages on a queue, as described in "JMS Queue Browsers" on page 773. This section then explains how to compile, package, and run the example using the GlassFish Server.

Writing the Client for the Queue Browser Example

To create a `QueueBrowser` for a queue, you call the `Session.createBrowser` method with the queue as the argument. You obtain the messages in the queue as an `Enumeration` object. You can then iterate through the `Enumeration` object and display the contents of each message.

The `messagebrowser/src/java/MessageBrowser.java` client performs the following steps:

1. Injects resources for a connection factory and a queue.
2. Creates a `Connection` and a `Session`.
3. Creates a `QueueBrowser`:

```
QueueBrowser browser = session.createBrowser(queue);
```

4. Retrieves the `Enumeration` that contains the messages:

```
Enumeration msgs = browser.getEnumeration();
```

5. Verifies that the `Enumeration` contains messages, then displays the contents of the messages:

```
if ( !msgs.hasMoreElements() ) {
    System.out.println("No messages in queue");
} else {
    while (msgs.hasMoreElements()) {
        Message tempMsg = (Message)msgs.nextElement();
        System.out.println("Message: " + tempMsg);
    }
}
```

6. Closes the connection, which automatically closes the session and `QueueBrowser`.

The format in which the message contents appear is implementation-specific. In the GlassFish Server, the message format looks like this:

```
Message contents:
Text:   This is message 3 from producer
Class:                  com.sun.messaging.jmq.jmsclient.TextMessageImpl
getJMSMessageID():      ID:14-128.149.71.199(f9:86:a2:d5:46:9b)-40814-1255980521747
getJMSTimestamp():      1129061034355
getJMSCorrelationID():  null
JMSReplyTo:             null
JMSDestination:         PhysicalQueue
getJMSDeliveryMode():   PERSISTENT
getJMSRedelivered():    false
getJMSType():           null
getJMSExpiration():     0
getJMSPriority():       4
Properties:             null
```

You will use the connection factory and queue you created for "A Simple Example of Synchronous Message Receives" on page 792.

▼ To Build, Package, Deploy, and Run the `MessageBrowser` Client Using NetBeans IDE

To build, package, deploy, and run the `MessageBrowser` example using NetBeans IDE, follow these steps.

You also need the `Producer` example to send the message to the queue, and one of the consumer clients to consume the messages after you inspect them. If you did not do so already, package these examples.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**
   tut-install`/examples/jms/simple/`
3. **Select the `messagebrowser` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the project and select Build.**
7. **Run the `Producer` client, sending one message to the queue:**
   a. **Right-click the `producer` project and select Properties.**
   b. **Select Run from the Categories tree.**
   c. **In the Arguments field, type the following:**
      `queue`
   d. **Click OK.**
   e. **Right-click the project and select Run.**
      The output of the client looks like this:

```
Destination type is queue
Sending message: This is message 1 from producer
```

8. **Run the `MessageBrowser` client. Right-click the `messagebrowser` project and select Run.**
   The output of the client looks something like this:

```
Message:
Text: This is message 1 from producer
Class: com.sun.messaging.jmq.jmsclient.TextMessageImpl
getJMSMessageID(): ID:12-128.149.71.199(8c:34:4a:1a:1b:b8)-40883-1255980521747
getJMSTimestamp(): 1129062957611
getJMSCorrelationID(): null
JMSReplyTo: null
JMSDestination: PhysicalQueue
getJMSDeliveryMode(): PERSISTENT
getJMSRedelivered(): false
getJMSType(): null
getJMSExpiration(): 0
getJMSPriority(): 4
Properties: null
Message:
Class: com.sun.messaging.jmq.jmsclient.MessageImpl
getJMSMessageID(): ID:13-128.149.71.199(8c:34:4a:1a:1b:b8)-40883-1255980521747
```

```
getJMSTimestamp(): 1129062957616
getJMSCorrelationID(): null
JMSReplyTo: null
JMSDestination: PhysicalQueue
getJMSDeliveryMode(): PERSISTENT
getJMSRedelivered(): false
getJMSType(): null
getJMSExpiration(): 0
getJMSPriority(): 4
Properties: null
```

The first message is the `TextMessage`, and the second is the non-text control message.

9 Run the `SynchConsumer` client to consume the messages.

a. Right-click the `synchconsumer` project and select Properties.

b. Select Run from the Categories tree.

c. In the Arguments field, type the following:

```
queue
```

d. Click OK.

e. Right-click the project and select Run.

The output of the client looks like this:

```
Destination type is queue
Reading message: This is message 1 from producer
```

▼ To Build, Package, Deploy, and Run the `MessageBrowser` Client Using Ant and the `appclient` Command

To build, package, deploy, and run the `MessageBrowser` example using Ant, follow these steps.

You also need the `Producer` example to send the message to the queue, and one of the consumer clients to consume the messages after you inspect them. If you did not do so already, package these examples.

To run the clients, you need two terminal windows.

1 In a terminal window, go to the `messagebrowser` directory.

```
cd ../messagebrowser
```

2 Type the following command:

```
ant
```

The targets place the application client JAR file in the `dist` directory for the example.

3 Go to the `producer` directory.

4. **Run the `Producer` client, sending one message to the queue:**

   ```
   appclient -client client-jar/producerClient.jar queue
   ```

   The output of the client looks like this (along with some additional output):

   ```
   Destination type is queue
   Sending message: This is message 1 from producer
   ```

5. **Go to the `messagebrowser` directory.**

6. **Deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

   ```
   ant getclient
   ```

   Ignore the message that states that the application is deployed at a URL.

7. **Because this example takes no command-line arguments, you can run the `MessageBrowser` client using the following command:**

   ```
   ant run
   ```

   Alternatively, you can type the following command:

   ```
   appclient -client client-jar/messagebrowserClient.jar
   ```

   The output of the client looks something like this (along with some additional output):

   ```
   Message:
   Text: This is message 1 from producer
   Class: com.sun.messaging.jmq.jmsclient.TextMessageImpl
   getJMSMessageID(): ID:12-128.149.71.199(8c:34:4a:1a:1b:b8)-40883-1255980521747
   getJMSTimestamp(): 1255980521747
   getJMSCorrelationID(): null
   JMSReplyTo: null
   JMSDestination: PhysicalQueue
   getJMSDeliveryMode(): PERSISTENT
   getJMSRedelivered(): false
   getJMSType(): null
   getJMSExpiration(): 0
   getJMSPriority(): 4
   Properties: null
   Message:
   Class: com.sun.messaging.jmq.jmsclient.MessageImpl
   getJMSMessageID(): ID:13-128.149.71.199(8c:34:4a:1a:1b:b8)-40883-1255980521767
   getJMSTimestamp(): 1255980521767
   getJMSCorrelationID(): null
   JMSReplyTo: null
   JMSDestination: PhysicalQueue
   getJMSDeliveryMode(): PERSISTENT
   getJMSRedelivered(): false
   getJMSType(): null
   getJMSExpiration(): 0
   getJMSPriority(): 4
   Properties: null
   ```

   The first message is the `TextMessage`, and the second is the non-text control message.

8 Go to the `synchconsumer` directory.

9 Run the `SynchConsumer` client to consume the messages:

```
appclient -client client-jar/synchconsumerClient.jar queue
```

The output of the client looks like this (along with some additional output):

```
Destination type is queue
Reading message: This is message 1 from producer
```

Running JMS Clients on Multiple Systems

JMS clients that use the GlassFish Server can exchange messages with each other when they are running on different systems in a network. The systems must be visible to each other by name (the UNIX host name or the Microsoft Windows computer name) and must both be running the GlassFish Server.

Note – Any mechanism for exchanging messages between systems is specific to the Java EE server implementation. This tutorial describes how to use the GlassFish Server for this purpose.

Suppose that you want to run the `Producer` client on one system, `earth`, and the `SynchConsumer` client on another system, `jupiter`. Before you can do so, you need to perform these tasks:

1. Create two new connection factories
2. Change the name of the default JMS host on one system
3. Edit the source code for the two examples
4. Recompile and repackage the examples

Note – A limitation in the JMS provider in the GlassFish Server may cause a runtime failure to create a connection to systems that use the Dynamic Host Configuration Protocol (DHCP) to obtain an IP address. You can, however, create a connection *from* a system that uses DHCP *to* a system that does not use DHCP. In the examples in this tutorial, `earth` can be a system that uses DHCP, and `jupiter` can be a system that does not use DHCP.

When you run the clients, they will work as shown in Figure 46–1. The client run on `earth` needs the queue on `earth` only in order that the resource injection will succeed. The connection, session, and message producer are all created on `jupiter` using the connection factory that points to `jupiter`. The messages sent from `earth` will be received on `jupiter`.

FIGURE 46–1 Sending Messages from One System to Another



For examples showing how to deploy more complex applications on two different systems, see "An Application Example That Consumes Messages from a Remote Server" on page 841 and "An Application Example That Deploys a Message-Driven Bean on Two Servers" on page 847.

▼ To Create Administered Objects for Multiple Systems

To run these clients, you must do the following:

- Create a new connection factory on both `earth` and `jupiter`
- Create a destination resource on both `earth` and `jupiter`

You do not have to install the tutorial examples on both systems, but you must be able to access the filesystem where it is installed. You may find it more convenient to install the tutorial examples on both systems if the two systems use different operating systems (for example, Windows and Solaris). Otherwise you will have to edit the file *tut-install*`/examples/bp-project/build.properties` and change the location of the `javaee.home` property each time you build or run a client on a different system.

1 **Start the GlassFish Server on `earth`.**

2 **Start the GlassFish Server on `jupiter`.**

3. **To create a new connection factory on `jupiter`, follow these steps:**

   a. **From a command shell on `jupiter`, go to the directory** *tut-install*`/examples/jms/simple/producer/`.

   b. **Type the following command:**

      ```
      ant create-local-factory
      ```

      The `create-local-factory` target, defined in the `build.xml` file for the `Producer` example, creates a connection factory named `jms/JupiterConnectionFactory`.

4. **To create a new connection factory on `earth` that points to the connection factory on `jupiter`, follow these steps:**

   a. **From a command shell on `earth`, go to the directory** *tut-install*`/examples/jms/simple/producer/`.

   b. **Type the following command:**

      ```
      ant create-remote-factory -Dsys=remote-system-name
      ```

      Replace *remote-system-name* with the actual name of the remote system.

      The `create-remote-factory` target, defined in the `build.xml` file for the `Producer` example, also creates a connection factory named `jms/JupiterConnectionFactory`. In addition, it sets the `AddressList` property for this factory to the name of the remote system.

Additional resources will be created when you deploy the application, if they have not been created before.

The reason the `glassfish-resources.xml` file does not specify `jms/JupiterConnectionFactory` is that on `earth` the connection factory requires the `AddressList` property setting, whereas on `jupiter` it does not. You can examine the targets in the `build.xml` file for details.

Changing the Default Host Name

By default, the default host name for the JMS service on the GlassFish Server is `localhost`. To access the JMS service from another system, however, you must change the host name. You can change it to either the actual host name or to `0.0.0.0`.

You can change the default host name using either the Administration Console or the `asadmin` command.

▼ To Change the Default Host Name Using the Administration Console

1. **On `jupiter`, start the Administration Console by opening a browser at `http://localhost:4848/`.**

2. **In the navigation tree, expand the Configurations node, then expand the server-config node.**
3. **Under the server-config node, expand the Java Message Service node.**
4. **Under the Java Message Service node, expand the JMS Hosts node.**
5. **Under the JMS Hosts node, select `default_JMS_host`.**
   The Edit JMS Host page opens.
6. **In the Host field, type the name of the system, or type `0.0.0.0`.**
7. **Click Save.**
8. **Restart the GlassFish Server.**

▼ To Change the Default Host Name Using the `asadmin` Command

1. **Specify a command like one of the following:**

```
asadmin set server-config.jms-service.jms-host.default_JMS_host.host="0.0.0.0"
```

```
asadmin set server-config.jms-service.jms-host.default_JMS_host.host="hostname"
```

2. **Restart the GlassFish Server.**

▼ To Edit, Build, Package, Deploy, and Run the Clients Using NetBeans IDE

These steps assume that you have the tutorial installed on both of the two systems you are using and that you are able to access the file system of `jupiter` from `earth` or vice versa. You will edit the source files to specify the new connection factory. Then you will rebuild and run the clients. Follow these steps.

1. **To edit the source files, follow these steps:**

   a. **On `earth`,, open the following file in NetBeans IDE:**
      tut-install`/examples/jms/simple/producer/src/java/Producer.java`

   b. **Find the following line:**

```
@Resource(lookup = "jms/ConnectionFactory")
```

   c. **Change the line to the following:**

```
@Resource(lookup = "jms/JupiterConnectionFactory")
```

   d. **Save the file.**

e. **On `jupiter`, open the following file inNetBeans IDE:**

tut-install`/examples/jms/simple/synchconsumer/src/java/SynchConsumer.java`

f. **Repeat Step b and Step c, then save the file.**

2 **To recompile and repackage the `Producer` example on `earth`, right-click the `producer` project and select Clean and Build.**

3 **To recompile and repackage the `SynchConsumer` example on `jupiter`, right-click the `synchconsumer` project and select Clean and Build.**

4 **On `earth`, deploy and run `Producer`. Follow these steps:**

a. **Right-click the `producer` project and select Properties.**

b. **Select Run from the Categories tree.**

c. **In the Arguments field, type the following:**

```
queue 3
```

d. **Click OK.**

e. **Right-click the project and select Run.**

The output looks like this (along with some additional output):

```
Destination type is topic
Sending message: This is message 1 from producer
Sending message: This is message 2 from producer
Sending message: This is message 3 from producer
```

5 **On `jupiter`, run `SynchConsumer`. Follow these steps:**

a. **Right-click the `synchconsumer` project and select Properties.**

b. **Select Run from the Categories tree.**

c. **In the Arguments field, type the following:**

```
queue
```

d. **Click OK.**

e. **Right-click the project and select Run.**

The output of the program looks like this (along with some additional output):

```
Destination type is queue
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
```

```
Reading message: This is message 3 from producer
```

▼ To Edit, Build, Package, Deploy, and Run the Clients Using Ant and the `appclient` Command

These steps assume that you have the tutorial installed on both of the two systems you are using and that you are able to access the file system of `jupiter` from `earth` or vice versa. You will edit the source files to specify the new connection factory. Then you will rebuild and run the clients.

1. **To edit the source files, follow these steps:**

   a. **On `earth`,, open the following file in a text editor:**

      tut-install`/examples/jms/simple/producer/src/java/Producer.java`

   b. **Find the following line:**

      ```
      @Resource(lookup = "jms/ConnectionFactory")
      ```

   c. **Change the line to the following:**

      ```
      @Resource(lookup = "jms/JupiterConnectionFactory")
      ```

   d. **Save and close the file.**

   e. **On `jupiter`, open the following file in a text editor:**

      tut-install`/examples/jms/simple/synchconsumer/src/java/SynchConsumer.java`

   f. **Repeat Step b and Step c, then save and close the file.**

2. **To recompile and repackage the `Producer` example on `earth`, type the following:**

   ```
   ant
   ```

3. **To recompile and repackage the `SynchConsumer` example on `jupiter`, go to the `synchconsumer` directory and type the following:**

   ```
   ant
   ```

4. **On `earth`, deploy and run `Producer`. Follow these steps:**

   a. **On `earth`, from the `producer` directory, create any needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

      ```
      ant getclient
      ```

      Ignore the message that states that the application is deployed at a URL.

   b. **To run the client, type the following:**

      ```
      appclient -client client-jar/producerClient.jar queue 3
      ```

The output looks like this (along with some additional output):

```
Destination type is topic
Sending message: This is message 1 from producer
Sending message: This is message 2 from producer
Sending message: This is message 3 from producer
```

5 **On `jupiter`, run `SynchConsumer`. Follow these steps:**

a. **From the `synchconsumer` directory, create any needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

```
ant getclient
```

Ignore the message that states that the application is deployed at a URL.

b. **To run the client, type the following:**

```
appclient -client client-jar/synchconsumerClient.jar queue
```

The output of the program looks like this (along with some additional output):

```
Destination type is queue
Reading message: This is message 1 from producer
Reading message: This is message 2 from producer
Reading message: This is message 3 from producer
```

Undeploying and Cleaning the Simple JMS Examples

After you finish running the examples, you can undeploy them and remove the build artifacts.

You can also use the `asadmin` `delete-jms-resource` command to delete the destinations and connection factories you created. However, it is recommended that you keep them, because they will be used in most of the examples later in this chapter. After you have created them, they will be available whenever you restart the GlassFish Server.

Writing Robust JMS Applications

The following examples show how to use some of the more advanced features of the JMS API.

A Message Acknowledgment Example

The `AckEquivExample.java` client shows how both of the following two scenarios ensure that a message will not be acknowledged until processing of it is complete:

- Using an asynchronous message consumer (a message listener) in an `AUTO_ACKNOWLEDGE` session
- Using a synchronous receiver in a `CLIENT_ACKNOWLEDGE` session

With a message listener, the automatic acknowledgment happens when the `onMessage` method returns (that is, after message processing has finished). With a synchronous receiver, the client acknowledges the message after processing is complete. If you use `AUTO_ACKNOWLEDGE` with a synchronous receive, the acknowledgment happens immediately after the `receive` call; if any subsequent processing steps fail, the message cannot be redelivered.

The example is in the following directory:

tut-install`/examples/jms/advanced/ackequivexample/src/java/`

The example contains an `AsynchSubscriber` class with a `TextListener` class, a `MultiplePublisher` class, a `SynchReceiver` class, a `SynchSender` class, a `main` method, and a method that runs the other classes' threads.

The example uses the following objects:

- `jms/ConnectionFactory`, `jms/Queue`, and `jms/Topic`: resources that you created for "A Simple Example of Synchronous Message Receives" on page 792.
- `jms/ControlQueue`: an additional queue
- `jms/DurableConnectionFactory`: a connection factory with a client ID (see "Creating Durable Subscriptions" on page 779, for more information)

The new queue and connection factory are created at deployment time.

▼ To Build, Package, Deploy, and Run the `ackequivexample` Using NetBeans IDE

1 To build and package the client, follow these steps.

a. From the File menu, choose Open Project.

b. In the Open Project dialog, navigate to:

tut-install`/examples/jms/advanced/`

c. Select the `ackequivexample` folder.

d. Select the Open as Main Project check box.

e. **Click Open Project.**

f. **In the Projects tab, right-click the project and select Build.**

2 **To run the client, right-click the `ackequivexample` project and select Run.**

The client output looks something like this (along with some additional output):

```
Queue name is jms/ControlQueue
Queue name is jms/Queue
Topic name is jms/Topic
Connection factory name is jms/DurableConnectionFactory
  SENDER: Created client-acknowledge session
  SENDER: Sending message: Here is a client-acknowledge message
  RECEIVER: Created client-acknowledge session
  RECEIVER: Processing message: Here is a client-acknowledge message
  RECEIVER: Now I'll acknowledge the message
SUBSCRIBER: Created auto-acknowledge session
SUBSCRIBER: Sending synchronize message to control queue
PUBLISHER: Created auto-acknowledge session
PUBLISHER: Receiving synchronize messages from control queue; count = 1
PUBLISHER: Received synchronize message;  expect 0 more
PUBLISHER: Publishing message: Here is an auto-acknowledge message 1
PUBLISHER: Publishing message: Here is an auto-acknowledge message 2
SUBSCRIBER: Processing message: Here is an auto-acknowledge message 1
PUBLISHER: Publishing message: Here is an auto-acknowledge message 3
SUBSCRIBER: Processing message: Here is an auto-acknowledge message 2
SUBSCRIBER: Processing message: Here is an auto-acknowledge message 3
```

3 **After you run the client, you can delete the destination resource `jms/ControlQueue` by using the following command:**

```
asadmin delete-jms-resource jms/ControlQueue
```

You will need the other resources for other examples.

▼ To Build, Package, Deploy, and Run `ackequivexample` Using Ant

1 **In a terminal window, go to the following directory:**

tut-install`/examples/jms/advanced/ackequivexample/`

2 **To compile and package the client, type the following command:**

```
ant
```

3 **To create needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs, type the following command:**

```
ant getclient
```

Ignore the message that states that the application is deployed at a URL.

4. **Because this example takes no command-line arguments, you can run the client using the following command:**

   ```
   ant run
   ```

   Alternatively, you can type the following command:

   ```
   appclient -client client-jar/ackequivexampleClient.jar
   ```

   The client output looks something like this (along with some additional output):

   ```
   Queue name is jms/ControlQueue
   Queue name is jms/Queue
   Topic name is jms/Topic
   Connection factory name is jms/DurableConnectionFactory
     SENDER: Created client-acknowledge session
     SENDER: Sending message: Here is a client-acknowledge message
     RECEIVER: Created client-acknowledge session
     RECEIVER: Processing message: Here is a client-acknowledge message
     RECEIVER: Now I'll acknowledge the message
   SUBSCRIBER: Created auto-acknowledge session
   SUBSCRIBER: Sending synchronize message to control queue
   PUBLISHER: Created auto-acknowledge session
   PUBLISHER: Receiving synchronize messages from control queue; count = 1
   PUBLISHER: Received synchronize message;  expect 0 more
   PUBLISHER: Publishing message: Here is an auto-acknowledge message 1
   PUBLISHER: Publishing message: Here is an auto-acknowledge message 2
   SUBSCRIBER: Processing message: Here is an auto-acknowledge message 1
   PUBLISHER: Publishing message: Here is an auto-acknowledge message 3
   SUBSCRIBER: Processing message: Here is an auto-acknowledge message 2
   SUBSCRIBER: Processing message: Here is an auto-acknowledge message 3
   ```

5. **After you run the client, you can delete the destination resource `jms/ControlQueue` by using the following command:**

   ```
   asadmin delete-jms-resource jms/ControlQueue
   ```

   You will need the other resources for other examples.

A Durable Subscription Example

The `DurableSubscriberExample.java` example shows how durable subscriptions work. It demonstrates that a durable subscription is active even when the subscriber is not active. The example contains a `DurableSubscriber` class, a `MultiplePublisher` class, a `main` method, and a method that instantiates the classes and calls their methods in sequence.

The example is in the following directory:

tut-install`/examples/jms/advanced/durablesubscriberexample/src/java/`

The example begins in the same way as any publish/subscribe client: The subscriber starts, the publisher publishes some messages, and the subscriber receives them. At this point, the

subscriber closes itself. The publisher then publishes some messages while the subscriber is not active. The subscriber then restarts and receives the messages.

▼ To Build, Package, Deploy, and Run `durablesubscriberexample` Using NetBeans IDE

1. **To compile and package the client, follow these steps:**
   a. **From the File menu, choose Open Project.**
   b. **In the Open Project dialog, navigate to:**
      tut-install`/examples/jms/advanced/`
   c. **Select the `durablesubscriberexample` folder.**
   d. **Select the Open as Main Project check box.**
   e. **Click Open Project.**
   f. **In the Projects tab, right-click the project and select Build.**
2. **To run the client, right-click the `durablesubscriberexample` project and select Run.**
   The output looks something like this (along with some additional output):

```
Connection factory without client ID is jms/ConnectionFactory
Connection factory with client ID is jms/DurableConnectionFactory
Topic name is jms/Topic
Starting subscriber
PUBLISHER: Publishing message: Here is a message 1
SUBSCRIBER: Reading message: Here is a message 1
PUBLISHER: Publishing message: Here is a message 2
SUBSCRIBER: Reading message: Here is a message 2
PUBLISHER: Publishing message: Here is a message 3
SUBSCRIBER: Reading message: Here is a message 3
Closing subscriber
PUBLISHER: Publishing message: Here is a message 4
PUBLISHER: Publishing message: Here is a message 5
PUBLISHER: Publishing message: Here is a message 6
Starting subscriber
SUBSCRIBER: Reading message: Here is a message 4
SUBSCRIBER: Reading message: Here is a message 5
SUBSCRIBER: Reading message: Here is a message 6
Closing subscriber
Unsubscribing from durable subscription
```

3. **After you run the client, you can delete the connection factory `jms/DurableConnectionFactory` by using the following command:**

```
asadmin delete-jms-resource jms/DurableConnectionFactory
```

▼ To Build, Package, Deploy, and Run `durablesubscriberexample` Using Ant

1. **In a terminal window, go to the following directory:**

   tut-install`/examples/jms/advanced/durablesubscriberexample/`

2. **To compile and package the client, type the following command:**

   ```
   ant
   ```

3. **To create any needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs, type the following command:**

   ```
   ant getclient
   ```

   Ignore the message that states that the application is deployed at a URL.

4. **Because this example takes no command-line arguments, you can run the client using the following command:**

   ```
   ant run
   ```

   Alternatively, you can type the following command:

   ```
   appclient -client client-jar/durablesubscriberexampleClient.jar
   ```

5. **After you run the client, you can delete the connection factory `jms/DurableConnectionFactory` by using the following command:**

   ```
   asadmin delete-jms-resource jms/DurableConnectionFactory
   ```

A Local Transaction Example

The `TransactedExample.java` example demonstrates the use of transactions in a JMS client application. The example is in the following directory:

tut-install`/examples/jms/advanced/transactedexample/src/java/`

This example shows how to use a queue and a topic in a single transaction as well as how to pass a session to a message listener's constructor function. The example represents a highly simplified e-commerce application in which the following things happen.

1. A retailer sends a `MapMessage` to the vendor order queue, ordering a quantity of computers, and waits for the vendor's reply:

   ```
   producer = session.createProducer(vendorOrderQueue);
   outMessage = session.createMapMessage();
   outMessage.setString("Item", "Computer(s)");
   outMessage.setInt("Quantity", quantity);
   outMessage.setJMSReplyTo(retailerConfirmQueue);
   producer.send(outMessage);
   ```

```
System.out.println("Retailer: ordered " + quantity + " computer(s)");
orderConfirmReceiver = session.createConsumer(retailerConfirmQueue);
connection.start();
```

2. The vendor receives the retailer's order message and sends an order message to the supplier order topic in one transaction. This JMS transaction uses a single session, so you can combine a receive from a queue with a send to a topic. Here is the code that uses the same session to create a consumer for a queue and a producer for a topic:

   ```
   vendorOrderReceiver = session.createConsumer(vendorOrderQueue);
   supplierOrderProducer = session.createProducer(supplierOrderTopic);
   ```

   The following code receives the incoming message, sends an outgoing message, and commits the session. The message processing has been removed to keep the sequence simple:

   ```
   inMessage = vendorOrderReceiver.receive();
   // Process the incoming message and format the outgoing
   // message
   ...
   supplierOrderProducer.send(orderMessage);
   ...
   session.commit();
   ```

3. Each supplier receives the order from the order topic, checks its inventory, and then sends the items ordered to the queue named in the order message's `JMSReplyTo` field. If it does not have enough in stock, the supplier sends what it has. The synchronous receive from the topic and the send to the queue take place in one JMS transaction.

   ```
   receiver = session.createConsumer(orderTopic);
   ...
   inMessage = receiver.receive();
   if (inMessage instanceof MapMessage) {
       orderMessage = (MapMessage) inMessage;
   }
   // Process message
   MessageProducer producer =
       session.createProducer((Queue) orderMessage.getJMSReplyTo());
   outMessage = session.createMapMessage();
   // Add content to message
   producer.send(outMessage);
   // Display message contentssession.commit();
   ```

4. The vendor receives the replies from the suppliers from its confirmation queue and updates the state of the order. Messages are processed by an asynchronous message listener; this step shows the use of JMS transactions with a message listener.

   ```
   MapMessage component = (MapMessage) message;
   ...
   orderNumber = component.getInt("VendorOrderNumber");
   Order order = Order.getOrder(orderNumber).processSubOrder(component);
   session.commit();
   ```

5. When all outstanding replies are processed for a given order, the vendor message listener sends a message notifying the retailer whether it can fulfill the order.

   ```
   Queue replyQueue = (Queue) order.order.getJMSReplyTo();
   MessageProducer producer = session.createProducer(replyQueue);
   ```

```
MapMessage retailerConfirmMessage = session.createMapMessage();
// Format the message
producer.send(retailerConfirmMessage);
session.commit();
```

6. The retailer receives the message from the vendor:

```
inMessage = (MapMessage) orderConfirmReceiver.receive();
```

Figure 46–2 illustrates these steps.

FIGURE 46–2 Transactions: JMS Client Example



The example contains five classes: `GenericSupplier`, `Order`, `Retailer`, `Vendor`, and `VendorMessageListener`. The example also contains a `main` method and a method that runs the threads of the `Retailer`, `Vendor`, and two supplier classes.

All the messages use the `MapMessage` message type. Synchronous receives are used for all message reception except for the case of the vendor processing the replies of the suppliers. These replies are processed asynchronously and demonstrate how to use transactions within a message listener.

At random intervals, the `Vendor` class throws an exception to simulate a database problem and cause a rollback.

All classes except `Retailer` use transacted sessions.

The example uses three queues named `jms/AQueue`, `jms/BQueue`, and `jms/CQueue`, and one topic named `jms/OTopic`.

▼ To Build, Package, Deploy, and Run `transactedexample` Using NetBeans IDE

1. **In a terminal window, go to the following directory:**

   tut-install`/examples/jms/advanced/transactedexample/`

2. **To compile and package the client, follow these steps:**

   a. **From the File menu, choose Open Project.**

   b. **In the Open Project dialog, navigate to:**

      tut-install`/examples/jms/advanced/`

   c. **Select the `transactedexample` folder.**

   d. **Select the Open as Main Project check box.**

   e. **Click Open Project.**

   f. **In the Projects tab, right-click the project and select Build.**

3. **To deploy and run the client, follow these steps:**

   a. **Right-click the `transactedexample` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **In the Arguments field, type a number that specifies the number of computers to order:**

      `3`

   d. **Click OK.**

   e. **Right-click the project and select Run.**

   The output looks something like this (along with some additional output):

```
Quantity to be ordered is 3
Retailer: ordered 3 computer(s)
Vendor: Retailer ordered 3 Computer(s)
Vendor: ordered 3 monitor(s) and hard drive(s)
Monitor Supplier: Vendor ordered 3 Monitor(s)
```

```
Monitor Supplier: sent 3 Monitor(s)
  Monitor Supplier: committed transaction
  Vendor: committed transaction 1
Hard Drive Supplier: Vendor ordered 3 Hard Drive(s)
Hard Drive Supplier: sent 1 Hard Drive(s)
Vendor: Completed processing for order 1
  Hard Drive Supplier: committed transaction
Vendor: unable to send 3 computer(s)
  Vendor: committed transaction 2
Retailer: Order not filled
Retailer: placing another order
Retailer: ordered 6 computer(s)
Vendor: JMSException occurred: javax.jms.JMSException:
Simulated database concurrent access exception
javax.jms.JMSException: Simulated database concurrent access exception
        at TransactedExample$Vendor.run(Unknown Source)
  Vendor: rolled back transaction 1
Vendor: Retailer ordered 6 Computer(s)
Vendor: ordered 6 monitor(s) and hard drive(s)
Monitor Supplier: Vendor ordered 6 Monitor(s)
Hard Drive Supplier: Vendor ordered 6 Hard Drive(s)
Monitor Supplier: sent 6 Monitor(s)
  Monitor Supplier: committed transaction
Hard Drive Supplier: sent 6 Hard Drive(s)
  Hard Drive Supplier: committed transaction
  Vendor: committed transaction 1
Vendor: Completed processing for order 2
Vendor: sent 6 computer(s)
Retailer: Order filled
  Vendor: committed transaction 2
```

4. **After you run the client, you can delete the destination resources from the IDE or by using the following commands:**

```
asadmin delete-jms-resource jms/AQueue
asadmin delete-jms-resource jms/BQueue
asadmin delete-jms-resource jms/CQueue
asadmin delete-jms-resource jms/OTopic
```

▼ To Build, Package, Deploy, and Run `transactedexample` Using Ant and the `appclient` Command

1. **In a terminal window, go to the following directory:**

   tut-install`/examples/jms/advanced/transactedexample/`

2. **To build and package the client, type the following command:**

   ```
   ant
   ```

3. **Create needed resources, deploy the client JAR file to the GlassFish Server, then retrieve the client stubs:**

   ```
   ant getclient
   ```

   Ignore the message that states that the application is deployed at a URL.

4. **Use a command like the following to run the client.**

   The argument specifies the number of computers to order.

   ```
   appclient -client client-jar/transactedexampleClient.jar 3
   ```

   The output looks something like this (along with some additional output):

   ```
   Quantity to be ordered is 3
   Retailer: ordered 3 computer(s)
   Vendor: Retailer ordered 3 Computer(s)
   Vendor: ordered 3 monitor(s) and hard drive(s)
   Monitor Supplier: Vendor ordered 3 Monitor(s)
   Monitor Supplier: sent 3 Monitor(s)
     Monitor Supplier: committed transaction
     Vendor: committed transaction 1
   Hard Drive Supplier: Vendor ordered 3 Hard Drive(s)
   Hard Drive Supplier: sent 1 Hard Drive(s)
   Vendor: Completed processing for order 1
     Hard Drive Supplier: committed transaction
   Vendor: unable to send 3 computer(s)
     Vendor: committed transaction 2
   Retailer: Order not filled
   Retailer: placing another order
   Retailer: ordered 6 computer(s)
   Vendor: JMSException occurred: javax.jms.JMSException:
   Simulated database concurrent access exception
   javax.jms.JMSException: Simulated database concurrent access exception
           at TransactedExample$Vendor.run(Unknown Source)
     Vendor: rolled back transaction 1
   Vendor: Retailer ordered 6 Computer(s)
   Vendor: ordered 6 monitor(s) and hard drive(s)
   Monitor Supplier: Vendor ordered 6 Monitor(s)
   Hard Drive Supplier: Vendor ordered 6 Hard Drive(s)
   Monitor Supplier: sent 6 Monitor(s)
     Monitor Supplier: committed transaction
   Hard Drive Supplier: sent 6 Hard Drive(s)
     Hard Drive Supplier: committed transaction
     Vendor: committed transaction 1
   Vendor: Completed processing for order 2
   Vendor: sent 6 computer(s)
   Retailer: Order filled
     Vendor: committed transaction 2
   ```

5. **After you run the client, you can delete the destination resources by using the following command:**

   ```
   asadmin delete-jms-resource jms/AQueue
   asadmin delete-jms-resource jms/BQueue
   asadmin delete-jms-resource jms/CQueue
   asadmin delete-jms-resource jms/OTopic
   ```

An Application That Uses the JMS API with a Session Bean

This section explains how to write, compile, package, deploy, and run an application that uses the JMS API in conjunction with a session bean. The application contains the following components:

- An application client that invokes a session bean
- A session bean that publishes several messages to a topic
- A message-driven bean that receives and processes the messages using a durable topic subscriber and a message selector

You will find the source files for this section in the directory *tut-install*`/examples/jms/clientsessionmdb/`. Path names in this section are relative to this directory.

Writing the Application Components for the `clientsessionmdb` Example

This application demonstrates how to send messages from an enterprise bean (in this case, a session bean) rather than from an application client, as in the example in Chapter 25, "A Message-Driven Bean Example." Figure 46–3 illustrates the structure of this application.

FIGURE 46–3 An Enterprise Bean Application: Client to Session Bean to Message-Driven Bean



The Publisher enterprise bean in this example is the enterprise-application equivalent of a wire-service news feed that categorizes news events into six news categories. The

message-driven bean could represent a newsroom, where the sports desk, for example, would set up a subscription for all news events pertaining to sports.

The application client in the example injects the Publisher enterprise bean's remote home interface and then calls the bean's business method. The enterprise bean creates 18 text messages. For each message, it sets a `String` property randomly to one of six values representing the news categories and then publishes the message to a topic. The message-driven bean uses a message selector for the property to limit which of the published messages it receives.

Coding the Application Client: `MyAppClient.java`

The application client, `clientsessionmdb-app-client/src/java/MyAppClient.java`, performs no JMS API operations and so is simpler than the client in Chapter 25, "A Message-Driven Bean Example." The client uses dependency injection to obtain the Publisher enterprise bean's business interface:

```
@EJB(name="PublisherRemote")
static private PublisherRemote publisher;
```

The client then calls the bean's business method twice.

Coding the Publisher Session Bean

The Publisher bean is a stateless session bean that has one business method. The Publisher bean uses a remote interface rather than a local interface because it is accessed from the application client.

The remote interface, `clientsessionmdb-ejb/src/java/sb/PublisherRemote.java`, declares a single business method, `publishNews`.

The bean class, `clientsessionmdb-ejb/src/java/sb/PublisherBean.java`, implements the `publishNews` method and its helper method `chooseType`. The bean class also injects `SessionContext`, `ConnectionFactory`, and `Topic` resources and implements `@PostConstruct` and `@PreDestroy` callback methods. The bean class begins as follows:

```
@Stateless
@Remote({PublisherRemote.class})
public class PublisherBean implements PublisherRemote {

    @Resource
    private SessionContext sc;

    @Resource(lookup = "jms/ConnectionFactory")
    private ConnectionFactory connectionFactory;

    @Resource(lookup = "jms/Topic")
    private Topic topic;
    ...
```

The `@PostConstruct` callback method of the bean class, `makeConnection`, creates the `Connection` used by the bean. The business method `publishNews` creates a `Session` and a `MessageProducer` and publishes the messages.

The `@PreDestroy` callback method, `endConnection`, deallocates the resources that were allocated by the `@PostConstruct` callback method. In this case, the method closes the `Connection`.

Coding the Message-Driven Bean: `MessageBean.java`

The message-driven bean class, `clientsessionmdb-ejb/src/java/mdb/MessageBean.java`, is almost identical to the one in Chapter 25, "A Message-Driven Bean Example." However, the `@MessageDriven` annotation is different, because instead of a queue the bean is using a topic with a durable subscription, and it is also using a message selector. Therefore, the annotation sets the activation config properties `messageSelector`, `subscriptionDurability`, `clientId`, and `subscriptionName`, as follows:

```
@MessageDriven(mappedName = "jms/Topic", activationConfig =  {
    @ActivationConfigProperty(propertyName = "messageSelector",
            propertyValue = "NewsType = 'Sports' OR NewsType = 'Opinion'")
    , @ActivationConfigProperty(propertyName = "subscriptionDurability",
            propertyValue = "Durable")
    , @ActivationConfigProperty(propertyName = "clientId",
            propertyValue = "MyID")
    , @ActivationConfigProperty(propertyName = "subscriptionName",
            propertyValue = "MySub")
    })
```

Note – For a message-driven bean, the destination is specified with the `mappedName` element instead of the `lookup` element.

The JMS resource adapter uses these properties to create a connection factory for the message-driven bean that allows the bean to use a durable subscriber.

Creating Resources for the `clientsessionmdb` Example

This example uses the topic named `jms/Topic` and the connection factory `jms/ConnectionFactory`, which are used in previous examples.. If you deleted the connection factory or topic, they will be recreated when you deploy the example.

▼ To Build, Package, Deploy, and Run the `clientsessionmdb` Example Using NetBeans IDE

1 To compile and package the project, follow these steps:

a. From the File menu, choose Open Project.

b. In the Open Project dialog, navigate to:

tut-install`/examples/jms/`

c. Select the `clientsessionmdb` folder.

d. Select the Open as Main Project check box and the Open Required Projects check box.

e. Click Open Project.

f. In the Projects tab, right-click the `clientsessionmdb` project and select Build.

This task creates the following:

- An application client JAR file that contains the client class file and the session bean's remote interface, along with a manifest file that specifies the main class and places the EJB JAR file in its classpath
- An EJB JAR file that contains both the session bean and the message-driven bean
- An application EAR file that contains the two JAR files

2 Right-click the project and select Run.

This command creates any needed resources, deploys the project, returns a JAR file named `clientsessionmdbClient.jar`, and then executes it.

The output of the application client in the Output pane looks like this (preceded by application client container output):

```
To view the bean output,
 check <install_dir>/domains/domain1/logs/server.log.
```

The output from the enterprise beans appears in the server log (*domain-dir*`/logs/server.log`), wrapped in logging information. The Publisher session bean sends two sets of 18 messages numbered 0 through 17. Because of the message selector, the message-driven bean receives only the messages whose `NewsType` property is `Sports` or `Opinion`.

▼ To Build, Package, Deploy, and Run the `clientsessionmdb` Example Using Ant

1. **Go to the following directory:**

   tut-install`/examples/jms/clientsessionmdb/`

2. **To compile the source files and package the application, use the following command:**

   ```
   ant
   ```

   The `ant` command creates the following:

   - An application client JAR file that contains the client class file and the session bean's remote interface, along with a manifest file that specifies the main class and places the EJB JAR file in its classpath
   - An EJB JAR file that contains both the session bean and the message-driven bean
   - An application EAR file that contains the two JAR files

   The `clientsessionmdb.ear` file is created in the `dist` directory.

3. **To create any needed resources, deploy the application, and run the client, use the following command:**

   ```
   ant run
   ```

   Ignore the message that states that the application is deployed at a URL.

   The client displays these lines (preceded by application client container output):

   ```
   To view the bean output,
    check <install_dir>/domains/domain1/logs/server.log.
   ```

   The output from the enterprise beans appears in the server log file, wrapped in logging information. The Publisher session bean sends two sets of 18 messages numbered 0 through 17. Because of the message selector, the message-driven bean receives only the messages whose `NewsType` property is `Sports` or `Opinion`.

An Application That Uses the JMS API with an Entity

This section explains how to write, compile, package, deploy, and run an application that uses the JMS API with an entity. The application uses the following components:

- An application client that both sends and receives messages
- Two message-driven beans
- An entity class

You will find the source files for this section in the directory *tut-install*`/examples/jms/clientmdbentity/`. Path names in this section are relative to this directory.

Overview of the `clientmdbentity` Example Application

This application simulates, in a simplified way, the work flow of a company's human resources (HR) department when it processes a new hire. This application also demonstrates how to use the Java EE platform to accomplish a task that many JMS applications need to perform.

A JMS client must often wait for several messages from various sources. It then uses the information in all these messages to assemble a message that it then sends to another destination. The common term for this process is *joining messages*. Such a task must be transactional, with all the receives and the send as a single transaction. If not all the messages are received successfully, the transaction can be rolled back. For an application client example that illustrates this task, see "A Local Transaction Example" on page 823.

A message-driven bean can process only one message at a time in a transaction. To provide the ability to join messages, an application can have the message-driven bean store the interim information in an entity. The entity can then determine whether all the information has been received; when it has, the entity can report this back to one of the message-driven beans, which then creates and sends the message to the other destination. After it has completed its task, the entity can be removed.

The basic steps of the application are as follows.

1. The HR department's application client generates an employee ID for each new hire and then publishes a message (M1) containing the new hire's name, employee ID, and position. The client then creates a temporary queue, `ReplyQueue`, with a message listener that waits for a reply to the message. (See "Creating Temporary Destinations" on page 778 for more information.)
2. Two message-driven beans process each message: One bean, `OfficeMDB`, assigns the new hire's office number, and the other bean, `EquipmentMDB`, assigns the new hire's equipment. The first bean to process the message creates and persists an entity named `SetupOffice`, then calls a business method of the entity to store the information it has generated. The second bean locates the existing entity and calls another business method to add its information.
3. When both the office and the equipment have been assigned, the entity business method returns a value of `true` to the message-driven bean that called the method. The message-driven bean then sends to the reply queue a message (M2) describing the assignments. Then it removes the entity. The application client's message listener retrieves the information.

Figure 46–4 illustrates the structure of this application. Of course, an actual HR application would have more components; other beans could set up payroll and benefits records, schedule orientation, and so on.

Figure 46–4 assumes that `OfficeMDB` is the first message-driven bean to consume the message from the client. `OfficeMDB` then creates and persists the `SetupOffice` entity and stores the office information. `EquipmentMDB` then finds the entity, stores the equipment information, and learns that the entity has completed its work. `EquipmentMDB` then sends the message to the reply queue and removes the entity.

FIGURE 46–4 An Enterprise Bean Application: Client to Message-Driven Beans to Entity



Writing the Application Components for the `clientmdbentity` Example

Writing the components of the application involves coding the application client, the message-driven beans, and the entity class.

Coding the Application Client: `HumanResourceClient.java`

The application client, `clientmdbentity-app-client/src/java/HumanResourceClient.java`, performs the following steps:

1. Injects `ConnectionFactory` and `Topic` resources
2. Creates a `TemporaryQueue` to receive notification of processing that occurs, based on new-hire events it has published
3. Creates a `MessageConsumer` for the `TemporaryQueue`, sets the `MessageConsumer`'s message listener, and starts the connection
4. Creates a `MessageProducer` and a `MapMessage`
5. Creates five new employees with randomly generated names, positions, and ID numbers (in sequence) and publishes five messages containing this information

The message listener, `HRListener`, waits for messages that contain the assigned office and equipment for each employee. When a message arrives, the message listener displays the information received and determines whether all five messages have arrived. When they have, the message listener notifies the `main` method, which then exits.

Coding the Message-Driven Beans for the `clientmdbentity` Example

This example uses two message-driven beans:

- `clientmdbentity-ejb/src/java/eb/EquipmentMDB.java`
- `clientmdbentity-ejb/src/java/eb/OfficeMDB.java`

The beans take the following steps:

1. They inject `MessageDrivenContext` and `ConnectionFactory` resources.
2. The `onMessage` method retrieves the information in the message. The `EquipmentMDB`'s `onMessage` method chooses equipment, based on the new hire's position; the `OfficeMDB`'s `onMessage` method randomly generates an office number.
3. After a slight delay to simulate real world processing hitches, the `onMessage` method calls a helper method, `compose`.
4. The `compose` method takes the following steps:
   a. It either creates and persists the `SetupOffice` entity or finds it by primary key.
   b. It uses the entity to store the equipment or the office information in the database, calling either the `doEquipmentList` or the `doOfficeNumber` business method.
   c. If the business method returns `true`, meaning that all of the information has been stored, it creates a connection and a session, retrieves the reply destination information from the message, creates a `MessageProducer`, and sends a reply message that contains the information stored in the entity.
   d. It removes the entity.

Coding the Entity Class for the `clientmdbentity` Example

The `SetupOffice` class, `clientmdbentity-ejb/src/java/eb/SetupOffice.java`, is an entity class. The entity and the message-driven beans are packaged together in an EJB JAR file. The entity class is declared as follows:

```
@Entity
public class SetupOffice implements Serializable {
```

The class contains a no-argument constructor and a constructor that takes two arguments, the employee ID and name. It also contains getter and setter methods for the employee ID, name, office number, and equipment list. The getter method for the employee ID has the `@Id` annotation to indicate that this field is the primary key:

```
@Id public String getEmployeeId() {
    return id;
}
```

The class also implements the two business methods, `doEquipmentList` and `doOfficeNumber`, and their helper method, `checkIfSetupComplete`.

The message-driven beans call the business methods and the getter methods.

The `persistence.xml` file for the entity specifies the most basic settings:

```
<?xml version="1.0" encoding="UTF-8"?>
<persistence version="2.0"
             xmlns="http://java.sun.com/xml/ns/persistence"
             xmlns:xsi="http://www.w3.org/2001/XMLSchema-instance"
             xsi:schemaLocation="http://java.sun.com/xml/ns/persistence
               http://java.sun.com/xml/ns/persistence/persistence_2_0.xsd">
  <persistence-unit name="clientmdbentity-ejbPU" transaction-type="JTA">
    <provider>org.eclipse.persistence.jpa.PersistenceProvider</provider>
    <jta-data-source>jdbc/__default</jta-data-source>
    <class>eb.SetupOffice</class>
    <properties>
      <property name="eclipselink.ddl-generation" value="drop-and-create-tables"/>
    </properties>
  </persistence-unit>
</persistence>
```

Creating Resources for the `clientmdbentity` Example

This example uses the connection factory `jms/ConnectionFactory` and the topic `jms/Topic`, both of which you used in "An Application That Uses the JMS API with a Session Bean" on page 829. It also uses the JDBC resource named `jdbc/__default`, which is enabled by default when you start the GlassFish Server.

If you deleted the connection factory or topic, they will be created when you deploy the example.

▼ To Build, Package, Deploy, and Run the `clientmdbentity` Example Using NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/jms/`
3. **Select the `clientmdbentity` folder.**
4. **Select the Open as Main Project check box and the Open Required Projects check box.**
5. **Click Open Project.**
6. **In the Projects tab, right-click the `clientmdbentity` project and select Build.**

   This task creates the following:

   - An application client JAR file that contains the client class and listener class files, along with a manifest file that specifies the main class
   - An EJB JAR file that contains the message-driven beans and the entity class, along with the `persistence.xml` file
   - An application EAR file that contains the two JAR files along with an `application.xml` file
7. **If the Java DB database is not already running, follow these steps:**

   a. **Click the Services tab.**

   b. **Expand the Databases node.**

   c. **Right-click the Java DB node and select Start Server.**
8. **In the Projects tab, right-click the project and select Run.**

   This command creates any needed resources, deploys the project, returns a client JAR file named `clientmdbentityClient.jar`, and then executes it.

   The output of the application client in the Output pane looks something like this:

```
PUBLISHER: Setting hire ID to 50, name Bill Tudor, position Programmer
PUBLISHER: Setting hire ID to 51, name Carol Jones, position Senior Programmer
PUBLISHER: Setting hire ID to 52, name Mark Wilson, position Manager
PUBLISHER: Setting hire ID to 53, name Polly Wren, position Senior Programmer
PUBLISHER: Setting hire ID to 54, name Joe Lawrence, position Director
Waiting for 5 message(s)
New hire event processed:
  Employee ID: 52
  Name: Mark Wilson
```

```
  Equipment: PDA
  Office number: 294
Waiting for 4 message(s)
New hire event processed:
  Employee ID: 53
  Name: Polly Wren
  Equipment: Laptop
  Office number: 186
Waiting for 3 message(s)
New hire event processed:
  Employee ID: 54
  Name: Joe Lawrence
  Equipment: Java Phone
  Office number: 135
Waiting for 2 message(s)
New hire event processed:
  Employee ID: 50
  Name: Bill Tudor
  Equipment: Desktop System
  Office number: 200
Waiting for 1 message(s)
New hire event processed:
  Employee ID: 51
  Name: Carol Jones
  Equipment: Laptop
  Office number: 262
```

The output from the message-driven beans and the entity class appears in the server log, wrapped in logging information.

For each employee, the application first creates the entity and then finds it. You may see runtime errors in the server log, and transaction rollbacks may occur. The errors occur if both of the message-driven beans discover at the same time that the entity does not yet exist, so they both try to create it. The first attempt succeeds, but the second fails because the bean already exists. After the rollback, the second message-driven bean tries again and succeeds in finding the entity. Container-managed transactions allow the application to run correctly, in spite of these errors, with no special programming.

You can run the application client repeatedly.

▼ To Build, Package, Deploy, and Run the `clientmdbentity` Example Using Ant

1 Go to the following directory:

tut-install`/examples/jms/clientmdbentity/`

2 To compile the source files and package the application, use the following command:

```
ant
```

The `ant` command creates the following:

- An application client JAR file that contains the client class and listener class files, along with a manifest file that specifies the main class
- An EJB JAR file that contains the message-driven beans and the entity class, along with the `persistence.xml` file
- An application EAR file that contains the two JAR files along with an `application.xml` file

3 To create any needed resources, deploy the application, and run the client, use the following command:

```
ant run
```

This command starts the database server if it is not already running, then deploys and runs the application.

Ignore the message that states that the application is deployed at a URL.

The output in the terminal window looks something like this (preceded by application client container output):

```
running application client container.
PUBLISHER: Setting hire ID to 50, name Bill Tudor, position Programmer
PUBLISHER: Setting hire ID to 51, name Carol Jones, position Senior Programmer
PUBLISHER: Setting hire ID to 52, name Mark Wilson, position Manager
PUBLISHER: Setting hire ID to 53, name Polly Wren, position Senior Programmer
PUBLISHER: Setting hire ID to 54, name Joe Lawrence, position Director
Waiting for 5 message(s)
New hire event processed:
  Employee ID: 52
  Name: Mark Wilson
  Equipment: PDA
  Office number: 294
Waiting for 4 message(s)
New hire event processed:
  Employee ID: 53
  Name: Polly Wren
  Equipment: Laptop
  Office number: 186
Waiting for 3 message(s)
New hire event processed:
  Employee ID: 54
  Name: Joe Lawrence
  Equipment: Java Phone
  Office number: 135
Waiting for 2 message(s)
New hire event processed:
  Employee ID: 50
  Name: Bill Tudor
  Equipment: Desktop System
  Office number: 200
Waiting for 1 message(s)
New hire event processed:
  Employee ID: 51
  Name: Carol Jones
```

```
Equipment: Laptop
Office number: 262
```

The output from the message-driven beans and the entity class appears in the server log, wrapped in logging information.

For each employee, the application first creates the entity and then finds it. You may see runtime errors in the server log, and transaction rollbacks may occur. The errors occur if both of the message-driven beans discover at the same time that the entity does not yet exist, so they both try to create it. The first attempt succeeds, but the second fails because the bean already exists. After the rollback, the second message-driven bean tries again and succeeds in finding the entity. Container-managed transactions allow the application to run correctly, in spite of these errors, with no special programming.

You can run the application client repeatedly.

An Application Example That Consumes Messages from a Remote Server

This section and the following section explain how to write, compile, package, deploy, and run a pair of Java EE modules that run on two Java EE servers and that use the JMS API to interchange messages with each other. It is a common practice to deploy different components of an enterprise application on different systems within a company, and these examples illustrate on a small scale how to do this for an application that uses the JMS API.

However, the two examples work in slightly different ways. In this first example, the deployment information for a message-driven bean specifies the remote server from which it will *consume* messages. In the next example, the same message-driven bean is deployed on two different servers, so it is the client module that specifies the servers (one local, one remote) to which it is *sending* messages.

This first example divides the example in Chapter 25, "A Message-Driven Bean Example," into two modules: one containing the application client, and the other containing the message-driven bean.

You will find the source files for this section in *tut-install*`/examples/jms/consumeremote/`. Path names in this section are relative to this directory.

Overview of the `consumeremote` Example Modules

Except for the fact that it is packaged as two separate modules, this example is very similar to the one in Chapter 25, "A Message-Driven Bean Example":

- One module contains the application client, which runs on the remote system and sends three messages to a queue.
- The other module contains the message-driven bean, which is deployed on the local server and consumes the messages from the queue on the remote server.

The basic steps of the modules are as follows.

1. The administrator starts two Java EE servers, one on each system.
2. On the local server, the administrator deploys the message-driven bean module, which specifies the remote server where the client is deployed.
3. On the remote server, the administrator places the client JAR file.
4. The client module sends three messages to a queue.
5. The message-driven bean consumes the messages.

Figure 46–5 illustrates the structure of this application. You can see that it is almost identical to Figure 25–1 except that there are two Java EE servers. The queue used is the one on the remote server; the queue must also exist on the local server for resource injection to succeed.

FIGURE 46–5 A Java EE Application That Consumes Messages from a Remote Server



Writing the Module Components for the `consumeremote` Example

Writing the components of the modules involves

- Coding the application client
- Coding the message-driven bean

The application client, `jupiterclient/src/java/SimpleClient.java`, is almost identical to the one in "The `simplemessage` Application Client" on page 452.

Similarly, the message-driven bean, `earthmdb/src/java/MessageBean.java`, is almost identical to the one in "The Message-Driven Bean Class" on page 453. The only significant difference is that the activation config properties include one property that specifies the name of the remote system. You need to edit the source file to specify the name of your system.

Creating Resources for the `consumeremote` Example

The application client can use any connection factory that exists on the remote server; it uses `jms/ConnectionFactory`. Both components use the queue named `jms/Queue`, which you created for "A Simple Example of Synchronous Message Receives" on page 792. The message-driven bean does not need a previously created connection factory; the resource adapter creates one for it.

Any missing resources will be created when you deploy the example.

Using Two Application Servers for the `consumeremote` Example

As in "Running JMS Clients on Multiple Systems" on page 812, the two servers are referred to as `earth` and `jupiter`.

The GlassFish Server must be running on both systems.

Before you can run the example, you must change the default name of the JMS host on `jupiter`, as described in "To Change the Default Host Name Using the Administration Console" on page 814. If you have already performed this task, you do not have to repeat it.

Which system you use to package and deploy the modules and which system you use to run the client depend on your network configuration (which file system you can access remotely). These instructions assume that you can access the file system of `jupiter` from `earth` but cannot access the file system of `earth` from `jupiter`. (You can use the same systems for `jupiter` and `earth` that you used in "Running JMS Clients on Multiple Systems" on page 812.)

You can package both modules on `earth` and deploy the message-driven bean there. The only action you perform on `jupiter` is running the client module.

▼ To Build, Package, Deploy, and Run the `consumeremote` Modules Using NetBeans IDE

To edit the message-driven bean source file and then package, deploy, and run the modules using NetBeans IDE, follow these steps.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/jms/consumeremote/`
3. **Select the `earthmdb` folder.**
4. **Select the Open as Main Project check box.**
5. **Click Open Project.**
6. **Edit the `MessageBean.java` file as follows:**

   a. **In the Projects tab, expand the `earthmdb`, Source Packages, and `mdb` nodes, then double-click `MessageBean.java`.**

   b. **Find the following line within the `@MessageDriven` annotation:**

   ```
   @ActivationConfigProperty(propertyName = "addressList",
       propertyValue = "remotesystem"),
   ```

   c. **Replace `remotesystem` with the name of your remote system.**
7. **Right-click the `earthmdb` project and select Build.**

   This command creates a JAR file that contains the bean class file.
8. **From the File menu, choose Open Project.**
9. **Select the `jupiterclient` folder.**
10. **Select the Open as Main Project check box.**
11. **Click Open Project.**

12 In the Projects tab, right-click the `jupiterclient` project and select Build.

This target creates a JAR file that contains the client class file and a manifest file.

13 Right-click the `earthmdb` project and select Deploy.

14 To copy the `jupiterclient` module to the remote system, follow these steps:

a. Change to the directory `jupiterclient/dist`:

```
cd ../jupiterclient/dist
```

b. Type a command like the following:

```
cp jupiterclient.jar F:/
```

That is, copy the client JAR file to a location on the remote filesystem. You can use the file system graphical user interface on your system instead of the command line.

15 To run the application client, follow these steps:

a. If you did not previously create the queue and connection factory on the remote system (`jupiter`), go to *tut-install*`/examples/jms/consumeremote/jupiterclient` on the remote system and type the following command:

```
ant add-resources
```

b. Go to the directory on the remote system (`jupiter`) where you copied the client JAR file.

c. To deploy the client module and retrieve the client stubs, use the following command:

```
asadmin deploy --retrieve . jupiterclient.jar
```

This command deploys the client JAR file and retrieves the client stubs in a file named `jupiterclientClient.jar`

d. To run the client, use the following command:

```
appclient -client jupiterclientClient.jar
```

On `jupiter`, the output of the `appclient` command looks like this (preceded by application client container output):

```
Sending message: This is message 1 from jupiterclient
Sending message: This is message 2 from jupiterclient
Sending message: This is message 3 from jupiterclient
```

On `earth`, the output in the server log looks something like this (preceded by logging information):

```
MESSAGE BEAN: Message received: This is message 1 from jupiterclient
MESSAGE BEAN: Message received: This is message 2 from jupiterclient
MESSAGE BEAN: Message received: This is message 3 from jupiterclient
```

▼ To Build, Package, Deploy, and Run the `consumeremote` Modules Using Ant

To edit the message-driven bean source file and then package, deploy, and run the modules using Ant, follow these steps.

1. **Open the file** *tut-install*`/examples/jms/consumeremote/earthmdb/src/java/mdb/MessageBean.java` **in an editor.**

2. **Find the following line within the `@MessageDriven` annotation:**

```
@ActivationConfigProperty(propertyName = "addressList",
    propertyValue = "remotesystem"),
```

3. **Replace `remotesystem` with the name of your remote system, then save and close the file.**

4. **Go to the following directory:**

   tut-install`/examples/jms/consumeremote/earthmdb/`

5. **Type the following command:**

```
ant
```

   This command creates a JAR file that contains the bean class file.

6. **Type the following command:**

```
ant deploy
```

7. **Go to the `jupiterclient` directory:**

```
cd ../jupiterclient
```

8. **Type the following command:**

```
ant
```

   This target creates a JAR file that contains the client class file and a manifest file.

9. **To copy the `jupiterclient` module to the remote system, follow these steps:**

   a. **Change to the directory `jupiterclient/dist`:**

```
cd ../jupiterclient/dist
```

   b. **Type a command like the following:**

```
cp jupiterclient.jar F:/
```

      That is, copy the client JAR file to a location on the remote filesystem.

10 To run the application client, follow these steps:

a. If you did not previously create the queue and connection factory on the remote system (`jupiter`), go to *tut-install*`/examples/jms/consumeremote/jupiterclient` on the remote system and type the following command:

```
ant add-resources
```

b. Go to the directory on the remote system (`jupiter`) where you copied the client JAR file.

c. To deploy the client module and retrieve the client stubs, use the following command:

```
asadmin deploy --retrieve . jupiterclient.jar
```

This command deploys the client JAR file and retrieves the client stubs in a file named `jupiterclientClient.jar`

d. To run the client, use the following command:

```
appclient -client jupiterclientClient.jar
```

On `jupiter`, the output of the `appclient` command looks like this (preceded by application client container output):

```
Sending message: This is message 1 from jupiterclient
Sending message: This is message 2 from jupiterclient
Sending message: This is message 3 from jupiterclient
```

On `earth`, the output in the server log looks something like this (preceded by logging information):

```
MESSAGE BEAN: Message received: This is message 1 from jupiterclient
MESSAGE BEAN: Message received: This is message 2 from jupiterclient
MESSAGE BEAN: Message received: This is message 3 from jupiterclient
```

An Application Example That Deploys a Message-Driven Bean on Two Servers

This section, like the preceding one, explains how to write, compile, package, deploy, and run a pair of Java EE modules that use the JMS API and run on two Java EE servers. The modules are slightly more complex than the ones in the first example.

The modules use the following components:

- An application client that is deployed on the local server. It uses two connection factories, one ordinary one and one that is configured to communicate with the remote server, to create two publishers and two subscribers and to publish and to consume messages.
- A message-driven bean that is deployed twice: once on the local server, and once on the remote one. It processes the messages and sends replies.

In this section, the term *local server* means the server on which both the application client and the message-driven bean are deployed (`earth` in the preceding example). The term *remote server* means the server on which only the message-driven bean is deployed (`jupiter` in the preceding example).

You will find the source files for this section in *tut-install*`/examples/jms/sendremote/`. Path names in this section are relative to this directory.

Overview of the `sendremote` Example Modules

This pair of modules is somewhat similar to the modules in "An Application Example That Consumes Messages from a Remote Server" on page 841 in that the only components are a client and a message-driven bean. However, the modules here use these components in more complex ways. One module consists of the application client. The other module contains only the message-driven bean and is deployed twice, once on each server.

The basic steps of the modules are as follows.

1. You start two Java EE servers, one on each system.
2. On the local server (`earth`), you create two connection factories: one local and one that communicates with the remote server (`jupiter`). On the remote server, you create a connection factory that has the same name as the one that communicates with the remote server.
3. The application client looks up the two connection factories (the local one and the one that communicates with the remote server) to create two connections, sessions, publishers, and subscribers. The subscribers use a message listener.
4. Each publisher publishes five messages.
5. Each of the local and the remote message-driven beans receives five messages and sends replies.
6. The client's message listener consumes the replies.

Figure 46–6 illustrates the structure of this application. M1 represents the first message sent using the local connection factory, and RM1 represents the first reply message sent by the local MDB. M2 represents the first message sent using the remote connection factory, and RM2 represents the first reply message sent by the remote MDB.

FIGURE 46–6 A Java EE Application That Sends Messages to Two Servers



Writing the Module Components for the `sendremote` Example

Writing the components of the modules involves coding the application client and the message-driven bean.

Coding the Application Client: `MultiAppServerClient.java`

The application client class, `multiclient/src/java/MultiAppServerClient.java`, does the following.

1. It injects resources for two connection factories and a topic.
2. For each connection factory, it creates a connection, a publisher session, a publisher, a subscriber session, a subscriber, and a temporary topic for replies.
3. Each subscriber sets its message listener, `ReplyListener`, and starts the connection.

4. Each publisher publishes five messages and creates a list of the messages the listener should expect.
5. When each reply arrives, the message listener displays its contents and removes it from the list of expected messages.
6. When all the messages have arrived, the client exits.

Coding the Message-Driven Bean: `ReplyMsgBean.java`

The message-driven bean class, `replybean/src/ReplyMsgBean.java`, does the following:

1. Uses the `@MessageDriven` annotation:

   ```
   @MessageDriven(mappedName = "jms/Topic")
   ```
2. Injects resources for the `MessageDrivenContext` and for a connection factory. It does not need a destination resource because it uses the value of the incoming message's `JMSReplyTo` header as the destination.
3. Uses a `@PostConstruct` callback method to create the connection, and a `@PreDestroy` callback method to close the connection.

The `onMessage` method of the message-driven bean class does the following:

1. Casts the incoming message to a `TextMessage` and displays the text
2. Creates a connection, a session, and a publisher for the reply message
3. Publishes the message to the reply topic
4. Closes the connection

On both servers, the bean will consume messages from the topic `jms/Topic`.

Creating Resources for the `sendremote` Example

This example uses the connection factory named `jms/ConnectionFactory` and the topic named `jms/Topic`. These objects must exist on both the local and the remote servers.

This example uses an additional connection factory, `jms/JupiterConnectionFactory`, which communicates with the remote system; you created it in "To Create Administered Objects for Multiple Systems" on page 813. This connection factory must exist on the local server.

The `build.xml` file for the `multiclient` module contains targets that you can use to create these resources if you deleted them previously.

To create the resource needed only on the local system, use the following command:

```
ant create-remote-factory -Dsys=remote-system-name
```

The other resources will be created when you deploy the application.

▼ To Enable Deployment on the Remote System

GlassFish Server by default does not allow deployment from a remote system. You must execute an `asadmin` command on the remote system to enable deployment of the message-driven bean on that system.

1. **From a command prompt on the remote system (`jupiter`), run the following command:**

   ```
   asadmin enable-secure-admin
   ```

2. **Stop and restart the server on `jupiter`.**

▼ To Use Two Application Servers for the `sendremote` Example

If you are using NetBeans IDE, you need to add the remote server in order to deploy the message-driven bean there. To do so, follow these steps.

1. **In NetBeans IDE, click the Runtime tab.**
2. **Right-click the Servers node and select Add Server. In the Add Server Instance dialog, follow these steps:**
   a. **Select GlassFish Server 3.1 from the Server list.**
   b. **In the Name field, specify a name slightly different from that of the local server, such as `GlassFish Server 3.1 (2)`.**
   c. **Click Next.**
   d. **For the Server Location, browse to the location of the GlassFish Server on the remote system. This location must be visible from the local system.**
   e. **Click Next.**
   f. **Select the Register Remote Domain radio button.**
   g. **In the Host Name field, type the name of the remote system.**
   h. **Click Finish.**

Next Steps Before you can run the example, you must change the default name of the JMS host on `jupiter`, as described in "To Change the Default Host Name Using the Administration Console" on page 814. If you have already performed this task, you do not have to repeat it.

▼ To Build, Package, Deploy, and Run the `sendremote` Modules Using NetBeans IDE

1. **To build the `replybean` module, follow these steps:**
   a. **From the File menu, choose Open Project.**
   b. **In the Open Project dialog, navigate to:**
      tut-install`/examples/jms/sendremote/`
   c. **Select the `replybean` folder.**
   d. **Select the Open as Main Project check box.**
   e. **Click Open Project.**
   f. **In the Projects tab, right-click the `replybean` project and select Build.**
      This command creates a JAR file that contains the bean class file.
2. **To build the `multiclient` module, follow these steps:**
   a. **From the File menu, choose Open Project.**
   b. **Select the `multiclient` folder.**
   c. **Select the Open as Main Project check box.**
   d. **Click Open Project.**
   e. **In the Projects tab, right-click the `multiclient` project and select Build.**
      This command creates a JAR file that contains the client class file and a manifest file.
3. **To create any needed resources and deploy the `multiclient` module on the local server, follow these steps:**
   a. **Right-click the `multiclient` project and select Properties.**
   b. **Select Run from the Categories tree.**
   c. **From the Server list, select GlassFish Server 3.1 (the local server).**
   d. **Click OK.**

e. **Right-click the `multiclient` project and select Deploy.**

   You can use the Services tab to verify that `multiclient` is deployed as an App Client Module on the local server.

4 **To deploy the `replybean` module on the local and remote servers, follow these steps:**

   a. **Right-click the `replybean` project and select Properties.**

   b. **Select Run from the Categories tree.**

   c. **From the Server list, select GlassFish Server 3.1 (the local server).**

   d. **Click OK.**

   e. **Right-click the `replybean` project and select Deploy.**

   f. **Right-click the `replybean` project again and select Properties.**

   g. **Select Run from the Categories tree.**

   h. **From the Server list, select GlassFish Server 3.1 (2) (the remote server).**

   i. **Click OK.**

   j. **Right-click the `replybean` project and select Deploy.**

      You can use the Services tab to verify that `replybean` is deployed as an EJB Module on both servers.

5 **To run the application client, right-click the `multiclient` project and select Run Project.**

   This command returns a JAR file named `multiclientClient.jar` and then executes it.

   On the local system, the output of the `appclient` command looks something like this:

```
running application client container.
...
Sent message: text: id=1 to local app server
Sent message: text: id=2 to remote app server
ReplyListener: Received message: id=1, text=ReplyMsgBean processed message: text: id=1
to local app server
Sent message: text: id=3 to local app server
ReplyListener: Received message: id=3, text=ReplyMsgBean processed message: text: id=3
to local app server
ReplyListener: Received message: id=2, text=ReplyMsgBean processed message: text: id=2
to remote app server
Sent message: text: id=4 to remote app server
ReplyListener: Received message: id=4, text=ReplyMsgBean processed message: text: id=4
to remote app server
Sent message: text: id=5 to local app server
```

```
ReplyListener: Received message: id=5, text=ReplyMsgBean processed message: text: id=5
to local app server
Sent message: text: id=6 to remote app server
ReplyListener: Received message: id=6, text=ReplyMsgBean processed message: text: id=6
to remote app server
Sent message: text: id=7 to local app server
ReplyListener: Received message: id=7, text=ReplyMsgBean processed message: text: id=7
to local app server
Sent message: text: id=8 to remote app server
ReplyListener: Received message: id=8, text=ReplyMsgBean processed message: text: id=8
to remote app server
Sent message: text: id=9 to local app server
ReplyListener: Received message: id=9, text=ReplyMsgBean processed message: text: id=9
to local app server
Sent message: text: id=10 to remote app server
ReplyListener: Received message: id=10, text=ReplyMsgBean processed message: text:
id=10 to remote app server
Waiting for 0 message(s) from local app server
Waiting for 0 message(s) from remote app server
Finished
Closing connection 1
Closing connection 2
```

On the local system, where the message-driven bean receives the odd-numbered messages, the output in the server log looks like this (wrapped in logging information):

```
ReplyMsgBean: Received message: text: id=1 to local app server
ReplyMsgBean: Received message: text: id=3 to local app server
ReplyMsgBean: Received message: text: id=5 to local app server
ReplyMsgBean: Received message: text: id=7 to local app server
ReplyMsgBean: Received message: text: id=9 to local app server
```

On the remote system, where the bean receives the even-numbered messages, the output in the server log looks like this (wrapped in logging information):

```
ReplyMsgBean: Received message: text: id=2 to remote app server
ReplyMsgBean: Received message: text: id=4 to remote app server
ReplyMsgBean: Received message: text: id=6 to remote app server
ReplyMsgBean: Received message: text: id=8 to remote app server
ReplyMsgBean: Received message: text: id=10 to remote app server
```

▼ To Build, Package, Deploy, and Run the `sendremote` Modules Using Ant

1 To package the modules, follow these steps:

a. Go to the following directory:

tut-install`/examples/jms/sendremote/multiclient/`

b. Type the following command:

```
ant
```

This command creates a JAR file that contains the client class file and a manifest file.

c. **Change to the directory `replybean`:**

```
cd ../replybean
```

d. **Type the following command:**

```
ant
```

This command creates a JAR file that contains the bean class file.

2 **To deploy the `replybean` module on the local and remote servers, follow these steps:**

a. **Verify that you are still in the directory `replybean`.**

b. **Type the following command:**

```
ant deploy
```

Ignore the message that states that the application is deployed at a URL.

c. **Type the following command:**

`ant deploy-remote -Dsys=`*remote-system-name*

Replace *remote-system-name* with the actual name of the remote system.

3 **To deploy and run the client, follow these steps:**

a. **Change to the directory `multiclient`:**

```
cd ../multiclient
```

b. **Type the following command:**

```
ant getclient
```

c. **Type the following command:**

```
ant run
```

On the local system, the output looks something like this:

```
running application client container.
...
Sent message: text: id=1 to local app server
Sent message: text: id=2 to remote app server
ReplyListener: Received message: id=1, text=ReplyMsgBean processed message: text: id=1
to local app server
Sent message: text: id=3 to local app server
ReplyListener: Received message: id=3, text=ReplyMsgBean processed message: text: id=3
to local app server
ReplyListener: Received message: id=2, text=ReplyMsgBean processed message: text: id=2
to remote app server
Sent message: text: id=4 to remote app server
```

```
ReplyListener: Received message: id=4, text=ReplyMsgBean processed message: text: id=4
to remote app server
Sent message: text: id=5 to local app server
ReplyListener: Received message: id=5, text=ReplyMsgBean processed message: text: id=5
to local app server
Sent message: text: id=6 to remote app server
ReplyListener: Received message: id=6, text=ReplyMsgBean processed message: text: id=6
to remote app server
Sent message: text: id=7 to local app server
ReplyListener: Received message: id=7, text=ReplyMsgBean processed message: text: id=7
to local app server
Sent message: text: id=8 to remote app server
ReplyListener: Received message: id=8, text=ReplyMsgBean processed message: text: id=8
to remote app server
Sent message: text: id=9 to local app server
ReplyListener: Received message: id=9, text=ReplyMsgBean processed message: text: id=9
to local app server
Sent message: text: id=10 to remote app server
ReplyListener: Received message: id=10, text=ReplyMsgBean processed message: text:
id=10 to remote app server
Waiting for 0 message(s) from local app server
Waiting for 0 message(s) from remote app server
Finished
Closing connection 1
Closing connection 2
```

On the local system, where the message-driven bean receives the odd-numbered messages, the output in the server log looks like this (wrapped in logging information):

```
ReplyMsgBean: Received message: text: id=1 to local app server
ReplyMsgBean: Received message: text: id=3 to local app server
ReplyMsgBean: Received message: text: id=5 to local app server
ReplyMsgBean: Received message: text: id=7 to local app server
ReplyMsgBean: Received message: text: id=9 to local app server
```

On the remote system, where the bean receives the even-numbered messages, the output in the server log looks like this (wrapped in logging information):

```
ReplyMsgBean: Received message: text: id=2 to remote app server
ReplyMsgBean: Received message: text: id=4 to remote app server
ReplyMsgBean: Received message: text: id=6 to remote app server
ReplyMsgBean: Received message: text: id=8 to remote app server
ReplyMsgBean: Received message: text: id=10 to remote app server
```

◆ ◆ ◆ CHAPTER 47

Advanced Bean Validation Concepts and Examples

This chapter describes how to create custom constraints, custom validator messages, and constraint groups using the Java API for JavaBeans Validation (Bean Validation).

The following topics are addressed here:

Creating Custom Constraints

Bean Validation defines annotations, interfaces, and classes to allow developers to create custom constraints.

Using the Built-In Constraints To Make a New Constraint

Bean Validation includes several built-in constraints that can be combined to create new, reusable constraints. This can simplify constraint definitions by allowing developers to define a custom constraint made up of several built-in constraints that may then be applied to component attributes with a single annotation.

EXAMPLE 47–1 The `@Email` Constraint

```
@Pattern.List({
    @Pattern(regexp = "[a-z0-9!#$%&'*+/=?^_`{|}~-]+(?:\\."
        +"[a-z0-9!#$%&'*+/=?^_`{|}~-]+)*"
        +"@(?:[a-z0-9](?:[a-z0-9-]*[a-z0-9])?\\.)+[a-z0-9](?:[a-z0-9-]*[a-z0-9])?")
})
@Constraint(validatedBy = {})
@Documented
```

EXAMPLE 47–1 The `@Email` Constraint *(Continued)*

```
@Target({ElementType.METHOD,
    ElementType.FIELD,
    ElementType.ANNOTATION_TYPE,
    ElementType.CONSTRUCTOR,
    ElementType.PARAMETER})
@Retention(RetentionPolicy.RUNTIME)
public @interface Email {

    String message() default "{invalid.email}";

    Class<?>[] groups() default {};

    Class<? extends Payload>[] payload() default {};

    @Target({ElementType.METHOD,
        ElementType.FIELD,
        ElementType.ANNOTATION_TYPE,
        ElementType.CONSTRUCTOR,
        ElementType.PARAMETER})
    @Retention(RetentionPolicy.RUNTIME)
    @Documented
    @interface List {
        Email[] value();
    }
}
```

This custom constraint can then be applied to an attribute.

```
...
@Email
protected String email;
...
```

Customizing Validator Messages

Bean Validation includes a resource bundle of default messages for the build-in constraints. These messages can be customized, and localized for non-English speaking locales.

The `ValidationMessages` Resource Bundle

The `Validationmessages` resource bundle and the locale variants of this resource bundle contain strings that override the default validation messages. The `ValidationMessages` resource bundle is typically a properties file, `ValidationMessages.properties`, in the default package of an application.

Localizing Validation Messages

Locale variants of `ValidationMessages.properties` are added by appending an underscore and the locale prefix. For example, the Spanish locale variant resource bundle would be `ValidationMessages_es.properties`.

Grouping Constraints

Constraints may be added to one or more groups. Constraint groups are used to create subsets of constraints, so only certain constraints will be validated for a particular object. By default, all constraints are included in the `Default` constraint group.

Constraint groups are represented by interfaces.

```
public interface Employee {}

public interface Contractor {}
```

Constraint groups can inherit from other groups.

```
public interface Manager extends Employee {}
```

When a constraint is added to an element, the constraint declares which groups that constraint belongs by specifying the class name of the group interface name in the `groups` element of the constraint.

```
@NotNull(groups=Employee.class)
Phone workPhone;
```

Multiple groups can be declared by surrounding the groups with angle brackets ({ and }) and separating the groups class names with commas.

```
@NotNull(groups={ Employee.class, Contractor.class })
Phone workPhone;
```

If a group inherits from another group, validating that group results in validating all constraints declared as part of the supergroup. For example, validating the `Manager` group results in the `workPhone` field being validated, because `Employee` is a super-interface of `Manager`.

Customizing Group Validation Order

By default, constraint groups are validated in no particular order. There are some cases where some groups should be validated before others. For example, in a particular class basic data should be validated before more advanced data.

To set the validation order for a group, add a `javax.validation.GroupSequence` annotation on the interface definition, listing the order in which the validation should occur.

```
@GroupSequence({Default.class, ExpensiveValidationGroup.class})
public interface FullValidationGroup {}
```

When validating `FullValidationGroup`, first the `Default` group is validated. If all the data passes validation, then the `ExpensiveValidationGroup` group is validated. If a constraint is part of part of both the `Default` and `ExpensiveValidationGroup` groups, the constraint is validated as part of the `Default` group, and will not be validated on the subsequent `ExpensiveValidationGroup` pass.

◆ ◆ ◆ CHAPTER 48

Using Java EE Interceptors

This chapter discusses how to create interceptor classes and methods that interpose on method invocations or lifecycle events on a target class.

The following topics are addressed here:

Overview of Interceptors

Interceptors are used in conjunction with Java EE managed classes to allow developers to invoke interceptor methods in conjunction with method invocations or lifecycle events on an associated *target class*. Common uses of interceptors are logging, auditing, or profiling.

Interceptors can be defined within a target class as an *interceptor method*, or in an associated class called an *interceptor class*. Interceptor classes contain methods that are invoked in conjunction with the methods or lifecycle events of the target class.

Interceptor classes and methods are defined using metadata annotations, or in the deployment descriptor of the application containing the interceptors and target classes.

Note – Applications that use the deployment descriptor to define interceptors are not portable across Java EE servers.

Interceptor methods within the target class or in an interceptor class are annotated with one of the metadata annotations defined in Table 48–1.

TABLE 48–1 Interceptor Metadata Annotations

Interceptor Metadata Annotation	Description
`javax.interceptor.AroundInvoke`	Designates the method as an interceptor method.
`javax.interceptor.AroundTimeout`	Designates the method as a timeout interceptor, for interposing on timeout methods for enterprise bean timers.
`javax.annotation.PostConstruct`	Designates the method as an interceptor method for post-construct lifecycle events.
`javax.annotation.PreDestroy`	Designates the method as an interceptor method for pre—destroy lifecycle events.

Interceptor Classes

Interceptor classes may be designated with the optional `javax.interceptor.Interceptor` annotation, but interceptor classes aren't required to be so annotated. Interceptor classes *must* have a public, no-argument constructor.

The target class can have any number of interceptor classes associated with it. The order in which the interceptor classes are invoked is determined by the order in which the interceptor classes are defined in the `javax.interceptor.Interceptors` annotation. This order can be overridden in the deployment descriptor.

Interceptor classes may be targets of dependency injection. Dependency injection occurs when the interceptor class instance is created, using the naming context of the associated target class, and before any `@PostConstruct` callbacks are invoked.

Interceptor Lifecycle

Interceptor classes have the same lifecycle as their associated target class. When a target class instance is created, an interceptor class instance is also created for each declared interceptor class in the target class. That is, if the target class declares multiple interceptor classes, an instance of each class is created when the target class instance is created. The target class instance and all interceptor class instances are fully instantiated before any `@PostConstruct` callbacks are invoked, and any `@PreDestroy` callbacks are invoked before the target class and interceptor class instances are destroyed.

Interceptors and Contexts and Dependency Injection for the Java EE Platform

Contexts and Dependency Injection for the Java EE Platform (CDI) builds on the basic functionality of Java EE interceptors. For information on CDI interceptors, including a discussion of interceptor binding types, see "Using Interceptors" on page 506.

Using Interceptors

Interceptors are defined using one of the interceptor metadata annotations listed in Table 48–1 within the target class, or in a separate interceptor class. The following code declares an `@AroundTimeout` interceptor method within a target class.

```
@Stateless
public class TimerBean {
...
    @Schedule(minute="*/1", hour="*")
    public void automaticTimerMethod() { ... }

    @AroundTimeout
    public void timeoutInterceptorMethod(InvocationContext ctx) { ... }
...
}
```

If interceptor classes are used, use the `javax.interceptor.Interceptors` annotation to declare one or more interceptors at the class or method level of the target class. The following code declares interceptors at the class level.

```
@Stateless
@Interceptors({PrimaryInterceptor.class, SecondaryInterceptor.class})
public class OrderBean { ... }
```

The following code declares a method-level interceptor class.

```
@Stateless
public class OrderBean {
...
    @Interceptors(OrderInterceptor.class)
    public void placeOrder(Order order) { ... }
...
}
```

Intercepting Method Invocations

The `@AroundInvoke` annotation is used to designate interceptor methods for managed object methods. Only one around-invoke interceptor method per class is allowed. Around-invoke interceptor methods have the following form:

```
@AroundInvoke
<visibility> Object <Method name>(InvocationContext) throws Exception { ... }
```

For example:

```
@AroundInvoke
public void interceptOrder(InvocationContext ctx) { ... }
```

Around-invoke interceptor methods can have public, private, protected, or package-level access, and must not be declared static or final.

Around-invoke interceptors can call any component or resource callable by the target method on which it interposes, have the same security and transaction context as the target method, and run in the same Java virtual machine call-stack as the target method.

Around-invoke interceptors can throw any exception allowed by the throws clause of the target method. They may catch and suppress exceptions, and then recover by calling the `InvocationContext.proceed` method.

Using Multiple Method Interceptors

Use the `@Interceptors` annotation to declare multiple interceptors for a target method or class.

```
@Interceptors({PrimaryInterceptor.class, SecondaryInterceptor.class,
        LastInterceptor.class})
public void updateInfo(String info) { ... }
```

The order of the interceptors in the `@Interceptors` annotation is the order in which the interceptors are invoked.

Multiple interceptors may also be defined in the deployment descriptor. The order of the interceptors in the deployment descriptor is the order in which the interceptors will be invoked.

```
...
<interceptor-binding>
    <target-name>myapp.OrderBean</target-name>
    <interceptor-class>myapp.PrimaryInterceptor.class</interceptor-class>
    <interceptor-class>myapp.SecondaryInterceptor.class</interceptor-class>
    <interceptor-class>myapp.LastInterceptor.class</interceptor-class>
    <method-name>updateInfo</method-name>
</interceptor-binding>
...
```

To explicitly pass control to the next interceptor in the chain, call the `InvocationContext.proceed` method.

Sharing Data Across Interceptors

The same `InvocationContext` instance is passed as an input parameter to each interceptor method in the interceptor chain for a particular target method. The `InvocationContext`

instance's `contextData` property is used to pass data across interceptor methods. The `contextData` property is a `java.util.Map<String, Object>` object. Data stored in `contextData` is accessible to interceptor methods further down the interceptor chain.

The data stored in `contextData` is not sharable across separate target class method invocations. That is, a different `InvocationContext` object is created for each invocation of the method in the target class.

Accessing Target Method Parameters From an Interceptor Class

The `InvocationContext` instance passed to each around-invoke method may be used to access and modify the parameters of the target method. The `parameters` property of `InvocationContext` is an array of `Object` instances that corresponds to the parameter order of the target method. For example, for the following target method:

```
@Interceptors(PrimaryInterceptor.class)
public void updateInfo(String firstName, String lastName, Date date) { ... }
```

The `parameters` property, in the `InvocationContext` instance passed to the around-invoke interceptor method in `PrimaryInterceptor`, is an `Object` array containing a `String` object (`firstName`), a `String` object (`lastName`), and a `Date` object (`date`).

The parameters can be accessed and modified using the `InvocationContext.getParameters` and `InvocationContext.setParameters` methods, respectively.

Intercepting Lifecycle Callback Events

Interceptors for lifecycle callback events (post-create and pre-destroy) may be defined in the target class or in interceptor classes. The `@PostCreate` annotation is used to designate a method as a post-create lifecycle event interceptor. The `@PreDestroy` annotation is used to designate a method as a pre-destroy lifecycle event interceptor.

Lifecycle event interceptors defined within the target class have the following form:

```
void <Method name>() { ... }
```

For example:

```
@PostCreate
void initialize() { ... }
```

Lifecycle event interceptors defined in an interceptor class have the following form:

```
void <Method name>(InvocationContext) { ... }
```

For example:

```
@PreDestroy
void cleanup(InvocationContext ctx) { ... }
```

Lifecycle interceptor methods can have public, private, protected, or package-level access, and must not be declared static or final.

Lifecycle interceptor methods are called in an unspecified security and transaction context. That is, portable Java EE applications should not assume the lifecycle event interceptor method has access to a security or transaction context. Only one interceptor method for each lifecycle event (post-create and pre-destroy) is allowed per class.

Using Multiple Lifecycle Callback Interceptors

Multiple lifecycle interceptors may be defined for a target class by specifying the interceptor classes in the `@Interceptors` annotation:

```
@Interceptors({PrimaryInterceptor.class, SecondaryInterceptor.class,
        LastInterceptor.class})
@Stateless
public class OrderBean { ... }
```

The order in which the interceptor classes are listed in the `@Interceptors` annotation defines the order in which the interceptors are invoked.

Data stored in the `contextData` property of `InvocationContext` is not sharable across different lifecycle events.

Intercepting Timeout Events

Interceptors for EJB timer service timeout methods may be defined using the `@AroundTimeout` annotation on methods in the target class or in an interceptor class. Only one `@AroundTimeout` method per class is allowed.

Timeout interceptors have the following form:

```
Object <Method name>(InvocationContext) throws Exception { ... }
```

For example:

```
@AroundTimeout
protected void timeoutInterceptorMethod(InvocationContext ctx) { ... }
```

Timeout interceptor methods can have public, private, protected, or package-level access, and must not be declared static or final.

Timeout interceptors can call any component or resource callable by the target timeout method, and are invoked in the same transaction and security context as the target method.

Timeout interceptors may access the timer object associated with the target timeout method through the `InvocationContext` instance's `getTimer` method.

Using Multiple Timeout Interceptors

Multiple timeout interceptors may be defined for a given target class by specifying the interceptor classes containing `@AroundTimeout` interceptor methods in an `@Interceptors` annotation at the class level.

If a target class specifies timeout interceptors in an interceptor class, and also has a `@AroundTimeout` interceptor method within the target class itself, the timeout interceptors in the interceptor classes are called first, then the timeout interceptors defined in the target class. For example, in the following example, assume that the `PrimaryInterceptor` and `SecondaryInterceptor` class have timeout interceptor methods.

```
@Interceptors({PrimaryInterceptor.class, SecondaryInterceptor.class})
@Stateful
public class OrderBean {
...
    @AroundTimeout
    private void last(InvocationContext ctx) { ... }
...
}
```

The timeout interceptor in `PrimaryInterceptor` will be called first, then the timeout interceptor in `SecondaryInterceptor`, and finally the `last` method defined in the target class.

The `interceptor` Example Application

The `interceptor` example demonstrates how to use an interceptor class, containing an `@AroundInvoke` interceptor method, with a stateless session bean.

The `HelloBean` stateless session bean is a simple enterprise bean with a two business methods, `getName` and `setName` to retrieve and modify a string. The `setName` business method has an `@Interceptors` annotation that specifies an interceptor class, `HelloInterceptor`, for that method.

```
@Interceptors(HelloInterceptor.class)
public void setName(String name) {
    this.name = name;
}
```

The `HelloInterceptor` class defines an `@AroundInvoke` interceptor method, `modifyGreeting`, that converts the string passed to `HelloBean.setName` to lower case.

```
@AroundInvoke
public Object modifyGreeting(InvocationContext ctx) throws Exception {
    Object[] parameters = ctx.getParameters();
    String param = (String) parameters[0];
    param = param.toLowerCase();
    parameters[0] = param;
    ctx.setParameters(parameters);
```

```
    try {
        return ctx.proceed();
    } catch (Exception e) {
        logger.warning("Error calling ctx.proceed in modifyGreeting()");
        return null;
    }
}
```

The parameters to `HelloBean.setName` are retrieved and stored in an `Object` array by calling the `InvocationContext.getParameters` method. Because `setName` only has one parameter, it is the first and only element in the array. The string is set to lower case, and stored in the `parameters` array, then passed to `InvocationContext.setParameters`. To return control to the session bean, `InvocationContext.proceed` is called.

The user interface of `interceptor` is a JavaServer Faces web application that consists of two Facelets views, `index.xhtml`, which has a form for entering the name, and `response.xhtml`, which displays the final name.

Running the `interceptor` Example Application in NetBeans IDE

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to** *tut-install*`/examples/ejb/`**.**
3. **Select the `interceptor` folder and click Open Project.**
4. **In the Projects tab, right-click the `interceptor` project and select Run.**

   This will compile, deploy, and run the `interceptor` example, opening a web browser page to `http://localhost:8080/interceptor/`.
5. **Type a name into the form and select Submit.**

   The name will be converted to lowercase by the method interceptor defined in the `HelloInterceptor` class.

Running the `interceptor` Example Applications Using Ant

1. **Go to the following directory:**

   tut-install`/examples/ejb/interceptor/`

2. **To compile the source files and package the application, use the following command:**

   ```
   ant
   ```

   This command calls the `default` target, which builds and packages the application into a WAR file, `interceptor.war`, located in the `dist` directory.

3. **To deploy and run the application using Ant, use the following command:**

   ```
   ant run
   ```

   This command deploys and runs the `interceptor` example, opening a web browser page to `http://localhost:8080/interceptor/`.

4. **Type a name into the form and select Submit.**

   The name will be converted to lowercase by the method interceptor defined in the `HelloInterceptor` class.

PART IX

Case Studies

Part IX presents a case study that uses multiple Java EE technologies. This part contains the following chapter:

- Chapter 49, “Duke's Tutoring Case Study Example”

◆ ◆ ◆ CHAPTER 49

Duke's Tutoring Case Study Example

The Duke's Tutoring example application is a tracking system for a tutoring center for students. Students or their guardians can check in and out, the tutoring center can track attendance and status updates, and store contact information for guardians and students.

The following topics are addressed here:

Design and Architecture of Duke's Tutoring

Duke's Tutoring is a web application that incorporates several Java EE technologies. It exposes both a main interface (for students and guardians) and an administration interface (for tutoring center staff to maintain the system). The business logic for both interfaces is provided by enterprise beans. The enterprise beans use the Java Persistence API to create and store the application's data in the database.

FIGURE 49–1 Architecture of the Duke's Tutoring Example Application.



Duke's Tutoring uses the following Java EE 6 platform features:

- Java Persistence API entities
  - Java API for JavaBeans Validation (Bean Validation) annotations on the entities for verifying data
  - A custom Bean Validation annotation, `@Email`, for validating email addresses
- Enterprise beans
  - Local, no-interface view session and singleton beans
  - JAX-RS resources in a session bean
  - Java EE security constraints on the administrative interface business methods
  - All enterprise beans packaged within the WAR
- JavaServer Faces technology, using Facelets for the web front-end
  - Templating
  - Composite components
  - A custom formatter, `PhoneNumberFormatter`
  - Security constraints on the administrative interface
  - AJAX-enabled Facelets components

The Duke's Tutoring application has two main user interfaces, both packaged within a single WAR file:

- The main interface, for students, guardians, and staff
- The administrative interface used by the staff to manage the students and guardians, and to generate attendance reports

Apart from the main and administrative interface, there is a JUnit test that demonstrates how to use the embedded EJB container to test the business logic of the session beans.

Main Interface

The main interface allows students and staff to check students in and out, and record when students are outside at the playground.

Java Persistence API Entities Used in the Main Interface

The entities used in the main interface encapsulate data stored and manipulated by Duke's Tutoring, and are located in the `dukestutoring.entity` package.

The `Person` entity defines attributes common to students and guardians tracked by the Duke's Tutoring application. These attributes are the person's name and contact information, including phone numbers and email address. The phone number and email address attributes have Bean Validation annotations to ensure that the submitted data is well-formed. The email attribute uses a custom validation class, `dukestutoring.util.Email`. `Person` has two subclasses, `Student` and `Guardian`. For additional data common to all people, the `PersonDetails` entity is used to store attributes like pictures and the person's birthday that aren't included in the `Person` entity for performance reasons.

The `Student` entity stores attributes specific to the students that come to tutoring. This includes information like the student's grade level and school. The `Guardian` entity's attributes are specific to the parents or guardians of a `Student`. Students and guardians have a many-to-many relationship. That is, a student may have a one or more guardians, and a guardian may have one or more students.

The `Address` entity represents a mailing address, and is associated with `Person` entities. Addresses and people have a many-to-one relationship. That is, one person may have many addresses.

The `TutoringSession` entity represents a particular day at the tutoring center. A particular tutoring session tracks which students attended that day, and which students went to the park. Associated with `TutoringSession` is the `StatusEntry` entity, which logs when a student's status

changes. Student's status changes when they check in to a tutoring session, when they go to the park, and when they check out. The status entry allows the tutoring center staff to track exactly which students attended a tutoring session, when they checked in and out, which students went to the park while they were at the tutoring center, and when they went to and came back from the park.

For information on creating Java Persistence API entities, see Chapter 32, "Introduction to the Java Persistence API." For information on validating entity data, see"Validating Persistent Fields and Properties" on page 541 and Chapter 47, "Advanced Bean Validation Concepts and Examples."

Enterprise Beans Used in the Main Interface

The enterprise beans used in the main interface provide the business logic for Duke's Tutoring, and are located in the `dukestutoring.ejb` package.

`ConfigBean` is singleton session bean used to create the default students when the application is initially deployed, and to create an automatic EJB timer that creates tutoring session entities every weekday.

`RequestBean` is a stateless session bean containing the business methods for the main interface. Students or staff can check students in and out and track when they go to and come back from the park. The bean also has business methods for retrieving lists of students. The business methods in `RequestBean` use strongly-typed Criteria API queries to retrieve data from the database.

For information on creating and using enterprise beans, see Part IV, "Enterprise Beans." For information on creating strongly-typed Criteria API queries, see Chapter 35, "Using the Criteria API to Create Queries."

Facelets Files Used in the Main Interface

The Duke's Tutoring application uses Facelets to display the user interface, and makes extensive use of the templating features of Facelets. Facelets is the default display technology for JavaServer Faces, and consists of XHTML files located in the *tut-install*`/examples/case-studies/dukes-tutoring/web` directory.

The following Facelets files are used in the main interface:

`template.xhtml`
: Template file for the main interface.

`error.xhtml`
: Error file if something goes wrong (this shouldn't occur).

`index.xhtml`
Landing page for the main interface.

`park.xhtml`
Page showing who is currently at the park.

`current.xhtml`
Page showing who is currently in today's tutoring session.

`statusEntries.xhtml`
Page showing the detailed status entry log for today's session.

`resources/components/allStudentsTable.xhtml`
A composite component for a table displaying all active students.

`resources/components/currentSessionTable.xhtml`
A composite component for a table displaying all students in today's session.

`resources/components/parkTable.xhtml`
A composite component for a table displaying all students currently at the park.

`WEB-INF/includes/navigation.xhtml`
XHTML fragment for the main interface's navigation bar.

`WEB-INF/includes/footer.xhtml`
XHTML fragment for the main interface's footer.

For information on using Facelets, see Chapter 5, "Introduction to Facelets."

Helper Classes Used in the Main Interface

The following helper classes, in the `dukestutoring.util` package, are used in the main interface:

`CalendarUtil`	A class that provides a method to strip the unnecessary time data from `java.util.Calendar` instances.
`Email`	Custom Bean Validation annotation class for validating email addresses in the `Person` entity.
`StatusType`	An enumerated type defining the different statuses that a student can have. Possible statuses are: `IN`, `OUT`, and `PARK`. `StatusType` is used throughout the application, including in the `StatusEntry` entity, and throughout the main interface. `StatusType` also defines a `toString` method that returns a localized translation of the status based on the locale.

Properties Files

The strings used in the main interface are encapsulated into resource bundles to allow the display of localized strings in multiple locales. Each of the following properties files has locale-specific files, appended with the locale code, containing the translated strings for that locale. For example, `Messages_es.properties` contains the localized strings for Spanish locales.

`ValidationMessages.properties`
: Strings for the default locale used by the Bean Validation runtime to display validation messages. This file must be named `ValidationMessages.properties` and located in the default package as required by the Bean Validation specification.

`dukestutoring/web/messages/Messages.properties`
: Strings for the default locale for the main and administration Facelets interface.

For information on localizing web applications, see "Registering Custom Localized Static Text" on page 237 and "Registering Custom Error Messages" on page 234.

Deployment Descriptors Used in Duke's Tutoring

The following deployment descriptors are used in Duke's Tutoring:

`src/conf/beans.xml`	An empty deployment descriptor file used to enable the CDI runtime.
`web/WEB-INF/faces-config.xml`	The JavaServer Faces configuration file.
`src/conf/persistence.xml`	The Java Persistence API configuration file.
`web/WEB-INF/glassfish-web.xml`	The GlassFish-specific configuration file.
`web/WEB-INF/web.xml`	The web application configuration file.

No enterprise bean deployment descriptor is used in Duke's Tutoring. Annotations in the enterprise bean class files are used for the configuration of enterprise beans in this application.

Administration Interface

The administration interface of Duke's Tutoring is used by the tutoring center staff to manage the data used by the main interface: the students, the student's guardians, and the addresses. The administration interface uses many of the same components as the main interface. Additional components that are only used in the administration interface are described here.

Enterprise Beans Used in the Administration Interface

The following enterprise beans, in the `dukestutoring.ejb` package, are used in the administration interface:

`AdminBean` A stateless session bean for all the business logic used in the administration interface. Contains security constraint annotations to allow invocation of the business methods only by authorized users.

Facelets Files Used in the Administration Interface

The following Facelets files are used in the administration interface:

`admin/adminTemplate.xhtml`	Template for the administration interface.
`admin/index.xhtml`	Landing page for the administration interface.
`admin/login.xhtml`	Login page for the security-constrained administration interface.
`admin/loginError.xhtml`	Page displayed if there are errors authenticating the administration user.
`admin/address` directory	Pages that allow you to create, edit, and delete `Address` entities.
`admin/guardian` directory	Pages that allow you to create, edit, and delete `Guardian` entities.
`admin/student` directory	Pages that allow you to create, edit, and delete `Student` entities.
`resources/components/formLogin.xhtml`	Composite component for a login form using Java EE security.
`WEB-INF/includes/adminNav.xhtml`	XHTML fragment for the administration interface's navigation bar.

Running the Duke's Tutoring Case Study Application

This section describes how to build, package, deploy, and run the Duke's Tutoring application.

Setting Up GlassFish Server

Before running the Duke's Tutoring application, set up the security realm used by Duke's Tutoring with users and groups. The user names and passwords set in this security realm are used to log in to the administration interface of Duke's Tutoring.

Duke's Tutoring maps users in the `admins` group of the server's security realm to the `Administrator` role used in the security constraint annotations in `AdminBean`.

▼ Adding a User to the File Realm in GlassFish Server

Use the Administration Console of GlassFish Server to add a new user to the `file` security realm.

Before You Begin Make sure GlassFish Server is started as described in "Starting and Stopping the GlassFish Server" on page 71.

1. **Open a web browser to the Administration Console at `http://localhost:4848`.**
2. **In the left pane, expand Configurations → server-config → Security → Realms, and click "file."**
3. **On the Edit Realm page, click Manage Users.**
4. **On the File Users page, click New.**
5. **In the User ID field, type a user name under User ID.**
6. **In the Group List field, type `admins`.**
7. **In the New Password and Confirm New Password fields, type a password.**
8. **Click OK.**

Running Duke's Tutoring

This section describes how to build, deploy, and run Duke's Tutoring in NetBeans IDE and using Ant.

▼ To Build and Deploy Duke's Tutoring in NetBeans IDE

Before You Begin You must have already configured GlassFish Server as a Java EE server in NetBeans IDE, as described in "To Add GlassFish Server as a Server in NetBeans IDE" on page 70.

1. **From the File menu, choose Open Project.**
2. **In the Open Project dialog, navigate to:**

   tut-install`/examples/case-studies/`
3. **Select the `dukes-tutoring` folder.**
4. **Select the Open as Main Project check box and the Open Required Projects check box.**
5. **Click Open Project.**

Note – The first time you open Duke's Tutoring in NetBeans, you will see error glyphs in the project pane. This is expected, as the metamodel files used by the enterprise beans for Criteria API queries have not yet been generated.

---

6. **Right-click `dukes-tutoring` in the project pane and select Run.**

   This will build, package, and deploy Duke's Tutoring to GlassFish Server, starting the Java DB database and GlassFish Server if they've not already been started. After the application has been successfully deployed, the Duke's Tutoring main interface will open in a web browser if NetBeans IDE has been configured to open web applications in a web browser.

▼ To Build and Deploy Duke's Tutoring Using Ant

Before You Begin Make sure GlassFish Server is started as described in "Starting and Stopping the GlassFish Server" on page 71, and Java DB server is started as described in "Starting and Stopping the Java DB Server" on page 72.

1. **In a terminal window, go to:**

   tut-install`/examples/case-studies/dukes-tutoring/`
2. **Type the following command:**

   ```
   ant all
   ```

   This command builds, packages, and deploys Duke's Tutoring to GlassFish Server.

Using Duke's Tutoring

Once Duke's Tutoring is running on GlassFish Server, use the main interface to experiment with checking students in and out or sending them to the park.

Using the Main Interface of Duke's Tutoring

1. **In a web browser, open the main interface at the following URL:**

   ```
   http://localhost:8080/dukes-tutoring/
   ```

2. **Use the main interface to check students in and out, and to log when the students go to the park.**

Using the Administration Interface of Duke's Tutoring

Follow these instructions to log in to the administration interface of Duke's Tutoring and add new students, guardians, and addresses.

1. **In a web browser, open the administration interface at the following URL:**

   ```
   http://localhost:8080/dukes-tutoring/admin/index.xhtml
   ```

   This will redirect you to the login page.

2. **At the login page, enter the username and password you configured in** **"Adding a User to the File Realm in GlassFish Server" on page 880** **.**

3. **Use the administration interface to add or modify students, guardians, or addresses.**

Index

A

D

E

F

G

K

L

M

N

O

P

Q

R

S

T

U

V

W

X